

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PWD/JMD/CB/TENDER/2024-25-
To

1870-74

DATED: 12/06/25

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject :- Tender Notice.

Enclosed kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on Department website as per notification of Principal Secretary (PW) to the Govt. of HP vide No. PBW(B)A(3)1/2024 dated 03.01.2024 as the works mentioned in the notice inviting tender are urgent/emergent nature of works in public interest.

Encl:-As above


Executive Engineer,
HPPWD Division,
Jawalamukhi.

Copy forwarded to the following:-

1. The FC-Cum Secy.(PW) to the Govt. of HP.Shimla-2.
2. The Engineer-in-Chief, HPPWD., Shimla.
3. The Chief Engineer(KZ) HP.PWD. Dharamshala.
4. The Superintending Engineer, Circle HP.PWD. Dehra.
5. All the Executive Engineer under North Zone.
6. All the Assistant Engineer under Dehra Division.
7. The Deputy Commissioner Kangra at Dharamshala.
8. The SDM/Tehsil/President MC Jawalamukhi.
9. The BDO Dehra /Pragpur/ Nagrota Surian/Surani.
10. Notice Board.
11. All the Head of Branches.
12. All the Contractors working under Jawalamukhi Division.


Executive Engineer,
HP.PWD Division,
Jawalamukhi.

H. P. P.W.D. TENDER

Sealed item rate tenders on the form 6&8 are invited by the **Executive Engineer Jawalamukhi Division HPPWD., Jawalamukhi** on behalf of the Governor of HP for the following works from the approved and eligible contractors (C&D Class) enlisted in HPPWD.

TENDER SCHEDULE:

- | | |
|---|----------------------------|
| 1. Date and time of receipt of application for tender form: | 21.06.2025 upto 12.00 Noon |
| 2. Date and time of issue of tender form: | 23.06.2025 upto 5.00 PM |
| 3. Date and time of receipt of tenders: | 24.06.2025 upto 10.30AM |
| 4. Date and time of opening of tenders: | 24.06.2025 at 11.00 AM |

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Jawalamukhi Division HPPWD Jawalamukhi must accompany with each tender.

Job No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
01	Restoration of rain damages on Sihoti Pihri Road KM 0/0 to 8/00 (SH: P/L Cement Concrete Pavement at RD 0/724 to 0/742) SDF/2024/749	Rs. 99,713.00	Rs.2,000/-	One Month	Rs.350/-
02	Restoration of rain damages on Sihoti Pihri Road KM 0/0 to 8/00 (SH: P/L Cement Concrete Pavement at RD 0/746 to 0/763.50) SDF/2024/750	Rs. 99,695.00	Rs.2,000/-	One Month	Rs.350/-
03	Restoration of Rain Damages on link road Majheen Nahallian Pian-Da-Ghatta Road to village Dib KM 0/0 to 9/270 (SH: P/L Cement Concrete Paver Block at RD 2/099 to 2/165.15).	Rs. 99,877.00	Rs.2,000/-	One Month	Rs.350/-
04	Restoration of Rain Damages on Nahallian Pihri Bhangolu-Da-Ghatta Road KM 0/0 to 10/00 (SH: P/L Cement Concrete Pavement at RD 1/625 to 1/643.50) SDF/2024/755	Rs. 99,252.00	Rs.2,000/-	One Month	Rs.350/-
05	Construction of link road from Pihri Bhadrol to Jujhpur G.P. Pihri (SH: C/o PCC Edge Wall with Drain at RD 0/570 to 0/578.50 and ROFD at RD 0/750 to 0/810) BSP/2024/15	Rs. 83,569.00	Rs.2,000/-	One Month	Rs.350/-
06	Construction of link road from Pihri Bhadrol to Jujhpur G.P. Pihri (SH: C/o PCC Edge Wall with Drain at RD 0/560 to 0/566 and ROFD at RD 0/675 to 0/735) BSP/2024/15	Rs. 81,803.00	Rs.2,000/-	One Month	Rs.350/-
07	Construction of link road from Pihri Bhadrol to Jujhpur G.P. Pihri (SH: C/o PCC Edge Wall with Drain at RD 0/545 to 0/554 and ROFD at RD 0/600 to 0/660) BSP/2024/15	Rs. 85,958.00	Rs.2,000/-	One Month	Rs.350/-
08	Restoration of Rain Damages on link road Majheen Nahallian Pian-Da-Ghatta Road to Village Dib KM 0/0 to 9/270 (SH: P/L Cement Concrete Paver Block at RD 2/032 to 2/098.20).	Rs. 99,984.00	Rs.2,000/-	One Month	Rs.350/-
09	Construction of link road to the house of Sh. Ashok Kumar in Village Tipnallah (SH: Formation Cutting at RD 0/0 to 0/300) SDP/2024/542	Rs. 99,720.00	Rs.2,000/-	One Month	Rs.350/-
1	The contractors/firms should possess the following documents (Photocopy to be attached):				
(i)	Latest renewal of enlistment.				
(ii)	PAN (Permanent Account No.)				
(iii)	Registration under HP GST/ (TIN No.).				
(iv)	EPF (Employee Provident Fund Account No.)				
2	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case.				
3	If any of the date mentioned above happened/to be Gazetted Holidays the same shall be processed on next working day.				
4	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).				
5	The Contractor will have to submit affidavit alongwith application for issue of tender that he has not more than two works in hand.				
6	The next tender will be issued only after completion of previous works in hand.				
7	The offer of the tender shall remain valid upto 30 days after the opening.				


Executive Engineer
HPPWD Division Jawalamukhi
Distt Kangra H.P.

Exigency Certificate

It is certified that the tenders invited vide this office NIT
No.....1370-74.....dated.....12/06/25..... are of emergent nature of work and in
public interest.

Place:

Dated:


Executive Engineer,
HPPWD Division,
Jawalamukhi.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99713.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of rain damages on Sihoti Pihri Road Km. 0/0 to 8/00 (SH:-Providing and laying cement concrete pavement at RD. 0/050 to 0/724 to 0/742) SDF/2024/749

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	9.20 Cubic meter	4100.00	Rupees Four Thousand One Hundred Only	Per Cubic meter	37,720.00
2	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty five) Nominal mix 1:1.5:3(one cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST,sale tax or any other taxes imposed by the Government.	9.05 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	61,993.00
	Total					99,713.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill quantity is correct and approved
Rs 99,713 only.

Executive Engineer,
 Jawalamulhi Division,
 HPWD Jawalamulhi

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99695.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of rain damages on Sihoti Pihri Road Km. 0/0 to 8/00 (SH:-Providing and laying cement concrete pavement at RD. 0/050 to 0/746 to 0/763.50) SDF/2024/750

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	9.63 Cubic meter	4100.00	Rupees Four Thousand One Hundred Only	Per Cubic meter	39,483.00
2	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty five) Nominal mix 1:1.5:3(one cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST,sale tax or any other taxes imposed by the Government.	8.79 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	60,212.00
Total						99,695.00
% Above/below						
Quoted Amount in Figures						
Quoted Amount in Words						

Executive Engineer,
 Jawalamulhi Division,
 HPPWD Jawalamulhi

Bill of Materials for Cement concrete pavement for
 Rs 99,695/- only

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99877.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of rain damages on Majheen Nahlian Pian Da Ghatta Road to link road to village Dib Km.0/00 to 9/270 (SH:- laying cement concrete paver block at RD. 2/099 to 2/165.15)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	21.83 Cubic meter	300.00	Rupees Three Hundred Only	Per Cubic meter	6,549.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	9.92 Cubic meter	4050.00	Rupees Four Thousand Fifty Only	Per Cubic meter	40,176.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 80 mm of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	99.23 Square metre	289.20	Rupees Two Hundred Eighty Nine And Paise Twenty Only	Per Square metre	28,697.00
4	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty five) Nominal mix 1:1.5:3(one cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	3.57 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	24,455.00
	Total					99,877.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

*Billing quantity checked and approved
for Rs 99877/- only*

[Signature]
Executive Engineer,
Jawalamulhi Division,
HPPWD Jawalamulhi

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99252.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of rain damages on Nahlian Pihri Bhangolu da Ghatta Road Km. 0/0 to 10/00 (SH:-Providing and laying cement concrete pavement at RD. 1/625 to 1/643.50) SDF/2024/755

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	8.67 Cubic meter	4100.00	Rupees Four Thousand One Hundred Only	Per Cubic meter	35,547.00
2	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty five) Nominal mix 1:1.5:3(one cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST,sale tax or any other taxes imposed by the Government.	9.30 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	63,705.00
Total						99,252.00

% Above/below

Quoted Amount in Figures

Quoted Amount in Words

Bill of quantity checked and approved for Rs. 99,252.00/- only.

Executive Engineer,
 Jawalamulhi Division,
 PWD Jawalamulhi

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 83569.00

Earnest Money :-Rs.2000.00

Time Limit :- One Month.

Name of work:- Link road from Pihri Bahdrol to jujhpr G.P. Pihri (BSP/2024/15).(SH:- C/O PCC Edge wall with Drain at RD 0/570 to 0/578.5 ROFD at RD 0/750 to 0/810).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	10.12 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	2,935.00
2	Excavation for road way in hilly areas in all heights and depths and in all kinds of soil by manual/ mechanical means, including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling or wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades, cutting and trimming of side slopes, camber, super elevation and levels shown as per the drawings and as directed by the Engineer-in Charge complete in conformity with the requirements of MORD Technical Specification clause 302,304 and 1603 and sorting out and stacking of useful materials with in all leads and lifts of material in acquired road width and transporting of un-useful materials for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to required width of road or on approved dumping sites through all modes of transportation including head load or animal transport or by mechanical means including leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him to the extent of damage occurred in all cases. The rate including Royalty, Malkhana, Octroi, toll tax, sales tax or GST any other taxes imposed by the Government.	72.38 Cubic metre	300.00	Rupees Three Hundred Only	Per Cubic metre	21,714.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation of all type of structure like Drains, etcetera including pumping or bailing out water/dewatering (surface and sub soil water) removal of the slush which may arise at the time of laying under water, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 or as per direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	11.60 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	57,420.00
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.	6.00 Number	250.00	Rupees Two Hundred Fifty Only	Each	1,500.00
	Total					83,569.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for Rs 83569/- only.

[Signature]
Executive Engineer,
J/Mukhi Division,
WPPWD/Mukhi.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 81803.00
 Earnest Money :-Rs.2000.00
 Time Limit :- One Month.

Name of work:- Link road from Pihri Bahdrol to jujhpur G.P. Pihri (BSP/2024/15).(SH:- C/O PCC Edge wall with Drain at RD 0/560 to 0/566 & ROFD at RD 0/675 to 0/735).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	7.14 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	2,071.00
2	Excavation for road way in hilly areas in all heights and depths and in all kinds of soil by manual/ mechanical means, including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling or wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades, cutting and trimming of side slopes, camber, super elevation and levels shown as per the drawings and as directed by the Engineer-in Charge complete in conformity with the requirements of MORD Technical Specification clause 302,304 and 1603 and sorting out and stacking of useful materials with in all leads and lifts of material in acquired road width and transporting of un-useful materials for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to required width of road or on approved dumping sites through all modes of transportation including head load or animal transport or by mechanical means including leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him to the extent of damage occurred in all cases. The rate including Royalty, Malkhana, Octroi, toll tax, sales tax or GST any other taxes imposed by the Government.	69.38 Cubic metre	300.00	Rupees Three Hundred Only	Per Cubic metre	20,814.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation of all type of structure like Drains, etcetera including pumping or bailing out water/dewatering (surface and sub soil water) removal of the slush which may arise at the time of laying under water, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 or as per direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	11.65 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	57,668.00
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204 3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.	5.00 Number	250.00	Rupees Two Hundred Fifty Only	Each	1,250.00
	Total					81,803.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

*Bill of quantity checked and approved
for Rs 81803/- only.*

[Signature]
Executive Engineer,
J/Mukhi Division,
HPPWD/JMukhi.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 85958.00
Earnest Money :-Rs.2000.00
Time Limit :- One Month.

Name of work:- Link road from Pihri Bahdrol to jujhpur G.P. Pihri (BSP/2024/15). (SH:- C/O PCC Edge wall with Drain at RD 0/545 to 0/554 & ROFD at RD 0/600 to 0/660).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	8.19 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	2,375.00
2	Excavation for road way in hilly areas in all heights and depths and in all kinds of soil by manual/ mechanical means, including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling or wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades, cutting and trimming of side slopes, camber, super elevation and levels shown as per the drawings and as directed by the Engineer-in Charge complete in conformity with the requirements of MORD Technical Specification clause 302,304 and 1603 and sorting out and stacking of useful materials with in all leads and lifts of material in acquired road width and transporting of un-useful materials for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to required width of road or on approved dumping sites through all modes of transportation including head load or animal transport or by mechanical means including leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him to the extent of damage occurred in all cases. The rate including Royalty, Malkhana, Octroi, toll tax, sales tax or GST any other taxes imposed by the Government.	72.30 Cubic metre	300.00	Rupees Three Hundred Only	Per Cubic metre	21,690.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation of all type of structure like Drains, etcetera including pumping or bailing out water/dewatering (surface and sub soil water) removal of the slush which may arise at the time of laying under water, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 or as per direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	12.15 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	60,143.00
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.	7.00 Number	250.00	Rupees Two Hundred Fifty Only	Each	1,750.00
	Total					85,958.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for RS 85958/- only.

*Executive Engineer,
Mukhi Division,
HPPWD/Mukhi.*

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99984.00
Earnest Money :-Rs. 2000.00
Time Limit :- One Month.

Name of work:- Restoration of rain damages on Majheon Nahllian Pian Da Ghatta Road to link road to village Dib Km.0/00 to 9/270 (SH:- laying cement concrete paver block at RD. 2/032 to 2/098.20)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	21.98 Cubic meter	300.00	Rupees Three Hundred Only	Per Cubic meter	6,594.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	9.93 Cubic meter	4050.00	Rupees Four Thousand Fifty Only	Per Cubic meter	40,217.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 80 mm of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	99.30 Square metre	289.20	Rupees Two Hundred Eighty Nine And Paise Twenty Only	Per Square metre	28,718.00
4	Providing and laying mechanically mixed and vibrated concrete for Reinforced concrete Grade-M25 (M-Twenty five) Nominal mix 1:1.5:3(one cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	3.57 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	24,455.00
	Total					99,984.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

*Billed quantity checked and approved
for Rs 99,984/- only.*

Executive Engineer,
Jawalamulhi Division,
PPWD Jawalamulhi

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99720.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Name of work:- C/O Link Road to House of Sh Ashok Kumar Village Tipnala Mohal (SH: Formation Cutting at RD 0/0 to 0/300) (SDP/2024/542)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount	
			Figures	Words			
1	Excavation for road way in hilly areas in all heights and depths and in all kinds of soil by manual/ mechanical means, including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling or wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades, cutting and trimming of side slopes, camber, super elevation and levels shown as per the drawings and as directed by the Engineer-in Charge complete in conformity with the requirements of MORD Technical Specification clause 302.304 and 1603 and sorting out and stacking of useful materials with in all leads and lifts of material in acquired road width and transporting of un-useful materials for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to required width of road or on approved dumping sites through all modes of transportation including head load or animal transport or by mechanical means including leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him to the extent of damage occurred in all cases. The rate including Royalty, Malkhana, Octroi, toll tax, sales tax or GST any other taxes imposed by the Government.	332.40	Cubic metre	300.00	Rupees Three Hundred Only	Per Cubic metre	99,720.00
	Total						99,720.00
		% Above/below					
		Quoted Amount in Figures					
		Quoted Amount in Words					

Bill of quantities checked and approved

*Bill of quantity checked and approved
for Rs. 99,720/- only.*

Executive Engineer,
 Jawahar Mulhi Division,
 PWD Jawahar Mulhi