



E-Mail ID - ccpwd-jha-bll@hp.gov.in

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Scaled Item / percentage rate tender(s) on PWD form No 6 & 7/8 are hereby invited by the Executive Engineer Jhandutta HPPWD Jhandutta on behalf of the Governor of HP for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tenders. The undersigned reserves the right to accept / reject any application / tender or all the tenders without assigning any reasons.

Date of receipt of application for tender form

27/06/2025 upto 12:00 PM

Date of issue/sale of Tender forms

27/06/2025 from 02:00 PM to 04:00 PM

Date of opening of tender

28/06/2025 at 11:00AM

The tender shall be received up to **10:30AM on 28/06/2025** and will be opened on the same day at **11:00AM** in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (Non-refundable) on **27/06/2025 from 02:00 PM to 04:00 PM**.

The Earnest money in the shape of National Saving Certificate/Deposit at call/ Time Deposit /Account/ In any of the Post-Office /Nationalized Bank in H.P. duly pledged in favour of Executive Engineer, Jhandutta Division, HP-PWD, Jhandutta must accompany with each application. Conditional tender and the tenders received without earnest money will simultaneously be rejected.

Sr. No.	Name of work	Estimated cost	Earnest Money	Cost of form	Time limit
1	R/o repair of BJSM road from Km. 0/0 to 20/0 (SH: Maintenance of earthen shoulders and C/o unlined surface drain between Km. 9/0 to 10/500)	99575.00	2000/-	350/-	Two Month
2	R/o repair of BJSM road from Km. 0/0 to 20/0 (SH: Maintenance of earthen shoulders and C/o unlined surface drain between Km. 11/0 to 12/500)	99399.00	2000/-	350/-	Two Month
3	RRD on Vijaypur to Rahiyan road Km. 0/0 to 1/200 and link road to Kaseh Km. 0/0 to 1/0 under Sub Division Jhandutta (SH: Hiring of Excavator cum loader and Tipper for removal of slips, clearing of drains & other restoration works)	96300.00	2000/-	350/-	One Month
4	RRD on Samoh to Dingu road Km. 0/0 to 2/0 under Sub Division Jhandutta (SH: Hiring of Excavator cum loader for removal of slips, clearing of drains & other restoration works)	94500.00	2000/-	350/-	One Month
5	Balance work of RCC Slab Culvert to link road from Panol Jhandutta road to Village Baroha (SH: C/o approaches to 3.00 mtr. Slab Culvert at RD 0/600) Deposit Work	86119.00	1700/-	350/-	Three Month
6	R/o repair of link road to Bagdu Khurd at Km. 0/0 to 5/0 (SH: Hiring of Excavator cum loader / JCB for construction of unlined surface drain, dressing of berms & other restoration works etc. at various reaches) (SDF/2024/309)	94500.00	1900/-	350/-	Two Month

Certified that tender of above works are being called of emergent nature in exigency of public interest.

Terms and conditions:



DRAFT SCHEDULE OF QUANTITY

Name of Work :- R/O Repair of BJSM road from km 0/00 to 20/00 (SH:- Maintenance of earthen Shoulders and c/o unlined surface drain b/w Km 9/00 to 10/500)				Estimated cost:- ₹ 99575.00		Only
				Earnest Money:- ₹ 2000.00		Only
				Time allowed:- Two Month		
Sr. No.	Description of iteams	Quantity	Rate		Unit	Amount
			Figures	words		
1	Maintenance of Earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead as per technical specification Clause 1903 complete as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	1908.00	46.10	INR forty six and Paise ten Only	Per square Meter	87959.00
2	C/O unlined drain of average cross sectional area 0.40 sqmt in soil to specified lines,grades,levels and dimensioning to the requirement Of Clause 307, excavated materials to be used in embankments within a lead of 50 mtrs complete as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	264.00	44.00	INR forty four Only	Per Running Meter	11616.00
Total:-						99575.00

Draft Schedule of quantity No 82 for the year 2025-26
approved for Rs - 99575/- only

Estimate No. 82
DNIT No. 82
Account No.


Executive Engineer,
Jhandutta Division
HPPWD, Jhandutta

DRAFT SCHEDULE OF QUANTITY

Name of Work :- R/O Repair of BJSM road from km 0/00 to 20/00 (SH:-
Maintenance of earthen Shoulders and c/o unlined surface drain b/w Km
11/00 to 12/500)

Name of Work :- R/O Repair of BJSM road from km 0/00 to 20/00 (SH:- Maintenance of earthen Shoulders and c/o unlined surface drain b/w Km 11/00 to 12/500)							Estimated cost:- ₹ 99399.00		Only
							Earnest Money:- ₹ 2000.00		Only
							Time allowed:- Two Month		
Sr. No.	Description of items	Quantity	Rate		Unit	Amount			
			Figures	words					
1	Maintenance of Earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting in with appropriate equipment at OMC upto a lead as per technical specification Clause 1903 complete as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	1908.00	46.10	INR forty six and Paise ten Only	Per square Meter	87959.00			
2	C/O unlined drain of average cross sectional area 0.40 sqmt in soil to specified lines,grades,levels and dimensioning to the requirement of Clause 307, excavated materials to be used in embankments within a lead of 50 mtrs complete as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	260.00	44.00	INR forty four Only	Per Running Meter	11440.00			
Total:-						99399.00			

Draft Schedule of Quantity No 83 for the year 2025-26
approved for Rs-993991/- only

Estimate No. 83
DNIT No. 83
Account No.

Executive Engineer,
Jhanda Division
HPPWD, Jhanda

3

Draft Schedule of Quantity

Estimated Cost:-
Earnest Money:-

96300
2000.00

Time:-

One Month

Name of work:- Restoration of rain damages on Vijaypur to Rahiyan road km.0/0 to 1/200 and Link road to kaseh km0/0 to 1/0 under sub Division Jhandutta(SH:- Hiring of Excavator cum loader and Tipper for removal of slips, clearing of drains & other restoration works)

Sr.	Description of item	Qty.	In Figure	Rate	In Words	Unit	Amount
1	Providing one number Excavator cum loader/LCB in good condition on hire basis site of work for removal of slips with in all leads and lifts as per the direction of Engineer - in -Charge. The dumping site of material be arranged by the contractor at his own level and no dumping will be allowed along road side or in forest land falling, which the contractor will be responsible for any kind of panel action as per rule of Honble Court.	66.00	1050	Rupees one thousand fifty and paise Nil only		Per Hour	69300
2	Hiring of Tipper 5.5 cum capacity having lift system for carriage of material to different site of work with in all leads and lifts to the entire satisfaction of the Engineer - in -Charge. The dumping site of material be arranged by the contractor at his own level and no dumping will be allowed along road side or in forest land falling, which the contractor will be responsible for any kind of panel action as per rule of Honble Court.	60.00	450.00	Rupees four hundred fifty and paise Nil only		Per Hour	27000.00
						Total	96300

Draft Schedule of Quantity No 77 for the year 2025-26 approved for Rs - 96300/- only

DNR. No - 77

SH mode - 77

Executive Engineer,
Jhandutta Division,
HPPWD, Jhandutta

est

4

Draft Schedule of Quantity

Estimated Cost:- 94500
Earnest Money:- 2000.00
Time:- One Month

Name of work:- Restoration of rain damages on samoh to Dingu road km.0/0 to 2/0 under sub Division jhandutta(SH;- Hiring of Excavator cum loader for removal of slips, clearing of drains & other restoration works)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing one number Excavator cum loader/JCB in good condition on hire basis site of work for removal of slips with in all leads and lifts as per the direction of Engineer - in -Charge . The dumping site of material be arranged by the contractor at his own level and no dumping will be allowed along road side or in forest land failling ,which the contractor will be responsible for any kind of panel action as per rule of Hon'ble Court .	90.00	1850	Rupees one thousand Eighty and paise Nil only	Per Hour	94500
					Total	94500

Draft Schedule of quantity No 78 for the year 2025-26
approved for Rs- 94500/- only

DNIT No- 78

Estimate No- 78

Executive Engineer,
Jhandutta Division,
HPPWD, Jhandutta

DRAFT SCHEDULE OF QUANTITY

Name of Work :- Balabce work of RCC Slab Culvert to link road from Panol Jhandutta road to village Baroha (SH:- Construction of approaches to 3.00 mtr Slab Culvert at RD 0/600). (Deposit Work)		Estimated cost:- ₹ 86119.00		Only		
		Earnest Money:- ₹ 1700.00		Only		
		Time allowed:- Three Month				
Sr. No.	Description of iteams	Quantity	Rate		Unit	Amount
			Figures	words		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas including getting out and disposal of excavated earth lead upto all lift and leads as directed by Engineer-in-charge. in Ordinary rock including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constrecution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.30	216.90	INR two hundred sixteen point nine zero Only	Per Cubic Meter	1366.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:5:10 (one Cement isto five coarse sand) isto ten graded, Crushed stone aggregate 40 mm (forty millimeter) nominal size) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constrecution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.38	4400.60	INR four thousand four hundred point six zero Only	Per Cubic Meter	80883.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constrecution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.40	890.00	INR eight hundred ninety point zero zero Only	Per Cubic Meter	2136.00

4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm (one hundred millimeter) dia. PVC pipe extending through the full width of the structures with slope of 1V:20H towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constrecution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.00	289.00	INR two hundred eighty nine point zero zero Only	Each	1734.00
Total:-						86119.00

*Draft Schedule of quantity No 455 for the year 2024-25
approved for Rs-86119/-only*

Estimate No. 455
DNIT No. 455
Head of Account .
Available Fund:-/-only

Wd
Executive Engineer,
Jhandutta Division,
HPPWD, Jhandutta

6

DRAFT SCHEDULE OF QUANTITY.

DRAFT SCHEDULE OF QUANTITIES						
	Name of work :- R/O Repair of link road to Bhagdu Khurd at Km . 0/0 to 5/00 (SH:-Hiring of Excavator cum loader/JCB for Construction of Unlined surface drain, dressing of berms and other restoration works etc. at various reaches) (SDF/2024/309)	Estimated Cost:- Rs. 94500.00		/-Only		
		Earnest Money:- Rs. 1900.00		/-Only		
		Time allowed::- Two Month				
Sr No.	Description of items.	Quantity	Rate In		Unit	Amount
			In Figure	In words.		
1	2	3	4	5	6	7
1	Providing one number Exacavator cum loader/JCB in good condition on hire bases at site of work for removal of slip.The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other constrction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	90.00	1050.00	Rs. One thousand fifty only.	Per Hours	94500.00
Total						94500.00

Terms and Condition:-

- Draft schedule of quantity No 84 for the year 2025-26 approved for Rs- 94500/- only*
- 1 The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge.
 - 2 The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work
 - 3 No extra charges will be payable to the contractor for any type of loss/repair of machinery during
 - 4 The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the

Estimate No. 84

DNIT No. 84


Head of Account .

Available Fund:-/-only


Wol
Executive Engineer,
Jhandutta Division
HPPWD, Jhandutta

1. The tender forms will not be issued to those contractors whose performance is not found Satisfactory.
2. The contractors should have executed two similar types of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within last five years.
3. GST, EPF No, Earnest Money, Tender form cost, copy of Enlistment should be accompanied with application.
4. Application without all documents will not be entertained.
5. Proxy Application will not be entertained.
6. Payment for the works under N.I.T. shall be made as & when sufficient funds are available with the Department.
7. Tender form shall not be issued to those contractors who have two or more work in hand.

... HIM SUCHNA AVAM JAN SAMPARK...


Executive Engineer,
Jhandutta Division,
HPPWD, Jhandutta.

Dated:-


20/06/2025

No. PW-JDT-CB-EA-I-Tender Notice/2024-25- 2227-31

Copy forwarded to following:-

1. The Engineer-in-Chief, HPPWD Shimla-2 for kind information please.
2. The Chief Engineer (HZ), HPPW., Hamirpur for kind information please.
3. The Superintending Engineer, 10th Circle, HPPWD., Bilaspur for information please.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in & cc-pwd-hp@nic.in for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division for information.
6. Drawing Branch.
7. Accounts Branch
8. Notice Board.


Executive Engineer,
Jhandutta Division,
HPPWD, Jhandutta.