

**Office of the Executive Engineer, HPPWD., Division Kangra
Himachal Pradesh Public works Department Kangra-176001
Phone No. & Fax No. 01892.265028 e-mail:- ee-kan-hp@nic.in
NOTICE INVITING TENDER**

Sealed percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Division, HP: PWD, Kangra on behalf of the Governor of Himachal Pradesh for the following work from the approved and eligible contractors/firms enlisted in HPPWD in the appropriate class for the work mentioned below on **18.06.2025 up to 11-00 A.M.** and will be opened on the same day at **11-30 A.M.** in the presence of intending contractors or their authorized representatives who may wish to be present. The tender forms can be obtained from this office on cash payment (non refundable) on **17.06.2025 up to 4.00 P.M.** The tender applications for issue of tender forms will be received in this office on **16.06.2025 up to 05.00 P.M.** The earnest money in shape FDR National Saving certificate/Saving Account/Time Deposit Account in any of the Post Office/National Bank in H.P. duly pledged in favour of Executive Engineer, HPPWD., Division, Kangra. The conditional tenders and the tenders received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days.

Sr. No.	Name of work	Estimated cost	Earnest Money	Cost of tender form	Time Limit
1	C/O Community Centre at Khart (SH- Excavation, form work, M-20 and Random rubble masonry for toilet blocks & septic tank)(Deposit work)	99980/-	2000/-	350/-	One Month
2	C/O crate wire wall work to approach road near to Kohala to Nagni Mata Mandir in Ghurkari Beat of Ghurkari(Deposit work)	99867/-	2000/-	350/-	One Month
3	C/O Panchyat Road to Upper Simble Khola km. 0/00 to 0/350(SH- C/O Protection wall at RD 0/130 to 0/140)	99990/-	2000/-	350/-	Two Month
4	Balance work of Govt. Degree College at Matour Tehsil & Distt. Kangra(SH- P/F stainless steel railing in entrance portion)	99983/-	2000/-	350/-	One Month
5	Additional work for the C/O Transgender Toilet in Judicial Court Complex at Kangra(SH- C/O Toilet Block)	99989/-	2000/-	350/-	One Month
6	Repair and Restoration on various roads under HPPWD Sub Division Kangra (SH- Maintenance of earthen shoulder, Bush cutting, C/O Unlined drain surface etc.)	97506/-	2000/-	350/-	One Month
7	C/O Pucca Path to the House of Sh. Om Parkash Soni ward No-1 at Jogipur(SH- C/O Path)(Deposit work)	99128/-	2000/-	350/-	Two Month
8	Balance work of Govt. Degree College at Matour Tehsil & Distt. Kangra(SH- P/F stainless steel railing in Block-I 1 st floor to third floor block-2 first to second floor)	99983/-	2000/-	350/-	One Month

Certified that tender of above works are being called of urgent nature in public interest.

TERMS & CONDITIONS:-

1. The contractors/firms should be produce the attested copy of latest enlistment and renewal enlisted in HPPWD, GST No. and EPF No. with the application failing which their application will not be entertained.
2. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
3. The Earnest Money for the above works should be required at the time of sale of tender forms.
4. The contractor/firms should be quoted percentage rate in the tender both in figures and in words failing which tender is likely to be rejected.
5. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.


Executive Engineer,
HPPWD, Division, Kangra,
Distt. Kangra (H.P.)

(On behalf of Governor of Himachal Pradesh)

Dated: - 10/06/25.

Endst:- No.PW/KD/CB/Tenders/2025-26-
Copy is forwarded to:-

1. The Computer Cell Office of the Engineer-in-Chief, HPPWD., Shimla for uploading the NIT on the Department website.
2. The Chief Engineer (KZ) HPPWD., Dharamshala for information please.
3. The Superintending Engineer, 5th Circle, HPPWD., Palampur for information please.
4. All the Assistant Engineer's working under Kangra Division.
5. NIT Register.
6. All Head of Branches.
7. Notice Board.



Executive Engineer,
HPPWD, Division, Kangra,
Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY						
Name of work :- Construction of Community Centre at Khart . (Sh: Excavation , Form work, M-20 and Random rubble masonry for toilet blocks & septic tank). (Deposit work)				Estimate cost-		99980.00
				Earnest money-		2000.00
				Time limit-		One month
Sr .No.	Sub-Head and items of work	Quantity	Unit	Rates in		Amount
				Figures	Words	
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m and as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	39.41	Cum	489.20	Rupees Four Hundred & Eighty Nine Paise Twenty Only	19279.00
2 (i)	Centering and shuttering including strutting, propping etc. and removal of form for : Lintels, beams, plinth beams, girders, bressumers and cantilevers and as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	3.40	Sqm	387.15	Rupees Three Hundred & Eighty Seven - Paise Fifteen Only	1316.00
(ii)	Centering and shuttering including strutting, propping etc. and removal of form for :Suspended floors, roofs, landings, balconies and access platform and as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	16.69	Sqm	468.30	Rupees Four Hundred & Sixty Eight - Paise Thirty Only	7816.00

(iii)	Centering and shuttering including strutting, propping etc. and removal of form for :Edges of slabs and breaks in floors and walls Under 20 cm wide and as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	18.57	Sqm	131.50	Rupees One Hundred & Thirty One - Paise Fifty Only	2442.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering 1:5:10 (1 cement : 5 coarse sand): 10 graded stone aggregate 40 mm nominal size) and as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	0.66	Cum	4685.75	Rupees Four Thousand Six Hundred & Eighty Five - Paise Seventy Five	3093.00
4	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:2:4 (1 cement :2 coarse sand :4 graded stone aggregate 20 mm nominal size) as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes	2.54	Cum	6301.15	Rupees Six Thousand Three Hundred & One - Paise Fifteen Only	16005.00
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Mild steel and Medium Tensile steel bar and as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	262.2	Kg	107.45	Rupees One Hundred & Seven - Paise Fourty Five Only	28169.00

6	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with :Cement mortar 1:6 (1 cement : 6 coarse sand) and as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikana, toll tax, GST or any other taxes imposed by the Government.	4.37	Cum	5002.35	Rupees Five Thousand & Two Paise Thirty Five Only	21860.00
Total						
						99980.00

Excess =	%
Less =	%


 Executive Engineer,
 Kangra Division,
 HP PWD, Kangra.

3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8. Granular material as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, Tol Tax, sale tax or other taxes imposed by the Government	16.95	Per cubic metre	1428.00	Rupees One Thousand Four Hundred & Twenty Eight Only	24205.00
	total					99867.00

Excess = %

Less = %


Executive Engineer
HP.PWD, Division
Kangra Division

SCHEDULE OF QUANTITY

NAME OF WORK:- CONSTRUCTION OF PANCHYAT ROAD TO UPPER SIMBLE KHOLA KM.0/00 TO 0/350(SUB HEAD:- CONSTRUCTION OF PROTECTION WALL AT RD.0/130 TO 0/140		Estimated Cost:- Earnest Money:- Time Limit:-		99990.00 2000/- TWO MONTH	
Sr. No	DESCRIPTION OF ITEM	QTY.	UNIT	RATES	
				In Figures	In Words
1	Earthwork in excavation for all type of road structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m (fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3 m depth The rate is inclusive for carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, toll tax, sale tax or other taxes imposed by the Government.	20.62	Per Cubic metres	489.20	Rupees Four Hundred & Eighty Nine - Paise Twenty Only
2	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I. wire conforming to IS:280 and IS4826 in c 100x100mm mesh including 10% extra for laps of joints laid with stone boulder weighing not less than 25 kg each as per drawing and technical specification clause 1801,including carriage of materials with in all leads, lifts, of materials and other incidentals. The rates including octroi, royalty, malikhana ,toll tex ,sale tex or other taxes imposed by the Government.	26.00	Per Cubic metre	3190.15	Rupees Three Thousand One Hundred & Ninety - Paise Fifteen Only
3	Construction of embankment with approved materials obtained from borrow pits with a lift up to 1.5 mtr. transporting to site. Sprwearing grading to required slope and compacting to meet requirement of table 300.1 and 300.2 with a lead up to 1000 mtr as per technical specification clause 301.5 and as per direction of the Engineer-in Charges. including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkhana, toll tax, GST or other taxes imposed by the Government	20.71	Per Cubic metre	336.00	Rupees Three Hundred & Thirty Six Only
				TOTAL	99990.00

EXCESS= %

LESS = %


 Executive Engineer
 HPPWD Kangra
 DIVISION KANGRA

SCHEDULE OF QUANTITY

NAME OF WORK:-BALANCE WORK OF GOVT. DEGREE COLLEGE AT MATOUR TEHSIL AND DISTRICT KANGRA(SUB HEAD:- PROVIDING AND FIXING STAINLESS STEEL RAILING IN ENTRANCE PORTION						
Sr. No	Description of work	Qty	Unit	Rates		AMOUNT
				In Figures	In Words	
						One Month
1	Providing and fixing stainless steel Knock down railing of KICH AISI Grade 316 of 38 mm (Thirty eight millimetres) diameters hand rail fixed on 10x50mm (ten into fifty millimetres) SS flats baluster (design code DT 53-2-163) placed at 1200mm(one thousand two hundred millimetres) centre to centre along with 3(Three) numbers at the rate of 16mm (Sixteen millimetres) mild rails connected at the side of balustered would be fixed on the floor with casted based plate minimum 6mm (Six millimetre) thickness based plates shall be consealed with suitable S.S.316 GRADE covered cap railing height to be taken at the rate of 85cm (Eighty five centimetres) from floor level, with in all leads. lifts of materials and other incidentals, as pefr approved drawing, design and as directed by the engineer-in Charge,leads, The rate including octroi, royalty, toll tax, sale tax or other taxes imposed by the Government.	35.92	Per Running Metres	2783.50	Rupees Two Thousand Seven Hundred & Eighty Three - Paise Fifty Only	99983.00
		Total:				99983.00

EXCESS = %

LESS = %


 Executive Engineer,
 HPPWD Kangra
 Division Kangra.

SCHEDULE OF QUANTITY


Name of work :- Additional work for the Construction of Tarnsgender Toilet in Judicial Complex at Kangra. (Sh:- Construction of toilet block)

Sr.N o.	Sub-Head and items of work	Quantity	Unit	Estimate cost-		Amount
				Figures	Words	
				Earnest money- Time limit-		One month.
1	Earth work in excavation by mechanical means (Hydraulic excavator/manual means over areas exceeding 30cm depth, 1.5m width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50m and lift upto 1.5m, as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental.	2.71	Per cubic metre	489.20	Rupees Four Hundred & Eighty Nine - Paise Twenty Only	1326.00
2	Random rubble masonry/polygonal rubble masonry (Uncoursed/brought to courses) with hard stone of approved quality in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 Sand : 12 Graded stone aggregate 20mm nominal size) in cement mortar 1:6 (1 cement:6 sand) in breast walls and retaining wall as per the direction of Engineer-in-charge including carriage of material within all leads, lifts of materials and other incidentals. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	3.88	Per cubic metre	4200.00	Rupees Four Thousand Two Hundred Only	16296.00
3	Filling in plinth with sand under floors including watering, ramming, consolidating and dressing complete as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental as per the direction of Engineer-in-charge including carriage of material within all leads, lifts of materials and other incidentals. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	1.25	Per cubic metre	1428.00	Rupees One Thousand Four Hundred & Twenty Eight Only	1785.00
4 (i)	Centering and shuttering including strutting, propping etc. and removal of form for : Lintels, beams, plinth beams, girders, bressomers and cantilevers within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	14.56	Per Sqm	387.15	Rupees Three Hundred & Eighty Seven - Paise Fifteen Only	5637.00

4 (ii)	Centering and shuttering including strutting, propping etc. and removal of form for : suspended floors, roofs, landings, balconies and access platform within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	12.97	Per Sqm	468.30	Rupees Four Hundred & Sixty Eight - Paise Thirty Only	6074.00
5	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size) within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	2.98	Per cubic metre	7450.85	Rupees Seven Thousand Four Hundred & Fifty - Paise Eighty Five Only	22204.00
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level Thermo-Mechanically treated bars of grade Fe-500D or more within all leads, lifts of materials and other incidentals. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	358.79	Per Kg	94.00	Rupees Ninety Four Only	33726.00
7	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required within all leads, lifts of materials and other incidentals. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	1.00	Each	8251.20	Rupees Eight Thousand Two Hundred & Fifty One - Paise Twenty Only	8251.00
8	Providing and fixing stone slab with table rubbed, edges rounded and polished, of size 75x50 cm deep and 1.8 cm thick, fixed in urinal partitions by cutting a chase of appropriate width with chase cutter and embedding the stone in the chase with epoxy grout or with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 6 mm nominal size) as per direction of Engineer-in-charge and finished smooth within all leads, lifts of materials and other incidentals. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	0.09	Per Sqm	3216.9	Rupees Three Thousand Two Hundred & Sixteen - Paise Ninety Only	290.00

9	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank complete in all respect within all leads, lifts of materials and other incidentals. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	500	Per/ Liter	8.80 Rupees Eight - Paise Eighty Only	4400.00
TOTAL					99989.00

ESCESS = %
LESS = %


 Executive Engineer
 HP.PWD. Division
 Kangra Division

SCHEDULE OF QUANTITY

NAME OF WORK : Repair and Restoration on various roads under HP.PWD Sub Division Kangra (SH: - Maintenance of earthen shoulder , Bush cutting, C/O unlined drain surface etc.)					Estimated Cost:-	97506.00
					Earnest Money:-	2000.00
					Time Limit:-	One Month
Sr. No.	Description of work	Qty	Unit	Rates		AMOUNT
				In Figures	In Words	
1	Maintenance of Earthen shoulder (filling with fresh selected soil) making up lose of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any leads as per technical specification clause 1903. The rate is inclusive for carriage of material within all leads, lifts and other incidentals.	1080.00	Per Square meter	46.75	Rupees Forty Six - Paise Seventy Five Only	50490.00
2	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, shrubs, samplings and trees of girth upto 300mm, removal of stumps of such trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used of auctioned, upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150 mm in thickness as per Technical Specification Claus 201 by manual means in area of non- thorny jungle.	2100.00	Per Square meter	7.70	Rupees Seven - Paise Seventy Only	16170.00
3	Construction of unlined surface drains of average cross sectional area 0.40 sqm in soil to specified lines grades levels and dimensions. Excavated material to be used in embankment within all leads and lifts as per technical specifications clause 307 manual means, as per teh direction of the Engineer-in- Charge including carriage of material within all leads, lifts and other incidentals. The rate including of octroi, royalty , Malkana, toll tax, sale tax or other taxes imposed by teh Government.	118.00	Per Running meter	102.76	Rupees One Hundred & Two - Paise Seventy Six Only	12126.00
4	Cutting of branches of trees and shrubs from the road way or within R.O.W. including disposal of wood and leaves to suitable location as per technical specifications clause 1914. The rate is inclusive for carriage of material within all leads, lifts and other incidental	240.00	Each	78.00	Rupees Seventy Eight Only	18720.00
		Total:				97506.00

EXCESS=	0%
LESS=	0%


 Executive Engineer,
 HPPWD Kangra
 Division Kangra.

SCHEDULE OF QUANTITY


NAME OF WORK :- CONSTRUCTION OF PUCCA PATH TO THE HOUSE OF SH. OM PARKASH SONI WARD NO -1
AT JOGIPUR (SUB HEAD:- CONSTRUCTION OF PATH, (DEPOSIT WORK)

Sr. No.	DESCRIPTION OF ITEM	QTY.	UNIT	RATES		Estimated Cost:- Earnest Money:- 2000/-	Two Month AMOUNT
				In Figures	In Words		
1	Providing and laying 60mm (Sixty millimetre) thick NTC interlocking blocks heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50 (M-fifty) grade i.e. border or kurb black grey or coloured over sub base of concrete with 25mm (Twenty five millimetre) thick average thickness of cement mortar 1:4 (One cement isto Four sand) laid over join ted with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing of polishing complete (sub base concrete floor to be paid for separately) as directed by the Engineer- In-charge, within all leads, lifts of materials and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	94.00	Per Square metres	1054.55	Rupees One Thousand & Fifty Four - Paise Fifty Five Only	99128.00	99128.00
				TOTAL		99128.00	99128.00

BMT checked and approved for Rs. 99,128/- only

EXCESS= %

LESS = %


 Executive Engineer
 HPPWD Kangra
 Division Kangra

SCHEDULE OF QUANTITY

NAME OF WORK:-BALANCE WORK OF GOVT. DEGREE COLLEGE AT MATOUR TEHSIL AND DISTRICT KANGRA(SUB HEAD:- PROVIDING AND FIXING STAINLESS STEEL RAILING IN BLOCK- 1 1ST FLOOR TO THIRD FLOOR BLOCK-2 FIRST FLOOR TO SECOND FLOOR.					Estimated Cost:- Earnest Money:- Time Limit:-	99983.00 2000/- One Month
Sr. No	Description of work	Qty	Unit	Rates		AMOUNT
				In Figures	In Words	
1	Providing and fixing stainless steel knock down railing of KICH AISI Grade 316 of 38 mm (Thirty eight millimetres) diameters hand rail fixed on 10x50mm (ten into fifty millimetres) SS flats baluster (design code DT 53-2-163) placed at 1200mm(one thousand two hundred millimetres) centre to centre along with 3(Three) numbers at the rate of 16mm (Sixteen millimetres) mild rails connected at the side of baluster would be fixed on the floor with casted based plate minimum 6mm (Six millimetre) thickness based plates shall be consealed with suitable S.S.316 GRADE covered cap railing height to be taken at the rate of 85cm (Eighty five centimetres) from floor level, with in all leads, lifts of materials and other incidentals, as per approved drawing, design and as directed by the engineer-in Charge. leads, The rate including octroi, royalty, toll tax, sale tax or other taxes imposed by the Government.	35.92	Per Running Metres	2783.50	Rupees Two Thousand Seven Hundred & Eighty Three - Paise Fifty Only	99983.00
		Total:				99983.00

EXCESS = %

LESS = %


 Executive Engineer,
 HPPWD Kangra
 Division Kangra.

SCHEDULE OF QUANTITY

NAME OF WORK:- Construction of Crate wire wall work to Approach road Near to Kohala to Nagni Mata Mandir in Ghurkari Beat of Ghurkari . Composite					Estimate cost-	
					Earnest money-	2000.00
					Time limit-	One month.
Sr.No.	Sub-Head and items of work	Quantity	Unit	Figures	Rates in Words	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling, wedging out rockst(where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per direction of the Engineer -in-Charge including setting out construction of shorting and bracing, removal of stupms and other delerious materials and disposal of materials upto any lead and upto any lift including dressing os sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shorting and strutting and pumping and bailing out water(surface and sub soil water) upto any depths and any quantam of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-charge including carriage of material within all leads, and lifts and other incidental	14.72	Per cubic metre	489.20	Rupees Four Hundred & Eighty Nine - Paise Twenty Only	7201.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as per the entire satisfaction and direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi royalty Malkhana toll tax sale tax or other taxes imposed by the Government	21.46	Per cubic metre	3190.15	Rupees Three Thousand One Hundred & Ninety - Paise Fifteen Only	68461.00