



HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer National Highway Division HPPWD Theog.

Email: eeenh-theog-hp@gov.in Phone/ Fax No.: 01783-238900

NO.PW.THG/CB/TENDER/Tender Notice/2024 1410-12
To


Dated:- 25/6/2025

The Executive Engineer,(IT)
Nigam Vihar Shimla 2

Subject:- Publication of tender Notice.


Enclose please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on department website as per Notification Pr. Secy. (PW)) to the Govt. of HP letter No PBW(B)A(3)1/2024 dated 03.01.2024 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl:- Schedule of Quantity.


Executive Engineer,
NH Division,
H.P.P.W.D., Theog

Copy forwarded to the Superintending Engineer NH Circle Shimla HP PWD for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer(IT) Cell), Nigam Vihar Shimla-2 for information and further necessary action please.


Executive Engineer,
NH Division,
H.P.P.W.D., Theog

Himachal Pradesh
Public Works Department
Notice Inviting Tender

Sealed Percent rates tender form No 7 & 8 are hereby invited by the Executive Engineer NH Division HP PWD Theog for the following works on behalf of the Governor of Himachal Pradesh from the eligible contractors enlisted in HP PWD so as to reach in this office as per time schedule Given below:-

- | | | |
|---|---|--------------------------|
| 1 | Date of receipt of Applications for tender forms: | 01.07.2025 upto 12:00 PM |
| 2 | Date of issue/sale of Tender forms:- | 02.07.2025 upto 4:00 PM |
| 3 | Date of receipt of Tender:- | 03.07.2025 upto 10:30 AM |
| 4 | Date of opening of Tender | 03.07.2025 upto 11:00 AM |


Sr. No	Job No.	Name of Works	Estimated Cost	Earnest Money	Cost of form	Time Period for completion
1	1	O/R. on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/000 (SH:- Hiring of JCB Excavator Cum loader for removal of slips & maintenance of earthen shoulder at various R.D 18/00 to 20/00).	99000/-	2000	350/-	3 Months
2	2	O/R. on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/000 (SH:- Hiring of JCB Excavator Cum loader for removal of slips & maintenance of earthen shoulder at various R.D 20/00 to 25/00).	99000/-	2000	350/-	3 Months
3	3	R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- Hiring of Tipper for carriage of muck at RD 18/000 to 20/00)	98800/-	2000	350/-	3 Month
4	4	R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- Hiring of Tipper for carriage of muck at RD 20/000 to 25/00)	98800/-	2000	350/-	3 Months
5	5	R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- (SH:- Hiring of JCB Excavator Cum loader for removal of slips & maintenance of earthen shoulder at R.D 0/00 to 17/000).	99000/-	2000	350/-	3 Months
6	6	R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- Hiring of Tipper for carriage of muck at RD 0/000 to 17/00)	98800/-	2000	350/-	3 Months
7	7	R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- (SH:- Hiring of JCB Excavator Cum loader for removal of slips & maintenance of earthen shoulder at R.D 17/000 to 30/000).	99000/-	2000	350/-	3 Months
8	8	R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- Hiring of Tipper for carriage of muck at RD 17/000 to 30/00)	98800/-	2000	350/-	3 Months

9	9	R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- Hiring of JCB Excavator Cum loader for removal of slips & maintenance of earthen shoulder at R.D 30/000 to 48/000).	99000/-	2000	350/-	3 Months
10	10	R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- Hiring of Tipper for carriage of muck at RD 30/000 to 48/00)	98800/-	2000	350/-	2 Months
11	11	R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- (SH:- Hiring of JCB Excavator Cum loader for removal of slips & maintenance of earthen shoulder at R.D 48/000 to 60/000).	99000/-	2000	350/-	3 Month
12	12	R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- Hiring of Tipper for carriage of muck at RD 48/000 to 60/00)	98800/-	2000	350/-	3 Months
13	13	R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- (SH:- Hiring of JCB Excavator Cum loader for removal of slips & maintenance of earthen shoulder at R.D 60/000 to 69/000).	99000/-	2000	350/-	3 Months
14	14	O/R. on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/000.(SH:C/o R/wall in PCC M15 at R.D. 5/486 to 5/487.50	99371/-	2000	350/-	3 Months
15	15	O/R. on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/000.(SH:C/o R/wall in PCC M15 at R.D. 5/487.50 to 5/488	99371/-	2000	350/-	3 Months

Terms & Conditions:- The tender documents shall be issued to those contractors/firms who fulfill the following documents with the application:

- 1 The valid enlistment/ registration of contractor in appropriate class.
- 2 Permanent Account Number(PAN)
- 3 GST Number and EPF No.
- 4 Earnest Money in the shape of National saving certificate/Time deposit account in any of the Post office in HP FDR from Tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & Cost tender form shall summarily be rejected.
- 5 Ambiguous/telegraphic/Conditional tender of tender by fax/ E-mail shall not be entertained/considered and will summarily be rejected.
- 6 Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.
- 7 The offer of the tender shall remain valid upto 120 days after the opening of tender.
- 8 If the date given above happens to be a holiday, the same shall be processed on next working days.
- 9 The Contractors/firm must quote their rates in words as well as in figures failing which Xen reserves the right to accept/reject any or all tenders.
- 10 The Tender form will not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed/completed the previous awarded works within the stipulated period of completion.
- 11 One Contractor should not have more than two works in hand at a time.

12 Works should be completed by the contractor within the stipulated period.



Executive Engineer,
NH Division,
H.P.P.W.D., Theog

Dated 25/01/2025

No/PW/NH/CB/Tender/2024 1401-9

Copy forwarded for information and necessary actions to:

- 1 The Engineer-in Chief HP PWD Nigam Vihar Shimla
- 2 The Chief Engineer, NH HP PWD Shimla 2
- 3 The Superintending Engineer NH Circle HP PWD Shimla .
- 4 All the Assistant Engineer working under this Division
- 5 The Drawing Branch/Account Branch in this office.
- 6 Notice Board.


Executive Engineer,
NH Division,
H.P.P.W.D., Theog


SCHEDULE OF QUANTITY

				Estimated Cost:	Rs -	99000.00
				Earnest Money	Rs:-	2000
				Time.	2 Month.	
Name of work :- R/R Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/000 (SH:- Hiring of JCB Excavator Cum loader for removal of slips & maintenance of earthen shoulder at R.D 18/00 to 28/00).						
Sr. No	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Hiring of Excavator cum loader for removal of slips for smooth flow of traffic in snow bound area with a minimum capacity of 250.00 cum of snow and 45.00 cum of slips i/c per day of oprator POL chrges. Maintenance of any minor and major accident and other damage to private and govt. property is the hole responsablity of the contractor. The work shall be executed as per Morth specification and as per the direction of Engineer -In-Charge.	90	hour	1100.00	Rupees one thousand one hundred only	99000.00
Total						99000.00
(Quoted Rates in Figures)(+/-)				(.....%)		
(Quoted Rates in words)(+/-)				(.....%)		


 Executive Engineer,
 NH Division HPPWD,
 Theog-


SCHEDULE OF QUANTITY

				Estimated Rs:- Cost:		99000.00
				Earnest Rs:- Money		2000
				Time.		2 Month.
Name of work :- R/R Damages on Theog Kotkhayi Hatkoti road NH-705 k.m. 0/000 to 69/000 (SH:- Hiring of JCB Excavator Cum loader for removal of slips & maintenance of earthen shoulder at R.D 20/00 to 25/00).						
Sr. No	Description of item	Quantity	Unit.	Rate		Amount
1	Hiring of Excavator cum loader for removal of slips for smooth flow of traffic in snow bound area with a minimum capacity of 250.00 cum of snow and 45.00 cum of slips i/c per day of oprator POL chrges. Maintenance of any minor and major accident and other damage to private and govt. property is the hole responsibility of the contractor. The work shall be executed as per Morth specification and as per the direction of Engineer -In-Charge.	90	hour	In figure	In words	
	Total			1100.00	Rupees one thousand one hundred only	99000.00
						99000.00
		(Quoted Rates in Figures)(+/ -)				(.....%)
		(Quoted Rates in words)(+/ -)				(.....%)


 Executive Engineer,
 NH Division HPPWD,
 Theog.

SCHEDULE OF QUANTITY

				Estimated Cost: Rs:-	98800.00	
				Earnest Money Rs:-	2000	
				Time. 3 Month.		
Name of work :- R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- Hiring of Tipper for carriage of muck at RD 18/000 to 20/00)						
Sr. No.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Hiring of tipper for carriage of material have in capacity 200 cft including P.O.L Charges shifting charges and other ancilliary equipment as required at site of the work shell have to carride out as per ministry of transport specification including all lead and lift as per the direction by the Engineer-in-charge.	19	Days	5200	Rupees Five Thousand Two Hundred Only	98800
	Total					98800
				(Quoted Rates in Figures)(+/-)		(.....%)
				(Quoted Rates in words)(+/-)		


Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

		Estimated Cost:	Rs:-	98800.00		
		Earnest Money	Rs:-	2000		
		Time.	3 Month.			
Name of work :- R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- Hiring of Tipper for carriage of muck at RD 25/000 to 25/00)						
Sr. No.	Description of item	Quantity	Unit.	Rate	Amount	
1	Hiring of tipper for carriage of material have in capacity 200 cft including P.O.L Charges shifting charges and other ancilliary equipment as required at site of the work shell have to carride out as per ministry of transport specification including all lead and lift as per the direction by the Engineer-in-charge.	19	Days	In figure	In words	98800
				5200	Rupees Five Thousand Two Hundred Only	
	Total					98800
		(Quoted Rates in Figures)(+/-)		(.....%)		
		(Quoted Rates in words)(+/-)				



 Executive Engineer,
 NH Division HPPWD,
 Theog.

SCHEDULE OF QUANTITY

Estimated Rs. -	99000.00
Cost:	
Earnest Rs:-	2000
Money	
Time. 3 Month.	

Name of work :- R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- (SH:- Hiring of JCB Excavator Cum loader for removal of slips & maintenance of earthen shoulder at R.D 0/000 to 17/000).

Sr. No	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Hiring of Excavator cum loader for removal of slips for smooth flow of traffic in snow bound area with a minimum capacity of 250.00 cum of snow and 45.00 cum of slips i/c per day of oprator POL chrges. Maintenance of any minor and major accident and other damage to private and govt. property is the hole responsibility of the contractor. The work shall be executed as per Morth specification and as per the direction of Engineer -In-Charge.	90	hour	1100.00	Rupees one thousand one hundred only	99000.00
	Total					99000.00
	(Quoted Rates in Figures)(+/-)			(.....%)		
	(Quoted Rates in words)(+/-)			(.....%)		


Executive Engineer,
NH Division HPPWD,
Theog.


SCHEDULE OF QUANTITY

98800.00

Estimated Cost:	Rs:-	98800.00
Earnest Money	Rs:-	2000
Time.	3 Month.	

Name of work :- R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- Hiring of Tipper for carriage of muck at RD 0/000 to 17/00)

Sr. No.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Hiring of tipper for carriage of material have in capacity 200 cft including P.O.L Charges shifting charges and other ancilliary equipment as required at site of the work shell have to caride out as per ministry of transport specification including all lead and lift as per the direction by the Engineer-in-charge.	19	Days	5200	Rupees Five Thousand Two Hundred Only	98800
	Total					98800
	(Quoted Rates in Figures)(+/-)		(.....%)			
	(Quoted Rates in words)(+/-)					



Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

			Estimated Rs:-	99000.00
			Cost:	
			Earnest Rs:-	2000
			Money	
			Time.	3 Month.

Name of work :- R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- (SH:- Hiring of JCB Excavator Cum loader for removal of slips & maintenance of earthen shoulder at R.D 17/000 to 30/000).

Sr. No	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Hiring of Excavator cum loader for removal of slips for smooth flow of traffic in snow bound area with a minimum capacity of 250.00 cum of snow and 45.00 cum of slips i/c per day of oprator POL chrges. Maintenance of any minor and major accident and other damage to private and govt. property is the hole responsibility of the contractor. The work shall be executed as per Morth specification and as per the direction of Engineer -In-Charge.	90	hour	1100.00	Rupees one thousand one hundred only	99000.00
	Total					99000.00
				(Quoted Rates in Figures)(+/-)	(.....%)	
				(Quoted Rates in words)(+/-)	(.....%)	


Executive Engineer,
NH Division HPPWD,
Theog.


SCHEDULE OF QUANTITY

Incent on

Estimated Cost:	Rs:-	98800.00
Earnest Money	Rs:-	2000
Time.	3 Month.	

Name of work :- R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- Hiring of Tipper for carriage of muck at RD 17/000 to 30/00)


Sr. No.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Hiring of tipper for carriage of material have in capacity 200 cft including P.O.L Charges shifting charges and other ancilliary equipment as required at site of the work shell have to carrie out as per ministry of transport specification including all lead and lift as per the direction by the Engineer-in-charge.	19	Days	5200	Rupees Five Thousand Two Hundred Only	98800
Total						98800
(Quoted Rates in Figures)(+/ -)				(.....%)		
(Quoted Rates in words)(+/ -)						


 Executive Engineer,
 NH Division HPPWD,
 Theog.

SCHEDULE OF QUANTITY

Name of work :- R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- Hiring of JCB Excavator Cum loader for removal of slips & maintenance of earthen shoulder at R.D 30/000 to 48/000).

Sr. No	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Hiring of Excavator cum loader for removal of slips for smooth flow of traffic in snow bound area with a minimum capacity of 250.00 cum of snow and 45.00 cum of slips i/c per day of oprator POL chrges. Maintenance of any minor and major accident and other damage to private and govt. property is the hole responsablity of the contractor. The work shall be executed as per Morth specification and as per the direction of Engineer -In-Charge.	90	hour	1100.00	Rupees one thousand one hundred only	99000.00
	Total					99000.00
	(Quoted Rates in Figures)(+/-)				(.....%)	
	(Quoted Rates in words)(+/-)				(.....%)	


Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

				Estimated Cost:	Rs:-	98800.00
				Earnest Money	Rs:-	2000
				Time.	3 Month.	
Name of work :- R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- Hiring of Tipper for carriage of muck at RD 30/000 to 48/00)						
Sr. No.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Hiring of tipper for carriage of material have in capacity 200 cft including P.O.L Charges shifting charges and other ancilliary equipment as required at site of the work shell have to carride out as per ministry of transport specification including all lead and lift as per the direction by the Engineer-in-charge.	19	Days	5200	Rupees Five Thousand Two Hundred Only	98800
	Total					98800
				(Quoted Rates in Figures)(+/-)	(.....%)	
				(Quoted Rates in words)(+/-)		



 Executive Engineer,
 NH Division HPPWD,
 Theog.

SCHEDULE OF QUANTITY

			Estimated Rs:-	99000.00
			Cost:	
			Earnest Rs:-	2000
			Money	
			Time. 2 Month.	

Name of work :- R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- (SH:- Hiring of JCB Excavator Cum loader for removal of slips & maintenance of earthen shoulder at R.D 48/000 to 60/000).

Sr. No	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Hiring of Excavator cum loader for removal of slips for smooth flow of traffic in snow bound area with a minimum capacity of 250.00 cum of snow and 45.00 cum of slips i/c per day of oprator POL chrges. Maintenance of any minor and major accident and other damage to private and govt. property is the hole responsibility of the contractor. The work shall be executed as per Morth specification and as per the direction of Engineer -In-Charge.	90	hour	1100.00	Rupees one thousand one hundred only	99000.00
	Total					99000.00
				(Quoted Rates in Figures)(+/-)	(.....%)	
				(Quoted Rates in words)(+/-)	(.....%)	


Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

98800.00


Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

Estimated Rs.- Cost:	99000.00
Earnest Rs.- Money	2000
Time.	2 Month.

Name of work :- R/R. Damages on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- (SH:- Hiring of JCB Excavator Cum loader for removal of slips & maintenance of earthen shoulder at R.D 60/000 to 69/000).

Sr. No	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Hiring of Excavator cum loader for removal of slips for smooth flow of traffic in snow bound area with a minimum capacity of 250.00 cum of snow and 45.00 cum of slips i/c per day of oprator POL chrges. Maintenance of any minor and major accident and other damage to private and govt. property is the hole responsibility of the contractor. The work shall be executed as per Morth specification and as per the direction of Engineer -In-Charge.	90	hour	1100.00	Rupees one thousand one hundred only	99000.00
	Total					99000.00
				(Quoted Rates in Figures)/(+/-)	(.....%)	
				(Quoted Rates in words)/(+/-)	(.....%)	


Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

				Estimated Cost:		99371
				Earnest Money		2000
				Time. 3 Month.		
Name of work :- O/R. on Theog Kotkhaiy Hatkoti road NH-705 k.m. 0/000 to 69/000.(SH:C/o B/wall in PCC M15 at R.D. 5/486.00 to 5/487.50)						
Sr. No	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Excavation in cutting for roadwork in soil with hydraulic excavator including cutting and loading in a tipper ,trimming bottom and side slopes, in accordance with requirement of lines, grades and cross sections and transporting to the embankment site with in all lifts and leads as per Drawing and Specification. . Any loss to public /private poperty during course of excavation shall be the whole the direction by the Engineer-in-charge.	3.39	Per Cum.	176.10	Rupees One Hundred Seventy Six and Paise Ten Only	597.00
2	Excavation for Structures .Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing ,removal of slumps and other deleterious matter ,dressing of sides and bottom , back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	3.34	Per Cum.	325.3	Rupees Three Hundred Twenty Five and Paise Thirty Only	1087.00
3	Providing and laying Plain Cement Concrete in M15 Grade in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100 , in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	12.1	Per Cum.	7600.00	Rupees Seven Thousand Six Hundred Only	92112.00
3	Providing and layingof filter mdia with granular material/stone crushed aggregate satisfying the requirements laid down in clause 2504.2.2 of MoRTH specifications to a thickness of not less than 600 mm (six hundred millimetre) with smaller size towards the soil and bigger size towards the wall and provided over the entire surface behind retaining walls abutment , wing wall and return walls to the full height compacted to a firm condition complete as per drawing and technical Specification, as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport etc.	2.11	Per Cum.	2282.80	Rupees Two Thousand Two Hundred Eighty Two and Paise Eighty Only	4817.00
5	Providing weep holes in Brick masonry/plain /reinforced concrete abutment,wing wall/return wall with 100 mm dia.AC pipe extending through the full width of the structure with slop of IV : 20 H towards drawing complete as per drawing and Technical Specifications and as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport etc.	3.0	Nos	252.70	Rupees Two Hundred Fifty Two and Paise Seventy Only	758.00
Total						99371.00
		(Quoted Rates in Figures)(+-)		(.....%)		
		(Quoted Rates in words)(+-)		(.....%)		

Executive Engineer
NH Division HPPWD
Theog

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY

Estimated Cost:

99371

Earnest Money

2000

Time. 3 Month.

Name of work :- O/R. on Theog Kotkhaiy Hatkoti road NH-705 k.m. 0/000 to 69/000.(SH:C/o B/wall in PCC M15 at R.D. 5/487.50 to 5/488.00)

Sr. No

Description of item

Quantity

Unit.

Rate

In figure

In words

Amount

1

Excavation in cutting for roadwork in soil with hydraulic excavator including cutting and loading in a tipper ,trimming bottom and side slopes, in accordance with requirement of lines, grades and cross sections and transporting to the embankment site with in all lifts and leads as per Drawing and Specification. . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials by all modes of transportation as per the direction by the Engineer-in-charge.

3.39

Per Cum.

176.10

Rupees One Hundred Seventy Six and Paise Ten Only

597.00

2

Excavation for Structures .Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing ,removal of slumps and other deleterious matter ,dressing of sides and bottom , back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.

3.34

Per Cum.

325.3

Rupees Three Hundred Twenty Five and Paise Thirty Only

1087.00

3

Providing and laying Plain Cement Concrete in M15 Grade in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100 , in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.

12.1

Per Cum.

7600.00

Rupees Seven Thousand Six Hundred Only

92112.00

3

Providing and layingof filter mdia with granular material/stone crushed aggregate satisfying the requirements laid down in clause 2504.2.2 of MoRTH specifications to a thickness of not less than 600 mm (six hundred millimetre) with smailer size towards the soil and bigger size towards the wall and provided over the entire surface behind retaining walls abutment , wing wall and return walls to the full hoiight compacted to a firm condition complete as per drawing and technical Specification, as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport etc.

2.11

Per Cum.

2282.80

Rupees Two Thousand Two Hundred Eighty Two and Paise Eighty Only

4817.00

5

Providing weep holes in Brick masonry/plain /reinforced concrete abutment,wing wall/return wall with 100 mm dia.AC pipe extending through the full width of the structure with slop of IV : 20 H towards drawing complete as per drawing and Technical Specifications and as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport etc.

3.0

Nos

252.70

Rupees Two Hundred Fifty Two and Paise Seventy Only

758.00

Total


99371.00

(Quoted Rates in Figures)(+-)

(.....%)

(Quoted Rates in words)(+-)

(.....%)


 Executive Engineer
 NH Division HPPWD
 Theog