

**Himachal Pradesh
Public Works Department**

No. PWP/Agr. Asstt./Tender/2024-25/ 2365-70

Dated/2-6-2025

To

The Executive Engineer (IT Cell),
Nirman Bhawan Nigam Vihar Shimla-2.
Himachal Pradesh Shimla -2.

Subject:- Publication of Tender Notice.

Enclosed please find herewith the Tender notice of works as given in the Notice inviting Tenders alongwith Schedule of quantities for uploading on departmental website as per Notification Secretary (PW) to the Govt. of HP letter No. PBW(B) A (3) 1/2024 dated Shimla -03.01.2025

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in public interest.

DA/ Stated as above

Executive Engineer
Palampur Division
HPPWD Palampur

Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

- 1 The Superintending Engineer 5th Circle, HP.PWD Palampur.
2. The drawing branch in this office.
- 3 All Assistant Engineer working under this Division
4. Notice Board.

Executive Engineer
Palampur Division
HPPWD Palampur

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
'NOTICE INVITING TENDERS'**

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P for the following work from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before 18.06.2025 up to 11.00 AM. And the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on 17.06.2025 up to 4.00 P.M and the application for issue of tender form shall be received 16.06.2025 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S. No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	C/o Pulli on Kuhal near Shri Sonu Kumar House Ward No. 3 (SH:- C/o U-shape drain along with grating & CC Pavement (SDP Deposit)	Rs. 49,198.00	Rs. 1,000.00	Two Months
2	S/R of Nagri to Manimahesh via Bhasmehar Rakh Society road (SH:- P/L Interlocking Tiles at RD 3/725 to 3/736 (Deposit)	Rs. 49,951.00	Rs. 1,000.00	Two Months
3	C/o Jeepable road from Sh. Desh Raj House to Sh. Ashok Kumar S/o late Sh. Nathu Ram House Village Rathan Ward No. 2 Mohal (SW:- P/L CC Pavement road Km 0/000 to 0/032 (Deposit)	Rs. 98,681.00	Rs. 2,000.00	Three Months
4	C/o Pucca Path near the land of Sh. Hardu Ram Village Jhanjhanda GP Bandla Nachir (SW:- C/o Pucca Path & R/Wall (Deposit)	Rs. 99,788.00	Rs. 2,000.00	Three Months
5	C/o Retaining wall to Protect the land of Sh. Arun Awawthi Ward No. 5 G.P Bandla Nachhir (SW:- C/o Retaining Wall (Deposit)	Rs. 99,473.00	Rs. 2,000.00	Three Months
6	C/o Retaining Wall to Protect the land of Sh. Hans Raj S/o Sh. Lutia Ram VPO Bandla Nachhir (SW:- C/o Retaining wall (Deposit)	Rs. 74,600.00	Rs. 1,500.00	Three Months
7	C/o Path from Sh. Jagdish House to Sh. Ramesh Chand House Ward No. 4 Mohal G.P Lahla (SH:- P/L stone Soling and CC Pavement) (Deposit)	Rs. 74,168.00	Rs. 2,000.00	Two Months
8	Restoration of Rain damages on various roads under Gopalpur Sub-division (SH:- Breaking of stones at various roads)	Rs. 99,000.00	Rs. 2,000.00	Two Months
9	C/o Statue of Martyr Sh. Sanjay Kumar Statue at Chachian Tehsil Palampur Distt. Kangra (HP) (SW:- Providing and fixing cast Iron ornamental grill (Deposit)	Rs. 99,813.00	Rs. 2,000.00	Two Months
10	Repair and maintenance of link road to village Toran Km 0/000 to 1/500 (SH:- P/L G-III & Patch work at various RD from 0/000 to 0/066 (MMSRRY)	Rs. 96,784.00	Rs. 2,000.00	Three Months
11	Repair and maintenance of link road to village Toran Km 0/000 to 1/500 (SH:- P/L G-III & Patch work at various RD from 0/066 to 0/133 (MMSRRY)	Rs. 94,946.00	Rs. 1,900.00	Three Months

12	Restoration of damages on NH-154 near Veterinary College Palampur to Bharmat Upper Km 0/000 to 1/500 (SW:- P/L Interlocking Paver Block from RD 0/430 to 0/451)	Rs. 99,365.00	Rs. 2,000.00	Three Months
13	Restoration of damages on NH-154 near Veterinary College Palampur to Bharmat Upper Km 0/000 to 1/500 (SW:- P/L Interlocking Paver Block from RD 0/452 to 0/475)	Rs. 99,760.00	Rs. 2,000.00	Three Months
14	C/o road from main road to Sh. Chater Singh House via Magzi Ram cow shed ward No 1 GP Darati (SH:- P/L CC Pavement at RD 0/00 to 0/035 (Deposit)	Rs. 99,225.00	Rs. 2,000.00	Two Months
15	Completion of Ambedkar Bhawan Jia (SH:- Painting of 1 st Floor, covering of staircase & P/F of windows etc (VKVNY Deposit)	Rs. 98,598.00	Rs. 2,000.00	Two Months
16	A/R & M/O MDR -78 Brahmtheru to Garh Mata & Gujredha to Gujredha road (SH:- Painting of Steel board & Writing letters)	Rs. 99,972.00	Rs. 2,000.00	Two Months
17	A/R & M/O MDR-55 & Bhagotla Rajnali Dharer road (SH:- Painting of Steel board & writing letters)	Rs. 99,972.00	Rs. 2,000.00	Two Months
18	A/R & M/O Dharamshala Palampur Holta Chadiyar road at RD 29/000 to 30/500 (Under OFC Deposit) (SH:- Providing and fixing Double Shank pavement marker Cat Eyes at Zebra crossing at various RDs)	Rs. 98,750.00	Rs. 2,000.00	One Months
19	A/R & M/O Dharamshala Palampur Holta Chadiyar road at RD 30/500 to 31/500 (Under OFC Deposit) (SH:- Providing and fixing Double Shank pavement marker Cat Eyes at Zebra crossing)	Rs. 978,750.00	Rs. 2,000.00	One Months
20	C/o Jeepable road Patti alongwith R/Wall near to house of Sh. Pritam Chand & Ravi Kumar Sarsawa foot bridge towards & Dharaman road ward No. 7 (SW:- C/o R/Wall 1 st Pusta (Deposit)	Rs. 98,382.00	Rs. 2,000.00	Three Months
21	C/o Jeepable road Patti alongwith R/Wall near to house of Sh. Pritam Chand & Ravi Kumar Sarsawa foot bridge towards & Dharaman road ward No. 7 (SW:- C/o R/Wall 2 nd Pusta (Deposit)	Rs. 99,288.00	Rs. 2,000.00	Three Months

Terms & Conditions-

Following documents should accompany the application for tenders.

1. G.S.T. No.
2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years
8. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand . Next tender will be issued

only after completion of previous works in hand.


Executive Engineer
Palampur Division
HPPWD Palampur

SCHEDULE OF QUANTITY						
Name of work:- C/o Pulli on Kuhl near Sh. Sonu Kumar House Ward No. 3. (SH:- C/o U-shape drain alongwith grating & C.C. Pavement). (SDP Deposit 0.50 Lacs)				Estimated cost Rs.		49198.00
				Earnest Money Rs.		1000.00
				Time Limits		Two Months
Sr. No.	Description of Item	Quantity	In Figures	Rate		Amount
				In Word	Unit	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	2.94			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement : Three sand : Six graded crushed / broken stone aggregate 20 mm (twenty millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depts including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	6.79			Per cubic metre.	
3	Steel work welded in built up sections Trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	173.28			Per Kilogram	
	Total					

Executive Engineer,
Palampur Division
HP PWD Palampur.

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY							
Name of work:- S/R of Nagri to Manimahesh via Bhasmehar Rakh Society road. (SH:- P/L interlocking tiles at Rd 3/725 to 3/736).				Estimated cost Rs.		49951.00	
				Earnest Money Rs.		1000.00	
				Time Limits		Two Months	
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	37.40			Per square metre		
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.33			Per cubic metre.		
	Total						


 Executive Engineer
 Palampur Division
 HP.PWD Palampur

Schedule of Quantity

Name of Work :- C/O Jeepable road from Sh. Desh Raj house to Sh. Ashok Kumar S/O Late Sh. Nathu Ram house village Rathan
Ward No. 2 Mohal
(S.W. 1:- P/L CC Pavement road km 0/000 to 0/032 Deposit)

Work No. 3

Estimated Cost :- Rs. 99,681/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months

Sl. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, toll tax, sale tax or other taxes imposed by the Government.	6.69			Per Cubic metre.	
2	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203, including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	13.38			Per Cubic metre.	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work :- C/O Pucca path near the Land of Sh. Handu Ram village Jhanjhra GP Bandia Nachhir
(S. W. :- C/o Pucca Path & R/Wall (Deposit))

Work No. 4

Estimated Cost :- 99,788/-

Earnest Money :- 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	8.19	Cubic metre		Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	19.53	Cubic metre		Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the government.	7.00	Nos.		Each	
4	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government.	3.57	Cubic metre		Per Cubic metre	
5	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203. including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	1.46	Cubic metres		Per Cubic metre.	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

of Work :- C/O Retaining wall to protect the land of Sh. Arun Awasthi W. No. 5 G.P. Bandla Nachhir
W :- C/O Retaining wall (Deposit)

Work No. 5

Estimated Cost :- 99,473/-

Earnest Money :- 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	8.19	Cubic metre		Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	19.53	Cubic metre		Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204,307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	7.00	Numbers		Each	
4	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government.	3.57	Cubic metre		Per Cubic metre	
5	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203, includingthe cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	1.41	Cubic metres		Per Cubic metre.	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work :- C/O Retaining wall to protect the land of Sh. Hans Raj S/o Sh. Lulia Ram VPO Bandla Nachhir
(S. W. :- C/O Retaining wall (Deposit))

Work No. 2

Estimated Cost :- 74,600/-

Earnest Money :- 1500/-

Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	6.90			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	16.46			Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	7.00			Each	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o path from Sh. Jagdish House to Sh. Ramesh Chand House ward No. 4 Mohal (GP Lahla). (SH:-P/L stone soling and C.C. pavement). **Deposit 0.75 Lacs**

SCHEDULE OF QUANTITY							Estimated cost Rs.	74168.00	
Name of work:- C/o path from Sh. Jagdish House to Sh. Ramesh Chand House ward No. 4 Mohal (GP Lahla). (SH:-P/L stone soling and C.C. pavement). Deposit 0.75 Lacs							Earnest Money Rs.		2000.00
							Time Limits		Two Months
							Rate		Amount
Sr. No.	Description of Item	Quantity	Rate		Unit				
			In Figures	In Word					
1	Stone soling properly hand-packed filling interslices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour). The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	5.25			Per cubic metre				
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arriisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	14.44			Per cubic metre.				
Total									

Executive Engineer,
Palampur Division
HP.PWD Palampur.

8

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on various road under Gopalpur Sub Division. (SH:- Breaking of stones at Various Roads).

Estimated cost Rs.
Earnest Money Rs.

99000.00
2000.00

Sr. No.	Description of Item	Quantity	Time Limits		Unit	Amount
			In Figures	In Word		
1	Hiring of JCB (Breaker) including P.O.L charges shifting charges and other ancillary equipments as per required at site of work for breaking of rocks. The disposal of this un-servicable material has to be done in the acquired width of the road to avoid damages to the properties of the people or in case any damage took place, the contractor is liable for it. The work shall have to be carried out as per ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	34.00			Per hour	
2	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	500.00			Per Running metre	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Statue of Martyr Sh. Sanjay Kumar Statue at Chachian Tehsil Palampur Distt. Kangra H.P. (SH:- Providing and Fixing cast iron ornamental grill). **Deposit**

Name of work:- C/o Statue of Martyr Sh. Sanjay Kumar Statue at Chachian Tehsil Palampur Distt. Kangra H.P. (SH:- Providing and Fixing cast iron ornamantle grill). Deposit							Estimated cost Rs.	99813.00
							Earnest Money Rs.	2000.00
Sr. No.	Description of Item	Quantity	Rate		Unit	Two Months Amount		
			In Figures	In Word				
							Time Limits	
1	Providing and fixing cast iron ornamental grill (Anarkali Grill) or equivalent 90cm (36") high as per approved design and technical specification or as per direction of Engineer- In - Charge. The rate is inclusive for carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	514.50			Per Kilogram			
	Total							

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work :- Repair and Maintenance of Link Road to village Toran km.0/000 to 1/500

Estimate Cost :- Rs. 96,784/-
Earnest Money :-Rs. 2000/-

Sub Work :- P/L G-III & Patch work at various RD from 0/000 to 0/066 (MMSRRY)

Time Limit :- Three months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		Rupees
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm(twenty millimetres) thick pre-mix carpet and seal coat type B specification Clause 1904.2.503 and 508.1. including carriage of materials, within all leads, lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	264.50		Square metre	Per Square metre	
2	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	2.98		Cubic metres	Per Cubic metre.	
Total :-						

Executive Engineer,
Palampur Division,
HPPWD Palampur

Schedule of Quantity

Name of Work :- Repair and Maintenance of Link Road to village Toran Km. 0/000 to 1/500

0/066 to 0/133

Sub Work :- P/L G-III & Patch work at various RD from 0/750 to 1/500 (MMSRRY)

Estimate Cost :- Rs. 94,946/-
Earnest Money :- Rs. 1900/-
Time Limit :- Three months

S. No	Description of Item	Quantity		Rate		Unit	Amount Rupees
				In figure	In Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimetres) thick pre-mix carpet and seal coat type B specification Clause 1904.2.503 and 508.1. including carriage of materials, within all leads, lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	259.50	Square metre			Per Square metre	
2	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	2.92	Cubic metres			Per Cubic metre.	
Total :-							

[Signature]
Executive Engineer,
Palampur Division,
HPPW/D Palampur

Schedule of Quantity

Line of Work :- Restoration of damages on NH-154 near Veterinary College Palampur to Bharmat Upper Km. 0/000 to 1/500
(S. W. :- P/L Interlocking Paver block from RD 0/430 to 0/451 **o/c Dept**)

Work No. **12**

Estimated Cost :- Rs. 99,365/-

Earnest Money :- Rs. 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	3.00	Cubic metres			Per Cubic metre.	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	67.58	Square Metre			Per square metre	
3	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix ,P.C.C.grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802,803,1202 &1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	1.00	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

name of Work :- Restoration of damages on NH-154 near Veterinary College Palampur to Bharmat Upper Km. 0/000 to 1/500

(S. W. :- P/L interlocking Paver block from RD 0/452 to 0/475 ofc Deposit

Work No. 13

Estimated Cost :- Rs. 99,760/-

Earnest Money :- Rs. 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, Wearing 53 to 22.4mm (Fifty thee to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	3.00			Per Cubic metre.	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	67.89			Per square metre	
3	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix ,P.C.C.grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802,803,1202 &1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	1.00			Per Cubic metre	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY

Name of work:- C/o road from main road to Sh. Chater Singh house via Magzi Ram cow shed ward No. 1 G.P. Drati, (SH:- P/L C.C. Pavement at Rd 0/00 to 0/035). **Deposit 2.00 Lacs**

Sr. No.	Description of Item	Quantity	Rate		Unit	Two Months Amount
			In Figures	In Word		
			Time Limits			
			Estimated cost Rs.	Earnest Money Rs.		
1	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	15.75			Per cubic metre.	99225.00
	Total					2000.00

Executive Engineer
Palampur Division
HP, PWD Palampur

15

SCHEDULE OF QUANTITY

Name of work:- Completion of Ambedkar Bhawan Jia. (SH:- Painting of 1st floor, covering of staircase & P/F of windows etc.).

VK/VNY deposit 2.00 Lacs

Estimated cost Rs.

98598.00

Earnest Money Rs.

2000.00

Time Limits

Two Months

Sl. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	480.00			Per Kilogram	
2	Providing and Fixing 0.60 mm (zero point six zero millimetre) thick prepainted steel sheet of Tata / Sail in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester(RNP) organic coating of 20 (Twenty) microns over 5 (five) microns primer coating to back coat of polyester of 5(five) microns over 5 (five) microns primer coating i/c fixing with prepainted iron or J or L hooks.bolts and nuts 6mm dia meter with prepainted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.00			Per Square Metre	
3	Providing and fixing 35 mm thick Kiln seasoned and chemically treated hollock wood glazed shutters for doors, windows and clerestory windows using 4 mm thick float glass panes, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	3.12			Per square metre	
4	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to openings /wooden frames with rawl plugs screws etc. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	37.44			Per Kilogram me	
5	Providing and applying Birla white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	105.61			Per square metre	
6	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @ 0.75 ltr /10 sqm. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	184.33			Per Square Metre	
7	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	3.12			Per Square metre	
8	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm (zero point nine zero litre per ten square metre) over an under coat of primer applied @0.75 ltr/10 sqm (zero point seven five litre per ten square metre) of approved brand and manufacture. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.74			Per square metre	
9	Providing and fixing 150x10 mm ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	10.00			Each	
10	Providing and fixing 100 mm ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etc. complete : The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	6.00			Each	

15

11	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, 500 ltr capacity IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank. The rate is inclusive of octroi, royalty, malkana, GST and all type of other taxes imposed by the Government.	500.00			Per litre	
12	Providing and fixing 15 mm dia nominal bore (External work) G.I. pipes complete with G.I. fittings including trenching and refilling etc. The rate is inclusive of octroi, royalty, malkana, GST and all type of other taxes imposed by the Government.	8.00			Per Running Metre	
13	Providing and fixing 15 mm nominal bore C.P. brass bib cock of approved quality conforming to IS:8931 : including cartilage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-In-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1.00			Each	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur, Jm

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O MDR-78, Brahmtheru to Garh Mata & Gujredha to Gujredha road. (SH:- Painting of Steel board & writing letters)

Name of work:- A/R & M/O MDR-78, Brahmtheru to Garh Mata & Gujredha to Gujredha road. (SH:- Painting of Steel board & writing letters)				Estimated cost Rs.		99972.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Months
Sr No.	Description of item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	10.80			Per square metre	
2	Writing letters or figures on any surface with black japan paint (stops,comas,hyphens and the like not to be measured and paid separately) Indian(letters/figures) . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	45000.00			Per letter per cm. height	
	Total					

Executive Engineer
Palampur Division
HP PWD Palampur

17

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O MDR-55 & Bhagotla Rajnali Dharer road. (SH:- Painting of Steel board & writing letters).

Name of work:- A/R & M/O MDR-55 & Bhagotla Rajnali Dharer road, (SH:- Painting of Steel board & writing letters).							Estimated cost Rs.	99972.00			
							Earnest Money Rs.	2000.00			
							Time Limits				
Description of Item							Quantity	Rate		Unit	Amount
								In Figures	In Word		
1	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government						10.80			Per square metre	
2	Writing letters or figures on any surface with black japan paint (stops,comas,hyphens and the like not to be measured and paid separately) Indian(letters/figures) . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.						45000.00			Per letter per cm. height	
	Total										

Executive Engineer
Palampur Division
HP PWD Palampur

Draft Schedule of Quantity

Estimated Cost : Rs. 98,750/-
 Earnest Money : Rs. 2000/-
 Time limit : One Month.

Name of Work :- A/R & M/O Dharamshala Palampur Holta Chadhar road at RD 29/00 to 30/500 (Under OFC deposit)

Sub Work :- Providing and Fixing Double Shank pavement marker Cat Eyes at Zebra Crossing & various RDs

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing and Fixing pavement marker(cat Eyes)Made out of ABS 3M /Every or equivalent plastic of size 100x90x20mm (One hundred into Ninety into twenty millimetre) having high intensity 30 degree micro cube corner spark glow reflector White/Red/ yellow double shank Heavy duty without nails having 50 mm stem of ABS . The pavement marker shall be installed with suitable epoxy ABS including carriage.of material and equipment in all leads and lifts with all mode of transportation and as per the direction of Engineer-in-charge.	250.00 Nos.			Each	

~~Executive Engineer~~
 Palampur Division
 HP PWD Palampur

Draft Schedule of Quantity

Name of Work :- A/R & M/O Dharamshala Palampur Holta Chadhiar road at RD 30/500 to

31/500 (Under OFC deposit)

Sub Work :- Providing and Fixing Double Shank pavement marker Cat Eyes at Zebra

Crossing .

Estimated Cost : Rs. 98,750/-

Earnest Money : Rs. 2000/-

Time limit : One Month.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing and Fixing pavement marker(cat Eyes)Made out of ABS 3M /Every or equivalent plastic of size 100x90x20mm (One hundred into Ninety into twenty millimetre) having high intensity 30 degree micro cube corner spark glow reflector White/Red/ yellow double shank Heavy duty without nails having 50 mm stem of ABS . The pavement marker shall be installed with suitable epoxy ABS including carriage.of material and equipment in all leads and lifts with all mode of transportation and as per the direction of Engineer-in-charge.	250.00 Nos.			Each	

Executive Engineer

Palampur Division

HP PWD Palampur

Schedule of Quantity

Work No. 20

Name of Work :- C/O Jeepable road Path alongwith R/wall near to house of Sh. Pritam Chand & Ravi Kumar Sarsawa foot bridge towards & Dharman road No-76-38 Rs. 7.

Estimate Cost :-Rs.98,382/-

Earnest Money :-Rs. 2000/-

Time Limit :- Three Months

Sub Work :-C/O R/wall Deposit 1st Pusta (Deposit)

S. No	Description of Item	Quantity		Rate		Unit	Amount Rupees
				In figure	In Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	12.74	Cubic metres			Per Cubic metre.	
2	Providing and Laying concrete for plain/reinforced concrete in open foundations 1:5:10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete including the cost of form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; within all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	22.05	Cubic metre			Per Cubic metre	
Total :-							

Executive Engineer,
Palampur Division,
HPPWD Palampur

Schedule of Quantity

Name of Work :- C/O Jeepable road Path alongwith R/wall near to house of Sh. Pritam Chand & Ravi Kumar Sarsawa foot bridge towards & Dharaman road ~~near~~ road no. 7
Sub Work :-C/O R/wall Deposit 2nd Pusta (Deposit)

Work No. 21

Estimate Cost :-Rs.99,288/-

Earnest Money :-Rs. 2000/-

Time Limit :- Three Months

S. No	Description of Item	Quantity		Rate		Unit	Amount Rupees
				In figure	In Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	6.30	Cubic metres			Per Cubic metre.	
2	Providing and Laying concrete for plain/reinforced concrete in open foundations 1:5:10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete including the cost of form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; within all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	22.68	Cubic metre			Per Cubic metre	
	Total :-						

Executive Engineer,
Palampur Division,
HPPWD Palampur