

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed item rate / percentage rate tender are hereby invited on Form No. 6& B by the Executive Engineer, Bhoranj Division, HPPWD, Bhoranj on behalf of the Government of Himachal Pradesh for the following works from the approved and eligible contractors/ firms of appropriate class enlisted in HPPWD (B&R) whose registration stood registered under the H.P. General Sales tax Act, 1968. As per latest instructions so as to reach and open in his office as per time schedule given below. The offer of the tender will be kept open for 20 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of Applications for tender form a/w requisite documents:- 16-07-2025 upto 10.00 AM to 11:00 AM.)
2. Date of issue/Sale of tender forms against Cash payment (Non- refundable) 16-07-2025 (3:00 PM to 5.00 PM)
3. Date of receipt of Tender:- 18-07-2025 at 10.30 AM.
4. Date of opening of Tender:- 18-07-2025 at 11.30 AM.

Sr. No.	Name of Road	Estimated Cost	Earnest Money	Time	Cost of Tender Form	Eligible class of Contractor
1	A/R & M/O Una Aghar Mandi road Km 79/00 to 91/00 (SH:- C/O B/wall at RD 83/850 to 83/857.50)	98715/-	2000/-	Two Months	Rs. 350/-	Class-D
2	R/M of various roads under Bhoranj Section Bhoranj Sub Division (SH:- Maintenance of earthen shoulder, unlined surface drain and removal of slips)	99310/-	2000/-	Two Months	Rs. 350/-	Class-D
3	A/R & M/O Una Aghar Mandi road Km 79/00 to 91/00 (SH:- C/O B/wall at RD 83/857.50 to 83/865)	98715/-	2000/-	Two Months	Rs. 350/-	Class-D
4	R/M of various roads under Jahu Section Bhoranj Sub Division (SH:- Maintenance of earthen shoulder , unlined surface drain and removal of slips)	99310/-	2000/-	Two Months	Rs. 350/-	Class-D
5	R/M of Awahdevi Bagwara Gharan Dera Parol road km 0/00 to 9/750(SH:- Maintenance of earthen shoulder 4/410 to 4/785 and surface drain in km 3/610 to 3/870)	99905/-	2000/-	Two Months	Rs. 350/-	Class-D
6	R/M of Chamboli Dadu road Km 0/00 to 3/500 (SH:- Maintenance of earthen shoulder 0/285 to 0/660, unlined surface drain in Km. 0/285 to 0/545 and removal of slips)	99364/-	2000/-	Three Months	Rs. 350/-	Class-D
7	C/O link road Chhatrail to Lower Dadu	93069/-	2000/-	Three	Rs. 350/-	Class

	km 0/00 to 1/630 (SH:- Formation cutting 5/7 wide road km 1/285 to 1/360)			Months		
8	C/O link road Chhatral to Lower Dadu km 0/00 to 1/630 (SH:- Formation cutting 5/7 wide road km 1/425 to 1/480)	99500/-	2000/-	Three Months	Rs. 350/-	Class-D
9	R/M of various roads under Bhareri Section Bhoranj Sub Division (SH:- Maintenance of earthen shoulder, unlined surface drain and removal of slips)	99310/-	2000/-	Three Months	Rs. 350/-	Class-D
10	R/M on (i) Tikker to Manoh via Dhirwin road (ii) Kharwar to Mehal via Karah (iii) Blokhar to Bhola road (iv) Mair Pandwin to town Bharari road (SH:- Maintenance of earthen shoulder, unlined surface drain and removal of slip)	99,972/-	2000/-	Three Months	Rs. 350/-	Class-D
11	R/M (i) Thalotu to Ladrour via Khutrin road (ii) Patta Balet via Kotlu Balet via Kotlu (iii) Kharwar to Jakhyol via Dhamrola (iv) Ladrour to Lathwan road via Dasmain (v) Ladrour to Lathwan via Jangi Mahadev Mandir & UAM road (SH:- Maintenance of earthen shoulder , unlined surface drain and removal of slip)	99,607/-	2000/-	Three Months	Rs. 350/-	Class-D
12	R/M of various roads under Chamboh Section Samirpur Sub Division (SH:- Maintenance of earthen shoulder , unlined surface drain and removal of slip)	97,993/-	2000/-	Three Months	Rs. 350/-	Class-D
13	R/M of various roads under Dho Section Samirpur Sub Division) (SH:- Maintenance of earthen shoulder , unlined surface drain and removal of slip)	99600/-	2000/-	Three Months	Rs. 350/-	Class-D
14	R/M of various roads under Barin Section Samirpur Sub Division) (SH:- Maintenance of earthen shoulder , unlined surface drain and removal of slips)	98569/-	2000/-	Three Months	Rs. 350/-	Class-D
15	R/M on link road village Patta Kotlu Balet km. 0/00 to 2/00 (SH:- Providing & fixing 150 PVC pipe for drainage the road surface water at RD 0/370)	90247/-	2000/-	Three Months	Rs. 350/-	Class-D

The earnest money in the shape of National Saving Certificate/ Time Deposit/ saving account of any post office or FDR of Nationalized Bank duly pledged in the name of undersigned must be accompanied with each tender. The Conditional tender and tender not accompanying the earnest money in the proper mode of deposit with summarily be rejected.

The tender form will not be issued to those contractors who have already two works in hand. The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.

The conditional/ ambiguous/ telephonic tenders or tender by fax shall not entertain considered in any case.

(i) No Violation of social distancing.

(ii) Mandatorily wearing of face cover by everyone.

(iii) It is further added that any violation of the National directives & guidelines of containment of pandemic Covid-19 is liable for prosecution under section of IPC 1860.

Certified that the above work is of emergent nature in exigency of Public interest.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

For and on behalf of Governor of HP.

Dated:- 09-07-2025

No:-PW/BHD/TA/NIT/2024- 4175-4216

Copy forwarded for information & necessary action to:-

1. The Engineer-in-Chief, Nirman Bhawan Nigam Vihar, HP:PWD., Shimla.
2. The Chief Engineer (HZ) HPPWD., Hamirpur.
3. The Superintending Engineer, 8th Circle HPPWD, Hamirpur.
4. All the Superintending Engineers/ Executive Engineers in HP.PWD.
5. The Deputy Commissioner, Hamirpur.
6. The Tehsildar, Bhoranj.
7. The B. D. O. Bhoranj.
8. The Municipal Committee, Bhoranj.
9. All the Assistant Engineers working under this Division.
10. Accounts Branch/ Drawing Branch/ Notice Board.
11. LokMitra, Bhoranj.
12. Various Contractors/ Firms.

Executive Engineer,
Bhoranj Division,
HPPWD, Bhoranj

NAME OF WORK:- AIR & M/O Una- Aghar- Mandi road km.79/00 to 91/00 . (SH:- C/O B/Mail at RD 83/850 to 83/857.50.)

SCHEDULE OF QUANTITY

Estimated Cost Rs 98715/-
Earnest Money Rs. 2000/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	13.73	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size)) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	21.45	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimetre) dia PVC pipe De-plas/finolex/ vecus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (IV): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.00	Each			
	Total					
	Terms and Condition:-					

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:-R/M of Various roads under Borani Section Borani Sub-Division.
Job:- Maintenance of earthen shoulder , unlined surface drain and Removal of Slips.)

Estimated Cost
Earnest Money
Time

Rs. 99310/-
Rs. 2000/-
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularities on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	750.00	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed by the engineer in charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	400.00	Per Running Mtr.			
3	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slope and disposal of cut material with in lift upto 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302.3.5 and 1611 and as per direction of Engineer-in-Charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	200.00	Per cubic metre			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Borani Division
MP PWD Borani

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O Una- Aghar- Mandi road km.79/00 to 91/00 . (SH:- C/O B/Wall at RD 83/857.50 to 83/865.)

Estimated Cost
Earnest Money
Time
Rs 98715/-
Rs. 2000/-
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	13.73	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	21.45	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe De-plas/finolex/ vecus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204, 3.7 as per direction of Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.00	Each			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhorani Division
HPPWD Bhorani

SCHEDULE OF QUANTITY

AME OF WORK:- R/M of Various roads under Jahu Section Bhoranj Sub-Division.
SH:- Maintenance of earthen shoulder ,unlined surface drain and Removal of slip.)


Estimated Cost
 Earnest Money
 Time

Rs. 99310/-
 Rs. 2000/-
 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularation on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	750.00	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Excavated material to be used in embankments with a lift uo to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specifacation clause 307 as directed bythe engineer in charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	400.00	Per Running Mtr.			
3	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming og slope and disposal of cut material with in lift upto 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302.3.5 and 1611 and as per directon of Engineer-in-Charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	200.00	Per cubic metre			
Total						

Terms and Condition:-

1.Work shall be executed as per PWD specification.


 Executive Engineer
 Bhoranj Division
 H.P.W.D Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- R/M of Awahdevi Bagwara Gharan Dera Parol road km. 0/00 to 9/750.

SH:- Maintenance of earthen shoulder 4/410 to 4/785 and unlined surface drain in km. 3/610 to 3/870.)

Estimated Cost
Earnest Money
Time

Rs. 99905
Rs. 2000/-
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularation on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1106.25	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Exacavated material to be used in embankments with a lift uo to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specifacation clause 307 as directed bythe engineer in charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	260.00	Per Running Mtr.			
Total						

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- R/M of Chambah Dadu road km. 0/00 to 3/500.

Part:- Maintenance of earthen shoulder 0/285 to 0/650 , unlined surface drain in km. 0/285 to 0/545 and Removal of slip 1

Estimated Cost
Earnest Money
Time

Rs. 99364/-
Rs. 2000/-
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularities on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	800.00	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions. Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed by the engineer in charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	260.00	Per Running Mtr.			
3	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming og slope and disposal of cut material with in lift upto 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302.3.5 and 1611 and as per direction of Engineer-in-Charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	200.00	Per cubic metre			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
(in PWD Bhoranj)

SCHEDULE OF QUANTITY

NAME OF WORK:- C/o of link road Chhatrail to lower dadu Km 0/0 to 1/630 (SH:- Formation Cutting 5/7 Mtr. Wide road Km. 1/285 to 1/360.)

Estimated Cost
Earnest Money
Time

Rs 98069/-
Rs. 2000/-
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Excavation in earth work in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side Water pollution, etc and to protect soil stability of hill side rock shall be excavated with chiseling and wedging our rock (where blasting is prohibited) All earth work in cutting/excavation including rock excavation shall be carried out true to line, grades, slopes, width, camber, super elevation and level as shown on the drawing as per direction of Engineer in Charge in conformity with the requirement of technical specification for rural roads august 2004 clause 16.2 of general conditions of contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and stage, disposal of unsuitable cut material in specified manner, trimming/filling of unevenness blindage and finishing of the road to specified diamensions or as directed by Engineer in charge for smooth riding. The recovery of useful stones shall be made from the contractor and recovery of 56.11 cubic meter useful stones shall be made @ 300/- per cubic meter on prorata basis in each running bill. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified /dimension in all leads and lifts as per the direction of Engineer in Charge.	365.93	Per Cubic Meter			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.


 Executive Engineer
 Bhoranj Division
 PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- C/o of link road Chhatrail to lower dadu Km 0/0 to 1/630 (SH:- Formation Cutting 5/7 Mtr. Wide road Km. 1/425 to 1/480.)

Estimated Cost
Earnest Money
Time

Rs 99500/-
Rs. 2000/-
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Excavation in earth work in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side. Water pollution, etc and to protect soil stability of hill side rock shall be excavated with chiseling and wedging our rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to line, grades, slopes, width, camber, super elevation and level as shown on the drawing as per direction of Engineer in Charge in conformity with the requirement of technical specification for rural roads august 2004 clause 16.2 of general conditions of contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and stage, disposal of unsuitable cut material in specified manner, trimming/filling of unevenness, blinding and finishing of the road to specified dimensions or as directed by Engineer in charge for smooth riding. The recovery of useful stones shall be made from the contractor and recovery of 56.92 cubic meter useful stones shall be made @ 300/- per cubic meter on prorata basis in each running bill. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified /dimension in all leads and lifts as per the direction of Engineer in Charge.	371.27	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
(H.P.W.D. Bhoranj)

SCHEDULE OF QUANTITY

NAME OF WORK:- R/M of Various roads under Bhareri Section Bhoranj Sub-Division.

(SH:- Maintenance of earthen shoulder ,unlined surface drain and Removal of slip.)

Estimated Cost
Earnest Money
Time

Rs. 99310/-
Rs. 2000/-
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularation on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	750.00	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Excavated material to be used in embankments with a lift uo to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specifacation clause 307 as directed bythe engineer in charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	400.00	Per Running Mtr.			
3	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming og slope and disposal of cut material with in lift upto 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302.3.5 and 1611 and as per directon of Engineer-in-Charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	200.00	Per cubic metre			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.P.W.D Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- R/M on (i) Tikker to Manoh via Dhirwin road (ii) Kharwar to mehal via karah (iii) Blokhar to Bhola road (iv) Mair Pandwin to Town karah road. (SH:- Maintenance of earthen shoulder, unlined surface drain and Removal of slip.)

Estimated Cost

Rs. 99972/-

Earnest Money

Rs. 2000/-

Time

2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularities on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	701.00	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines, grades, level and dimensions. Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed by the engineer in charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	300.00	Per Running Mtr.			
3	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slope and disposal of cut material with a lift up to 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302.3.5 and 1611 and as per direction of Engineer-in-Charge including entire carriage of material in all lead and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	261.51	Per cubic metre			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.P. PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- R/M on (i) Thiotu to lathrou via khutrin road (ii) Patra Balet via kotlu (iii) Kharwar to Jakhrol via Dhamrola (iv) Lathrou to lathwan road via Dasmalin (v) Lathrou to Lathwan via Janal mahadev Mandir & UAM road (SI:- Maintenance of earthen shoulder, unlined surface drain and Removal of slip.)

Estimated Cost Rs. 99607/-
Earnest Money Rs. 2000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material (irregularity on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	691.00	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines, grades, level and dimensions. Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed by the engineer in charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	250.00	Per Running Mtr.			
3	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming og slope and disposal of cut material with in lift upto 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302.3.5 and 1611 and as per direction of Engineer-in-Charge including entire carriage of material in all lead and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	277.02	Per cubic metre			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HR/PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- R/M of Various roads under Chambh Section Samitpur Sub-Division.
(S)- Maintenance of earthen shoulder, unlined surface drain and Removal of slip.)

Estimated Cost Rs. 97993/-
Earnest Money Rs. 2000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularity on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	721.50	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines, grades, level and dimensions. Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed by the engineer in charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	750.00	Per Running Mtr.			
3	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slope and disposal of cut material with in lift upto 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302.3.5 and 1611 and as per direction of Engineer-in-Charge including entire carriage of material in all lead and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	126.16	Per cubic metre			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
MP PWD Bhoranj

SCHEDULE OF QUANTITY

AME OF WORK:- R/M of Various roads under Dho Section Samirpur Sub-Division.

SH:- Maintenance of earthen shoulder, unlined surface drain and Removal of silt.)

Estimated Cost Rs. 99600/-
Earnest Money Rs. 2000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularity on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	700.00	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines, grades, level and dimensions. Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed by the engineer in charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	200.00	Per Running Mtr.			
3	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slope and disposal of cut material with in lift upto 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302.3.5 and 1611 and as per direction of Engineer-in-Charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	282.72	Per cubic metre			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.P.W.D Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:-R/M of Various roads under BarirSection Samipur Sub-Division.
(SH:- Maintenance of earthen shoulder ,unlined surface drain and Removal of slip.)

Estimated Cost Rs. 98569/-
Earnest Money Rs. 2000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularity on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	735.00	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed bythe engineer in charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	800.00	Per Running Mtr.			
3	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming og slope and disposal of cut material with in lift upto 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302,3.5 and 1611 and as per direction of Engineer-in-Charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	110.00	Per cubic metre			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.PWD Bhoranj

NAME OF WORK :- R/M on link road village Patta kotlu Balet km. 0/00 to 2/00 . (SH:- Providing & fixing 150 mm PVC pipe for drainage the road surface water at RD 0/370.)

SCHEDULE OF QUANTITY

Estimated Cost
Earnest Money
Rs 90247/-
Rs. 2000/-
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.55	Per Cubic Meter			
2	Providing and fixing unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes, 150mm dia PVC 4 kg pressure of superior band, supreme, d-blast, flex, victus, polyplast or its equivalent as per direction of Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	90.00	Per Running Meter			
3	Providing concrete for plain reinforced concrete in P.C.C. grade M-10 (M-ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm (twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.74	Per cubic meter			
4	Providing & fixing PVC pipe 150mm dia accessories as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12.00	Each			
I	Door bend	12.00	Each			
II	Elbow bend	12.00	Each			
III	Bend	14.00	Each			
5	Constructing masonry Chamber 30x30x50 cm inside, in brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for stop cock, with C. I. surface box 100x100 x75 mm (inside) with hinged cover fixed in cement concrete slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), i/c necessary excavation, foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12mm thick, finished with a floating coat of neat cement complete as per standard design : 18.32.1 With common burnt clay F.P.S. (non modular) bricks of class designation 7.5 as per direction of Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.00	Each			

Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per direction of Engineer- in -Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	40.00	Per kilogramme			
Total					
Terms and Condition:-					

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj