HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PWD/DEH/CB/TENDER/2024-25- 2788-2807 DATED: 11/7/25
To

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject :- Tender Notice.

Enclosed kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on Department website as per notification of Principal Secretary (PW) to the Govt. of HP vide No. PBW(B)A(3)1/2024 dated 03.01.2024 as the works mentioned in the notice inviting tender are urgent/emergent nature of works in public interest.

Encl:-As above

Executive Engineer,
HPPWD Division,
Dehra.

Copy forwarded to the following:-

1. The FC-Cum Secy.(PW) to the Govt. of HP.Shimla-2.
2. The Engineer-in-Chief, HPPWD., Shimla.
3. The Chief Engineer(KZ) HP.PWD. Dharamshala.
4. The Superintending Engineer, Circle HP.PWD. Dehra.
5. All the Executive Engineer under North Zone.
6. All the Assistant Engineer under Dehra Division.
7. The Deputy Commissioner Kangra at Dharamshala.
8. The SDM/Tehsil/President MC Dehra.
9. The BDO Dehra /Pragpur/ Nagrota Surian.
10. Notice Board.
11. All the Head of Branches.
12. All the Contractors working under Dehra Division.

Executive Engineer,
Dehra Division HP.PWD.,
Dehra.

H. P. P.W.D. TENDER

Sealed item rate tenders on the form 6&8 are invited by the **Executive Engineer Dehra Division HPPWD., Dehra** on behalf of the Governor of HP for the following works from the approved and eligible contractors (C&D Class) enlisted in HPPWD.

TENDER SCHEDULE:

1. Date and time of receipt of application for tender form: 18.07.2025 upto 12.00 Noon
2. Date and time of issue of tender form: 19.07.2025 upto 5.00 PM
3. Date and time of receipt of tenders: 21.07.2025 upto 10.30AM
4. Date and time of opening of tenders: 21.07.2025 at 11.00 AM

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dehra Division HPPWD Dehra must accompany with each tender.

Job No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
01	Construction of Road from Roshni Devi House to Kanta Devi Cowshed Ward No.-III (G.P. Bhatoli Phakorian) (SH: P/L Paver Block and U-Shape Drain) (Part-I) VKV/2023/1337	Rs. 74,645.00	Rs.2,000/-	Two Months	Rs.350/-
02	Repair of Culvert near the land of Jagdish Chand, Prakash Chand etc. Houses in Village Churan Ward No.-III (SH: Demolition and C/o 3.00 mtr. Span RCC Culvert and Wing Wall) VKV/2023/1089	Rs. 99,323.00	Rs.2,000/-	One Month	Rs.350/-
03	Construction of Culvert near Well (Kuan) in the land of Dhyan Singh and Shakti Chand etc. Houses in Village Rewari G.P. Meyol (SH: C/o 3.00 mtr. Span RCC Slab Culvert) VKV/2023/1318	Rs. 99,869.00	Rs.2,000/-	One Month	Rs.350/-
04	A/R & M/O Various Roads under HPPWD Sub Division Dehra in Distt. Kangra (H.P.) (SH: Painting & Writing in KM Stones, Culverts, Bridges, Sign Boards and Rain Shelter etc. in Dehra Section).	Rs. 99,830.00	Rs.2,000/-	Three Months	Rs.350/-
05	Restoration of Rain Damages on various Roads under HPPWD Sub Division Haripur (SH: Painting and Writing on KM Stones, Culverts, Bridges, Sign Boards and Rain Shelters etc.).	Rs. 99,956.00	Rs.2,000/-	Three Months	Rs.350/-
06	Construction of Jeepable Road from Main Road to Jagjeet Singh, Trilok Singh etc. in Ward No.-VII (G.P. Nandpur) (SH: P/L 60mm thick Paver Block from KM 0/0 to 0/027) VKV/2023/1946	Rs. 99,855.00	Rs.2,000/-	Two Months	Rs.350/-
07	Construction of Pucca Path from Rajeev Kumar House to Rakesh Kumar House in Ward No.-I (G.P. Kherian) (SH: C/o Cement Concrete Pavement) SDP/2023/761	Rs. 99,858.00	Rs.2,000/-	One Month	Rs.350/-
08	Construction of Road from Roshni Devi House to Kanta Devi Ghoshala in Ward No.-III (G.P. Bhatoli Phakorian) (SH: P/L Paver Block & U-Shape Drain, Part-II) VKV/2023/1337	Rs. 74,639.00	Rs.2,000/-	Two Months	Rs.350/-
09	Repair of Pucca Path from FCI to Joginder Singh House in Ward No.-IV (G.P. Dohag Paloti) (SH: C/o Cement Concrete Pavement at RD 0/175 to 0/215) SDP/2023/1500	Rs. 99,341.00	Rs.2,000/-	Two Months	Rs.350/-

10	Repair of Pucca Path from FCI to Joginder Singh House in Ward No.-IV (G.P. Dohag Paloti) (SH: C/o Cement Concrete Pavement at RD 0/215 to 0/255) SDP/2023/1500	Rs. 99,353.00	Rs.2,000/-	Two Months	Rs.350/-
11	Repair of link road from Main Road to Indu Parmar, Arjun Singh etc. in Ward No. 01 G.P. Boungta KM 0/0 to 0/350 (SH: P/L 60mm thick Interlocking Paver Block at RD 0/282.20 to 0/304.70) SDF/2024/1842	Rs. 99,661.00	Rs.2,000/-	Three Months	Rs.350/-
12	Repair of link road from Main Road to Indu Parmar, Arjun Singh etc. in Ward No. 01 G.P. Boungta KM 0/0 to 0/350 (SH: P/L 60mm thick Interlocking Paver Block at RD 0/304.70 to 0/327.20) SDF/2024/1842	Rs. 99,666.00	Rs.2,000/-	Three Months	Rs.350/-
13	Restoration of Rain Damages on link road to Shaheed Vijender Singh Marg KM 0/0 to 1/225 (SH: C/o U-Shape Drain at RD 0/430 to 0/455 and Cement Concrete Causeway at RD 0/450 to 0/467.50).	Rs. 99,170.00	Rs.2,000/-	Two Months	Rs.350/-
1 (i) (ii) (iii) (iv)	The contractors/firms should possess the following documents (Photocopy to be attached): Latest renewal of enlistment. PAN (Permanent Account No.) Registration under HP GST/ (TIN No.). EPF (Employee Provident Fund Account No.)				
2	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case.				
3	If any of the date mentioned above happened/to be Gazetted Holidays the same shall be processed on next working day.				
4	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).				
5	The Contractor will have to submit affidavit alongwith application for issue of tender that he has not more than two works in hand.				
6	The next tender will be issued only after completion of previous works in hand.				
7	The offer of the tender shall remain valid upto 30 days after the opening.				

Executive Engineer
HPPWD Division Dehra
Distt Kangra H.P
on behalf of Governor of Himachal Pradesh

Exigency Certificate

It is certified that the tenders invited vide this office NIT No...2788-2807...dated...11/07/25... are of emergent nature of work and in public interest.

Place:
Dated:

Executive Engineer,
HPPWD Division,
Dehra.

53

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 74,645.00
Earnest Money :- Rs. 2,000.00
Time Limit :- Two Month.

Name of work:- Construction of road from Roshni Devi house to Kanta Devi Ghoshala ward No.3 (G.P. Bhatoli Phakorian). (S.H.:-Providing and laying Paver Block & U-shape drain Part-I)). VKV/2023/1337.

Sr. No.		Quantity	Rate in		Units	Amount
			Figures	words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material.completeas per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	1.82 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	528.00
2	Plain reinforced cement concrete in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 ans 1203 (P.C.C 1:4:8) completeas per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	4.12 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	16,686.00
3	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 60mm (Sixty millimetre) of M-30 grade with approved color design and pattern in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, toll tax, sale tax ,GST or any other taxes imposed by the Government.	41.25 Cubic metre	950.00	Rupees Nine Hundred Fifty Only	Per Cubic metre	39,188.00

Sr. No.		Quantity	Rate in		Units	Amount
			Figures	words		
4	Providing & laying cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in open foundation like floors etc. laid to required slope and camber in panels as required including consolidation finishing and tamping complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	2.07 Cubic metre	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic metre	12,006.00
5	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 (1:3:6) 1 cement : 3 sand : 6 aggregate of nominal 20mm size)as per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	1.26 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	6,237.00
	Total					**74,645.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for Rs, 74,645.00/- only.

Executive Engineer,
Dehra Division,
HPPWD Dehra

(42)

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99,323.00
Earnest Money :- Rs. 2000.00
Time Limit :- one months.

Name of work :-Repair of culvert near the land of Jagdish Chand, Prakash Chand etc. House Village Churan ward No.3(S.H,:- Demolition and reconstruction of 3.0 mtr span R.C.C. Culvert & wing wall) VKV/2023/1089

Sr. No.	Description of Item	Qty.	Rate in		Units	Amount
			Figures	Words		
1	Demolishing R.C.C. work manually/ by mechanicalmeans including stacking of steel bars and disposal ofunserviceable material within 50 metres lead as perdirection of Engineer - in-charge.completeas per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads.lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	1.35 Cum	1465.35	Rupees One Thousand Four Hundred Sixty Five And Paise Thirty Five Only	Per Cubic Metre	1978.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m. dressing of sides and bottom and back filling in trenches with excavated suitable material.completeas per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government	5.00 Cum	290.00	Rupees Two Hundred Ninety Only	Per Cubic Metre	1450.00
3	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203, P.C.C nominal mix 1:4:8 (40 mm aggregates)completeas per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads.lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	1.00 Cum	4050.00	Rupees Four Thousand Fifty Only	Per Cubic Metre	4050.00

4	Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 ans 1204 (P.C.C. grade M -15 (1:2½ : 5) complete as per drawing and technical specification clauses 614, 709, 1204.3.7 completeas per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	9.00 Cum	5200.00	Rupees Five Thousand Two Hundred Only	Per Cubic Metre	46800.00
5	Providing & laying cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in super strucutre upto height 5.0 mtr in Bed block and dirt wall laid to required slope and camber in panels as required including consolidation finishing and tamping complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	3.15 Cum	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic Metre	18270.00
6	Supplying,fitting and placing HYSDbar reinforcement (Fe 415) in super structure complete as per drawings and technical specifications Clauses1002, 1010 &1202, including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	315.00 Kg	85.00	Rupees Eighty Five Only	Per Kilogram	26775.00
	Total =					**99,323.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for Rs. 99,323.00/- only

Executive Engineer
Dehra Division
HP.PWD. Dehra

(48)

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99,869.00
Earnest Money :- Rs. 2000.00
Time Limit :- one months.

Name of work :-Construction of culvert near well (kuan) in the land of Dhyan Singh and Shakti Chand etc. House Village Riwari G.P. Meyol (S.H,:- Construction of 3.0 mtr span R.C.C. Slab Culvert) VKV/2023/1318

Sr. No.	Description of Item	Qty.	Rate in		Units	Amount
			Figures	Words		
1	Demolishing R.C.C. work manually/ by mechanicalmeans including stacking of steel bars and disposal ofunserviceable material within 50 metres lead as perdirection of Engineer - in-charge.completeas per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads.lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax. GST or any other taxes imposed by the Government.	1.13 Cum	1465.35	Rupees One Thousand Four Hundred Sixty Five And Paise Thirty Five Only	Per Cubic Metre	1656.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material.completeas per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads.lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax. GST or any other taxes imposed by the Government	4.50 Cum	290.00	Rupees Two Hundred Ninety Only	Per Cubic Metre	1305.00
3	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. P.C.C nominal mix 1:4:8 (40 mm aggregates)completeas per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads.lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax. GST or any other taxes imposed by the Government.	1.25 Cum	4050.00	Rupees Four Thousand Fifty Only	Per Cubic Metre	5063.00

4	Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 ans 1204 (P.C.C. grade M -15 (1:2½ : 5) complete as per drawing and technical specification clauses 614, 709, 1204.3.7 completeas per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	9.00 Cum	5200.00	Rupees Five Thousand Two Hundred Only	Per Cubic Metre	46800.00
5	Providing & laying cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in super strucutre upto height 5.0 mtr in Bed block and dirt wall laid to required slope and camber in panels as required including consolidation finishing and tamping complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	3.15 Cum	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic Metre	18270.00
6	Supplying,fitting and placing HYSDbar reinforcement (Fe 415) in super structure complete as per drawings and technical specifications Clauses1002, 1010 &1202. including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	315.00 Kg	85.00	Rupees Eighty Five Only	Per Kilogram	26775.00
	Total =					**99,869.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for Rs 99,869.00/- only.

Executive Engineer
Dehra Division
HP.PWD. Dehra

82

PERCENTAGE BILL OF QUANTITY

Estimated Cost: Rs. 99830/-
Earnest Money: Rs. 2000/-
Time Limit : Three Month.

Name of Work: A/R & M/O Various roads under Dehra Sub Division (SH:- Painting and Writing on Km. Stone, Culverts, bridges Sign boards & Rain Shelter etc in Dehra Section)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Removing old paint from Steel and other metal surfaces and making the surface even with hand scraping complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials. The rates are inclusive octroi, royality, Malkana, toll tax, GST,sale tax, goods service tax, labour cess or other taxes imposed by the Government	23.92 Square metre	23.60	Rupees Twenty Three And Paise Sixty Only	Per square metre	565.00
2	Painting one coat (excluding priming coat) on previously painted steel and other metal surface with enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials. The rates are inclusive octroi, royality, Malkana, toll tax, GST,sale tax, goods service tax, labour cess or other taxes imposed by the Government.	23.92 Square metre	90.00	Rupees Ninety Only	Per square metre	2153.00
3	Painting two coats (excluding priming coat) on previously painted concrete/masonry/plastered surface with ready mixed paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials. The rates are inclusive octroi, royality, Malkana, toll tax, GST,sale tax, goods service tax, labour cess or other taxes imposed by the Government.	75.64 Square metre	90.00	Rupees Ninety Only	Per square metre	6808.00
4	Writing letter in figures of any surface with black Japan Paint (stops, comas, hyphens and the like not to be measured and paid seprately) as per drawings and Technical Specification Clause 1701 complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials. The rates are inclusive octroi, royality, Malkana, toll tax, GST,sale tax, goods service tax, labour cess or other taxes imposed by the Government.	21000.00 Per.Cm height per letter	2.95	Rupees Two And Paise Ninety Five Only	Per centimetre height per letter	61950.00
5	Painting index hands normal size or arrows(up to 40 cm long) on any surface with Black Japan complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials. The rates are inclusive octroi, royality, Malkana, toll tax, GST,sale tax, goods service tax, labour cess or other taxes imposed by the Government.	280.00 Figure	59.50	Rupees Fifty Nine And Paise Fifty Only	Per figure	16660.00
6	Finishing wall with water proofing cement paint of approved brand and manufacture (Nerolac Suraksha/Apex exterior) and of approved shade on decorated wall surfaces (two or more coats) to give an even shade after thoroughly brushing the surface to remove all dirt and remains of loose, powdered, materials, other foreign matter and sand, papered smooth including applying of putty as required for making the surface smooth complete as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental The rates are inclusive octroi, royality, Malkana, toll tax, GST,sale tax, goods service tax, labour cess or other taxes imposed by the Government	98.61 Square metre	70.00	Rupees Seventy Only	Per square metre	6903.00
7	White washing with lime on two coats on parapet walls and tree trunks including preparationof surface by cleaning scraping etc. as per technical specification clause 1915 complete as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental The rates are inclusive octroi, royality, Malkana, toll tax, GST,sale tax, goods service tax, labour cess or other taxes imposed by the Government.	416.58 Square metre	11.50	Rupees Eleven And Paise Fifty Only	Per square metre	4791.00
		TOTAL				99830.00
		% Above/below				
		Quoted Amount in Figures				
		Quoted Amount in Words				

Bill of quantity checked and approved for Rs 99830/- only.

Executive Engineer,
HPPWD Dehra ,
Division Dehra.

116

Dehra

PERCENTAGE BILL OF QUANTITY

Estimated Cost: Rs. 99956/-
Earnest Money: Rs. 2000/-
Time Limit : Three Month.

Name of Work: Restoration of Rain Damages on various roads under HPPWd Haripur Sub Division (SH:- Painting and Writing on Km. Stone, Culverts, bridges Sign boards & Rain Shelter etc) Section Haripur

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Removing old paint from Steel and other metal surfaces and making the surface even with hand scraping complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials. The rates are inclusive octroi, royality, Malkana, toll tax, GST,sale tax, goods service tax, labour cess or other taxes imposed by the Government.	31.50 Square metre	55.00	Rupees Fifty Five Only	Per square metre	1733.00
2	Painting one coat (excluding priming coat) on previously painted steel and other metal surface with enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials. The rates are inclusive octroi, royality, Malkana, toll tax, GST,sale tax, goods service tax, labour cess or other taxes imposed by the Government.	31.50 Square metre	65.00	Rupees Sixty Five Only	Per square metre	2048.00
3	Painting two coats (excluding priming coat) on previously painted concrete/masonry/plastered surface with ready mixed paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials. The rates are inclusive octroi, royality, Malkana, toll tax, GST,sale tax, goods service tax, labour cess or other taxes imposed by the Government.	110.00 Square metre	85.00	Rupees Eighty Five Only	Per square metre	9350.00
4	Writing letter in figures of any surface with black Japan Paint (stops, comas, hyphens and the like not to be measured and paid seprately) as per drawings and Technical Specification Clause 1701 complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials. The rates are inclusive octroi, royality, Malkana, toll tax, GST,sale tax, goods service tax, labour cess or other taxes imposed by the Government.	31250.00 Per Cm height per letter	2.70	Rupees Two And Paise Seventy Only	Per centimetre height per letter	84375.00
5	Painting index hands normal size or arrows(up to 40 cm long) on any surface with Black Japan complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials. The rates are inclusive octroi, royality, Malkana, toll tax, GST,sale tax, goods service tax, labour cess or other taxes imposed by the Government.	35.00 Figure	70.00	Rupees Seventy Only	Per figure	2450.00
	TOTAL					99956.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill Quantity checked & approved for Rs 99956/-

Executive Engineer,
HPPWD Dehra ,
Division Dehra.

(84)

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99,855.00
Earnest Money :- Rs. 2,000.00
Time Limit :- Two Month.

Name of work:- Construction of Jeepable road from main road to Jagjeet Singh,Trilok Singh etc. ward No. 7(G.P. Nandpur). (S.H.:-Providing and laying 60mm thick Paver Block from RD 0/000 to 0/027)). VKV/2023/1946

Sr. No.		Quantity	Rate in		Units	Amount
			Figures	words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material.completeas per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	4.22 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	1,224.00
2	Plain/reinforced cement concrete in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 ans 1203 (P.C.C 1:4:8) completeas per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads.lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	4.25 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	17,213.00
3	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 60mm (Sixty millimetre) of M-30 grade with approved color design and pattern in footpath, parks, lawns.drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand.compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, toll tax, sale tax ,GST or any other taxes imposed by the Government.	60.00 Cubic metre	950.00	Rupees Nine Hundred Fifty Only	Per Cubic metre	57,000.00

Sr. No.		Quantity	Rate in		Units	Amount
			Figures	words		
4	Providing & laying cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in open foundation like floors etc. laid to required slope and camber in panels as required including consolidation finishing and tamping complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	4.21 Cubic metre	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic metre	24,418.00
	Total					99,855.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approval for Rs 99855/- only

Executive Engineer,
Dehra Division,
HPPWD Dehra

89

PERCENTAGE BILL OF QUANTITY

ESTIMATED COST: - Rs. 99,858.00
EARNEST MONEY Rs. 2,000.00
TIME LIMIT : One month

Name of Work:-Construction of Pucca path from Rajeev Kumar house to Rakesh Kuamr House ward No.1 (GPKherian) (SH:-Construction of Cement Concrete pavement)SDP/2023/761.

Sr .No.	Description of item	Quantity	Rate		Units	Amount
			In figures	In words		
1	Preparation of sub grade by dressing to combor (Earth work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil completed as per HP.PWD specifications.and as directed by the Engineer-in-Charge complete including carriage of material within all leads, lifts and other incidentals as per specifications. approved drawing. design and as directed by the Engineer-in-charge. The rate is inclusive of octroi. royality. Malkhana. Toll tax. sale tax. GST and any other taxes imposed by the Government.	132.00 Sqm	2.50	Rupees Two And Paise Fifty Only	Per Square Meter	330.00
2	Stone soling properly hand packed with Kharanja Stone filling interstices with power road roller to the required gradient and camber including spreading and consolidation of binding materials moorum or earth etc.and as directed by the Engineer-in-Charge complete including carriage of material within all leads, lifts and other incidentals as per specifications. approved drawing. design and as directed by the Engineer-in-charge. The rate is inclusive of octroi. royality. Malkhana. Toll tax. sale tax. GST and any other taxes imposed by the Government.	19.80 Cum	1160.00	Rupees One Thousand One Hundred Sixty Only	Per Cubic Meter	22968.00
3	Providing and laying 1:2:4 concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802. 803. 1202 & 1203.and as directed by the Engineer-in-Charge including complete including carriage of material within all leads. lifts and other incidentals as per specifications. approved drawing. design and as directed by the Engineer-in-charge. The rate is inclusive of octroi. royality. Malkhana. Toll tax. sale tax. GST and any other taxes imposed by the Government.	13.20 Cum	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic Meter	76560.00
	Total Amount					99,858.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for Rs. 99,858.00/- only.

Executive Engineer,
Dehra Division,
HP.PWD., Dehra

(54)

JOB NO.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 74,639.00
Earnest Money :- Rs. 2,000.00
Time Limit :- Two Month.

Name of work:- Construction of road from Roshni Devi house to Kanta Devi Ghoshala ward No.3 (G.P. Bhatoli Phakorian). (S.H.:-Providing and laying Paver Block & U-shape drain Part-II). VKV/2023/1337.

Sr. No.		Quantity	Rate in		Units	Amount
			Figures	words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material.completeas per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	1.80 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	522.00
2	Plain/reinforced cement concrete in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 ans 1203 (P.C.C 1:4:8) completeas per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	4.12 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	16,686.00
3	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 60mm (Sixty millimetre) of M-30 grade with approved color design and pattern in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, toll tax, sale tax ,GST or any other taxes imposed by the Government.	41.25 Cubic metre	950.00	Rupees Nine Hundred Fifty Only	Per Cubic metre	39,188.00

Sr. No.		Quantity	Rate in		Units	Amount
			Figures	words		
4	Providing & laying cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in open foundation like floors etc, laid to required slope and camber in panels as required including consolidation finishing and tamping complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	2.07 Cubic metre	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic metre	12,006.00
5	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 (1:3:6) 1 cement : 3 sand : 6 aggregate of nominal 20mm size)as per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	1.26 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	6,237.00
	Total					74,639.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for Rs: 74,639.00/- only

Executive Engineer,
Dehra Division,
HPPWD Dehra

(55)

PERCENTAGE BILL OF QUANTITY

JOB NO.

Estimate Cost :- Rs. 99,341.00
Earnest Money :- Rs. 4,000.00
Time Limit :- Two Month.

Name of work:- Repair of Pucca path from FCI to Joginder Singh House ward No.4 (G.P. Dohag Paloti).(S.H.:-Construction of cement comcrete pavement from RD 0/175 to 0/215). SDP/2023/1500

Sr. No.		Quantity	Rate in		Units	Amount
			Figures	words		
1	Preparation of sub grade by dressing to combor (Earth work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil completed as per MORTH Technical specification including hauling of material in all leads. lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads.lifts and other incidental. The rates including Royality. Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	101.00 Square metre	1.50	Rupees One And Paise Fifty Only	Per square metre	152.00
2	Stone soling properly hand packed with Kharanja Stone filling interstices with power road roller to the required gradient and camber including spreading and consolidation of binding materials moorum or earth etc.and as directed by the Engineer-in-Charge complete including carriage of material within all leads. lifts and other incidentals as per specifications. approved drawing. design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royality. Malkhana. Toll tax. sale tax. GST and any other taxes imposed by the Government.	10.06 Cubic metre	1154.00	Rupees One Thousand One Hundred Fifty Four	Per Cubic metre	11,609.00
3	Providing & laying cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in open foundation like floors etc. laid to required slope and camber in panels as required including consolidation finishing and tamping complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads. lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax. GST or any other taxes imposed by the Government.	15.10 Cubic metre	5800.00	Rupees Five Thousand Eight Hundred	Per Cubic metre	87,580.00
	Total					99,341.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked & approved for Rs. 99,341.00/- only

Executive Engineer,
Dehra Division,
HPPWD Dehra

56

PERCENTAGE BILL OF QUANTITY

JOB NO. page

Estimate Cost :- Rs. 99,353.00
Earnest Money :- Rs. 2,000.00
Time Limit :- Two Month.

Name of work:- Repair of Pucca path from FCI to Joginder Singh House ward No.4 (G.P. Dohag Paloti).(S.H.:-Construction of cement comcrete pavement from RD 0/215 to 0/255). SDP/2023/1500

Sr. No.		Quantity	Rate in		Units	Amount
			Figures	words		
1	Preparation of sub grade by dressing to combor (Earth work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil completed as per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	101.00 Square metre	1.50	Rupees One And Paise Fifty Only	Per square metre	152.00
2	Stone soling properly hand packed with Kharanja Stone filling interstices with power road roller to the required gradient and camber including spreading and consolidation of binding materials moorum or earth etc.and as directed by the Engineer-in-Charge complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royality, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	10.07 Cubic metre	1154.00	Rupees One Thousand One Hundred Fifty Four	Per Cubic metre	11,621.00
3	Providing & laying cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in open foundation like floors etc. laid to required slope and camber in panels as required including consolidation finishing and tamping complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	15.10 Cubic metre	5800.00	Rupees Five Thousand Eight Hundred	Per Cubic metre	87,580.00
	Total					99,353.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for Rs 99,353/- only

Executive Engineer,
Dehra Division,
HPPWD Dehra

115

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99661.00
Earnest Money :-Rs. 2000.00
Time Limit :- Three Months.

Name of work:- Repair of link road from main road to Indu Parmar,Arjun Singh etc.ward No.1 GP Boungta km. 0/0 to 0/350 (SH:-P/L 60mm thick interlocking Paver Block in Km. 0/282.20 to 0/304.70) SDF/2024/1842

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	6.75 Cubic meter	290.00	Rupees Two Hundred Ninety Only	Per Cubic meter	1,958.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (fourty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	6.75 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	27,338.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation for all types of structure and the like in Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax,GST or any other taxes imposed by the Government.	2.55 Cubic metre	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic metre	14,790.00
4	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 80 mm (eighty millimetre) of M-30 grade with approved color design and pattern in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, toll tax, sale tax ,GST or any other taxes imposed by the Government.	58.50 Square metre	950.00	Rupees Nine Hundred Fifty Only	Per Square metre	55,575.00
	Total					99,661.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked & passed for ₹ 99661/-

Executive Engineer,
Dehra Division,
HPPWD Dehra

114

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99666.00
Earnest Money :-Rs. 2000.00
Time Limit :- Three Months.

Name of work:- Repair of link road from main road to Indu Parmar,Arjun Singh etc.ward No.1 GP Boungta km. 0/0 to 0/350 (SH:-P/L 60mm thick interlocking Paver Block in Km. 0/304.70 to 0/327.20) SDF/2024/1842

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	6.77 Cubic meter	290.00	Rupees Two Hundred Ninety Only	Per Cubic meter	1,963.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (fourty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	6.75 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	27,338.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation for all types of structure and the like in Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax,GST or any other taxes imposed by the Government.	2.55 Cubic metre	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic metre	14,790.00
4	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 80 mm (eighty millimetre) of M-30 grade with approved color design and pattern in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, toll tax, sale tax ,GST or any other taxes imposed by the Government.	58.50 Square metre	950.00	Rupees Nine Hundred Fifty Only	Per Square metre	55,575.00
	Total					99,666.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked & found for Rs 99666/

Executive Engineer,
Dehra Division,
PPWD Dehra

117

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99,170.00
Earnest Money :- Rs. 2,000.00
Time Limit :- Two Months.

Name of work:- Restoration of Rain Damages on link road to Shaheed Singh Marg in Km. 0/00 to 1/225 (SH:- Construction of U-Shape Drain at RD 0/430 to 0/455 and cement concrete causeway at RD 0/450 to 0/467.50).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	***Earth work in excavation in foundation for all types of structures*** such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	7.75 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	2,248.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-10 (M-Ten) nominal mix ***1:3:6*** (One cement isto three sand isto six graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water ***in open foundation*** for all type of structure and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900 and 1200 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, Toll tax or any other taxes imposed by the Government.	4.38 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	21,681.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, toll tax or any other taxes imposed by the Government.	5.25 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	21,263.00
4	Providing and laying mechanically mixed and vibrated plain/reinforced cement concrete Grade-M-25 (M-Twenty five) nominal mix ***1:1.5:3*** (One cement isto one and half sand isto three graded crushed stone aggregate 20mm (Twenty millimeter) nominal size ***in open foundation*** as per drawing and MORD technical specification clause 802, 803, 1202 and 1203 including the cost of form work and curing complete but excluding cost of reinforcement for reinforced concrete work as per satisfaction and direction of Engineer-in-Charge, including carriage of materials up to all leads, lifts. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	7.88 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	53,978.00
	TOTAL					**99,170.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked
& found to be Rs 99170/-

Executive Engineer,
Dehra Division,
HPPWD Dehra