

Himachal Pradesh
Public Works Department.

Through mail

No. PWH/HD/CB/T-I/2024-25

1580-82

Dated: -

28/06/2025

To


✓
The Executive Engineer (IT Cell)
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject: - **Publication of Notice inviting tender.**

Sir,

Enclosed please find herewith copy of notice inviting tender for publishing on departmental website for favour of further necessary action please.

Encl: As above


Executive Engineer,
HPPWD Division Haroli,
Distt.Una HP).

Copy along with copy of notice inviting tender is forwarded for information and necessary action to:-

1. The Superintending Engineer, 15th Circle, HP: PWD, Una.
2. Copy to Notice board.


Executive Engineer,
HPPWD Division Haroli,
Distt.Una HP).

Certificate

108082 Certified that the tenders for the works called vide this office letter No. PWH/HD/CB/T-1/2024-2
dated 28/06/2024 are required to be carried out immediately being emergent nature of work in public interest.


Executive Engineer,
HPPWD Division, Una,
Distt. Una HP).



HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDERS"

Percentage rate tender on PWD Form No. 6 & 8 a-e hereby invited by the Executive Engineer, Division H.P. on behalf of Governor of H.P for the following works from the approved and eligible contractors/firms enlisted in the PWD Department as per latest instructions, so as to reach and open in his office as per time schedule given below. The tender will be open for 45 days from the date of opening of tenders. The undersigned reserves the right to reject any tender without assigning any reasons.

1. Date of receipt of application for the tender form a/w requisite documents: - 05/07/2018 up to 10.30 (Non).

2. Date of issue/sale of tender forms against cash payment(non-refundable): - 07/07/2018 up to 3.00 PM

3. Date of receipt of tenders: - 08/07/2018 up to 10.30 AM

4. Date of opening of tenders: - 09/07/2018 at 11.00 AM

Sr. No.	Name of work	Estimated cost	EMD	Time Limit	Cost of tender	Eligible class of contract
1	2	3	4	5	6	7
1	Restoration of Gramin Sampark from main road to the house of Major Dhalbir Singh Ward No.5,6 GP Heera Nagar (SH: C/o CC pavement at RD 0/027 to 0/036 along with toe wall) Deposit work	99801.00	2000/-	One Month	350/-	Class- C & D
2	A/R & M/O on Gurplah to Gondpur road Km 0/00 to 10/500 (SH: Balance work for the C/o Rain Shelter P/L Granite stone flooring in rain shelter) Phase-VII	99820.00	2000/-	One Month	350/-	Class- C & D
3	Restoration of Gramin Sampark from main road to the house of Major Dhalbir Singh Ward No.5,6 GP Heera Nagar (SH: C/o CC pavement at RD 0/009 to 0/018 along with toe wall) Deposit work	99779.00	2000/-	One Month	350/-	Class- C & D
4	A/R & M/o Gurplah to Gondpur road Km 0/00 to 10/500 (SH: Balance work for the C/o Rain Shelter, P/L Granite Stone, flooring and Anarkali Grill in rain shelter) Phase-VIII	99606.00	2000/-	One month	350/-	Class- C & D
5	C/o link road from H/o Pawan Kaundal to Ward No.5 to Lower Badhera (SH: P/L 60mm thick paver block) Phase-III Deposit work	99535.00	2000/-	One month	350/-	Class- C & D
6	Painting work of Mini Secretariat building at Haroli Distt. Una (HP)(SH:-Exterior painting work to Building Phase-IV)Deposit Work	53746.00	1000/-	One Month	350/-	Class- C & D
7	Restoration of Gramin Sampark from H/o Sh.Surinder Singh to Shahid Baba Mandir WNO.2 GP Palkwah (SH: C/o 900mm dia Hume Pipe culvert at RD 0/250) Deposit work	82973.00	2000/-	One Month	350/-	Class- C & D
8	Restoration of link road from Lalpuri Vishnu Dham Kutia upto CHC Beetan in G.P. Beetan (SH:-P/L CC Pavement at RD. 0/023 to 0/053) Deposit Work(Balance Work).	99000.00	2000/-	One Month	350/-	Class- C & D
9	Restoration of Path in Rodiyan wall Gali upto Pathakan G.P. Bhadriaran Tehsil Haroli Distt. Una (H.P)(SH:-C/O V-Shape drain & CC Overlay at RD. 0/090.50 to 0/105.70) Under MMSY	98148.00	2000/-	One Month	350/-	Class- C & D
10	Restoration of Path in Rodiyan wall Gali upto Pathakan G.P. Bhadriaran Tehsil Haroli Distt. Una (H.P)(SH:-C/O V-Shape	97501.00	2000/-	One Month	350/-	Class- C & D

	drain & CC Overlay at RD. 0/075.40 to 0/090.50) Under MMSY					
11	Painting work of Mini Secretariat building at Haroli Distt. Una (HP)(SH:-Exterior painting work to Building Phase-III)Deposit Work	99206.00	2000/-	One Month	350/-	Class- C & D
12	Improvement of Black Spot on Ajouli Santokhgarh Tahliwal Polian road Km 0/0 to 13/400 (SH: C/o Speed Breaker with 100mm paver block & CC pavement in Tahliwal Market at RD 4/120 Bhs)	99169.00	2000/-	One Month	350/-	Class- C & D
13	C/O Levelling work in Playground near GSSS Nangal Khurd Mohalla Thal Nangal Khurd Phase-V) Deposit Work	99771.00	2000/-	One Month	350/-	Class- C & D
14	Restoration of Gramin Sampark from main road to the house of Major Dhalbir Singh Ward No.5,6 GP Heera Nagar (SH: C/o CC pavement at RD 0/018 to 0/027 along with toe wall) Deposit work	99899.00	2000/-	One Month	350/-	Class- C & D
15	Balance work for the C/o Community Park, Outdoor open gym at W.No.2 & 4 G.P.Dulehar Tehsil Haroli (SH: Hill side cutting for extended portion of park at RD 0/016 to 0/020) (Deposit work)	98000.00	2000/-	One Month	350/-	Class- C & D
16	C/O Levelling work in Playground near GSSS Nangal Khurd Mohalla Thal Nangal Khurd Phase-III) Deposit Work	99854.00	2000/-	One Month	350/-	Class- C & D
17	C/o link road from house of Champa Devi Km 0/0 to 1/200 (SH: C/o B/wall at RD 1/140 to 1/147.30 RHS)	98694.00	2000/-	One Month	350/-	Class- C & D
18	Restoration of link road from Lalpuri Vishnu Dham Kutia upto CHC Beetan in G.P. Beetan (SH:-P/L CC Pavement at RD. 0/053 to 0/083.20) Deposit Work(Balance Work)	99660.00	2000/-	One Month	350/-	Class- C & D
19	Restoration of Gramin Sampark from main road to Kumhar Basti ward No.4,5 GP Heeranagar (SH:-C/O CC Pavement at RD. 0/116 to 0/142.50) Deposit work	99348.00	2000/-	One Month	350/-	Class- C & D
20	Restoration of Gramin Sampark from main road to Kumhar Basti ward No.4,5 GP Heeranagar (SH:-C/O CC Pavement at RD. 0/142.50 to 0/169) Deposit work	99303.00	2000/-	One Month	350/-	Class- C & D
21	Repair & Maintenance of SDWG Collage at Beetan Tehsil Haroli Distt. Una (SH:-C/O R/wall behind the Play ground)Phase-II Deposit Work	98634.00	2000/-	One Month	350/-	Class- C & D
22	Restoration of rain damages on various road under section Dulehar Sub Division Tahliwal (SH: Dep'oyment of excavator cum loader & tipper for Treming of Access soil in berm removal of slips & C/o unlined drain etc. in rainy season etc.)	99100.00	2000/-	One Month	350/-	Class- C & D
23	C/o Gramin Sampark to house of Sh.Ram Lal S/o Sh.Tarsem Lal W.No.2 G.P.Beetan (SH: C/o CC pavement at RD 0/052 to 0/078) under MMSY	99277.00	2000/-	One Month	350/-	Class- C & D
24	C/o Gramin Sampark to house of Sh.Ram Lal S/o Sh.Tarsem Lal W.No.2 G.P.Beetan (SH: C/o CC pavement at RD 0/026 to 0/052) under MMSY	99463.00	2000/-	One Month	350/-	Class- C & D

25	C/O Levelling work in Playground near GSSS Nangal Khurd Mohalla Thai Nangal Khurd Phase-IV) Deposit Work	99866.00	2000/-	One Month	350/-	Class- C & D
26	Special repair & other work of EFC building at Pandoga (SH; Aluminium work, WS & SI etc.) Deposit work	98941.00	2000/-	One Month	350/-	Class- C & D
27	Restoration of rain damages on various road in Pandoga Section under Sub Divn Khad HPPWD (SH: Deployment of excavator cum loader & tipper for Treming of Access soil in berm removal of slips & C/o unlined drain etc. in rainy season etc.)	99550.00	2000/-	One Month	350/-	Class- C & D
28	Restoration of rain damages on various road in Khad Section under Sub Divn Khad HPPWD (SH: Deployment of excavator cum loader & tipper for Treming of Access soil in berm removal of slips & C/o unlined drain etc. in rainy season etc.)	99550.00	2000/-	One Month	350/-	Class- C & D
29	C/O Levelling work in Playground near GSSS Nangal Khurd Mohalla Thai Nangal Khurd Phase-II) Deposit Work	99982.00	2000/-	One Month	350/-	Class- C & D
30	Restoration of R/D on link road vill.Singan to HP Boundary (SH: C/o B/wall at RD 0/120 to 0/130.70)	99279.00	2000/-	One Month	350/-	Class- C & D
31	C/o link road to Harizan Basti Panjwar (SH: C/o CC pavement at RD 0/270 to 0/279.50) Deposit work.	99729.00	2000/-	One Month	350/-	Class- C & D
32	Repair & Maintenance of SDWG Collage at Beetan Tehsil Haroli Distt. Una (SH:-C/O R/wall behind the Play ground)Phase-I Deposit Work	99506.00	2000/-	One Month	350/-	Class- C & D
33	C/o link road from house of Champa Devi Km 0/0 to 1/200 (SH: C/o B/wall at RD 1/147.30 to 1/154.70 RHS)	99592.00	2000/-	One Month	350/-	Class- C & D
34	Balance work for the C/o Community Park, Outdoor open gym at W.No.2 & 4 G.P.Dulehar Tehsil Haroli (SH: C/o B/wall for protection of hill side on extended portion of park front side length: 11.00 RD 0/0 to 0/011) (Deposit work)	99459.00	2000/-	One Month	350/-	Class- C & D
35	A/R & M/O on Old Saloh Bhadouri road Km 0/0 to 9/615 (SH:P/L polished granite stonek marble work, P/F cat eyes etc. at Karampur Chowk)	99802.00	2000/-	One Month	350/-	Class- C & D
36	Restoratin of rain damage on link road to village Singan to HP boundary Km 0/00 to 1/300, Tahliwal Bathri road Km 0/00 to 7/700, Santokgharh Tahliwal Polian road in Tahliwal section under Sub Division Tahliwal HPPWD (SH: Deployment of excavator cum loader & tractor with trolly for Treming of Access soil on berms, C/o unlined drain & clearance of road side drains in rainy season etc.).	98100.00	2000/-	One Month	350/-	Class- C & D
37	Restoration of Gramin Sampark from H/o Sh.Surinder Singh to Shahid Baba Mandir WNO.2 GP Palkwah (SH: P/L CC pavement at RD 0/023.90 to 0/047.70) Deposit work	99153.00	2000/-	One Month	350/-	Class- C & D
38	C/o link road to Harizan Basti Panjwar (SH: C/o CC pavement at RD 0/289 to 0/308.50) Deposit work.	99691.00	2000/-	One Month	350/-	Class- C & D
39	Special repair & other work of EFC building at Pandoga (SH: C/o drain, P/L paver block In front of building) Deposit work	99636.00	2000/-	One Month	350/-	Class- C & D

40	Restoration of R/D on link road vill.Singan to HP Boundary (SH: C/o B/wall at RD 0/153 to 0/163.70)	99444.00	2000/-	One Month	350/-	Class- C & D
41	Restoratin of rain damage on Gurplah to Gondpur road Km 0/00 to 4/00, Panjawa Bathri road to Satsang Ghar Bathu Rahar Mohalla upto Gurplah Gondpur road Km 0/00 to 2/00, Link road Gowshala Bathri to main Bazar Bathri Km 0/00 to 1/100 in Tahliwal section under Sub Division Tahliwal HPPWD (SH: Deployment of excavator cum loader & tractor with trolly for Treming of Access soil on berms, C/o unlined drain & clearance of road side drains in rainy season etc.).	98100.00	2000/-	One Month	350/-	Class- C & D
42	Special repair & other work of EFC building at Pandoga (SH: C/o drain, P/L paver block in front of bulding) Deposit work	99778.00	2000/-	One Month	350/-	Class- C & D
43	Restoration of rain damages on varlous roads under Section Haroli Sub Division Haroli (SH: Deployment of excavator cum loader & tractor for treming of access soll in berm revoval of slips & C/o unlined drain etc. in rainy season)	98100.00	2000/-	One Month	350/-	Class- C & D
44	Restoration of rain damages on link road Old Haroli road Gugga Mandir upto Paljal Yojna Haroli Km 0/0 to 2/140 RHS(SH: C/o U-shape drain at RD 2/070 to 2/100-RHS)	99064.00	2000/-	One Month	350/-	Class- C & D

The earnest money in the shape of National Saving certificate/ time deposit/ saving account of any post office or FDR, Nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected. The tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained. The copy of valid enlistment, GST registration No., Income Tax, Pan No. and epf no. must be attached with application.

SPECIAL CONDITION: -

1. The contractor should produce a copy of valid enlistment/renewal letter at the time of application.
2. The contractor/firm shall have his resignation and GST No. and copy of same be attached with the application.
3. The earnest money for the above work should be submitted duly pledged in favour of Executive Engineer, Haroli Division HPPWD with the application for the purchase of tender forms. The application received without earnest money shall summarily be rejected.
4. The contractor/firms are required to insert the rate in words as well as figures, failing which Executive Engineer reserves the right to accept/rejects any or all tenders. If any of the date mentioned above happens to be local/gazet holidays, the same shall be process on next date.
5. The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which may be attached with their application a/w proof of ownership of machinery/legal tie up arrangement).
6. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.
7. The conditional/ambiguous/telegraphic tenders by fax shall not entertained/considered in any case.

HIM SUCHANA AVAM JAN SAMPARK.

Executive Engineer
HPPWD Division Haroli
Distt.Una(HP).Pin Code-177220
Email: ee-haroli-hp@hp.gov.in
On behalf of Governor of Himachal Pradesh.

SCHEDULE OF QUANTITY
Name of work: Restoration of Gramin Sampark from main road to the house of Major Dhabir Singh ward No 5,5, Gf Heeran Nagar (
SH : C/O C.C pavement at RD 0027 to 0036 alongwith toe wall) - Deposit work

S. No.	Description of work	Quantity	Unit	Figures	Estimated Cost	Time limit	One month
				Rate in Words	Estimated Money	Amount	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and rinning of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any lift of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, mukhama, joll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.10	Per cubic metre		99801	2000/-	
2	Providing and laying mechanically mixed and vibrated concrete for plant/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement four sand eight graded crushed /broken stone aggregate 40mm forty Millimeter) nominal size in or under water or ground complete including pumping or hauling out water/dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty, mukhama, joll tax, GST, labour cess or other taxes imposed by the Government.	21.36	Per cubic metre				
3	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 metre, transporting to site, spreading, grading to required slope and compacting to meet requirement of Table 300.1 and 300.2 with all leads as per Technical Specification Clause 301.5 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty, mukhama, joll tax, GST, labour cess or other taxes imposed by the Government.	17.40	Per cubic metre				
4	Construction of Granular Sub Base by providing well graded material, spreading in uniform layers with tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMG, and compacting with smooth wheel roller to achieve the desired density complete as per technical specification clause for grading 1 material including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty, mukhama, joll tax, GST, labour cess or other taxes imposed by the Government.	2.04	Per cubic metre				
5	Providing and laying (M-25) (M-twenty five) Grade Design Mix mechanically mixed and vibrated concrete for plant/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORI 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty, mukhama, joll tax, GST, labour cess or other taxes imposed by the Government.	3.94	Per cubic metre				
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B/C)17/20212 dated 7.8.2018							
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B/C)31/2020 dated 22.07.20							
Total:							0

Executive Engineer
Haroli Division
HPPWD

42

Schedule of quantity

Name of work:- A/R & M/O on Gurpiah to Gondpur road km. 0/00 to 10/500.)				Estimated Cost: Rs	₹ 99,820	
				Time:-	One month	
(SH: Balance work for the C/O Rain Shelter P/L Granite stone flooring in rain shelter) Phase-VII				Earnest Money:-	2000	
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge Polished Granite stone slab jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent, including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	28.52	Sqm			
Total						

Note-1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018

**Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)**

(28)

SCHEDULE OF QUANTITY

Name of work: Restoration of Gramin Sampark from main road to the house of Major Dhabir Singh Singh ward No 5/6 GP Heeran Nagar (SH : G/O C.C pavement at RD 0/009 to 0/018 alongwith toe wall) - Deposit work

S. No.	Description of work	Quantity	Unit	Estimated Cost	99779
				Earnest Money	20000/-
				Time limit	One month
				Rate in	Amount
				Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, mukhanna, joll tax, sale tax, CST, labour cess or other taxes imposed by the Government.	7.12	Per cubic metre		
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement, four sand eight graded crushed broken stone aggregate 40mm forty Millimeter) nominal size in or under water or ground complete including pumping or hauling out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including the cost of form work as per drawings and technical specification Clause 802 803 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty, mukhanna, joll tax, CST, labour cess or other taxes imposed by the Government.	21.36	Per cubic metre		
3	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 metre, transporting to site, spreading, grading to required slope and compacting to meet requirement of Table 300.1 and 300.2 with all leads as per Technical Specification Clause 301.5 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty, mukhanna, joll tax, CST, labour cess or other taxes imposed by the Government.	17.40	Per cubic metre		
4	Construction of Granular Sub Base by providing well graded material, spreading in uniform layers with tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMG, and compacting with smooth wheel roller to achieve the desired density complete as per technical specification clause for grading. 1 material including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty, mukhanna, joll tax, CST, labour cess or other taxes imposed by the Government.	2.03	Per cubic metre		
5	Providing and laying (M-25) (Twenty five) Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty, mukhanna, joll tax, CST, labour cess or other taxes imposed by the Government.	3.94	Per cubic metre		
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No PBW(B)(C)(17/2/2012 dated 7.8.2018				Total:	0
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No PBW(B)(A)(31/2020 dated 22.07.20					

Executive Engineer
Haroli Division
HPPWD

43

Schedule of quantity

Name of work:- A/R & M/O on Gurpiah to Gondpur road km. 0/00 to 10/500.)						Estimated Cost: Rs	One month
						Time:-	
(SH: Balance work for the C/O Rain Shelter/P/L Granite stone flooring & Anarkali Grill in rain shelter) Phase-VIII						Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge Polished Granite stone slab jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent, including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed	16.10	Sqm				
2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. FOR ANARKALI GRILL, including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	305.91	kg.				
Total							

Note:1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP
vide letter No. PBW (B) © (17) 2/202012 dated 07.08.2018

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Name of work :- C/O link road from H/O Pawan Kaundal to ward No -5 to Lower Badehira (SH: Ph. 60mm thick paver block).
Phase-III (Deposk work)

Estimated Cost 99535
Earnest Money 2000/-
Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	2.88	Per cubic metre			
2	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -1 material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government.	7.18	Per cubic metre			
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand :eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes.	7.18	Per cubic metre			
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M:twenty) nominal mix 1:2:4 (One cement :two sand :four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes.	1.82	Per cubic metre			
5	Providing and fixing heavy duty precast concrete inter locking paver block pavements having thickness 60mm (Sixty millimeter) (ISI mark) including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	73.20	Per square metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)/172/2012 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No. PBW(B)/A(31)/2020 dated 22.07.20					
						0

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Painting work of Mini Secretariat building at Haroli Distt. Una (SH: Exterior painting work to Building Phase -IV)- Deposit

Estimated Cost 53746

Earnest Money 4000/-

Time limit One month

S. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Finishing walls with Acrylic Satin exterior paint of required shade Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	294.40	Per Square metre			
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth completely including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	88.32	Per Square metre			
3	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacturer including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	43.40	Per Square metre			
4	Providing and fixing double scaffolding system (cup lock type) on the exterior side of building/structure, upto 25 metre height, above ground level, including additional rows of scaffolding in stepped manner as per requirement of site, made with 40mm dia M.S. tube, placed 1.5 metre centre to centre, horizontal & vertical tubes joint with cup & lock system with M.S. Tubes, M.S. tube chalis, M.S. clamps and staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for entire work of cleaning and/or painting and/or applying chemical and removing it thereafter. The scaffolding system shall be stiffened with racings, runners, connecting with the building etc. wherever required, if feasible, for inspection of work at required locations with essential safety features for the workmen etc., complete as per directions and approval of Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	128.40	Per square metre			
	Total					0

NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PRW(B)54732/0212 dated 7.11.2019

2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No PRW(B)A(31)/2020 dated 22.07.20

Executive Engineer
Haroli Divn.(PRWD),
Haroli

(7)

Schedule of quantity						
					Estimated Cost: Rs	₹ 82,973
Name of work : Restoration of Gramin Sampark from the H/O Sh. Surinder Singh to Shahid Baba Mandir Ward No. 2 GP Palkwah. (Deposit work)					Time:-	One month
(S.H. :- C/O 900 mm dia Hume pipe culvert at RD 0/250)					Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. including carriage of material within all leads . The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	22.02	Per/cum			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size). including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	5.77	Per/cum			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. - All work up to plinth level :1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size). including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	10.69	Per/cum			

89

4	Providing and laying Non Pressure NP-2 class (Medium duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax, octroi, royalty, malikana , toll tax, GST, labour cess or other taxes imposed by the Government..	5.00	Per/cum Rmt.		
	Total				
	Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				

89

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Name of work:- Restoration of Link road from Lalpuri Vishnu Dham Kuria upto CHC Beetan in G.P. Beetan					Estimated Cost: Rs	₹ 99,000
(SH: P/L CC Pavement at Rd. 0/023 to 0/053) - D/WORK (Balance work)					Time:-	One month
					Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words	Amount
1	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundations of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802.803.1202 & 1203. M 25 Nominal Mix 1 : 1.5:3, and as per Direction of Engineer -in -charge. including carriage of material within all leads including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government.	18.00	Cum.			
Total						

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) © (17) 2/2012 dated 07.08.2018

Executive Engineer,
H.P.W.D. Division
Distt. Una (H.P.)

50

Schedule of quantity

Name of work :- Restoration of Path In Rodiyan wali Gali upto Pathakan G.P. Bhadiaran Tehsil Haroli Distt. Una (H.P.) (Deposit work)						Estimated Cost: Rs	₹ 98,148
(SH: C/O V- Shape drain & CC Overlay at Rd. 0/090.50 to 0/105.70)						Time:-	One month
DESCRIPTION						Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	5.02	Cum.				
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802.803, 1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	10.72	Cum.				
3	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundations of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802.803, 1202 & 1203. M 25 Nominal Mix 1 : 1.5 : 3. and as per Direction of Engineer -in -charge, including carriage of material within all leads, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	9.12	Cum.				
4	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802.803, 1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 4 : 8, including carriage of material within all leads, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	1.82	Cum.				
Total							

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PW (B) 171 2/03/2012 dated 07.08.2018

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Sb

Schedule of quantity

Name of work :- Restoration of Path in Rodiyan wali Gali upto Pathakan G.P. Bhadluran Tehsil Haroli Distt. Una (H.P.) (Deposit work)						Estimated Cost: Rs	₹ 97,501
(SH: C/D V- Shape drain & CC Overlay at Rd 0/075.40 to 0/090.50)						Time:-	One month
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Earnest Money:-	Rate in words	2000 Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	4.98	Cum.				
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6,including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	10.65	Cum.				
3	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundations of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802,803,1202 & 1203. M 25 Nominal Mix 1 : 1.5:3. and as per Direction of Engineer -in -charge, including carriage of material within all leads, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	9.06	Cum.				
4	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8, including carriage of material within all leads, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1.81	Cum.				
Total							

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018

**Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)**

SS

SCHEDULE OF QUANTITY

Name of work: **Painting work of Mini Secretariat building at Haroli Dist. Una (SH: Exterior painting work to Building Phase -III)- Deposit work**

Estimated Cost **₹206**
 Estimated Month **2000-**
 Time limit **One month**

S. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Finishing walls with Acrylic Smooth exterior paint of required shade Old work (Two or more coat applied @ 1.67 lit/ 10 sqm) on existing cement paint surface including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, joll tax sale tax, GST, labour cess or other taxes imposed by the Government.	508.10	Per Square metre			
2	Providing and applying white cement based putty of average thickness 1 mm. of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, joll tax sale tax, GST, labour cess or other taxes imposed by the Government.	152.12	Per Square metre			
3	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 lit/ 10 sqm over an under coat of primer applied @ 0.80 lit/ 10 sqm of approved brand and manufacturer including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, joll tax sale tax, GST, labour cess or other taxes imposed by the Government.	81.90	Per Square metre			
4	Providing and fixing double scaffolding system (cup lock type) on the exterior side of building/structure, upto 25 metre height, above ground level, including additional rows of scaffolding in stepped manner as per requirement of site, made with 40mm dia M.S. tube, placed 1.5 metre centre to centre, horizontal & vertical tubes joint with cup & lock system with M.S. Tubes, M.S. tube chafis, M.S. clamps and staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for cution of work of cleaning and/ or pointing and/ or applying chemical and etimelting it thereafter. The scaffolding system shall be stiffened with facings, runners, connecting with the building etc, wherever required. If feasible, for inspection of work at required ocasions with essential safety features for the workmen etc., complete as per directions and approval of Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, joll tax sale tax, GST, labour cess or other taxes imposed by the Government.	254.60	Per square metre			
Total						0
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)/2012/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No PBW(B)/A(31)/2020 dated 22.07.20						

Executive Engineer
Haroli Divn. Haroli
Haroli

68

Handwritten: 12

Schedule of quantity

Schedule of quantity					Estimated Cost: Rs	₹ 99,169
Name of work :-Improvement of Black spot on Ajouli Santoshgarh Tahliwal Polian road km 0/00 to 13/400.					Time:-	One month
(SIH) C/O Speed breaker with 100mm paver block & CC Pavement in Tahliwal Market at Rd. 4/120 (Bhs)					Earnest Money:-	2000
S. NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words	Amount
1	Scarifying the existing bituminous road surface to a depth of 150 mm and disposal of scarified material with a lift upto 3 m and lead upto 1000 m as per Technical Specification Clause 301.4. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	70.00	Sqm			
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6 . including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	7.00	Cum.			

Handwritten: 629

3	Providing and laying heavy duty precast cement concrete inter locking paver blocks vibro compacted upto M-50 grade i/c border or kurb block grey or coloured over sub-base of concrete with 25mm thick average thickness of cement mortar 1:4 (1 cement : 4 sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks i/c curing rubbing & polishing complete (Sub base concrete floor to be paid for. 100mm thick inter locking blocks, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.00	Sqm		
4	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 804, 1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	0.67	Cum		

629

5	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(i) nominal mix 1:1.5:3. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.30	Cum			
	Total					
	Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018					


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

629

SCHEDULE OF QUANTITY

Name of work:- C/O Levelling work in playground near GSSS Nangal Khurd Mohalla Thai Nangal Khurd (Phase-V)- Deposit work

Estimated Cost 98771
Earnest Money 2000/-
Time limit One month

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil/jumper work and their intermediate classification of soil, setting out true to the required lines, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the technical specification MORD 2014 section 300 of claused and 1600.1 and sorting out useful materials and stacking the same in all leads and lifts on acquired width of road and transportation for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to required width of the road or to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tool and labour if required. Any loss to the public private property during the course to execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all the cases as per the direction of engineer-in-charge including carriage of material with in all leads and lifts. All useful material such as stone, shingle, sand and slates etcetera shall be sorted out. A recovery of 22.05cum stone to be obtained from excavation cutting at the rate of Rs. 300/- (Rupees three hundred only) per cubic metre shall be effected on prorata bases in each running bill for this item. including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	441.00	Per cubic metre			
2	Construction of embankment with approved material obtained at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Table 300.1 and 300.2 with a lead upto 1000 metre as per Technical Specification Clause 301.5 including carriage of material with in all leads and lifts and other incidentals as per MORD specification 2014. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	299.20	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)/1712/0212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)/A(31)/2020 dated 22.07.20				Total	0

39

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Executive Engineer
Harold Division
HPPWD

42/

Schedule of quantity

Name of work:- Balance work for the C/O Community Park, Outdoor open gym at ward no. 2 & 4 G.P. Dulehar Tehsil Haroli Distt Una					Estimated Cost: Rs	₹ 98,000
HP. (Deposit work)					Time:-	One month
(SH: Hill side cutting for extended portion of park Rd. 0/016 to 0/020)					Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words	Amount
1	Earth work in excavation in hilly area in all heights and depths and in all kind of soil by mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification 2014 clause 302, 1603 in association with other clauses, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government..	700.00	Cum.			
Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018						


 Executive Engineer,
 H.P.W.D. Division Haroli
 Distt. Una (H.P.)

114

SCHEDULE OF QUANTITY

Estimated Cost 99854
Earnest Money 2000/-
Time limit One month

Name of work:- C/O Levelling work in playground near GSSS Nangal Khurd Mohalla Thai Nangal Khurd (Phase-III)- Deposit work

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/ mechanical means including saturated soil comprising of ordinary soil/ jumper work and their intermediate classification of soil, setting out true to the required lines, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the technical specification MORD 2014 section 300 of claused and 1600.1 and sorting out useful materials and stacking the same in all leads and lifts on acquired width of road and transportation for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to required width of the road or to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tool and labour if required. Any loss to the public private property during the course to execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all the cases as per the direction of engineer-in-charge including carriage of material with in all leads and lifts. All useful material such as stone, shingle, sand and slates etcetera shall be sorted out. A recovery of 22.04cum stone to be obtained from excavation cutting at the rate of Rs. 300/- (Rupees three hundred only) per cubic metre shall be effected on prorata bases in each running bill for this item. including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	440.92	Per cubic metre			
2	Construction of embankment with approved material obtained at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Table 300.1 and 300.2 with a lead upto 1000 metre as per Technical Specification Clause 301.5 including carriage of material with in all leads and lifts and other incidentals as per MORD specification 2014. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	300.10	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)@17/2/0212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(31/2020 dated 22.07.20				Total	0

Executive Engineer
Haroli Division
HPPWD

37

17

SCHEDULE OF QUANTITY

Estimated Cost 98694
Earnest Money 2000/-
Time limit One month

Name of work: C/o link road from house of Champa Devi Km 0/00 to 1/200 (SH : C/o B/wall at RD 1/140 to 1/147.30-RHS)-
Deposit work

Sl. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.01	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement, four sand, eight, graded crushed /broken stone aggregate-40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax, octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	28.11	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709, 1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax, octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	14.00	Each			
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax, octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	4.67	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/2,0212 dated 7.8.2018				Total:	0
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No PBW(BIA/311/2020 dated 22.07.20					

108

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Name of work:- Restoration of Link road from Lalpuri Vishnu Dham Kutia upto CHC Beetan In G.P. Beetan					Estimated Cost: Rs	₹ 99,660
(SH: P/L CC Pavement at Rd. 0/053 to 0/083.20) — 12 work (Balance work)					Time:-	One month
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:- Rate in words	2000 Amount
1	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundation of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802.803, 1202 & 1203. M-25 Nominal Mix 1 : 1.5 : 3. and as per Direction of Engineer -in -charge. including carriage of material within all leads, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malldhana toll tax, GST, labour cess or other taxes imposed by the Government..	18.12	Cum.			
Total						

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PSW (B) ©

(17) 2/02012 dated 07.08.2018


Executive Engineer,
H.P.P.W.D. Division
Distt. Una (H.P.)



SCHEDULE OF QUANTITY

Name of work: Restoration of Gramin Sampark from main road to Kumhar Basti ward No 4, 5 GP Heeranagar (SH:CO CC pavement RD 0/116 to 0/142.50)- Deposit work

Estimated Cost
Earnest money
Time

95348
2000/-
One month

Sl. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Loosening of the ground upto a level of 300mm(three hundred millimetre) below the sub grade level, watered graded and compacted in layers to meet requirement of table 300.1 and 300.2 for sub grade construction as per technical specification clause 303.5.2 as per drawing and HP PWD, technical specification clause 303.5.2 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, or other taxes imposed by the Government.	23.85	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty millimetre) nominal size in or under water ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	7.95	Per cubic metre			
3	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface raising by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 201-4 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	5.96	Per cubic metre			
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations upto all heights for all type structure complete of plain with cement concrete standard concrete design mix of grade M-25 (M-twenty) cement contents not less than 400kg (four hundred kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	11.93	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/2/2012 dated 7.8.2018				Total:	0
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					

Executive Engineer
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Name of work: Restoration of Gramin Sampark from main road to Kumhar Basti ward No 4, 5 GP Heeranagar (SH: C/O CC pavement RD 0/142.50 to 0/169)- Deposit work

Estimated Cost 99303
Earnest money 2000/-
Time One month

Sl. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Loosening of the ground upto a level of 300mm(three hundred millimetre) below the sub grade level, watered graded and compacted in layers to meet requirement of table 300.1 and 300.2 for sub grade construction as per technical specification clause 303.5.2 as per drawing and HP PWD technical specification clause 303.5.2 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government.	23.80	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement, four sand eight graded crushed broken stone aggregate 40mm (forty millimeter) nominal size in or under water or ground complete including pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, Malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	7.95	Per cubic metre			
3	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, Malkhana, toll tax, GST labour cess or other taxes imposed by the Government.	5.92	Per cubic metre			
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations upto all heights for all type structure complete of plain with cement concrete standard concrete design mix of grade M-25 (M-twenty) cement contents not less than 400kg (four hundred kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana toll tax, GST labour cess or other taxes imposed by the Government.	11.93	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)(C)17/2/0212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)(A)(3)1/2020 dated 22.07.20				Total:	0

Executive Engineer
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

32

SCHEDULE OF QUANTITY

Name of work: Repair & Maintenance of SDWG College at Beetan Tehsil Haroli Distt Una (SH: C/O R/Wall behind the Play ground)- phase -II
 Estimated Cost 98634
 Earnest Money 2000/-
 Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	8.14	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government..	27.53	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(h)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709.1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government..	8.00	Each			
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government..	9.47	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)@1712/0212 dated 7.8.2018				Total:	0
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(311)/2020 dated 22.07.20					

Executive Engineer,
H.P.P.W.D. Division,
Distt. Una (H.P.)

19

2

20

SCHEDULE OF QUANTITY

Name of work : C/O Gramin Sampark to house of Sh. Ram Lal S/O Sh. Tarsem Lal ward No-2 G.P. Beetan (SH: C/O C.C. pavement at RD 0052 to 0078)-under MMSY

Estimated Cost 99277

Earnest Money 2000/-

Time limit One month

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	4.62	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government.	8.56	Per cubic metre			
3	Providing and laying (M-25) (M-twenty five) Grade mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government.	12.78	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)@1712/0212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B)@1311/2020 dated 22.07.20				Total:	0

Executive Engineer
Haroli Division
HPPWD

26

SCHEDULE OF QUANTITY

Name of work : C/O Gramin Sampark to house of Sh. Ram Lal S/O Sh. Tarsem Lal ward No-2 G.P. Beetan (SH: C/O C.C. pavement at RD 0/026 to 0/052)-under MMSY

Estimated Cost 99463
Earnest Money 2000/-
Time limit One month

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	4.68	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement four sand eight graded crushed /broken stone aggregate 40mm (forty millimeter) nominal size in or under water or ground complete including pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	8.58	Per cubic metre			
3	Providing and laying (M-25) (M-twenty five) Grade mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	12.80	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@/1732/0212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B)A(31)/2020 dated 24.07.20				Total:	0


Executive Engineer
Haroli Division
HPPWD

87

SCHEDULE OF QUANTITY

Name of work:- C/O Levelling work in playground near GSSS Nangal Khurd Mohalla Thal Nangal Khurd (Phase-IV)- Deposit work

Estimated Cost 99865
Earnest Money 2000/-
Time limit One month

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/ mechanical means including saturated soil comprising of ordinary soil/ jumper work and their intermediate classification of soil , setting out true to the required lines, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the technical specification MORD 2014 section 300 of claused and 1600 1 and sorting out useful materials and stacking the same in all leads and lifts on acquired width of road and transportation for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to required width of the road or to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machinerries, materials , tool and labour if required. Any loss to the public private property during the course to execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all the cases as per the direction of engineer-in-charge including carriage of material with in all leads and lifts. All useful material such as stone, shingle, sand and slates etcetera shall be sorted out. A recovery of 22.05cum stone to be obtained from excavation cutting at the rate of Rs. 300/- (Rupees three hundred only) per cubic metre shall be effected on prorata bases in each running bill for this item, including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana , toll tax, GST, labour cess or other taxes imposed by the Government.	441.00	Per cubic metre			
2	Construction of embankment with approved material obtained at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Table 300.1 and 300.2 with a lead upto 1000 metre as per Technical Specification Clause 301.5 including carriage of material with in all leads and lifts and other incidentals as per MORD specification 2014. The rate includes sale tax octroi, royalty, malikhana , toll tax, GST, labour cess or other taxes imposed by the Government.	300.10	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)(31)/2020 dated 22.07.20				Total	0

Executive Engineer
Haroli Division
HPPWD

38

SCHEDULE OF QUANTITY

Name of Work : Special repair & other work of EFC building at Pandoga (SH: Aluminium work, W.S & S.I. etc)-Deposit work.						Estimated Cost	98941
						Earnest Money	2000
						Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE in		AMOUNT	
				Figures	Words		
1	Providing and fixing 35 mm(thirty five millimetre) thick Second class teak wood shutters with ISI marked M.S. pressed butt hinges bright finished of required size wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screw entire carriage of material within all leads and lifts and other incidentals as per direction by the Engineer-in-charge. The rate includes octroi, royalty, malikhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	2.52	Per square metre				
2	Providing and fixing 12mm (Twelve millimetre) thick in wall lining flat pressed three layer (medium density) particle board or graded wood Prelaminated one side decorative lamination and other side balancing lamination Grade I, Type II, IS : 12823 marked, including printing coat on unexposed arrangement and screws etc. complete entire carriage of material within all leads and lifts and other incidentals as per direction by the Engineer-in-charge. The rate includes octroi, royalty, malikhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.65	Per square metre				
3	Providing and fixing anodized aluminium work for doors, windows, ventilators and partitions with Jindal aluminium extrusions built up standard tubular and other sections of approved make conforming to IS-733 and IS-1285 anodized transparent or dyed to required shade according to IS-1868 fixed with rawl plugs and screws or with fixing clips or with expansion hold fasteners including necessary filling up of gaps at junctions and top and bottom, sides with required PVC/neoprene fill etc. Aluminium sections shall be smooth, rust free, straight mitered and jointed mechanically where ever required including cleat angle, aluminium snap leading for glazing/ paneling, C.P. brass stainless steel screw. all complete as per architectural drawing for entire carriage of material within all leads and lifts and other incidentals as per direction by the Engineer-in-charge. The rate includes octroi, royalty, malikhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	2.65	Per Kilogramme				
4	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in paneling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge. Pre-laminated particle board with decorative lamination on one side and balancing lamination on other side entire carriage of material within all leads and lifts and other incidentals as per direction by the Engineer-in-charge. The rate includes octroi, royalty, malikhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	16.10	Per square metre				

	Providing and fixing 300x15mm(three hundred into sixteen millimeter) anodized aluminium sliding door bolts anodized colour or shade with bolts and nuts screws etcetera complete including carriage of material within all leads and lifts as directed by Engineer-in-Charge.The rate includes octroi, royalty,malkhana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	10.00	Each				
6	Providing and fixing 300X10mm(three hundred into ten millimetre) anodized aluminium tower bolts (barrel type)anodized colour or shade with bolts and nuts screws etcetra complete including carriage of material within all leads and lifts as directed by Engineer-in-Charge.The rate includes octroi, royalty,malkhana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	10.00	Each				
7	Providing and fixing 125mm(one hundred twenty five millimeter) aluminium handles anodized transparent or dyed to required colour and shade with necessary screws etcetera complete including carriage of material within all leads and lifts as directed by Engineer-in-Charge.The rate includes octroi, royalty,malkhana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	8.00	Each				
8	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6 mm angle iron and 3 mm M.S. gussel plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer Using M.S. angels 40x40x6 mm for diagonal braces complete including carriage of material within all leads and lifts and other incidentals as per direction by the Engineer-in-charge .The rate includes octroi, royalty,malkhana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	3.15	Per square metre				
9	Providing and fixing glazing with glass panes of 4 mm thickness (weight not less than 10 kg/ sqm in aluminium door, window, ventilator shutters make it Hindal Co., Jindal Indian aluminium Co. and partition etcetera with PVC/neoprens gasket etcetera complete upto any floor level/height complete including carriage of material within all leads and lifts and other incidentals as per direction by the Engineer-in-charge .The rate includes octroi, royalty,malkhana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	2.70	Per square metre				
10	Providing and fixing C.P brass bib tap with capstan head 15mm dia including carriage of material within all leads and lifts and other incidentals as per direction by the Engineer-in-charge .The rate includes octroi, royalty,malkhana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	4.00	Each				
11	Providing and fixing C.P brass stop cock 15mm dia including carriage of material within all leads and lifts and other incidentals as per direction by the Engineer-in-charge .The rate includes octroi, royalty,malkhana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	2.00	Each				
12	Providing and fixing 600x450 mm (six hundred into four hundred fifty millimetre) beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete of Atul, Modi Guard, Golden Fish make including enitre carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.00	Each				

10

	Providing and fixing 600x120x5 mm (six hundred into one hundred twenty into five millimetre) glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm long screws, rawl plugs etc., complete of Hindware or Cera make including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.00	Each				
14	Providing and fixing chromium plated brass soap dish with C.P. Brass brackets fixed to wooden cleats with C.P. Brass screws in all floor level/height including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.00	Each				
15	Providing and fixing P.V.C. connection with brass union 300 /450mm length 15 mm dia including carriage of material within all leads and lifts and other incidentals as per direction by the Engineer-in-charge. The rate includes octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	3.00	Each				
16	Providing and fixing 100 mm sand cast iron grating for gully, or nahni trap, including carriage of material within all leads and lifts and other incidentals as per direction by the Engineer-in-charge. The rate includes octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	3.00	Each				
17	Providing and fixing CP towel rail 600 mm long towel rail with total length of 645 mm, width 78 mm and effective height complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour weighing not less than 190gms of Hindware or Cera make including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.00	Each				
18	Providing and fixing vitreous China wash basin with single hole for pillar tap with CP or M.S. brackets painted white including cutting holes and making good the same but excluding fittings flat back Wash basin No. 10010 size 550mmx400mm (Five hundred fifty millimetre into four hundred millimetre) in white shade of Cera, Parryware sanitary ware, Neycer or its equivalent make including carriage of material within all leads and lifts and other incidentals as per direction by the Engineer-in-charge. The rate includes octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.00	Each				
19	Providing and fixing C.P. brass pillar tap with capstan head 15mm dia including carriage of material within all leads and lifts and other incidentals as per direction by the Engineer-in-charge. The rate includes octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.00	Each				

Providing and fixing 510x1040 mm (five hundred ten into one thousand forty millimetre) bowl depth 250mm Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required Kitchen sink with drain board including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, maikana, toll, tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.00	Each				
---	------	------	--	--	--	--

100

	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank, 1000 litre Sintex or equivalent (minimum 3 layer) make including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	500.00	Per Litre				
22	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two coat complete including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	153.55	Per square metre				
23	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand (Neolac/Assian/Dulux/Berger) and manufacture including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	43.81	Per square metre				
24	Painting steel work with deluxe multi surface paint system for interiors and exterior using Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture in any floor level/ height including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	6.22	Per square metre				
25	Finishing walls with Acrylic Smooth exterior paint of (Neolac/Assian/Dulux/Berger) Jenson and Nicholson (J&N) GF-olden Paint Aqualac make required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) upto any floor/height including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	105.11	Per square metre				
26	Providing and laying cement concrete work of grade M-25 (M-twenty five) mechanically mixed and vibrated including curing complete including cost of form work above plinth level in all depth/heights including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	0.10	Per cubic metre				
27	Providing and laying for steel of approved make for reinforced cement concrete work including bending, binding, straightening and placing in position complete in all floor level/ heights including cost of binding wire complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, sale tax, GST, labour cess or other taxes imposed by the Government.	30.46	Per Kilo gramme				

bo

Schedule of quantity

Name of work: -Restoration of rain damages on Various road in Pandoga section under Sub- Division Khad HPPWD.					Estimated Cost: Rs	₹ 99,550
(SH: Deployment of excavator Cum Loader for Treming of Access soil in berm Removal of slips & C/O unlined drain etc. in rainy season)					Time:-	One month
					Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Deployment of Hydraulic excavator 0.90 cum fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock (where blasting is prohibited) as per direction of the Engineer in charge i/c all leads and lifts. The cost of Lubricant diesel etc. operator will be borne by the contractor	90.50	P/ Hour			
Total						

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018

96

Executive Engineer,
H.P.P.W.D. Division Harohi
Distt. Una (H.P.)

28

Schedule of quantity

Name of work: -Restoration of rain damages on Various road in Khad section under Sub- Division Khad HPPWD.					Estimated Cost: Rs	₹ 99,550
(SH: Deployment of excavator Cum Loader for Treming of Access soil in berm Removal of slips & C/O unlined drain etc. in rainy season)					Time:-	One month
					Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Deployment of Hydraulic excavator 0.90 cum fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock (where blasting is prohibited) as per direction of the Engineer in charge i/c all leads and lifts. The cost of Lubricant diesel etc. operator will be borne by the contractor	90.50	P/ Hour			
Total						

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

97

Executive Engineer,
H.P.P.W.D. Division Haroh
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Estimated Cost 99982
Earnest Money 2000/-
Time limit One month

Name of work:- C/O Levelling work in playground near GSSS Nangal Khurd Mohalla Thai Nangal Khurd (Phase-II)- Deposit work

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil/ jumper work and their intermediate classification of soil, setting out true to the required lines, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the technical specification MORD 2014 section 300 of clause and 1600.1 and sorting out useful materials and stacking the same in all leads and lifts on acquired width of road and transportation for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to required width of the road or to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tool and labour if required. Any loss to the public private property during the course to execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all the cases as per the direction of engineer-in-charge including carriage of material with in all leads and lifts. All useful material such as stone, shingle, sand and slates etcetera shall be sorted out. A recovery of 22.04cum stone to be obtained from excavation cutting at the rate of Rs. 300/- (Rupees three hundred only) per cubic metre shall be effected on prorata bases in each running bill for this item. including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	440.90	Per cubic metre			
2	Construction of embankment with approved material obtained at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Table 300.1 and 300.2 with a lead upto 1000 metre as per Technical Specification Clause 301.5 including carriage of material with in all leads and lifts and other	300.40	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)@17/2/0212 dated 7.8.2018				Total	0
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B)A(31)/2020 dated 22.07.20					

Executive Engineer
Haroli Division
HPPWD

36

SCHEDULE OF QUANTITY

Name of work: Restoration of R/D on link road vill Singan to HP boundary (SH : C/o Biwall at RD 0/120 to 0/130.70)

Estimated Cost 99279
Earnest Money 2000/-
Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST labour cess or other taxes imposed by the Government.	12.84	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST labour cess or other taxes imposed by the Government.	27.50	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709.1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST labour cess or other taxes imposed by the Government.	14.00	Each			
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST labour cess or other taxes imposed by the Government.	7.70	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				Total:	0
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(31)/2020 dated 22.07.20					

**Executive Engineer,
H.P.P.W.D. Division Harohi
Distt. Una (H.P.)**

SCHEDULE OF QUANTITY

Estimated cost 99729
Earnest money 2000
Time limit One month

Name of Work: C/O Link road to Harijan Basti Panjlawar (SH:- C/O C.C. pavement at RD 0/270 to 0/279.50- Deposit work

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means. (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, Malkhana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	2.66	Per cubic metre			
2	Excavation in hilly area in all heights and depths and in all kind of soil by ordinary rock, hard rock, chiselling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification clause 302, 1603.1 and 1603.2 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, Malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	9.83	Per cubic metre			
3	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -> material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, Malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	9.40	Per cubic metre			
4	Providing and laying cement concrete 1:4:6 (one cement four sand eight graded crushed stone aggregate 40mm) forty millimeter nominal size, mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, Malkhana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	10.26	Per cubic metre			
5	Providing and laying (M-25) (M-twenty five) Grade mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents, not less than 410kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, Malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	9.76	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)X(17)20212 dated 7.8.2018				G.Total	0
	2) The bidder are requested to submit their bid as per modification issued by the Principal Secy PW to the Govt of HP vide letter No.PBW(B) A(31)2020 dated 22.7.2020 & Govt of HP vide letter No.PBW(B) A(3) 12/2020-1 dated 7.10.2021					

Executive Engineer
Haroli Division
HP.PWD, Haroli

(98)

SCHEDULE OF QUANTITY

Name of work: Repair & Maintenance of SDWG College at Beelan Tehsil Haroli Distt Una (SH/C/O R/Wall behind the Play ground)- phase -I
Deposit work

Estimated Cost 99506
Earnest Money 2000/-
Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Dismantling of cement concrete by mechanical means using pneumatic tools breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials upto any lead, stacking service able and unserviceable materials separately as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	17.50	Per cubic metre			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	6.88	Per cubic metre			
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement, four sand, eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	23.25	Per cubic metre			
4	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614, 709, 1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	8.00	Each			
5	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	8.00	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/2/2012 dated 7.8.2018				Total:	0
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No PBW(B)(A/31/2020 dated 22.07.20					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (Raj.)

SCHEDULE OF QUANTITY

Name of work: C/o link road from house of Champa Devi Km 0/00 to 1/200 (SH - C/o B/wall at RD 1/147.30 to 1/154.70-RHS)-
Deposit work

Estimated Cost 99592
Earnest Money 2000/-
Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of odrol, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.10	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water/dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government.	28.49	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709, 1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government.	12.00	Each			
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government.	4.58	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(17/2/2012 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No PBW(B)(A)(31/2/2020 dated 22.07.20				Total:	0

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.R.)

107

Schedule of quantity

Name of work:- Balance work for the C/O Community Park, Outdoor open gym at ward no. 2 & 4 G.P. Dulehar Tehsil Haroli Distt Una HP. (Deposit work)					Estimated Cost: Rs	₹ 99,459
(SH: C/O Breast wall for protection of hill side on extended portion of park front side length= 11.00 Rd. 0/00 to 0/011)					Time:-	One month
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:- Rate in words	2000 Amount
1	Earth work in excavation for structures such as Retaining walls, breasts walls, culverts, drains and parapets etcetra in all type of classification of soil as per drawing and technical specifications Clause 305 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m (Fifty metre), dressing of sides and bottom and back filling in trenches with excavated suitable material. Ordinary soil upto 3.00m (Three metre) depth. and as directed by the Engineer-in- Charge. . Including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	11.88	Cum.			
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:4:8. (one cement: four sand : eight graded crushed stone aggregate 40 mm (Forty millimetre nominal size)) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-charge. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	29.21	Cum.			
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	18.00	Each			
Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018						


Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

175

SCHEDULE OF QUANTITY

Estimates cost:- Rs. 99802/-
 Earnest Money:- Rs. 2000/-
 Time Limit:- One Month.

Name of work :- A/R & M/O on Old Saloh Bhadouri road Km 0/00 to 9/615 (SH: P/L polished granite stone, marble work, P/F cat eyes etc. at Karampur chowk)

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:3 (one cement : four coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete upto any floor level height as specified and as directed by the Engineer-in Charge. Polished Granite stone slab Jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	3.17	Per square metre			
2	Marble work gang saw cut (polished and machine cut) of thickness 18 mm for wall lining (veneer work), backing filled with a grout of average 12 mm thick in cement mortar 1:3 (1 cement : 3 coarse sand), including pointing with white cement mortar 1:2 (1 white cement : 2 marble dust) with an admixture of pigment to match the marble shade including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	10.10	Per square metre			
3	Steel (Tata/Sail/ Jindal) work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	353.52	Per Kilogramme			
4	Providing and fixing cat eye make (3M) Solar Powered of size 100x20mm (one hundred into twenty millimetre) made of heavy duty body shall be molded dual shank ASA /acrylic styrene acrylonitrile) or (HP/High impact polystyrene) or ABS having electronically welded micro prismatic lens with abrasion resistant coating as approved by Engineer-in-charge. The road stud shall support a load of 13635 by tested in accordance with ASTM D 4280. The slope of retro reflective surface shall be 35+/-5 degrees to base. The reflective panels on both side with at least 12cm (Twelve centimetre) of each area side. The luminance intensity should be as per the specification ASTM as recommended in BS-8873 part 4 1973 as per approved sample and manufacture by the Engineer-in-charge including carriage of material within all leads and lifts.	14.00	Each			
	Total					0
Notes:-	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)/17/2/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No. PBW(B)/A(3)/2020 dated 22.07.20					

Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

95

SCHEDULE OF QUANTITY					Estimated Cost	98100
					Earnest Money	2000/-
					Time limit	Two month
Name of work : Restoration of rain damages on link road to village Singan to HP boundary Km 0/00 to 1/300, Tahliwal Bathri road Km 0/00 to 7/700, Santoshgarh Tahliwal Polian road in Tahliwal Section under Sub-Division Tahliwal HP.PWD.,(SH:Deployment of excavator cum loader & tractor with trolley for Treming of Access soil on berms , C/o unlined drain & clearance of road side drains in rainy season etc.)						
S. No.	Description of work	Quantity	Unit	Figures	RATE In Words	AMOUNT
1	Hiring of hydraulic excavator 0.90 cum. fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock(where blasting is prohibited) as per direction of the Engineer-in-charge .The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	71.00	Per Hour			
2	Hiring of Tractor with Trolley 3.00cum capacity to be deployed for disposing/caring of material like earth kankar moorum, shingles and boulder etc. including cost of fuel, oil lubricants and wages of operational staff any repair breakage during operation will be carried out by the owner at his risk and cost including shifting of Tractor with Trolley from one place to other and six hours per day will be required working hours .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.00	Per Day			
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018.					Total:	0
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Schedule of quantity					Estimated Cost: Rs		₹ 99,153
Name of work :Restoration of Gramin Sampark from the H/O Sh. Surinder Singh to Shahid Baba Mandir Ward No. 2 GP Palkwah. (Deposit work)					Time:-		One month
(SH: P/L CC Pavement at Rd. 0/023.90 to 0/047.70)					Earnest Money:-		2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. including carriage of material within all leads. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	21.42	Cum.				
2	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	27.13	Cum.				
3	Construction of Embankment with Material Obtained from Roadway Cutting Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	35.70	Cum.				

91

4	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401.. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	5.36	Cum.		
5	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (CC 1:4:8). including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	7.14	Cum.		
6	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundations of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802,803,1202 & 1203, M 25 Nominal Mix 1 : 1.5:3. and as per Direction of Engineer -in -charge, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	10.71	Cum.		
Total					
Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. P&W (B) © (17) 2/02012 dated 07.08.2018					

91

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Estimated cost 59691
Earnest money 2000
Time limit One month

Name of Work: C/O link road to Harlijan Basti Panjawa (SH:- C/O C.C. pavement at RD 0/299 to 0/308.50). Deposit work

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.58	Per cubic metre			
2	Excavation in hilly area in all heights and depths and in all kind of soil by ordinary rock, hard rock, chiselling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification clause 302, 1603.1 and 1603.2 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	9.50	Per cubic metre			
3	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -1 material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	9.40	Per cubic metre			
4	Providing and laying cement concrete 1:4:8 (one cement: four sand eight graded crushed stone aggregate 40mm/ forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	10.20	Per cubic metre			
5	Providing and laying (M-25) (M-twenty five) Grade mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	9.80	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(17/20212 dated 7.8.2018.				G.Total	0
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No P.BW(B) A(3) 1/2020-1 dated 7.10.2021					

Executive Engineer
Haroli Division
HP.PWD.,Haroli

106

SCHEDULE OF QUANTITY

Name of Work : Special repair & other work of EFC building at Pandoga (SH: C/O drain , P/L paver block in front of building)-Deposit						99636
Work.						2000
						One month
S. No.	Description of work	Quantity	Unit	Figures	RATE In	AMOUNT
				Words	Time limit	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	8.40	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type structure complete of plain cement concrete grade M-10 (M-Ten) with cement contents not less than 250kg (Two hundred fifty kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water/dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government.	4.43	Per cubic metre			
3	Steel (Tata/Sail/Jindal) work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	340.20	Per Kilogramme			
4	Providing and laying of interlocking concrete block pavements having thickness 60mm thick as per drawing and technical specification clause 1504, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government.	57.26	Per square metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)(17)/20212 dated 7.8.2018				Total:	0
	2) The rates shall be inclusive of all types of taxes including GST etcetera)					

Executive Engineer
Haroli Division,
HPPWD Haroli

101

40

DRAFT SCHEDULE OF QUANTITY

Name of work: Restoration of R/O on link road vill Singan to HP boundary (SH : C/o Biwall at RD 0/153 to 0/163.70)

Estimated Cost 99444

Earnest Money 2000/-

Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octon, royalty, malikhana , toll tax, GST, labour cess or other taxes imposed by the Government.	12.84	Per cubic metre	160.00	Rupees One hundred sixty only	2054
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental The rate includes sale tax octon, royalty, malikhana , toll tax, GST labour cess or other taxes imposed by the Government.	27.50	Per cubic metre	3300.00	Rupees three thousand three hundred only	90750
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v) 20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 514.709, 1204.3.7 including carriage of material within all leads and lifts and other incidental The rate includes sale tax octon, royalty, malikhana , toll tax, GST labour cess or other taxes imposed by the Government.	14.00	Each	160.00	Rupees One hundred sixty only	2240
4	Providing Back filling behind abutment/ wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octon, royalty, malikhana , toll tax, GST labour cess or other taxes imposed by the Government.	8.00	Per cubic metre	550.00	Rupees five hundred fifty only	4400
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@1712/0212 dated 7.8.2018				Total:	99444
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(31)/2020 dated 22.07.20					

76

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY						
S. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
	Name of work : Restoration of rain damages on Gurplah to Gondpur road 0/00 to 4/00 , Panjawar Bathri road to Satsang Ghar Bathu Rahar Mohalla upto Gurplah Gondpur road Km 0/00 to 2/00 ,link road Gowshala Bathri to main Bazar Bathri Km 0/00 to 1/100 in Tahliwal Section under Sub-Division Tahliwal HP.PWD. (SH:Deployment of excavator cum loader & tractor with trolley for Treming of Access soil on berms , C/o unlined drain & clearance of road side drains in rainy season etc.)					Estimated Cost Earnest Money Time limit
						98100 2000/- Two month
1	Hiring of hydraulic excavator 0.90 cum. filed with rock breaker on through rate basis for making drain and side cuttings in hard rock(where blasting is prohibited) as per direction of the Engineer-in-charge .The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	71.00	Per Hour			
2	Hiring of Tractor with Trolley 3.00 cum. capacity to be deployed for disposing/carring of material like earth kankar moorum, shingles and boulder etc. including cost of fuel, oil lubricants and wages of operational staff any repair breakage during operation will be carried out by the owner at his risk and cost including shifting of Tractor with Trolley from one place to other and six hours per day will be required working hours .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.00	Per Day			
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)(17)2/20212 dated 7.8.2018 3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No. PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No. PBW(B) A(3) 1/2020-1 dated 7.10.2021						Total: 0

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Name of Work : Special repair & other work of EFC building at Pandoga (SH: Water proofing treatment on roof, P/L vitrified tile etc.) - Deposit work.					Estimated Cost		99778	
					Earnest Money		2000	
					Time limit		One Year	
S. No.	Description of work	Quantity	Unit	Figures	RATE In		AMOUNT	
					Words			
1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkials, architrave, holdfasts etc. complete and stacking upto any lead and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	3.00	Per cubic metre					
2	Repairs to plaster in patches of 2.50 Sq.M. and under and 10 to 15mm thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within any lead with cement mortar 1:3 (one cement : three sand) including entire carriage of material.	13.74	Per square metre					
3	Dismantling tiled floors laid in mortar upto floor two level including stacking of serviceable materials and disposal of un-serviceable materials within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	4.32	Per square metre					
4	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer, 3 mm thick water proofing membrane, black finished reinforced with glass fibre matt consisting of a coat of bitumen primer for bitumen membrane @ 0.40 lit/ltr/sqm by the same membrane manufactured of density at 25°C, 0.87-0.89 kg/litre and viscosity 70 - 160 cps. Over the primer coat the layer of butanetorch and sealing all joints etc., and preparing the surface complete. The vital physical and chemical parameters of the membrane shall be as under: Joint strength in longitudinal and transverse direction at 23°C as 350/300 N/5 cm. Tear strength in longitudinal and transverse direction as 60/60 N. Softening point of membrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D-5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane 3mm thick, including carriage of materials within all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	47.75	Per square metre					
5	Providing and laying Vitrified tiles Size of 600x600 mm (six hundred into six hundred millimetre) of Nitcol/Rak/Johnson/Orient/ Somany or its equivalent with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (one cement: three coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement and matching pigments etc. complete upto any floor level height 1 including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	32.10	Per square metre					

102

	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be as per the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	5.76	Per square metre		
7	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm (three hundred into three hundred millimetre) or more of 1st quality conforming to IS : 15622, of of Nitco / Khajana/ Somany/Johnson/ AGL/Orient/Raj make in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (one Cement : four Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including pointing the joints with white cement and matching pigments etc., complete including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	5.27	Per square metre		
8	Providing wood work in double frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length of Second class teak wood complete including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	0.05	Per cubic metre		
9	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, complete including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	2.70	Per square metre		
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No PBW(B)(17)2/0212 dated 7.8.2018			Total:	0
	2) The rates shall be inclusive of all types of taxes including GST etc(etera)				

Executive Engineer
Haroli Division,
HPPWD Haroli

102

43

Schedule of quantity

Name of work: -Restoration of rain damages on various road under section Haroli Sub-Division Haroli .					Estimated Cost: Rs	₹ 98,100
(SH: Deploymet of excavator Cum Loader & Tractor for Treming of Access soil in berm Removal of slips & C/O unlinrd drain etc. in rainy season etc.)					Time:-	One month
					Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Deploymet of Hudraulic excavator 0.90 cum fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock(where blasting is prohibited) as per direction of the Engineer in charge i/c all leads and lifts. The cost of Lubricant diesel etc. operator will be borne by the contractor.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	71.00	P/ Hour			
2	Hiring of Tractor with Trolley 3.00-cum. capacity to be deployed for disposing/carring of material like earth kankar moorum, shingles and boulder etc. including cost of fuel, oil lubricants and wages of operational staff any repair breakage during operation will be carried out by the owner at his risk and cost including shifting of Tractor with Trolley from one place to other and six hours per day will be required working hours , including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8 00	P/day			
Total						

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

603

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY						
Name of work :- Restoration of rain damage on link road Old Haroli road Gugga Mandir upto Pajal Vojna Haroli Km 0/00 to 2/140-RHS (SH: C/O U shape drain at RD 2/070 to 2/100- RHS)			Estimates cost:- Earnest Money:- Time Limit:-		99064 Rs. 2000/- One Month.	
S. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and running of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	38.25	Per Cubic metre.			
2	Providing and laying mechanically mixed and vibrated concrete for plain reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:3:6 (One cement three sand six graded crushed broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or building out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	21.38	Per Cubic metre.			
3	Providing and laying (M-25) (M-twenty five) Grade Design Mix mechanically mixed and vibrated concrete for plain reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	0.9	Per cubic metre			
4	Providing and laying mild steel medium tensile steel bars for steel (approved make) reinforcement for reinforced cement concrete work including bending, binding, straightening and placing in position complete in all floor level/ heights including cost of binding wire complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	60	Per Kg			
Note:-					Total:-	0
1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)(17)2/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(BA)(31)20120 dated 22.07.20						

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

127