

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PWD/JMD/CB/TENDER/2024-25
To

1947-55


DATED: 26-06-25

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject :- Tender Notice.


Enclosed kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on Department website as per notification of Principal Secretary (PW) to the Govt. of HP vide No. PBW(B)A(3)1/2024 dated 03.01.2024 as the works mentioned in the notice inviting tender are urgent/emergent nature of works in public interest.

Encl:-As above


Executive Engineer,
HPPWD Division,
Jawalamukhi.

Copy forwarded to the following:-

1. The FC-Cum Secy.(PW) to the Govt. of HP.Shimla-2.
2. The Engineer-in-Chief, HPPWD., Shimla.
3. The Chief Engineer(KZ) HP.PWD. Dharamshala.
4. The Superintending Engineer, Circle HP.PWD. Dehra.
5. All the Executive Engineer under North Zone.
6. All the Assistant Engineer under Dehra Division.
7. The Deputy Commissioner Kangra at Dharamshala.
8. The SDM/Tehsil/President MC Jawalamukhi.
9. The BDO Dehra /Pragpur/ Nagrota Surian/Surani.
10. Notice Board.
11. All the Head of Branches.
12. All the Contractors working under Jawalamukhi Division.



Executive Engineer,
HP.PWD Division,
Jawalamukhi.

Exigency Certificate

It is certified that the tenders invited vide this office NIT No.....1947-55.....dated...26/06/25 are of emergent nature of work and in public interest.

Place:

Dated:


Executive Engineer,
HPPWD Division,
Jawalanukhi.

H. P. P.W.D. TENDER


Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Jawalamukhi Division HPPWD., Jawalamukhi on behalf of the Governor of HP for the following works from the approved and eligible contractors (C&D Class) enlisted in HPPWD.

TENDER SCHEDULE:

- | | |
|---|--------------------------------|
| 1. Date and time of receipt of application for tender form: | 04.07.2025 upto 12.00 Noon |
| 2. Date and time of issue of tender form: | 04.07.2025 12:00 PM to 5.00 PM |
| 3. Date and time of receipt of tenders: | 05.07.2025 upto 10.30AM |
| 4. Date and time of opening of tenders: | 05.07.2025 at 11.00 AM |

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Jawalamukhi Division HPPWD Jawalamukhi must accompany with each tender.

Job No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
01	Repair and Maintenance of link road from Jarundi to Parountha KM 0/0 to 3/500 (SH: Removal of Slips, Bush Cutting & C/o Drain at Various RDs KM 0/0 to 3/500) SDF/2024/731	Rs. 99,646.00	Rs.2,000/-	One Month	Rs.350/-
02	Repair and Maintance of link road from Bulli to Sehorbala KM 0/0 to 3/500 (SH: Removal of Slips, Bush Cutting & C/o Drain at Various RDs 0/0 to 3/500) SDF/2024/730	Rs. 99,041.00	Rs.2,000/-	One Month	Rs.350/-
03	Repair and Maintenance of link road from Tihri to Daloh KM 0/0 to 8/240 (SH: Removal of Slips, Bush Cutting & C/o Drain at Various RD 4/120 to 8/240) SDF/2024/729	Rs. 99,085.00	Rs.2,000/-	One Month	Rs.350/-
04	Repair and Maintenance of link road from Bulli to Village Tal Harizan Basti KM 0/0 to 1/800 (SH: Removal of Slips, Bush Cutting & C/o Drain Various RD 0/0 to 3/00) SDF/2024/735	Rs. 99,682.00	Rs.2,000/-	One Month	Rs.350/-
05	Repair and Maintenance of link road from Tihri to Daloh KM 0/0 to 8/240 (SH: Removal of Slips, Bush Cutting & C/o Drain at Various RDs 0/0 to 4/120) SDF/2024/728	Rs. 99,117.00	Rs.2,000/-	One Month	Rs.350/-
06	Repair and Maintenance of Chowki to Kasar KM 0/0 to 5/00 (SH: Removal of Slips, Bush Cutting & C/o Drain at Various RDs 0/0 to 3/00) SDF/2024/726	Rs. 99,682.00	Rs.2,000/-	One Month	Rs.350/-
07	A/R & M/O HPPWD Rest House at Jawalamukhi in Distt. Kangra (H.P.) (SH: C/o Stone Masonry Boundary Wall and Shutter, Putty etc.).	Rs. 99,447.00	Rs.2,000/-	One Month	Rs.350/-
1	The contractors/firms should possess the following documents (Photocopy to be attached):				
(i)	Latest renewal of enlistment.				
(ii)	PAN (Permanent Account No.)				
(iii)	Registration under HP GST/ (TIN No.).				
(iv)	EPF (Employee Provident Fund Account No.)				
2	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case.				
3	If any of the date mentioned above happened/to be Gazetted Holidays the same shall be processed on next working day.				
4	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).				
5	The next tender will be issued only after completion of previous works in hand.				
6	The offer of the tender shall remain valid upto 30 days after the opening.				


Executive Engineer
HPPWD Division Jawalamukhi
Distt Kangra H.P
on behalf of Governor of Himachal Pradesh

PERCENTAGE BILL OF QUANTITY

Job No. page 1

Estimate Cost :- Rs.99646.00
Earnest Money :-Rs. 2000.00
Time Limit :- One Month.

Name of work:- Repair and maintenance of link road Jarundi to Prounthu Km. 0/00 to 3/500 (SH:-Removal of slips , Bush cutting & Construction of drain at various RD.3/500) SDF/2024/731

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, GST tax or any other taxes imposed by the Government	187.75 Square metre	135.00	Rupees One Hundred Thirty Five Only	Per Square metre	25,346.00
2	Cleaning jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30cm (Thirty centimeter) measured at a height of 1mtr (One metre) above ground and removal of rubbish upto a distance of 20mtr (Twenty metres) outside the periphery of the area cleared and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the	4275.00 Square metre	15.00	Rupees Fifteen Only	Per Square metre	64,125.00

Executive Engineer,
Jawalamulhi Division,
HPPWD Jawalamulhi

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99041.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Repair and maintenance of link road Bulli to Sehorbala Km. 0/00 to 3/500 (SH:-Removal of slips , Bush cutting & Construction of drain at various RD.3/500) SDF/2024/730

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, GST tax or any other taxes imposed by the Government	238.82 Square metre	135.00	Rupees One Hundred Thirty Five Only	Per Square metre	32,241.00
2	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30cm (Thirty centimeter) measured at a height of 1mtr (One metre) above ground and removal of rubbish upto a distance of 20mtr (Twenty metres) outside the periphery of the area cleared and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the	4050.00 Square metre	15.00	Rupees Fifteen Only	Per Square metre	60,750.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	110.00 Running metre	55.00	Rupees Fifty Five Only	Per Running metre	6,050.00
	Total					99,041.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for Rs 9,90,411/- only.

Executive Engineer,
Jawalamulhi Division,
APPWD Jawalamulhi

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99085.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Repair and maintenance of link road Tihri to Daloh Km. 0/00 to 8/240 (SH:-Removal of slips , Bush cutting & Construction of drain at various RD. 4/120 to 8/240) SDF/2024/729

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, GST tax or any other taxes imposed by the Government	154.15 Square metre	135.00	Rupees One Hundred Thirty Five Only	Per Square metre	20,810.00
2	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30cm (Thirty centimeter) measured at a height of 1mtr (One metre) above ground and removal of rubbish upto a distance of 20mtr (Twenty metres) outside the periphery of the area cleared and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the	4320.00 Square metre	15.00	Rupees Fifteen Only	Per Square metre	64,800.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307, and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	245.00 Running metre	55.00	Rupees Fifty Five Only	Per Running metre	13,475.00
Total						99,085.00
		% Above/below				
		Quoted Amount in Figures				
		Quoted Amount in Words				

*Bill of quantity checked and approved
for Rs 99,085/- only.*

Executive Engineer,
Jawalamudi Division,
BPMWD Jawalamudi

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99682.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Repair and maintenance of link road Bulli to village Tal Harizan Basti Road Km. 0/0 to 1/800 (SH:-Removal of slips , Bush cutting & Construction of drain at various RD. 0/00 to 3/00) SDF/2024/735

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, GST tax or any other taxes imposed by the Government	241.75 Square metre	135.00	Rupees One Hundred Thirty Five Only	Per Square metre	32,636.00
2	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30cm (Thirty centimeter) measured at a height of 1mtr (One metre) above ground and removal of rubbish upto a distance of 20mtr (Twenty metres) outside the periphery of the area cleared and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the	3150.00 Square metre	15.00	Rupees Fifteen Only	Per Square metre	47,250.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	350.00 Running metre	55.00	Rupees Fifty Five Only	Per Running metre	19,250.00
	Total					99,136.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Beddy quantity checked & approved
for Rs 99,136/-

Executive Engineer,
 Jawalamutti Division,
 H.P. WD Jawalamulhi

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99117.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Repair and maintenance of link road Tihri to Daloh Km. 0/00 to 8/240 (SH:-Removal of slips , Bush cutting & Construction of drain at various RD. 4/120) SDF/2024/728

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, GST tax or any other taxes imposed by the Government	146.88 Square metre	135.00	Rupees One Hundred Thirty Five Only	Per Square metre	19,829.00
2	Cleaving jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30cm (Thirty centimeter) measured at a height of 1mtr (One metre) above ground and removal of rubbish upto a distance of 20mtr (Twenty metres) outside the periphery of the area cleared and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the	4387.50 Square metre	15.00	Rupees Fifteen Only	Per Square metre	65,813.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	245.00 Running metre	55.00	Rupees Fifty Five Only	Per Running metre	13,475.00
	Total					99,117.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for Rs 99117/- only

Executive Engineer,
Jawalamulhi Division,
APPWD Jawalamulhi

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99682.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Repair and maintenance of link road Chowki to Kasar Km. 0/00 to 5/500 (SH:-Removal of slips , Bush cutting & Construction of drain at various RD. 0/00 to 3/00) SDF/2024/726

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, GST tax or any other taxes imposed by the Government	174.31 Square metre	135.00	Rupees One Hundred Thirty Five Only	Per Square metre	23,532.00
2	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30cm (Thirty centimeter) measured at a height of 1mtr (One metre) above ground and removal of rubbish upto a distance of 20mtr (Twenty metres) outside the periphery of the area cleared and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the	4545.00 Square metre	15.00	Rupees Fifteen Only	Per Square metre	68,175.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307, and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	145.00 Running metre	55.00	Rupees Fifty Five Only	Per Running metre	7,975.00
Total						99,682.00
		% Above/below				
		Quoted Amount in Figures				
		Quoted Amount in Words				

Bill of quantity checked and approved for Rs 99682 only.

Executive Engineer,
Jawalamulhi Division,
PPWD Jawalamulhi

PERCENTAGE BILL OF QUANTITY

Name of Work: - A/R & M/O HPPWD Rest House at Jawalamukhi Tehsil Jawalamukhi District Kangra Himachal Pradesh (SH:- C/O Stone Masonary Boundary wall & Shutter, Putty etc.

Estimated Cost:- 99447.00
Earnest Money:- 2000/-
Time Limit:- One Month

Sr. No.	Description of work	Qty.	Unit	Rate		Amount Rs.
				Figures	Words	
1	Random rubble masonry with hard stone of approved quality in foundation and plinth including leveling up with cement concrete 1:6:12 (one cement isto six sand isto Twelve graded stone aggregate) 20 mm (Twenty millimetre nominal size) at plinth level in cement mortar 1:6 (one cement isto six sand) including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	5.76	Per cubic metre	5843.55	Rupess Five Thousand Eight Hundred Forty Three And Paise Fifty Five Only	33659.00
2	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	83.30	Per Square metre	264.35	Rupess Two Hundred Sixty Four And Paise Thirty Five Only	22020.00
3	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately Sal wood complete as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	0.12	Per cubic metre	95763.05	Rupess Ninety Five Thousand Seven Hundred Sixty Three And Paise Five Only	11492.00
4	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, complete as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	3.69	Per Square metre	2779.10	Rupess Two Thousand Seven Hundred Seventy Nine And Paise Ten Only	10255.00

5	Providing and fixing anodized aluminium work No.14081 of Jindal/Hindalco for door and window ventilators and partitions wall frames extruded built up standard tubular and other sections of approved make conforming to IS:733 and IS:1285 anodized transparent or dyed to required shade according to IS:1868 (Minimum anodic coating of grade AC 15) fixed with rawl plugs and screws or with fixing clips or with expansion hold fasteners including necessary filling up of gaps at junctions at top, bottom and sides with required PVC/neoprene felt etcetra Aluminium sections shall be smooth, rust free, straight, mited and jointed mechanically where ever required including cleat angle, aluminium snap beading for glazing/paneling C.P. brass/stainless steel screws all complete as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	28.56	Per Kilogram	420.45	Rupees Four Hundred Twenty And Paise Forty Five Only	12008.00
6	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS:12823 Grade I Type II, in paneling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. Pre-laminated particle board with decorative lamination on both side as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	3.08	Per Square metre	949.20	Rupees Nine Hundred Forty Nine And Paise Twenty Only	2924.00
7	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose material and other foreign matters, sand papered smooth to give final matt finish to the surface complete. as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	83.30	Per Square metre	85.10	Rupees Eighty Five And Paise Ten Only	7089.00
Grand Total						99447.00
% Above/below						
Quoted Amount in Figures						
Quoted Amount in Words						

Executive Engineer,
Jawalamukhi Division,
HPPWD Jawalamukhi.

Assistant Engineer
H.P.P.W.D. Sd. Division
Jawalamukhi (H.P.)