HIMACHAL PRADESH
PUBLIC WORK DEPARTMENT

No. PW/DT/TA/ NIT /2025-26- 3653 Dated:- 14-7-2025

To,

The Executive Engineer
IT Cell Nirman Bhawan Nigam Vihar
HP PWD Shimla

Subject:_ Regarding NIT for uploading on HP PWD website .

Enclosed please find herewith the Notice inviting tender Notice along with schedule of quantity for uploading on HP PWD website. This is for your kind information and necessary action at your end please.

Encls:- NIT copy &12Nos copy of Schedule of quantity.

Executive Engineer
Tanda Division HP PWD
at Nagrota Bagwan

CERTIFICATE

Certified that the tenders of works, called vide this office letter No. PW-DT-NIT-2025-26-3638-52 Dated:- 14-07-2025 are urgent nature.

Executive Engineer
Tanda Division HP PWD
at Nagrota Bagwan

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Sealed item rate tender on form No. 6 & 8 are hereby invited by the **Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan** on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **22-07.2025** up to **11:00 A.M**. And the same shall be opened on the same day at **04:00 P.M**. in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) **on 21.07.2025** up to **4:00 P.M** and the application for issue of tender form shall be received on **19.07.2025** up to **12:00** noon. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1	Construction of Pucca Path from tiali to the House of Sh Madan Lal in Gram Panchayat Muhalkar (Chahri) in Distt Kangra HP deposit work (SH: Providing and laying cement concrete pavement (MPR/2018/199)	120360/-	2550.00	Two months
2	Restoration of rain damages on Nagrota Massal Rajhoon road km 0/00 to 8/00 in District Kangra HP Deposit work (SH: Construction of culvert flooring wrk at RD 1/580, Toe wall, Parapet Edge wall at RD 1/582 to 1/601. SDF/2024/1763).	180340/-	3650.00	One Months
3	Restoration of rain damages on link road from Main road Kandi Danoa to Maloona to House of Sh. Balbir Chand OBC Basti in District Kangra HP deposit work (SH: Providing and layng cement concdrete at Rd 0/120 to 0/219.50 (SDF/2024/1625).	199055/-	4000.00	One Months
4	Restoration of rain damages on link road to villae Rangehar upto the house of Dalip Singh G.P. Sadoon in Disrict Kangra HP Deposit work (SH: Providing & laying cement concrete at RD 0/150 to 0/224.50. SDF/2024/1633).	149044/-	3000.00	One Months
5	Restoration of rain damages on Satsang Bhawan RW in District Kangra HP Deposit work (SH: Providing and laying cement concrete at RD 0/00 to 0/099.50 SDF/2024/1619).	199055/-	4000.	One Months
6.	Construction of Children Park at Tikka Bhanyalkar Mouja Aerla in District Kangra HP Deposit work (SH: Construction of Retaining wall . SDP/ 2024/448).	249690/-	5000.00	One months
7.	Spacial repair to govt. I.t.I. Building at Sarotari in Distt. Kangra HP Deposit work (SH: Painting and Distempering etc).	271979/-	6250.00	Two Months
8	Restoration of rain damages on link Kapari Chowk to Govt. Aprehar Kanda in District Kangra H P deposit work (SH: Construction of Retaining wall at Rd 0/735 to 0/743. SDF/2024/1425).	198445/--	4000.00	One Months
9	Restoration of rian damages on link road Hachichik to Gujar Basti in District Kangra HP Deposit work (SH: Providing & laying cement concrete at RD 0/000 to 0/099.50 SDF/2024/1635).	199055/-	4000.00	One Months
10	Construction of Reteaining wall near the house of Krishan Kumar S/O Gorkhu Ram in District Kangra HP Deposit Work (SH: Construction of Retaining wall VKV/2024/2037).	149982/-	3000.00	One Months
11	Restoration of rain damages on Samloti Sarotri road in District Kangra HP Deposit work (SH: Construction of Edge wall at RD 3/420 to 3/440.80 VKV/2024/684).	149335/-	3000.00	One Months
12	Construction of Shed at Kiksha Dham at Tikka Khajji in Distt. Kangra HP (SH: Construction of Shed SDP/2024/1067)	144344/-	2900.00	Two Months

Terms &Conditions:-)

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
3. If any of the date mentioned above happened \to be Gazetted Holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
5. The Contractor will have to submit affidavit along with application for issue of tender form.
6. Next tender will be issued only after completion of previous works in hand.

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

HIMSUCHANA AVAM & JAN SAMPARK
(On behalf of Governor of Himachal Pradesh)

No.PW/NBD/TA/Tender/NIT/2025-26- 3638-52 **Dated/** 14-7-2025

Copy to the following for information and necessary action:-

1. The Chief Engineer (KZ), HPPWD, Dharamshala.
2. The Director, Information & Publications Department, H.P. Shimla.
3. The Executive Engineer IT Cell Shimla HP PWD Shimla.
4. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
5. The Deputy Commissioner, Kangra at Dharamshala.
6. All the S.E.s/E.E.s under North Zone.
7. The Sub-Divisional Officer(C) Nagrota Bagwan.
8. All the Assistant Engineer under this Division.
9. The Drawing /Accounts Branch in this office.
10. Notice Board.

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

Schedule of Quantity

ESTIMATED COST: - ₹ **120360.00**
EARNEST MONEY : - ₹ **2550.00**
TIME LIMIT : TWO MONTHS

NAME OF WORK : - **Construction of Pucca Path from Tiali to the house of Sh. Madan Lal in Gram Panchayat Muhalkar (Chahri) in Distt. Kangra (H.P.) Deposit work.**

SUB-HEAD : - ***Providing and laying cement concrete pavement. (MPR/2018/199).***

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (One Cement : Two coarse sand : Four graded stone aggregate 20mm (Twenty millimetres) nominal size complete as per HPPWD technical specification and within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-in-charge.	20.40 Cubic metres			Per cubic metre	
				TOTAL :-		

Executive Engineer,
H.P.P.W.D., Division,
Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - Rs. 180340.00
EARNEST MONEY : - Rs. 3650.00
TIME LIMIT : ONE MONTH

NAME OF WORK :- **Restoration of rain damages on Nagrota Massal Rajhoon road Km 0/000 to 8/000 in District Kangra, (H.P.). Deposit Work**

SUB-HEAD :- **Construction of culvert flooring work at RD 1/580, Toe wall, Parapet, Edge wall at RD 1/582 to 1/601. SDF/2024/1763.**

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	16.47 Cubic metres			Per cubic metre	
2	Stone Filling in plinth with approved stone under floors including watering, ramming, consolidating and dressing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royality, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	2.70 Cubic metres			Per cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:4:8 (One cement; four sand; eight graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	25.34 Cubic meters			Per cubic metre	
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:2:4 (One cement; two sand; four graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete in Toe wall including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	9.72 Cubic metres			Per cubic metre	
5	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royality, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	6.27 Cubic metres			Per cubic metre	
6	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm (One hundred milimetres) dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	11.00 Running metre			Per running metre	
				TOTAL :-		

Executive Engineer,
H.P.P.W.D. Division,
Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - Rs. 199055.00
EARNEST MONEY : - Rs. 4000.00
TIME LIMIT : ONE MONTH

NAME OF WORK :- **Restoration of rain damages on Link road Hachichik to Gujar Basti in District Kangra, (H.P.). Deposit Work**

SUB-HEAD :- **Providing & laying cement concrete at RD 0/000 to 0/099.50. SDF/2024/1635**

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
1	Providing, laying, spreading and compacting stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications Clause No. 405 and as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental.	11.19 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:2:4 (One cement; two sand; four graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	29.85 Cubic metres			Per cubic metre	
					TOTAL :-	

Executive Engineer,
H.P.P.W.D. Division,
Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - Rs. 149044.00
EARNEST MONEY : - Rs. 3000.00
TIME LIMIT : ONE MONTH

NAME OF WORK :- **Restoration of rain damages on link road to village Rangehar upto the house of Dilip Singh G.P. Sadoon in District Kangra, (H.P.). Deposit Work**

SUB-HEAD :- **Providing & laying cement concrete at RD 0/150 to 0/224.50. SDF/2024/1633.**

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
1	Providing, laying, spreading and compacting stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications Clause No. 405 and as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental.	8.38 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:2:4 (One cement; two sand; four graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	22.35 Cubic metres			Per cubic metre	
					TOTAL :-	

Executive Engineer,
H.P.P.W.D. Division,
Tanda at Nagrota Bagwan.

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST: - Rs. 199055.00
EARNEST MONEY : - Rs. 4000.00
TIME LIMIT : ONE MONTH

NAME OF WORK :- **Restoration of rain damages on Satsang Bhawan RW in District Kangra, (H.P.). Deposit Work**

SUB-HEAD :- **Providing & laying cement concrete at RD 0/000 to 0/099.50 SDF/2024/1619.**

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
1	Providing, laying, spreading and compacting stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications Clause No. 405 and as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental.	11.19 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:2:4 (One cement; two sand; four graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	29.85 Cubic metres			Per cubic metre	
					TOTAL :-	

Executive Engineer,
H.P.P.W.D. Division,
Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - Rs. 249690.00
EARNEST MONEY : - Rs. 5000.00
TIME LIMIT : ONE MONTH

NAME OF WORK :- **Construction of Children Park at Tikka Bhanyalkar Mouja Aerla in District Kangra, (H.P.). Deposit Work**

SUB-HEAD :- **Construction of Retaining wall. SDP/2024/448.**

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	22.74 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:5:10 (One cement; five sand; ten graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	60.01 Cubic metres			Per cubic metre	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	18.00 Running metre			Per running metre	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	4.63 Cubic metres			Per cubic metre	
					TOTAL :-	

Executive Engineer,
H.P.P.W.D. Division,
Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST: - ₹ **271979.00**
EARNEST MONEY : - ₹ **5450.00**
TIME LIMIT : - **TWO MONTHS**

NAME OF WORK : - **Spacial repair to Govt. I.T.I. Building at Sarotari in Distt. Kangra (H.P.) DEPOSIT WORK.**
SUB-HEAD : - ***Painting and Distempering etc;***

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
1	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) as per the directions of Engineer-In-Charge including entire carriage of materials within all leads, lifts and other incidentals.	2506.72 Square metres			Per square metre	
				TOTAL : -		

Executive Engineer,
H.P.P.W.D. Division,
Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - Rs. 198445.00
EARNEST MONEY : - Rs. 4000.00
TIME LIMIT : ONE MONTH

NAME OF WORK :- **Restoration of rain damages on link Kapari Chowk to Govt. Aprehar Kanda in District Kangra, (H.P.). Deposit Work**

SUB-HEAD :- **Construction of Retaining wall at RD 0/735 to 0/743. SDF/2024/1425.**

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications; approved drawing, design and as directed by the Engineer-in-charge.	21.86 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:5:10 (One cement; five sand; ten graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	47.38 Cubic metres			Per cubic metre	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	6.00 Running metre			Per running metre	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	7.28 Cubic metres			Per cubic metre	
					TOTAL :-	

Executive Engineer,
H.P.P.W.D. Division,
Tanda at Nagrota Bagwan.

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST: - Rs. 199055.00
EARNEST MONEY : - Rs. 4000.00
TIME LIMIT : ONE MONTH

NAME OF WORK :- **Restoration of rain damages on link road from Main road Kandi Danoa to Maloona to house of Sh. Balbir Chand OBC Basti in District Kangra, (H.P.). Deposit Work**

SUB-HEAD :- **Providing & laying cement concrete at RD 0/120 to 0/219.50 (SDF/2024/1625)**

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
1	Providing, laying, spreading and compacting stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications Clause No. 405 and as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental.	11.19 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:2:4 (One cement; two sand; four graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	29.85 Cubic metres			Per cubic metre	
					TOTAL :-	

Executive Engineer,
H.P.P.W.D. Division,
Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - Rs. 149982.00
EARNEST MONEY : - Rs. 3000.00
TIME LIMIT : ONE MONTH

NAME OF WORK :- **Construction of Retaining wall near the house of Krishan Kumar S/O Gorkhu Ram in District Kangra, (H.P.). Deposit Work**

SUB-HEAD :- **Construction of Retaining wall. VKV/2024/2037**

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	13.37 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:5:10 (One cement; five sand; ten graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	35.37 Cubic metres			Per cubic metre	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	9.00 Running metre			Per running metre	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	7.16 Cubic metres			Per cubic metre	
					TOTAL :-	

Executive Engineer,
H.P.P.W.D. Division,
Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - Rs. 149385.00
EARNEST MONEY : - Rs. 3000.00
TIME LIMIT : ONE MONTH

NAME OF WORK :- Restoration of rain damages on Samloti Sarotri road in District Kangra, (H.P.). Deposit Work

SUB-HEAD :- Construction of Edge wall at RD 3/420 to 3/440.80. VKV/2024/684

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	14.35 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:5:10 (One cement; five sand; ten graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	36.19 Cubic metres			Per cubic metre	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	13.00 Running metre			Per running metre	
				TOTAL :-		

Executive Engineer,
H.P.P.W.D. Division,
Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ **144344.00**
EARNEST MONEY:- ₹ **2900.00**
TIME LIMIT :- **TWO MONTHS**

NAME OF WORK : - **Construction of Shed at Kiksha Dham at Tikka Khajji in Distt. Kangra (H.P.)**
SUB-HEAD : - ***Construction of Shed (SDP/2024/1067)***

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead including entire carriage of materials within all leads, lifts and other incidentals.	0.36 Cubic meters			Per cubic metre	
2	Supplying, filling, spreading & leveling stone boulders of size range 5 cm to 20 cm (Five centimetre to twenty centimetre) nominal size in recharge pit, in the required thickness complete including carriage of material within all leads, lifts and other incidentals and further as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	3.00 Cubic metres			Per cubic metre	
3	Providing and laying cement concrete 1:2:4 (One cement: two sand: four graded crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete excluding cost of forms work in foundation and plinth, as directed by the Engineer-Incharge, including carriage of materials within all leads, lifts and other incidentals.	3.36 Cubic metres			Per cubic metre	
4	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc; including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. Electric resistance or induction butt welded tubes complete including entire carriage of materials within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge.	307.30 Kilograms			Per kilo gram	
5	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including entire carriage of materials within all leads, lifts and other incidentals	695.00 Kilogram			Per Kilo gram	
6	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineerin-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required within all leads, lifts of materials and other incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge.	29.68 Square metres			Per square metre	
					Total :-	

Executive Engineer,
H.P.P.W.D., Division,
Tanda at Nagrota Bagwan