

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW/CB/TA/ E-26/2025-26- 2146-48
To

Dated: 28/3/2025


The Executive Engineer (IT Cell)
HPPWD., Nirman Bhawan, Nigam Vihar,
Shimla-2
ee-pwd-hp@nie.in

Subject:- Publication of tender Notice on departmental site.

Sir,

Enclosed please find herewith the tender notice of works as given in the Notice inviting tenders for uploading on department web-site as per Notification of the Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No.PBW-(B)A9(3)1/2024 dated Shimla-2 the (3)1/2024 as the work mentioned in the tender notice are urgent in nature and public interest.


DA/As above.


Executive Engineer,
Nurpur Division, HPPWD,
Nurpur.

Copy forwarded for information to:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurpur.
2. The Computer Cell O/O Executive Engineer (IT Cell) Nigam Vihar Shimla -2

DA/As above.


Executive Engineer,
Nurpur Division, HPPWD,
Nurpur.

Sealed percentage rate tenders on the form are invited by the Executive Engineer Nurgur Division HPPWD, Nurgur on behalf of the Government of HP for the following works from the approved and eligible contractors invited to HPPWD.

- TENDER SCHEDULE:-**
1. Date and time of receipt of application for tender form: 07.09.2024 upto 2.00 P.M.
 2. Date and time of issue of tender form: 08.09.2024 upto 12.00 P.M.
 3. Date and time of receipt of tenders: 08.09.2024 upto 12.00 P.M.
 4. Date and time of opening of tenders: 08.09.2024 at 2.00 P.M.


The tenders form will be issued against each payment (non refundable). The earnest money in the shape of NSC/DR/Deposit at all of any of Post Office/Bank in H.P. duly pledged in the name of the Executive Engineer Nurgur Division HPPWD, Nurgur must accompany with each tender.

Job No.	Name of work	Estimated cost (Rs.)	Earliest money (Rs.)	Time limit	Class
1.	Restoration of rain damages on Both Chakki Dhar road Km 6.00 to 8.00 (SH: Removal of land slide/slips RD 3.700 to 4.500)	93500.00	2000.00	One Month	Class D
2.	Restoration of rain damages on joints to Khet road Km 6.00 to 6.224 (SH: Removal of land slide/slips RD 4.00 to 4.600)	93500.00	2000.00	One Month	Class D
3.	Restoration of rain damages on Nurgur, Sadwan, Malkwal, Sanjha Nalla road Km 0.00 to 15.390 (SH: CO RCC railing and approach, R/wall of Sanjha Nalla bridge at RD 15/390)	95915.00	2000.00	One Month	Class D
4.	Construction of public Health centre Sadwan Tehsil Nurgur Distt Kangra (HP) (SH: Construction of Shed)	99978.00	2000.00	One Month	Class D
5.	Restoration of rain damages on Various roads under Suliali Sub Division HPPWD Suliali (SH: Hiring of JCB/ Excavator cum loader for removal of slips under Suliali Section)	93500.00	2000.00	One Month	Class D
6.	Restoration of rain damages on Various roads under Suliali Sub Division HPPWD Suliali (SH: Hiring of JCB/ Excavator cum loader for removal of slips under Sadwan Section)	94600.00	2000.00	One Month	Class D
7.	Restoration of rain damages on Various roads under Nurgur Sub Division HPPWD Nurgur (SH: Hiring of JCB/ Excavator cum loader for removal of slips under Raja Ka Bagh)	96800.00	2000.00	One Month	Class D
8.	Restoration of rain damages on various roads under Suliali Sub Division HPPWD Suliali (SH: Hiring of JCB/ Excavator cum loader for Removal of Slips under Bhadwar Section)	93000.00	2000.00	One Month	Class D
9.	Restoration of rain damages on various roads under Nurgur Sub Division HPPWD Nurgur (SH: Hiring of JCB/ Excavator cum loader for Removal of Slips under Kherian Section)	96700.00	2000.00	One Month	Class D
10.	Restoration of rain damages on various roads under Nurgur Sub Division HPPWD Nurgur (SH: Hiring of JCB/ Excavator cum loader for Removal of Slips under Nurgur Section)	93500.00	2000.00	One Month	Class D
11.	Restoration of rain damages on various roads under Nurgur Sub Division HPPWD Nurgur (SH: Hiring of JCB/ Excavator cum loader for Removal of Slips under Talara Section)	94000.00	2000.00	One Month	Class D

The contractors/firms should possess the following documents (Photocopy to be attached):

1. The contractor should be registered as a dealer under HPST Act 1968 (GST number) from the Excise and taxation department.
2. The cess charges @1% (One percent) will be deducted from gross amount of work done by the contractor.
3. The contractor should produce photocopy of PAN No at time of application.
4. The contractor should produce copy of enlistment/renewal letter at the time of application.
5. The Executive Engineer reserves the right to accept/cancel any tender on performance based.
6. Telephonic or mail tenders are not acceptable.
7. Special care should be taken to write the rates both in figures and words, failing which tender likely to be rejected to be circumstances.
8. If the office happens to be closed on the date of opening of the tenders as specified the tenders will be opened on the next working day at the same time and venue.
9. Work has to be completed within stipulated time.
10. All requisite documents should be attached with the application.
10. Certified that the above works are urgent in nature, hence invited accordingly.


HIM SUCHNA AVAM JAN SAMPARK


Executive Engineer,
Nurgur Division, HPPWD,
Nurgur
(On behalf of Governor of HP).

dated 28/8/2025

PWN/CB/GA/E-26/2025-26/ 2147-48
Copy forwarded for information to:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurgur.
2. Notice Board.


Executive Engineer,
Nurgur Division, HPPWD,
Nurgur

SCHEDULE OF QUANTITY


Estimated cost = 99300.00
 Earnest money = 2000.00
 Time allowed = one month

TMT No. - 53

Name of work:-RR damages on Both Chalkki Dhar road km 0/0 to 8/00 (SI:- Removal of land slide/slips RD 3/7/00 to 4/5/00)

S.No	Description of Item	Quantity	Unit	Rate		Amount
				In figure	In words	
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift to 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611 including all leads lifts and carriage of materials.as per direction of Engineer-in-charge.	662.00	Per Cubic Metre	150.00	(Rs.One hundred Fifty only)	99300.00
Total =						Rs. 99,300.00

Draft schedule of quantity checked and approved for Rs. 99300.00 only



 Executive Engineer,
 Nurpur division,
 HPPWD Nurpur.

SCHEDULE OF QUANTITY

Estimated cost = 99300.00
 Earnest money = 2000.00
 allowed = one month
 Time

S.No	Name of work:- R/R damages on Jounta to Khet road km 0/0 to 0/555 (Sll:- Removal of land slide/slips RD 4/00 to 4/600)	Description of Item	Quantity	Unit	Rate		Amount
					In figure	In words	
1		Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift of 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611 including all leads lifts and carriage of materials.as per direction of Engineer-in-charge.	662.00	Per Cubic Metre	150.00	(Rs One hundred Fifty only)	99300.00
Total =							Rs. 99,300.00

Draft schedule of quantity checked and approved for Rs. 99300.00 only


 Executive Engineer,
 Nurpur division,
 HPPWD Nurpur.


Schedule of Quantity

Name of work :- RR damages on Nurpur, Sadwa, Malkwal, Sanjhi Nalla road KM 0/00 to 15/390
 Sub Head :- C/O RCC railing and Approach R/wall of Sanjhi Nalla bridge at RD 15/390)

Estimated Cost: Rs. 95935.00/-
 Earnest Money: Rs. 20000.00/-
 Time Limit: One Month

Sr.No	Description of Items	Quantity	Unit	In words	In fig	Amount
1	Dismantling Guard rails by manual means and disposal of dismantled material with all lifts and upto a lead of 1000 m, stacking serviceable materials and unserviceable materials separately as per Technical Specification Clause 202. as per entire satisfaction and direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rates including octroi, royalty, malkana, toll tax, G.S.T. or any other taxes imposed by the Government.	20.74	P/Rmt	One Hundred Ten Rupees and zero paise.	110.00	2281.00
2	Providing and fixing in position reinforced cement concrete railing of M-30 (M-thirty) with 12mm (twelve millimeters) nominal size aggregate including cost of reinforcement, form work and curing complete true to line and grade, tolerance of vertical RCC post not to exceed 1 in 500 (one in five hundred) center to center spacing between vertical posts not to exceed 2000 mm (two thousand millimeter) leaving adequate space between vertical post for expansion complete as per drawing and MORTH technical specifications section 1500, 1600, 1700 and 2703 and as per entire satisfaction and direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rates including octroi, royalty, malkana, toll tax, G.S.T. or any other taxes imposed by the Government.	20.74	P/Rmt	Two Thousand Six Hundred Fourteen Rupees and zero paise.	2614.00	54214.00
3	Providing and laying cement concrete 1:4:8 curing complete including the cost of farm work for plain/reinforced concrete in retaining walls, breast walls as per drawing and HPPWD, technical specification as per directions and satisfaction of Engineer-in-Charge. The rates including octroi, royalty, malkana, toll tax, G.S.T. or any other taxes imposed by the Government.	9.28	P/cum	Four Thousand Two Hundred Fifty Rupees and zero paise.	4250.00	39440.00
Total:-						95935.00

Draft schedule of quantity checked and approved for Rs. 95935.00 only


Executive Engineer
 Nurpur-Division
 HPPWD Nurpur


Draft Schedule of Quantity

Name of work:- C/O Public health sub Center Sadwan Tehsil Nurpur, Distt Kangra (H.P)
(SH:- Construction of shed)

Estimated Cost Rs. 99878.00/-
 Earnest money Rs. 2000/-
 Time limit: One Month

S.No.	Items of work	Quantity	In fig.	Rate		Unit	Amount
				In words			
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and bracing, removal of stumps and other deleterious material and disposal up to a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	0.38	364.00	Rupees Three Hundred Sixty Four and paise zero only		Cum	138.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level. 1:4:8 (1 Cement : 4 coarse sand : 8 gradedstone aggregate 20 mm nominal size)	0.38	4190.00	Rupees four thousand one hundred nineteen and paise zero only		Cum	1592.00
3	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. 80 mm dia nominal bore	25.20	840.00	Rupees eight hundred forty and Paise fifty only		Mtrs	21168.00
4	Providing and fixing angle iron frames for doors, windows and ventilators of mild steel Angle sections of size 45x45x6 mm, joints riveted and welded by angle iron 45x45x5 mm or 45x 5 mm flat pieces to the existing Iron frame or to the wall with dash fastener, including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer, all complete as per the direction of Engineer-In-charge.	176.00	105.00	Rupees one hundred five and Paise fifty only		KG	18480.00
5	Providing and fixing 0.60mm thick prepainted steel sheet with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6 mm dia meter with prepainted limpet and rubber washer complete with all accessories as required as per the direction of Engineer-In-charge.	30.00	1950.00	Rupees one thousand nine hundred fifty and Paise forty five only		Sqm	58500.00
Total:-							99878.00

Draft Schedule of Quantity checked & approved for Rs. 99878.00 only.



 Executive Engineer,
 Nurpur Division,
 HPPWD Nurpur.

Schedule of Quantity

Name of work: Restoration of rain damages on Various roads under Suliali Sub Division HPPWD Suliali.
 (Sub Head : Hiring of JCB/Excavator cum Loader for Removal of Slips under Suliali Section.)

Estimated cost: 93500/-
 Earnest Money: 1900/-
 Time/Limit : One month


Sr. No.	Description of item	Qty	Rate	Unit	Amount
1.	Hiring of JCB/Excavator cum Loader for Removal of Slips for cutting / widening of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from road surface up to any leads & lifts and up to any height and depth as per the direction of satisfaction of engineer-in charge. Any loss to public /private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/ Excavator owner. The fuel & operation staff for machine will be provided by the owner . The repair & spare watch & ward of machine also be borne by the contractor /owner. The daily log book will be maintained at site which should be duly verified the Engineer-in-charge. . The rates is including royalty, malkana, toll tax, sale tax or any other taxes and carriage of materials within all leads and lifts and other incidental	85.00	1100.00	Per Hours	93500.00
	TOTAL				93500.00


 Executive Engineer,
 Nurpur Division HP.PWD
 Nurpur.

Schedule of Quantity

Name of work: Restoration of rain damages on Various roads under Sulliall Sub Division HPPWD Sulliall.
 Sub Head : Hiring of JCB/Excavator cum Loader for Removal of Slips under Sadwan Section.)
 Estimated cost: 94600/-
 Earnest Money: 1900/-
 Time/ Limit : One month


Sr. No.	Description of item	Qty	Rate	Unit	Amount
1.	Hiring of JCB/Excavator cum Loader for Removal of Slips for cutting / widening of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from road surface up to any leads & lifts and up to any height and depth as per the direction of satisfaction of engineer-in charge. Any loss to public /private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/ Excavator owner. The fuel & operation shall be machine will be provided by the owner . The repair & spare watch & ward of machine also be borne by the contractor /owner. The daily log book will be maintained at site which should be duly verified the Engineer-in-charge. . The rates is including royalty, malkana, toll tax, sale tax or any other taxes and carriage of materials within all leads and lifts and other incidental	86.00	1100.00	Per Hours	94600.00
	TOTAL				94600.00


 Executive Engineer,
 Nurpur Division HP.PWD
 Nurpur.

Schedule of Quantity

Name of work: Restoration of rain damages on Various roads under Nurpur Sub Division HPPWD Nurpur.
 (Sub Head : Hiring of JCB/Excavator cum Loader for Removal of Slips under Raja ka Bag section.
 Estimated cost: 96800/-
 Earnest Money: 1900/-
 Time/ Limit : one month

Sr. No.	Description of item	Qty	Rate	Unit	Amount
1.	Hiring of JCB/Excavator cum Loader for Removal of Slips for cutting / widening of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from road surface up to any leads & lifts and up to any height and depth as per the direction of satisfaction of engineer-in-charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/ Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor /owner. The daily log book will be maintained at site which should be duly verified the Engineer-in-charge. . The rates is including royalty, malikana, toll tax, sale tax or any other taxes and carriage of materials within all leads and lifts and other incidental	88.00	1100.00	Per Hours	96800.00
TOTAL					96800.00



 Executive Engineer,
 Nurpur Division HP, PWD
 Nurpur.

Schedule of Quantity

Name of work: Restoration of rain damages on Various roads under Suliali Sub Division HPPWD Suliali,
 Sub Head : Hiring of JCB/Excavator cum Loader for Removal of Slips under Bhadwar Section.

Estimated cost: 22000/-
 Earnest Money: 1200/-
 Time/Limit : One month


Sr. No.	Description of item	Qty	Rate	Unit	Amount
1.	Hiring of JCB/Excavator cum Loader for Removal of Slips for cutting / widening of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from road surface up to any leads & lifts and up to any height and depth as per the direction of satisfaction of engineer-in-charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/ Excavator owner. The fuel & operation staff or machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified the Engineer-in-charge. The rates is including royally, malkana, toll tax, sale tax or any other taxes and carriage of materials within all leads and lifts and other incidental	80.00	1100.00	Per Hours	22000.00
	TOTAL				22000.00


 Executive Engineer,
 Nurpur Division HP, PWD
 Nurpur.

Schedule of Quantity

Name of work: Restoration of rain damages on Various roads under Nurpur Sub Division HPPWD Nurpur.
 Sub Head : Hiring of JCB/Excavator cum Loader for Removal of Slips under Kherian section.
 Estimated cost: 95700/-
 Earnest Money: 1900/-
 Time/ Limit : one month

Sr. No.	Description of item	Qty	Rate	Unit	Amount
1.	Hiring of JCB/Excavator cum Loader for Removal of Slips for cutting / widening of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from road surface up to any leads & lifts and up to any height and depth as per the direction of satisfaction of engineer-in-charge. Any loss to public /private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/ Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor /owner. The daily log book will be maintained at site which should be duly verified the Engineer-in-charge. . The rates is including royalty, malkana, toll tax, sale tax or any other taxes and carriage of materials within all leads and lifts and other incidental	87.00	1100.00	Per Hours	95700.00
	TOTAL				95700.00



 Executive Engineer,
 Nurpur Division HP.PWD
 Nurpur.


Schedule of Quantity

Name of work: Restoration of rain damages on Various roads under Nurpur Sub Division HPPWD Nurpur
 Sub Head : Hiring of JCB/Excavator cum Loader for Removal of Slips under Nurpur section.

Estimated cost: 93500/-
 Earnest Money: 1900/-
 Time/ Limit : one month

Sr. No.	Description of item	Qty	Rate	Unit	Amount
1.	Hiring of JCB/Excavator cum Loader for Removal of Slips for cutting / widening of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from road surface up to any leads & lifts and up to any height and depth as per the direction of satisfaction of engineer-in-charge. Any loss to public /private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/ Excavator owner. The fuel & operation staff for machine will be provided by the owner . The repair & spare watch & ward of machine also be borne by the contractor /owner. The daily log book will be maintained at site which should be duly verified the Engineer-in-charge. . The rates is including royalty, malkana, toll tax, sale tax or any other taxes and carriage of materials within all leads and lifts and other incidental	85.00	1100.00	Per Hours	93500.00
	TOTAL				93500.00





 Executive Engineer,
 Nurpur Division HP.PWD
 Nurpur.

Schedule of Quantity

Name of work: Restoration of rain damages on Various roads under Nurpur Sub Division HPPWD Nurpur.
 Sub Head : Hiring of JCB/Excavator cum Loader for Removal of Slips under Talara section.

Estimated cost: 94600/-
 Earnest Money: 1900/-
 Time/Limit : one month

Sr. No.	Description of item	Qty	Rate	Unit	Amount
1.	Hiring of JCB/Excavator cum Loader for Removal of Slips for cutting / widening of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from road surface up to any leads & lifts and up to any height and depth as per the direction of satisfaction of engineer-in-charge. Any loss to public /private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/ Excavator owner. The fuel & operation staff for machine will be provided by the owner . The repair & spare watch & ward of machine also be borne by the contractor /owner. The daily log book will be maintained at site which should be duly verified the Engineer-in-charge. . The rates is including royalty, malkana, toll tax, sale tax or any other taxes and carriage of materials within all leads and lifts and other incidental	86.00	1100.00	Per Hours	94600.00
TOTAL					94600.00


 Executive Engineer,
 Nurpur Division HP, PWD
 Nurpur.