

Himachal Pradesh
Public Works Department

No. PWH/HD/CB/T-I/2025-26
To

7609-11

Dated: - 19/11/2025

The Executive Engineer (IT Cell)
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject: - Publication of Notice inviting tender.

Sir,

Enclosed please find herewith copy of notice inviting tender for publishing on departmental website for favour of further necessary action please.

Encl: As above


Executive Engineer,
HPPWD Division Haroli,
Distt. Una HP).

Copy along with copy of notice inviting tender is forwarded for information and necessary action to:-


1. The Superintending Engineer, 15th Circle, HP: PWD, Una.
2. Copy to Notice board.


Executive Engineer,
HPPWD Division Haroli,
Distt. Una HP).

Certificate

Certified that the tenders for the works called vide this office letter No. PWH/HD/CB/T-1/2024-25-76

11 dated 19/11/2025 are required to be carried out immediately being emergent nature of work in public interest.


Executive Engineer,
Haroli Division, HPPWD
Haroli, Distt. Una HP).

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
" NOTICE INVITING TENDERS "

Percentage rate tender on PWD Form No. 6 & 8 are hereby invited by the Executive Engineer, Division H.P. on behalf of Governor of H.P for the following works from the approved and eligible contractors/firms enlisted in the PWD Department as per latest instructions, so as to reach and open in his office as per time schedule given below. The tender will be open for 45 days from the date of opening of tenders. The undersigned reserves the right to reject any tenders without assigning any reasons.

1. Date of receipt of application for the tender form a/w requisite documents: -
2. Date of issue/sale of tender forms against cash payment(non-refundable): -
3. Date of receipt of tenders: -
4. Date of opening of tenders: -

25-11-2025 up to 10.30 AM
26-11-2025 up to 3.00 PM
27-11-2025 up to 10.30 AM
27-11-2025 at 11.00 AM

Sr. No.	Name of work	Estimate d cost	EMD	Time Limit	Cost of tender	Eligible class of contract or
1	2	3	4	5	6	7
1	Restoration of rain damages on link road to village Bhoolgarh Km 0/0 to 2/600 (SH: C/O Retaining wall at RD 2/619 to 2/631 Lhs)	99522	2000/-	One Month	350/-	Class- C & D
2	C/o Bus Stand at Dulehar Tehsil Haroli Distt.Una (SH: Repair & repainting of Dulehar Bus stand building & Boundary wall etc.) Deposit work Phase-III	99204	2000/-	One Month	350/-	Class- C & D
3	A/R & M/O on link road to mohalla Sainia Swan Khad via Shiv Mandir Lower Ispur Km 0/0 to 1/00, Panjavar Bathri road Km 4/00 to 9/00, link road from Ispur Pandoga to Kayarian Km 0/0 to 2/900, Link road Petrol Pump Bhadsali to Una Hoshiarpur road to Pandoga Lower Sainian abadi Km 0/0 to 2/00 (SH: Supplying and fixing of sign boards, Painting on parapets, writing letters etc.)	99619	2000/-	One Month	350/-	Class- C & D
4	Construction of Boundary wall at Govt. Sr.Sec.School Bhadsali (SH: C/o Boundary wall legnth 11.90 mtr) Phase-I	99609	2000/-	One Month	350/-	Class- C & D
5	C/o link road from House of Champa Devi RD 0/00 to 1/200 (SH: C/o Retaining wall at RD 1/165 to 1/169.80 Rhs)	98703	2000/-	One month	350/-	Class- C & D
6	Improvement of black spot on Ajouli Santokhgarh Tahliwal Polian road Km 0/0 to 13/400 (SH: P/L Thermoplastic paint & P/F cat eye near speed breaker in Tahliwal Market at RD 3/845 to 4/120 (Bhs)	99528	2000/-	One month	350/-	Class- C & D
7	A/R & M/o on link road Umrili Beetan Singah road RD 0/0 to 6/550 (SH: C/o 1 No. speed breaker 80mm paver block with CC pavement, P/L Thermoplastic paint & P/F cat eye at RD 1/630 near Govt. Primary School Beetan)	99642	2000/-	One Month	350/-	Class- C & D
8	Restoration of Gramin Sampark along with R/wall to the campus of Mata Santoshi Temple at Khad GP Khad (SH: C/O CC pavement & C/o R/wall) Deposit work Phase-IV	99352	2000/-	One Month	350/-	Class- C & D

9	Restoration of rain damages on link road to village Naiyan Basti Baliwal Km 0/0 to 1/500 (SH: P/L 80mm thick paver blocks at RD 0/438.90 to 0/448.60)	98463	1700/-	15 day	350/-	Class- C & D
10	Construction of Boundary wall at Govt. Sr.Sec.School Bhadsali (SH: C/o Boundary wall legnth 11.50 mtr) Phase-XI	98100	2000/-	One Month	350/-	Class- C & D
11	Restoration of link orad to Co-operative Society Haroli vis GSSS Haroli Km 0/0 to 2/225 (SH: C/o Retaining wall in RD 1/950 to 1/974 Rhs)	98076	2000/-	One Month	350/-	Class- C & D
12	Restoration of rain damage on link road to Gondpur Jai Chand Km 0/0 to 0/800 (SH: C/o B/wall at RD 0/350 to 0/360.20 Bhs, C/o drain at RD 0/300 to 0/310-LHS)	99784/-	2000/-	One Month	350/-	Class- C & D
13	Balance work for C/o Community Park, outdoor open gym at WNo.2 & 4 GP Dulehar Tehsil Haroli Distt.Una (SH: Hill side cutting for extended portion of park RD 0/024 to 0/028) Deposit work	97300	2000/-	One Month	350/-	Class- C & D
14	C/o link road Nangal Khurd mohalla Thai Lower Mannuwal near GSSS Nangal Khurd Km 0/0 to 1/00 (SH: C/o Retaining wall in RD 0/589 to 0/600 Rhs) Deposit work	98923	2000/-	One Month	350/-	Class- C & D
15	Restoration of rain damages on link road to village Bhoolgarh Km 0/0 to 2/600 (SH: C/O Retaining wall at RD 2/607 to 2/619 Lhs)	99682	2000/-	One Month	350/-	Class- C & D
16	C/o Bus Stand at Dulehar Tehsil Haroli Distt.Una (SH: Repair & repainting of Dulehar Bus stand building & Boundary wall etc.) Deposit work Phase-I	99319	2000/-	One Month	350/-	Class- C & D
17	C/o link road Nangal Khurd mohalla Thai Lower Mannuwal near GSSS Nangal Khurd Km 0/0 to 1/00 (SH: P/L 80mm thick paver block RD 0/589 to 0/612) Deposit work	98604	2000/-	One Month	350/-	Class- C & D
18	Restoration of rain damages on Una Rampur Haroli Jaijon road Km 0/0 to 23/00 (SH: Repair of berms at various RDs from 12/00 to 16/00)	99572	2000/-	One Month	350/-	Class- C & D
19	Construction of Boundary wall at Govt. Sr.Sec.School Bhadsali (SH: C/o Boundary wall legnth 11.80 mtr) Phase-II	99243	2000/-	One Month	350/-	Class- C & D
20	C/o link road from House of Champa Devi RD 0/00 to 1/200 (SH: C/o Retaining wall at RD 1/169.80 to 1/177.20 Rhs)	99365	2000/-	One Month	350/-	Class- C & D
21	Restoration of rain damage on link road to Gondpur Jai Chand Km 0/0 to 0/800 (SH: C/o B/wall at RD 0/373.20 to 0/386.20 Bhs)	99635	2000/-	One Month	350/-	Class- C & D
22	Improvement of College Infrastructure at SDWG Govt.College Beetan Tehsil Haroli Distt.Una (SH: C/o Boundary wall) Phase-II (Deposit work)	99774	2000/-	One Month	350/-	Class- C & D

23	Restoration of Gramin Sampark along with R/wall to the campus of Mata Santoshi Temple at Khad GP Khad (SH: C/O CC pavement & C/o R/wall) Deposit work Phase-V	79256	2000/-	One Month	350/-	Class- C & D
24	C/o link road Nangal Khurd mohalla Thai Lower Mannuwal near GSSS Nangal Khurd Km 0/0 to 1/00 (SH: P/L 80mm thick paver block RD 0/635 to 0/657.80) posit work	97265	2000/-	One Month	350/-	Class- C & D
25	Restoration of link road to Co-operative Society Haroli vis GSSS Haroli Km 0/0 to 2/225 (SH: C/o Retaining wall in RD 1/460.90 to 1/476.40)	99605	2000/-	One Month	350/-	Class- C & D
26	Restoration of rain damages on link road to village Naiyan Basti Baliwal Km 0/0 to 1/500 (SH: P/L 80mm thick paver blocks at RD 0/419.50 to 0/429.10)	97447	2000/-	One Month	350/-	Class- C & D
27	Restoration of rain damage on link road to Gondpur Jai Chand Km 0/0 to 0/800 (SH: C/o B/wall at RD 0/386.20 to 0/395 & C/o CC pavement at RD 0/440 to 0/449 Lhs)	99311	2000/-	One Month	350/-	Class- C & D
28	Restoration of rain damages on link road to village Bhoolgarh Km 0/0 to 2/600 (SH: C/O Retaining wall at RD 2/579 to 2/595 Lhs)	98912	2000/-	One Month	350/-	Class- C & D
29	Construction of Boundary wali at Govt. Sr.Sec.School Bhadsali (SH: C/o Boundary wall legnth 11.40 mtr) Phase-VI	97731	2000/-	One Month	350/-	Class- C & D
30	C/o Bus Stand at Dulehar Tehsil Haroli Distt.Una (SH: Repair & repainting of Dulehar Bus stand building & Boundary wall etc.) Deposit work Phase-II	99205	2000/-	One Month	350/-	Class- C & D
31	C/o link road Nangal Khurd mohalla Thai Lower Mannuwal near GSSS Nangal Khurd Km 0/0 to 1/00 (SH: P/L 80mm thick paver block RD 0/657.80 to 0/680.80) Deposit work	98118	2000/-	15 day	350/-	Class- C & D
32	Restoration of rain damages on link road to village Bhoolgarh Km 0/0 to 2/600 (SH: C/O Retaining wall at RD 2/595 to 2/607 Lhs)	99682	2000/-	One Month	350/-	Class- C & D
33	Restoration of rain damage on link road to Gondpur Jai Chand Km 0/0 to 0/800 (SH: C/o CC pavement at RD 0/449 to 0/501 Lhs)	98670	2000/-	One Month	350/-	Class- C & D
34	C/o link road Nangal Khurd mohalla Thai Lower Mannuwal near GSSS Nangal Khurd Km 0/0 to 1/00 (SH: P/L 80mm thick paver block RD 0/612 to 0/635) Deposit work	98118	2000/-	One Month	350/-	Class- C & D
35	Construction of Boundary wall at Govt. Sr.Sec.School Bhadsali (SH: C/o Boundary wall legnth 11.30 mtr) Phase-VII	97362	2000/-	One Month	350/-	Class- C & D
36	Restoration of rain damage on link road to Gondpur Jai Chand Km 0/0 to 0/800 (SH: C/o B/wall at RD 0/360.20 to 0/373.20 Bhs)	99795	2000/-	One Month	350/-	Class- C & D

37	Improvement of College Infrastructure at SDWG Govt.College Beetan Tehsil Haroli Distt.Una (SH: C/o Boundary wall) Phase-I (Deposit work)	99744 99774	2000/-	One Month	350/-	Class- C & D
38	A/R & M/O on link road to village Nagnoli Km 0/0 to 5/00, Panjavar Bathri road Km 0/0 to 4/200, link road to village Khad at Km 0/0 to 3/500 (SH: Supplying and fixing of sign boards, Painting on bridge, Parapets Bridge & writing letters etc.)	99875	2000/-	One Month	350/-	Class- C & D
39	A/R & M/O on lin road Pandoga Barrier to Panjavar road Km 0/0 to 9/00 (SH: Painting over bridges, parapets & writing letters etc at RD 0/250,2/438,3/784)	99984	2000/-	One Month	350/-	Class- C & D
40	Construction of Boundary wall at Govt. Sr.Sec.School Bhadsali (SH: C/o Boundary wall legnth 11.30 mtr) Phase-IX	97362	2000/-	One Month	350/-	Class- C & D
41	A/R & M/o on Una Rampur Haroli Palkwah Jaijon road Km 0/0 to 23/00 & Panjavar Bathri road Km 0/0 to 34/00 (SH: Painting on rain shelter at near Swan Bridge, Kangar & Road)	98927	2000/-	One Month	350/-	Class- C & D
42	Improvement of College Infrastructure at SDWG Govt. College Beetan Tehsil Haroli Distt.Una (SH: C/o Boundary wall) Phase-III (Deposit work)	99675	2000/-	One Month	350/-	Class- C & D
43	Restoration of rain damage on link road to Polian to Janani to providing R/wall at RD 3/070 to 3/090 RHS & U-shape drain at RD 2/140 to 2/183 RHS (SH: c/o R/wall at RD 3/070 to 3/080-RHS) Deposit work	99474	2000/-	One Month	350/-	Class- C & D
44	Restoration of rain damage on Pandoga to Pandoga Barrier road Km 0/0 to 9/00 (SH: C/O r/wall at RD 2/360.50 to 2/369.40)	98581	2000/-	One Month	350/-	Class- C & D
45	Repair of pot holes on link road Nagnoli to Harijan Basti Chappro Chhoti Khad Gujran Tarkhana Khuhi wala road Km 0/0 to 3/345 (SH: Patch work at RD 2/800 to 3/070)	99434	2000/-	One Month	350/-	Class- C & D
46	C/o link road Laluwal to Polian Km 0/0 to 3/400 under 5054-MMSY (SH: P/L 20mm thick premix carpet at RD 1/698 to 2/035) Deposit work	98792	2000/-	One Month	350/-	Class- C & D
47	A/R & M/O on Gondpur Turf Jai Chand to Jhol Majra road Km 0/0 to 2/500, A/R & M/O on link road to village Gondpur Turf Jai Chand Km 0/0 to 1/00 & L/R Umralli Beetan to Umralli Gahua Km 0/0 to 1/200 (SH: Painting work on parapets & culvert etc.)	99201	2000/-	One Month	350/-	Class- C & D
48	Construction of Boundary wall at Govt. Sr.Sec.School Bhadsali (SH: C/o Boundary wall legnth 11.70 mtr) Phase-III	98838	2000/-	One Month	350/-	Class- C & D
49	Repair & restoration work of road Baba Sidh Chano Temple to Mata Mandir WNo.7 GP Badhera (SH: C/o CC pavement & edge wall at RD 0/034.50 to 0/041.50) Deposit work	84601	2000/-	One Month	350/-	Class- C & D

50	Repair of pot holes on link road Nagnoli to Harijan Basti Chappro Chhoti Khad Gujran Tarkhana Khuhi wala road Km 0/0 to 3/345 (SH: Patch work at RD 3/100 to 3/326)	99887	2000/-	One Month	350/-	Class- C & D
51	Balance work for restoration of rain damage on link road Boolgarh Bhadsali to the H/o Sh.Beesham Singh GP Bhadsali (SH: C/o R./wall downstream side of culvert RD 0/017 to 0/021.50 Rhs)	50676	1000/-	One Month	350/-	Class- C & D
52	C/o link orad Laluwal to Polian Km 0/0 to 3/400 under 5054-MMSY (SH: P/L 20mm thick premix carpet at RD 2/035 to 2/375) Deposit work	99672	2000/-	One Month	350/-	Class- C & D
53	A/r & M/O on Santokhgarh Tahliwal Polian Jaijon road (HP Boundary) 8/500 to 13/00 & A/R & M.O on Umrli Beetan road Km 0/0 to 1/350 (SH: Painting work on parapets & culvert etc.)	99514	2000/-	One Month	350/-	Class- C & D
54	Construction of Boundary wall at Govt. Sr.Sec.School Bhadsali (SH: C/o Boundary wall legnth 11.50 mtr) Phase-V	98100	2000/-	One Month	350/-	Class- C & D
55	Repair & restoration work of road Baba Sidh Chano Temple to Mata Mandir WNo.7 GP Badhera (SH: C/o CC pavement & edge wall at RD 0/026.10 to 0/034.50) Deposit work	98538	2000/-	One Month	350/-	Class- C & D
56	Restoration of rain damage on link road to Polian to Janani to Providing R/wall at RD. 3/070 to 3/090 RHS & U-shape drain at RD. 2/140 to 2/185 RHS (SH:-U-shape drain at RD. 2/140 to 2/180 RHS(Deposit work)	97776	2000/-	One Month	350/-	Class- C & D
57	C/o link orad Laluwal to Polian Km 0/0 to 3/400 under 5054-MMSY (SH: P/L 20mm thick premix carpet at RD 2/375 to 2/714) Deposit work	99378	2000/-	One Month	350/-	Class- C & D
58	Repair of pot holes on link road Nagnoli to Harijan Basti Chappro Chhoti Khad Gujran Tarkhana Khuhi wala road Km 0/0 to 3/345 (SH: Patch work at RD 2/450 to 2/788)	99590	2000/-	One Month	350/-	Class- C & D
59	Balance work for restoration of rain damage on link road Boolgarh Bhadsali to the H/o Sh.Beesham Singh GP Bhadsali (SH: C/o R./wall downstream side of culvert RD 0/008.50 to 0/017 Rhs)	97710	2000/-	One Month	350/-	Class- C & D
60	Repair & restoration work of road Baba Sidh Chano Temple to Mata Mandir WNo.7 GP Badhera (SH: C/o CC pavement & edge wall at RD 0/017.50 to 0/026.10) Deposit work	97358	2000/-	One Month	350/-	Class- C & D
61	Construction of Boundary wall at Govt. Sr.Sec.School Bhadsali (SH: C/o Boundary wall legnth 10.00 mtr) Phase-XII	90816	2000/-	One Month	350/-	Class- C & D
62	Restoration of rain damage on Pandoga to Pandoga Barrier road Km 0/0 to 9/00 (SH:•C/O r/wall at RD 2/325 to 2/333.60)	99582	2000/-	One Month	350/-	Class- C & D
63	C/o link road Laluwal to Polian Km 0/0 to 3/400 under 5054-MMSY (SH: P/L 20mm thick premix carpet at RD 3/052 to 3/390) Deposit work	99085	2000/-	One Month	350/-	Class- C & D

64	Balance work for restoration of rain damage on link road Boolgarh Bhadsali to the H/o Sh.Beesham Singh GP Bhadsali (SH: C/o R./wall downstream side of culvert RD 0/00 to 0/008.50 Rhs)	97870	2000/-	One Month	350/-	Class- C & D
65	Restoration of rain damage on Pandoga to Pandoga Barrier road Km 0/0 to 9/00 (SH: C/O r/wall at RD 2/333.60 to 2/342.30)	99335	2000/-	One Month	350/-	Class- C & D
66	C/o link road Laluwal to Polian Km 0/0 to 3/400 under 5054-MMSY (SH: P/L 20mm thick premix carpet at RD 0/0 to 0/340) Deposit work	99672	2000/-	One Month	350/-	Class- C & D
67	Restoration of rain damage on link road to Polian to Janani to providing R/wall at RD 3/070 to 3/090 RHS & U-shape drain at RD 2/140 to 2/183 RHS (SH: c/o R/wall at RD 3/080 to 3/090-RHS) Deposit work	99204	2000/-	One Month	350/-	Class- C & D
68	C/o link road Laluwal to Polian Km 0/0 to 3/400 under 5054-MMSY (SH: P/L 20mm thick premix carpet at RD 1/020 to 1/360) Deposit work	99672	2000/-	One Month	350/-	Class- C & D
69	Construction of Boundary wall at Govt. Sr.Sec.School Bhadsali (SH: C/o Boundary wall legnth 11.60 mtr) Phase-IV	98572	2000/-	One Month	350/-	Class- C & D
70	Restoration of rain damage on Pandoga to Pandoga Barrier road Km 0/0 to 9/00 (SH: C/O r/wall at RD 2/342.50 to 2/351.50)	99672	2000/-	One Month	350/-	Class- C & D
71	C/o link road Laluwal to Polian Km 0/0 to 3/400 under 5054-MMSY (SH: P/L 20mm thick premix carpet at RD 3/040 to 0/681) Deposit work	99964	2000/-	One Month	350/-	Class- C & D
72	Restoration of rain damage on Pandoga to Pandoga Barrier road Km 0/0 to 9/00 (SH: C/O r/wall at RD 2/351.50 to 2/360.50)	99672	2000/-	One Month	350/-	Class- C & D
73	C/o link road Laluwal to Polian Km 0/0 to 3/400 under 5054-MMSY (SH: P/L 20mm thick premix carpet at RD 0/681 to 1/020) Deposit work	99378	2000/-	One Month	350/-	Class- C & D
74	Construction of Boundary wall at Govt. Sr.Sec.School Bhadsali (SH: C/o Boundary wall legnth 11.20 mtr) Phase-VIII	96960	2000/-	One Month	350/-	Class- C & D
75	Restoration of rain damage on link orad Harijan basti Panjavar (SH: P/L 1:1.5:3 CC pavement in RD 0/315 to 0/325)	99895	2000/-	One Month	350/-	Class- C & D
76	Construction of Boundary wall at Govt. Sr.Sec.School Bhadsali (SH: C/o Boundary wall legnth 10.00 mtr) Phase-X	97731	2000/-	One Month	350/-	Class- C & D

The earnest money in the shape of National Saving certificate/ time deposit/ saving account of any post office or FDR, Nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected. The tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained. The copy of valid enlistment, GST registration No., Income Tax, Pan No. and epf no. must be attached with application.

SPECIAL CONDITION: -

3. The earnest money for the above work should be submitted duly pledged in favour of Executive Engineer, Haroli Division HPPWD with the application for the purchase of tender forms. The application received without earnest money shall summarily be rejected.
4. The contractor/firms are required to insert the rate in words as well as figures, failing which Executive Engineer reserves the right to accept/rejects any or all tenders. If any of the date mentioned above happens to be local/gazetted holidays, the same shall be process on next date.
5. The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which may be attached with their application a/w proof of ownership of machinery/legal tie up arrangement).
6. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.
7. The conditional/ambiguous/telegraphic tenders by fax shall not entertained/considered in any case.

HIM SUCHANA AVAM JAN SAMPARK.


Executive Engineer
HPPWD Division Haroli
Distt.Una(HP).Pin Code-177220

Email: ee-harolli-hp@hp.gov.in
On behalf of Governor of Himachal Pradesh

Schedule of quantity

Name of Work :- Restoration of rain damages on Link road to Village Boolgarh km. 0/00 to 2/600 (SH :- C/O Retaining wall at RD. 2/619 to 2/631 Lhs)						Estimated Cost: Rs	₹ 99,522
						Time:-	One month
						Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government..	8.64	Cum	160.00	Rupees One Hundred Sixty Only	1382	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malikana ,toll tax,GST,labour cess or other taxes imposed by the Government..	28.44	Cum	3300.00	Rupees Three Thousand Three Hundred Only	93852	
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malikana ,toll tax,GST,labour cess or other taxes imposed by the Government..	7.00	Each	160.00	Rupees One Hundred Sixty Only	1120	
4	Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government	5.76	Cum	550.00	Rupees Five Hundred Fifty Only	3168	
					Total	99522	
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018						
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021						
	Percentage quoted rate in figures						
	Percentage quoted rate in words						
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Schedule of quantity

Name of work: - Construction of Bus stand at Dulehar Tehsil Haroli Distt. Una HP. (SH: Repair & Repainting of Dulehar Bus stand Building & Boundary wall etc.) (Deposit work) Phase-III						Estimated Cost: Rs	Time:-	₹ 99,204
						One month		
Earnest Money:-								
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	2000		
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	504.06	sqm	10.00	Rupees Ten Only	Amount 5041.00		
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	126.02	sqm	65.00	Rupees SixtyFive Only	8191.00		
3	Finishing walls with Acrylic Smooth exterior paint of required shade Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	504.06	sqm	85.00	Rupees EightyFive Only	42845.00		
4	providing and fixing double scaffolding system (cup lock type) on the exterior side of building/structure, upto 25 metre height, above ground level, including additional rows of scaffolding in stepped manner as per requirement of site, made with 40mm dia M.S. tube, placed 1.5 metre centre to centre, horizontal & vertical tubes joint with cup & lock system with M.S. Tubes, M.S. tube chalis, M.S. clamps and staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for cution of work of cleaning and/ or pointing and/ or applying chemical and moving it thereafter. The scaffolding system shall be stiffened with racings, runners, connecting with the building etc, wherever required, if feasible, for inspection of work at required ocations with essential safety features for the workmen etc., complete as per directions and approval of Engineer-in-charge. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	229.40	sqm	188.00	Rupees One Hundred EightyEight Only	43127.00		
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018						Total	99204	
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021								
Percentage quoted rate in figures								
Percentage quoted rate in words								
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected								

Executive Engineer,
H.P.P.W.D. Division Ha
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O on link road to Mohalla Sainia Swan khad via shiv Mandir Lower Ispur 0/00 to 1/00, Panjawaar Bathri road km 4/00 to 9/00 , link road from Ispur Pandoga to Kavarian 0/00 to 2/900, Link road Petrol Pump Bhadsali to Una Hoshiarpur road to Pandoga lower Sania abadi 0/00 to 2/00 (SH:- Supplying and fixing of sign boards, Painting on Parapets ,Writing letters etc)

Estimated Cost 99619/-
Earnest Money 2000
Time limit One month

S No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Supplying and fixing direction and place identification sign board as per IRC:67 made of 1.5mm (one point five millimeter) thick MS sheeting vide Clause 1701.23 with area exceeding 0.90 sqm supported on 40mm dia MS pipe painted with red lead primer as approved drawing and and technical specification clause 1701(1200mmx900mm)including size board including carriage of material within all leads and lifts and other incidentals as per the direction of Engineer-in-charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.00	each	6200	Rupees six thousand two hundred only	31000
2	Painting steel work with Deluxe Multi surface paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including entire carriage of material within all leads and lifts and other incidentals as per the direction of Engineer-in-charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	10.80	sqm	80	Rupees eighty only	864
3	Writing letter of figures on any surface with black japan paint including stops, commas, hyphen extra including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	15000.00	Per letter per centimeter height	1.75	Rupees one and seventy five paise only	26250
4	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	296.46	sqm	10.00	Rupees ten only	2965

5	Providing and applying apex paint (two or more coats) on any surface with Asian paint, Nerolac, Burger at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat preparation of surface, etc. complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	296.46	sqm	130.00	Rupees one hundred thirty only	38540
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)(17)2/0212 dated 7.8.2018				Total	99619
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the					

Executive Engineer,
P.P.W.D. Division Ha
Distt. Una (H.P.)

Schedule of quantity

Name of work:- Construction of Boundary wall at Govt Sr.Sec. School Bhadsali Distt. Una .						
(SH: C/O Boundary wall length =11.90 mtr.) Phase-I						
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Excavation in foundation trenches etc. in earth work,lift upto 1.50 mtrs. stacking the excavated soil not more than 3 mtrs clear from the edge of the excavation and then returning the stacked soil in 15 cm layers when required in to plinths sides of foundations etc consolidating each deposited layer by ramming as watering and then disposing of all surplus excavated earth as directed with in all leads of 20 mtrs.Length of boundary wall pick work including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	7.14	Cum.	160.00	Rupees One Hundred Sixty Only	1142
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1.43	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	4719 4712
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	7.14	Cum	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	27489
4	Providing form work with steel plates 3.15mm.thick welded with angle iron in frame 30x30x5mm. so as to give a fair finish including centering, shuttering, strutting and propping etc. with wooden battens and ballies, height of propping and centering below supporting floor to ceiling not exceeding 4 Mtrs. and removal of the same for insitu-reinforced concrete & plain concrete work in: including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	28.56	Sqm.	350.00	Rupees Three Hundred Fifty Only	9996
5	Providing and laying damp proof course 38 mm thick cement concrete 1:2:4 (1cement:2 sand:4 graded stone aggregates 12.5 mm nominal size) and curing complete. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	3.57	Sqm.	284.20	Rupees Two Hundred EightyFour Paise Twenty Only	1015
6	Applying coat of hot bitumen (Mexpphalt) 80/100 or equivalent) using 1.70 kg per sqm. on damp proof course after cleaning the surface with a piece of cloth lightly soaked with kerosene oil. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	3.57	Sqm.	95.85	Rupees NinetyFive Paise EightyFive Only	342
7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in: Cement mortar 1:4 (1 cement : 4 coarse sand), including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	6.14	Cum	6550.00	Rupees Six Thousand Five Hundred Fifty Only	40224 40217

99609

₹ 99,630

One month
2000

8	15mm thick cement plaster in single coat on rough side of concrete stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and rounded angles not exceeding 80mm in girth and finished even in and smooth in cement mortar 1:4 (1 cement : 4 sand) including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	46.44	Sqm	210.00	Rupees Two Hundred Ten Only	9753
9	Providing & Laying Cement Concrete 1 : 2 : 4 (1 Cement : 2 Sand : 4 Graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work in :-String courses ,coping, bed plates . including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	0.22	Cum	4500.00	Rupees Four Thousand Five Hundred Only	990 1009
10	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm). including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	46.44	Sqm	85.00	Rupees EightyFive Only	3947 3948
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	99609 99630
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B)(A)(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Name of work:- C/O link road from House of Champa devi Rd. 0/00 to 1/200 (Deposit work)

(SH: C/O Retaining wall at Rd. 1/165 to 1/169.80 Rhs)

S.NO	DESCRIPTION	Qty	Unit	T.Rate	Estimated Cost: Rs	
					Earnest Money:- Rate in words	One month 2000 Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.61	Cum.	160.00	Rupees One Hundred Sixty Only	737
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	22.38	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	73854
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.00	nos	160.00	Rupees One Hundred Sixty Only	1280
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.07	Cum.	450.00	Rupees Four Hundred Fifty Only	1382
5	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundations of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802,803,1202 & 1203. M 25 Nominal Mix 1 : 1.5:3. and as per Direction of Engineer-in-charge, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.90	Cum.	5500.00	Rupees Five Thousand Five Hundred Only	21450
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018					
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B)(A)(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures				Total	98703
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

6

Schedule of quantity

Name of work :- Improvement of Black spot on Ajouli Santoshgarh Tahliwal Polian road km 0/00 to 13/400.				Estimated Cost: Rs		₹ 99,528
(SH: P/L Thermoplastic paint & P/F Cat eye near Speed breaker in Tahliwal Market at Rd. 3/845 & 4/120 (Bhs)				Time:-		One month
S.NO				Earnest Money:-		2000
	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing and laying of hot applied thermoplastic compound 2.5 mm (two point five millimetre)thick including reflectorising glass beads @ 250 gms (at the rate of two hundred fifty gram per square metre)per sqm area, thickness of 2.5 mm(two point five millimetre) is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	75.60	Sqm	580.00	Rupees Five Hundred Eighty Only	43848

2	Providing and fixing cat eye make)(3M) of size 100x20mm made of heavy duty body shall be molded dual shank ASA /Acyclic styrene acyloretrite) or HP/High impact polystyrene) ort ABS having electronically welded micro prismatic lens with abrasion resistant coating as approved by Engineer-in-charge. The road stud shall support a load of 13635 by tested in accordance with ASTM D4280.The slope of retro reflective surface shall be 35+/-5 degrees to base. The reflective panels on both side with at least 12cm. of each area side. The luminance intensity should be as per the specification ASTM as recommended in BS-8873 part 4 1973 as per approved sample and manufacture by the Engineer-in-charge .including carriage of materail within all leads and lifts . including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	192.00	Cum.	290.00	Rupees Two Hundred Ninety Only	55680
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	99528
	notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Schedule of quantity					Estimated Cost: Rs	₹ 99,642
Name of work :- improvement of blacktop on link road Umralli Beetan Singah road RD 0/00 to 6/550					Time:-	One month
(SH: C/O 1 Nos Speed breaker 80 mm paver block with CC Pavement P/L Thermoplastic paint & P/F Cat eye at Rd 1/630 near Govt Primary School Beetan)					Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Scarifying the existing bituminous road surface to a depth of 150 mm and disposal of scarified material with a lift upto 3 m and lead upto 1000 m as per Technical Specification Clause 301.4. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	27.50	Cum.	13.50	Rupees Thirteen Paise Fifty Only	371
2	Providing and laying cement concrete 1:4:8. (One cement: five sand : ten graded stone aggregate 40 mm nominal size) and curing complete excluding cost of centring and shuttering in foundation and plinth . including all leads and lifts and carriage of materials and other incidentals. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.75	Cum.	3250.00	Rupees Three Thousand Two Hundred Fifty Only	8938

3	Providing and laying heavy duty precast cement concrete inter locking paver blocks vibro compacted upto M-50 grade i/c border or kurb block grey or coloured over sub-base of concrete with 25mm thick average thickness of cement mortar 1:4 (1 cement : 4 sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks i/c curing. rubbing & polishing complete (Sub base concrete floor to be paid for. 80mm thick inter locking blocks, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	11.00	Sqm	1000.00	Rupees One Thousand Only	11000
4	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,804,1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	0.16	cum	4500.00	Rupees Four Thousand Five Hundred Only	720

5	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundations of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802.803,1202 & 1203. M 25 Nominal Mix 1 : 1.5:3. and as per Direction of Engineer -in -charge, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	4.95	cum	5500.00	Rupees Five Thousand Five Hundred Only	27225
6	Providing and laying of hot applied thermoplastic compound 2.5 mm (two point five millimetre)thick including reflectorising glass beads @ 250 gms (at the rate of two hundred fifty gram per square metre)per sqm area, thickness of 2.5 mm(two point five millimetre) is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	39.60	sqm	580.00	Rupees Five Hundred Eighty Only	22968

SCHEDULE OF QUANTITY

Name of work :- Restoration of Gramin Sampark alongwith R/wall to the campus of Mata Santoshi Temple at khad GP Khad (SH: C/O CC pavement & C/O R/wall - Phase-IV)- Deposit work

Estimates cost:- Rs.99352/-
Earnest Money:- Rs. 2000/-
Time Limit:- One Month.

S. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octori, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	11.60	Per Cubic metre	160 00	Rupees one hundred sixty only	1856
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802,803,1202 and 1203	26.82	Per Cubic metre	3300 00	Rupees three thousand three hundred only	88506
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(s):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204,3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octori, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	6.00	Each	160 00	Rupees one hundred sixty only	960
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-25 (M-twenty five) nominal mix in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octori, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	1.46	Per Cubic metre	5500 00	Rupees five thousand five hundred only	8030
Note:-	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@1702/0212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)/A(31)/2020 dated 22.07.20 Percentage quoted rate in Figures Percentage quoted rate in words					
	Total					99352
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
H.P.P.W.D. Division Haridwar
Distt. Una (H.P.)

Schedule of quantity

Name of work :- Restoration of rain damages on link road to village Naiyan Basti Ballial road km. 0/00 to 1/500)						Estimated Cost: Rs	₹ 98,463
(SH: P/L 80 mm thick paver blocks at Rd. 0/438.90 to 0/448.60)						Time:-	One month
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Earnest Money:-	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	23.79	Cum.	160.00	Rupees One Hundred Sixty Only		3806.00
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	5.60	Cum.	3850.00	Rupees Three Thousand Eight Hundred Fifty Only		21567.00
3	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.28	Cum.	1100.00	Rupees One Thousand One Hundred Only		8003.00
4	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 4 : 8. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	4.85	Cum.	3300.00	Rupees Three Thousand Three Hundred Only		16005.00
5	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	48.50	Cum.	850.00	Rupees Eight Hundred Fifty Only		41225.00
6	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 804, 1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	1.75	Cum.	4500.00	Rupees Four Thousand Five Hundred Only		7857.00
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018				Total		98463
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B/A)(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B/A)(31)/2020-1 Dated 07.10.2021						
	Percentage quoted rate in figures						
	Percentage quoted rate in words						
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Schedule of quantity

Name of work:- Construction of Boundary wall at Govt Sr.Sec. School Bhadsali Distt. Una .						
(SH: C/O Boundary wall length =11.50 mtr.) Phase-XI						
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Excavation in foundation trenches etc. in earth work,lift upto 1.50 mtrs. stacking the excavated soil not more than 3 mtrs clear from the edge of the excavation and then returning the stacked soil in 15 cm layers when required in to plinths sides of foundations etc consolidating each deposited layer by ramming as watering andthen disposing of all surplus excavated earth as directed with in alleads of 20 mtrs.Length of boundary wall pick work including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	6.90	Cum.	160.00	Rupees One Hundred Sixty Only	1104
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.38	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	4554
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802.803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	6.90	Cum	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	26565
4	Providing form work with steel plates 3.15mm.thick welded with angle iron in frame 30x30x5mm. so as to give a fair finish including centring, shuttering, strutting and propping etc. with wooden battens and ballies, height of propping and centring below supporting floor to ceiling not exceeding 4 Mtrs. and removal of the same for insitu-reinforced concrete & plain concrete work in: including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	27.60	Sqm.	350.00	Rupees Three Hundred Fifty Only	9660
5	Providing and laying damp proof course 38 mm thick cement concrete 1:2:4 (1cement:2 sand:4 graded stone aggregates 12.5 mm nominal size) and curing complete. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	3.45	Sqm.	284.20	Rupees Two Hundred EightyFour Paise Twenty Only	980
6	Applying coat of hot bitumen (Mexphalt) 80/100 or equivalent) using 1.70 kg per sqm. on damp proof course after cleaning the surface with a piece of cloth lightly soaked with kerosene oil. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	3.45	Sqm.	95.85	Rupees NinetyFive Paise EightyFive Only	331
7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand). including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	6.14	Cum	6550.00	Rupees Six Thousand Five Hundred Fifty Only	40224

98/100

Estimated Cost: Rs	₹ 98,128
Time:-	One month
Earnest Money:-	2000

40217

100

8	15mm thick cement plaster in single coat on rough side of concrete stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and rounded angles not exceeding 80mm in girth and finished even in and smooth in cement mortar 1:4 (1 cement : 4 sand). including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	46.44	Sqm	210.00	Rupees Two Hundred Ten Only	9752 9753
9	Providing & Laying Cement Concrete 1 : 2 : 4 (1Cement :2Sand :4 Graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work and reinforcement for reinforced cement concrete work in :-String courses ,coping, bed plates . Including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	0.22	Cum	4500.00	Rupees Four Thousand Five Hundred Only	990 1009
10	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm). including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	46.44	Sqm	85.00	Rupees EightyFive Only	3947 3948
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	98100 98128
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Name of Work:- Restoration of link road to Co-Operative society Haroli via GSSS Haroli K.M. 0/00 to 2/225						Estimated Cost: Rs	₹ 98,076
(SH: C/O Retaining wall in Rd. 1/950 to 1/974 Rhs).						Time:-	One month
						Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	8.64	Cum.	160.00	Rupees One Hundred Sixty Only	1382	
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	26.46	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	87318	
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 .including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, t	19.00	Each	160.00	Rupees One Hundred Sixty Only	3040	
4	Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	11.52	Cum.	550.00	Rupees Five Hundred Fifty Only	6336	
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				Total:	98076	
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20						
	Percentage quoted rate in Figures						
	Percentage quoted rate in words						
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damage on link road to Gondpur Jaichand km 0/00 to 0/800(SH:- C/o B/wall at RD 0/350 to 0/360.20-BHS, C/o drain at RD 0/300 to 0/310-LHS)	Estimates cost:-	99784/-
	Earnest Money:-	Rs. 2000/-
	Time Limit:-	One Month.

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government	15.12	Per Cubic metre.	160.00	Rupees one hundred sixty only	2419
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax, octroi, royalty, malkhana, toll	22.75	Per Cubic metre.	3300.00	Rupees three thousand three hundred only	75075
3	Providing weepholes in brick masonry/ stone masonry plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709, 1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax, octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	15.00	Each	160.00	Rupees One hundred only	2400
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:3:6 (One cement three sand six graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax, octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	5.10	Per Cubic metre.	3900.00	Rupees three thousand nine hundred only	19890
Note:-	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No PBW(B)(17)/20212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No PBW(B) A(31)/2020 dated 22.7.2020 & Govt. of HP vide letter No PBW(B) A(3) 1/2020-1 dated 7.10.2021				Total:-	99784
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Schedule of quantity

Name of work:- Balance work for the C/O Community Park, Outdoor open gym at ward no. 2 & 4 G.P. Dulehar Tehsil Haroli Distt Una HP. (Deposit work)					Estimated Cost: Rs	₹ 97,300
(SH: Hill side cutting for extended portion of park Rd. 0/024 to 0/028)					Time:-	One month
					Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation in hilly area in all heights and depths and in all kind of soil by mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification 2014 clause 302, 1603 in association with other clauses. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	695.00	Cum.	140.00	Rupees One Hundred Forty Only	97300
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	97300
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)(A)(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(31)/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


 Executive Engineer,
 P.P.W.D. Division Haroli
 Distt. Una (H.P.)

319

Schedule of quantity

Name of work : <u>Name of Work:- C/O of link road Nangal Khurd Mohalla Thai Lower Mannuwal near GSSS Nangal Khurd km. 0/00 to 1/00.</u>					Estimated Cost: Rs	₹ 98,923
(SH: C/O Retaining wall in Rd. 0/589 to 0/600 Rhs).					Time:-	One month
					Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	8.58	Cum.	160.00	Rupees One Hundred Sixty Only	1373
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	27.42	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	90478
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 .including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	20.00	Each	160.00	Rupees One Hundred Sixty Only	3200
4	Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	7.04	Cum.	550.00	Rupees Five Hundred Fifty Only	3872
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@1712/0212 dated 7.8.2018					Total:	98923
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Executive Engineer,
H.P.W.D. Division Haridwar
Distt. Una (H.P.)

422

Schedule of quantity							
Name of Work :- Restoration of rain damages on Link road to Village Boolgarh km. 0/00 to 2/600 (SH :- C/O Retaining wall at RD. 2/607 to 2/619 Lhs)							
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Estimated Cost: Rs Time:-	₹ 99,682 One month
					Earnest Money:-		2000
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge..including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.64	Cum	160.00	Rupees One Hundred Sixty Only		1382
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	28.44	Cum	3300.00	Rupees Three Thousand Three Hundred Only		93852
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.00	Each @ 10mm	160.00	Rupees One Hundred Sixty Only		1280
4	Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkhana, toll tax , sale tax or other taxes imposed by the Government	5.76	Cum	550.00	Rupees Five Hundred Fifty Only		3168
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018					Total	99682
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)(A)(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(3)1/2020-1 Dated 07.10.2021						
	Percentage quoted rate in figures						
	Percentage quoted rate in words						
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Name of Work :-	Quantity	Estimated Cost: Rs	Time:-
Restoration of rain damages on Link road to Village Boolgarh km. 0/00 to 2/600		₹ 99,682	One month
(SH :- C/O Retaining wall at RD. 2/607 to 2/619 Lhs)			

S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Earnest Money:-	2000
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	8.64	Cum	160.00	Rupees One Hundred Sixty Only		1382
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malkhana ,toll tax, GST, labour cess or other taxes imposed by the Government..	28.44	Cum	3300.00	Rupees Three Thousand Three Hundred Only		93852
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malkhana ,toll tax, GST, labour cess or other taxes imposed by the Government..	8.00	Each	160.00	Rupees One Hundred Sixty Only		1280
4	Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkhana, toll tax , sale tax or other taxes imposed by the Government	5.76	Cum	550.00	Rupees Five Hundred Fifty Only		3168
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total		99682
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021						
	Percentage quoted rate in figures						
	Percentage quoted rate in words						
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Executive Engineer,
H.R.P.W.D. Division Haroli

Schedule of quantity

Name of work: - Construction of Bus stand at Dulehar Tehsil Haroli Distt. Una HP.					
(SH: Repair & Repainting of Dulehar Bus stand Building & Boundary wall etc.) (Deposit work) Phase-I					
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Estimated Cost: Rs
					Time:- Earnest Money:-
					Rate In words
					Amount
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	892.75	sqm	10.00	Rupees Ten Only
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	223.19	sqm	65.00	Rupees SixtyFive Only
3	Finishing walls with Acrylic Smooth exterior paint of required shade Old work ("Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	892.75	sqm	85.00	Rupees EightyFive Only
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018				Total
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (BIA(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A(31)/2020-1 Dated 07.10.2021				99319
	Percentage quoted rate in figures				
	Percentage quoted rate in words				
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected				

Executive Engineer,
P.P.W.B. Division Haroli
Distt. Una (H.P.)

431

Draft Schedule of quantity

Name of Work:- C/O of link road Nangal Khurd Mohalla Thai Lower Mannuwal near GSSS Nangal Khurd km. 0/00 to 1/00.					Estimated Cost: Rs	₹ 98,604
[SH: Providing & laying 80 mm thick paver block at Rd. 0/589 to 0/612].					Time:-	One month
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Earnest Money:- Rate in words	2000 Amount
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	39.60	Cum.	240.00	Rupees Two Hundred Forty Only	9504
2	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.60	Cum.	1100.00	Rupees One Thousand One Hundred Only	7260
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.60	nos	3300.00	Rupees Three Thousand Three Hundred Only	21780
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80mm as per drawings and Technical Specification Clause 1504. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	66.00	Cum.	850.00	Rupees Eight Hundred Fifty Only	56100
5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 804, 1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	0.88	Cum.	4500.00	Rupees Four Thousand Five Hundred Only	3960
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@/17/2/0212 dated 7.8.2018				Total:	98604
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Schedule of quantity

Name of work: - Restoratin of rain damages on Una Rampur Haroli Jaijon road km 0/00 to 23/00						Estimated Cost: Rs	₹ 99,572
(SH: Repair of Berms at Various RDs from km. 12/00 to 16/00)						Time:-	One month
						Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	1810.40	Sqm	55.00	Rupees FiftyFive Only	99572	
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	101572	
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20						
	Percentage quoted rate in Figures						
	Percentage quoted rate in words						
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Executive Engineer,
P.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Name of work:- Construction of Boundary wall at Govt Sr.Sec. School Bhadsali Distt. Una .					Estimated Cost: Rs	
(SH: C/O Boundary wall length =11.80 mtr.) Phase-II					Time:-	One month
					Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words	Amount
1	Excavation in foundation trenches etc. in earth work, lift upto 1.50 mtrs. stacking the excavated soil not more than 3 mtrs clear from the edge of the excavation and then returning the stacked soil in 15 cm layers when required in to plinths sides of foundations etc consolidating each deposited layer by ramming as watering and then disposing of all surplus excavated earth as directed with in all leads of 20 mtrs.Length of boundary wall pick work. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	7.08	Cum	160.00	Rupees One Hundred Sixty Only	1133
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up 40 plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1.42	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	4686 4673
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	7.08	Cum	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	27258
4	Providing form work with steel plates 3.15mm thick welded with angle iron in frame 30x30x5mm. so as to give a fair finish including centering, shuttering, strutting and propping etc. with wooden battens and ballies, height of propping and centering below supporting floor to ceiling not exceeding 4 Mtrs. and removal of the same for insitu-reinforced concrete & plain concrete work in: including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	28.32	Sqm.	350.00	Rupees Three Hundred Fifty Only	9912
5	Providing and laying damp proof course 38 mm thick cement concrete 1:2:4 (1cement:2 sand:4 graded stone aggregates 12.5 mm nominal size) and curing complete. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	3.54	Sqm.	284.20	Rupees Two Hundred EightyFour Paise Twenty Only	1006
6	Applying coat of hot bitumen (Mexphalt) 80/100 or equivalent) using 1.70 kg per sqm. on damp proof course after cleaning the surface with a piece of cloth lightly soaked with kerosene oil. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	3.54	Sqm.	95.85	Rupees NinetyFive Paise EightyFive Only	339
7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand). including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	6.14	Cum	6550.00	Rupees Six Thousand Five Hundred Fifty Only	40217 40224

94240

487

8	15mm thick cement plaster in single coat on rough side of concrete stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and rounded angles not exceeding 80mm in girth and finished even in and smooth in cement mortar 1:4 (1 cement : 4 sand). including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	46.44	Sqm	210.00	Rupees Two Hundred Ten Only	9752 9753
9	Providing & Laying Cement Concrete 1 : 2 : 4 (1Cement :2Sand :4 Graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work and reinforcement for reinforced cement concrete work in :-String courses ,coping, bed plates . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	0.22	Cum	4500.00	Rupees Four Thousand Five Hundred Only	990 1009
10	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm). including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	46.44	Sqm	85.00	Rupees EightyFive Only	3947 3948
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/20212 dated 07.08.2018				Total	99240 99255
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

2

Estimated Cost: Rs	₹ 99,365
--------------------	----------

DESCRIPTION

I

SCHEDULE OF QUANTITY

					Estimates cost:-	
					Earnest Money:-	99635/-
					Time Limit:-	Rs. 2000/-
					One Month.	
Name of work :- Restoration of rain damage on link road to Gondpur Jaichand km 0/00 to 0/800(SH:- C/o B/wall at RD 0/373.20 to 0/386.20 - BHS)						
S. No.	Description of work	Quantity	Unit	Rate In Figures Words	AMOUNT	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.80	Per Cubic metre.	160.00 Rupees one hundred sixty only	1248	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll	28.99	Per Cubic metre.	3300.00 Rupees three thousand three hundred only	95667	
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(thundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709, 1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	17.00	Each	160.00 Rupees One hundred sixty only	2720	
Note:-	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No.PBW(B) A(31)/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021			Total:-	99635	
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
P.P.W.D. Division Ha
Distt. Una (H/R)

SCHEDULE OF QUANTITY

Estimated cost 99620 99774
Earnest money 2000
Time limit One month

Name of work: Improvement of College infrastructure at SDWG Govt. College Beetan Tehsil Haroli Distt. Una (SH: C/O boundary wall) Phase-II (P) Work

SCHEDULE OF WORK / ITEM(S)						
S.No	Description of Work / Item(s)	Qty	Unit	RATE In		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	8.00	Per cubic metre	160.00	Rupees one hundred sixty only	1280
2	Providing and laying cement concrete 1:4:8 (one cement: four sand,eight graded crushed stone aggregate 40mm, forty millimeter nominal size) mechanically mixed and curing complete excluding cost of form work in all work upto plinth level and breast wall including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.60	Per cubic metre	3350.00	Rupees three thousand three hundred fifty only	5360
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:3:6 (one Cement : three coarse sand): six graded crushed stone aggregate 20 mm(twenty millimetre) (twenty millimetre) nominal size) as directed by Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.00	Per cubic metre	3950.00	Rupees three thousand nine hundred fifty only	31600
4	Providing form work with steel plates 3.15mm (three point fifteen millimeter) thick welded with angle iron in frame of 30x30x5 mm (thirty into thirty into five millimeter) size so as to give a fair finish including centering shuttering strutting and propping etcetera with wooden battens and ballies for all heights of propping and centering below supporting floor to ceiling and removal of the same for insitu reinforcement and plain concrete work in foundation footing and bases of columns etcetera and mass concrete including carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	32.00	Per square metre	280.00	Rupees two hundred eighty only	8960
5	Providing and laying damp proof course 38mm (thirty eight millimeter)thick with cement concrete 1:2:4 (One cement:two sand:four graded crushed stone aggregate 12.5mm (twelve point five millimeter)nominal size) and curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax ,GST,labour cess or other taxes imposed by the Government.	4.00	Per square metre	270.00	Rupees two hundred seventy only	1080
6	Applying a coat of hot bitumen (mexphalt 80/100(eighty/hundred) or equivalent using 1.70 kg. (one point seventy kilogramme)per square meter on damp proof course after cleaning the surface with a piece of cloth lightly soaked with kerosene oil including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	4.00	Per square metre	100.00	Rupees one hundred only	400

7	Brick work with common burnt clay F.P.S. (Non modular) bricks of class designation 7.5 in superstructure above plinth level upto all floor level /height in all shapes and size cement mortar 1:6 (one cement: six sand) including curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	5.60	Per cubic metre	6950.00	Rupees six thousand nine hundred fifty only	38920
8	15mm (fifteen millimetre) cement plaster in single coat on rough side of brick/concrete/stone walls for interior plastering in all floor level/any height including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (eighty millimetre) in girth and finished even and smooth in cement mortar 1:6 (one cement: six sand) including curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	41.54	Per square metre	195.00	Rupees one hundred ninety five only	8100
9	Providing and laying cement concrete work grade M-20 (M-twenty twenty) in retaining walls, return walls, walls (any thickness) including attached pillars, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain windows sills, filets, sunken floor etc. upto floor all level and curing complete including the cost of centering, shuttering and finishing including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	0.21	Per cubic metre	5550.00	Rupees five thousand five hundred fifty only	1166
10	Finishing walls with Acrylic Smooth exterior paint of required shade Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	41.54	Per Square metre	70.00	Rupees seventy only	2908
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)@17/20212 dated 7.8.2018					Total	99774
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No. PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Executive Engineer
Haroli Division
HP.PWD., Haroli

945

SCHEDULE OF QUANTITY

Name of work :- Restoration of Gramin Sampark alongwith R/wall to the campus of Mata Santoshi Temple at khad GP Khad (SH: C/O CC pavement & C/O R/wall - Phase-V)- Deposit work

Estimates cost:- Rs.79256/-
Earnest Money:- Rs. 2000/-
Time Limit:- One Month.

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	8.96	Per Cubic metre.	160.00	Rupees one hundred sixty only	1434
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under waterlor ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203	20.84	Per Cubic metre.	3300.00	Rupees three thousand three hundred only	68772
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1:(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709.1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	5.00	Each	160.00	Rupees one hundred sixty only	800
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-25 (M-twenty five) nominal mix in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802. 803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	2	Per Cubic metre.	5500	Rupees five thousand five hundred only	8250
Total						
Note:-	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@1712/0212 dated 7.8.2018					79256
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)/A(31)/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Tenderer with seal

396

Draft Schedule of quantity

Name of Work:- C/O of link road Nangal Khurd Mohalla Thal Lower Mannuwal near GSSS Nangal Khurd km. 0/00 to 1/00.
(SH: Providing & laying 80 mm thick paver block at Rd. 0/635 to 0/657.80).

S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:- Rate in words	Estimated Cost: Rs	One month 2000 Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.52	Cum.	240.00	Rupees Two Hundred Fourty Only		4925
2	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.84	Cum.	1100.00	Rupees One Thousand One Hundred Only		7524
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.84	nos	3300.00	Rupees Three Thousand Three Hundred Only		22572
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80mm as per drawings and Technical Specification Clause 1504. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	68.40	Cum.	850.00	Rupees Eight Hundred Fifty Only		58140
5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 804, 1202 & 1203 P.C.C. grade M 20 Nominal and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	0.91	Cum.	4500.00	Rupees Four Thousand Five Hundred Only		4104
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(17)/2021 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)(A)(31)/2020 dated 22.07.20				Total:	97265	
	Percentage quoted rate in Figures						
	Percentage quoted rate in words						
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Draft Schedule of quantity

Name of Work:- Restoration of link road to Co-Operative society Haroli via GSSS Haroli K.M. 0/00 to 2/225								Estimated Cost: Rs	₹ 99,605
(SH: Providing & laying 80 mm thick paver block at Rd. 1/460.90 to 1/476.40).								Time:-	One month
								Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.93	Cum.	160.00	Rupees One Hundred Sixty Only	3348			
2	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.98	Cum.	1100.00	Rupees One Thousand One Hundred Only	7673			
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.98	Cum	3300.00	Rupees Three Thousand Three Hundred Only	23018			
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80mm as per drawings and Technical Specification Clause 1504. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	69.75	Sqm	850.00	Rupees Eight Hundred Fifty Only	59288			
5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,804,1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1.40	Cum.	4500.00	Rupees Four Thousand Five Hundred Only	6278			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				Total:	99605			
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(31)/2020 dated 22.07.20								
	Percentage quoted rate in Figures								
	Percentage quoted rate in words								
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.								

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

407

Schedule of quantity

Name of work :- Restoration of rain damages on link road to village Naiyan Basti Balliwal road km. 0/00 to 1/500)
(SH: P/L 80 mm thick paver blocks at Rd. 0/419.50 to 0/429.10)

Estimated Cost: Rs						₹ 97,447
Time:-						One month
Earnest Money:-						2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	23.54	Cum.	160.00	Rupees One Hundred Sixty Only	3767.00
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	5.54	Cum.	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	21344.00
3	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. The rate is including of octroi, royalty, Malkhana, toll tax, sale tax or other taxes imposed by the Government.	7.20	Cum.	1100.00	Rupees One Thousand One Hundred Only	7920.00
4	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 4 : 8, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	4.80	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	15840.00
5	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	48.00	Cum	850.00	Rupees Eight Hundred Fifty Only	40800.00
6	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 804, 1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	1.73	Cum.	4500.00	Rupees Four Thousand Five Hundred Only	7776.00
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018					
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note - Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					
					Total	97447

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damage on link road to Gondpur Jaichand km 0/00 to 0/800(SH:- C/o B/wall at RD 0/386.20 to 0/395 & C/o CC pavement RD 0/440 to 0/449-BHS)						Estimates cost:- Earnest Money:- Time Limit:-	99311/- Rs. 2000/- One Month.
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	5.28	Per Cubic metre.	160.00	Rupees one hundred sixty only	845	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 20mm (twenty millimeter) nominal size in or under water ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802 803 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	22.27	Per Cubic metre.	3300.00	Rupees three thousand three hundred only	73491	
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614, 709, 1204 3.7 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	1.35	Each	1100.00	Rupees one thousand one hundred only	1485	
4	Construction of Granular Sub Base by providing well graded material, spreading in uniform layers with tractor mount roller on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	10.00	Per Cubic metre.	160.00	Rupees one hundred sixty only	1600	
5	Providing and laying (M-25) (M-twenty five) Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	3.98	Per Cubic metre.	5500.00	Rupees five thousand five hundred only	21890	
Note:-	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No PBW(B)(17)20212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No PBW(B) A(3) 1/2020-1 dated 7.10.2021 Percentage quoted rate in Figures Percentage quoted rate in words						99311
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Schedule of quantity

Name of Work :- Restoration of rain damages on Link road to Village Boolgarh km. 0/00 to 2/600					Estimated Cost: Rs	₹ 98,912
(SH :- C/O Retaining wall at RD. 2/579 to 2/595 Lhs)					Time:-	One month
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge..including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.00	Cum	160.00	Rupees One Hundred Sixty Only	1280
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	27.20	Cum	3300.00	Rupees Three Thousand Three Hundred Only	89760
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	14.00	Each	160.00	Rupees One Hundred Sixty Only	2240
4	Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkhana, toll tax , sale tax or other taxes imposed by the Government	10.24	Cum	550.00	Rupees Five Hundred Fifty Only	5632
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018				Total	98912
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Name of work:- Construction of Boundary wall at Govt Sr.Sec. School Bhadsali Distt. Una .

					Estimated Cost: Rs	Time:-	One month	2000
					Earnest Money:-			
					Rate in words	T.Rate	Unit	Qty
S.NO	DESCRIPTION	Unit	Qty	T.Rate	Amount			
1	Excavation in foundation trenches etc. in earth work, lift upto 1.50 mtrs. stacking the excavated soil not more than 3 mtrs clear from the edge of the excavation and then returning the stacked soil in 15 cm layers when required in to plinths sides of foundations etc consolidating each deposited layer by ramming as watering and then disposing of all surplus excavated earth as directed with in alleads of 20 mtrs.Length of boundary wall pick work including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	Cum.	6.84	160.00	Rupees One Hundred Sixty Only	1094		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	Cum.	1.37	3300.00	Rupees Three Thousand Three Hundred Only	4521 4514		
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	Cum	6.84	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	26334		
4	Providing form work with steel plates 3.15mm.thick welded with angle iron in frame 30x30x5mm. so as to give a fair finish including centering, shuttering, strutting and propping etc. with wooden battens and ballies, height of propping and centering below supporting floor to ceiling not exceeding 4 Mtrs. and removal of the same for insitu-reinforced concrete & plain concrete work in: including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	Sqm.	27.36	350.00	Rupees Three Hundred Fifty Only	9576		
5	Providing and laying damp proof course 38 mm thick cement concrete 1:2:4 (1 cement:2 sand:4 graded stone aggregates 12.5 mm nominal size) and curing complete, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	Sqm.	3.42	284.20	Rupees Two Hundred EightyFour Paise Twenty Only	972		
6	Applying coat of hot bitumen (Mexpphalt) 80/100 or equivalent) using 1.70 kg per sqm. on damp proof course after cleaning the surface with a piece of cloth lightly soaked with kerosene oil. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	Sqm.	3.42	95.85	Rupees NinetyFive Paise EightyFive Only	328		
7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand), including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	Cum	6.14	6550.00	Rupees Six Thousand Five Hundred Fifty Only	40217 40224		

97731

99

lun

8	15mm thick cement plaster in single coat on rough side of concrete stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and rounded angles not exceeding 80mm in girth and finished even in and smooth in cement mortar 1:4 (1 cement : 4 sand). including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	46.44	Sqm	210.00	Rupees Two Hundred Ten Only	9752 9753
9	Providing & Laying Cement Concrete 1 : 2 : 4 (1 Cement : 2 Sand : 4 Graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work in :-String courses, coping, bed plates . Including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	0.22	Cum	4500.00	Rupees Four Thousand Five Hundred Only	990 1009
10	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm). including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	46.44	Sqm	85.00	Rupees EightyFive Only	3947 3948
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	97731 97752
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Name of work :- Construction of Bus stand at Dulehar Tehsil Haroli Distt. Una HP. (SH: Repair & Repainting of Dulehar Bus stand Building & Boundary wall etc.) (Deposit work) Phase-II					Estimated Cost: Rs		₹ 99,205
					Time:-		One month
					Earnest Money:-		2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Removing dry or oil bound distemper by washing and scraping and sand paping the wall surface smooth including necessary repairs to scratches complete. including cartiage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	571.84	sqm	10.00	Rupees Ten Only	5718.00	
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. including cartiage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	142.96	sqm	65.00	Rupees SixtyFive Only	9292.00	
3	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two coat. including cartiage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	149.60	sqm	75.00	Rupees SeventyFive Only	11220.00	
4	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture. including cartiage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	12.45	sqm	74.00	Rupees SeventyFour Only	921.00	
5	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture. including cartiage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	360.99	sqm	78.00	Rupees SeventyEight Only	28157.00	
6	Finishing walls with Acrylic Smooth exterior paint of required shade Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface. including cartiage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	71.65	sqm	85.00	Rupees EightyFive Only	6090.00	
7	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. including cartiage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	120.00	Kg	98.00	Rupees NinetyEight Only	11760.00	
8	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with. 4.0 mm thick glass panes. including cartiage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	11.83	Sqm	847.55	Rupees Eight Hundred FourtySevenPaise FiftyFive Only	10027.00	

9	Providing & fixing Corrugated polycarbonated transparent sheet 0.80 mm thick to 1.20mm thick, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax, octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	18.00	Sqm	890.00	Rupees Eight Hundred Ninety Only	16020.00
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	99205
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


 Executive Engineer,
 P.P.W.D. Division Haridwar
 Distt. Una (H.P.)

Draft Schedule of quantity

Name of Work:- C/O of link road Nangal Khurd Mohalla Thai Lower Mannuwal near GSSS Nangal Khurd km. 0/00 to 1/00.						Estimated Cost: Rs	₹ 98,118
(SH: Providing & laying 80 mm thick paver block at Rd. 0/657.80 to 0/680.80).						Time:-	One month
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:- Rate in words	2000 Amount	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.70	Cum.	240.00	Rupees Two Hundred Forty Only	4968	
2	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.90	Cum.	1100.00	Rupees One Thousand One Hundred Only	7590	
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.90	nos	3300.00	Rupees Three Thousand Three Hundred Only	22770	
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80mm as per drawings and Technical Specification Clause 1504. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	69.00	Cum.	850.00	Rupees Eight Hundred Fifty Only	58650	
5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,804,1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	0.92	Cum.	4500.00	Rupees Four Thousand Five Hundred Only	4140	
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				Total:	98118	
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(31)/2020 dated 22.07.20						
	Percentage quoted rate in Figures						
	Percentage quoted rate in words						
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Executive Engineer,
P.P.W.D. Division Ha
Distt. Una (H.P.)

Schedule of quantity

Name of Work :- Restoration of rain damages on Link road to Village Boolgarh km. 0/00 to 2/600						Estimated Cost: Rs	₹ 99,682
(SH :- C/O Retaining wall at RD. 2/595 to 2/607 Lhs)						Time:-	One month
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Earnest Money:-	2000
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge..including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.64	Cum	160.00	Rupees One Hundred Sixty Only		1382
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	28.44	Cum	3300.00	Rupees Three Thousand Three Hundred Only		93852
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.00	Each	160.00	Rupees One Hundred Sixty Only		1280
4	Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkhana, toll tax , sale tax or other taxes imposed by the Government	5.76	Cum	550.00	Rupees Five Hundred Fifty Only		3168
					Total		99682
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018						
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)(A)(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(3)1/2020-1 Dated 07.10.2021						
	Percentage quoted rate in figures						
	Percentage quoted rate in words						
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damage on link road to Gondpur Jaichand km 0/00 to 0/800(SH:- C/o CC pavement at RD 0/449to 0/501-LHS)						
		Estimates cost:- Earnest Money:- Time Limit:-		98670/- Rs. 2000/- One Month.		

Executive Engineer,
P.P.W.D. Division Haridwar
Distt. Una (H.A.)

438

Draft Schedule of quantity

Name of Work:- C/O of link road Nangal Khurd Mohalla Thai Lower Mannuwal near GSSS Nangal Khurd km. 0/00 to 1/00.						Estimated Cost: Rs	₹ 98,118
(SH: Providing & laying 80 mm thick paver block at Rd. 0/612 to 0/635).						Time:-	One month
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:- Rate in words	Amount	2000
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.70	Cum.	240.00	Rupees Two Hundred Forty Only	4968	
2	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.90	Cum.	1100.00	Rupees One Thousand One Hundred Only	7590	
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.90	nos	3300.00	Rupees Three Thousand Three Hundred Only	22770	
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80mm as per drawings and Technical Specification Clause 1504. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	69.00	Cum.	850.00	Rupees Eight Hundred Fifty Only	58650	
5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,804,1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	0.92	Cum.	4500.00	Rupees Four Thousand Five Hundred Only	4140	
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	98118	
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20						
	Percentage quoted rate in Figures						
	Percentage quoted rate in words						
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Executive Engineer,
P.P.W.D. Division Ha
Distt. Una (H.P.)

423

Schedule of quantity

Name of work:- Construction of Boundary wall at Govt Sr.Sec. School Bhadsali Distt. Una .							Estimated Cost: Rs				
(SH: C/O Boundary wall length =11.30 mtr.) Phase-VII							Time:-				
S.NO							Earnest Money:-				
DESCRIPTION							Qty	Unit	T.Rate	Rate in words	Amount
1	Excavation in foundation trenches etc. in earth work,lift upto 1.50 mtrs. stacking the excavated soil not more than 3 mtrs clear from the edge of the excavation and then returning the stacked soil in15 cm layers when required in to plinths sides of foundations etc consolidating each deposited layer by ramming as watering andthen disposing of all surplus excavated earth as directed with in allleads of 20 mtrs.Length of boundary wall pick work. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.						6.78	Cum.	160.00	Rupees One Hundred Sixty Only	1085
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.						1.36	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	4488
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.						6.78	Cum	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	26103
4	Providing form work with steel plates 3.15mm.thick welded with angle iron in frame 30x30x5mm. so as to give a fair finish including centering, shuttering, strutting and propping etc. with wooden battens and ballies, height of propping and centering below supporting floor to ceiling not exceeding 4 Mtrs. and removal of the same for insitu-reinforced concrete & plain concrete work in: including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.						27.12	Sqm.	350.00	Rupees Three Hundred Fifty Only	9492
5	Providing and laying damp proof course 38 mm thick cement concrete 1:2:4 (1 cement:2 sand:4 graded stone aggregates 12.5 mm nominal size) and curing complete. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.						3.39	Sqm.	284.20	Rupees Two Hundred EightyFour Paise Twenty Only	963
6	Applying coat of hot bitumen (Mexphalt) 80/100 or equivalent) using 1.70 kg per sqm. on damp proof course after cleaning the surface with a piece of cloth lightly soaked with kerosene oil. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.						3.39	Sqm.	95.85	Rupees NinetyFive Paise EightyFive Only	325
7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand). including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.						6.14	Cum	6550.00	Rupees Six Thousand Five Hundred Fifty Only	40224

97362

₹ 97,377

One month 2000

8	15mm thick cement plaster in single coat on rough side of concrete stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and rounded angles not exceeding 80mm in girth and finished even in and smooth in cement mortar 1:4 (1 cement : 4 sand). including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	46.44	Sqm	210.00	Rupees Two Hundred Ten Only	9752 -9753
9	Providing & Laying Cement Concrete 1 : 2 : 4 (1Cement :2Sand :4 Graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work and reinforcement for reinforced cement concrete work in :-String courses ,coping, bed plates . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.22	Cum	4500.00	Rupees Four Thousand Five Hundred Only	990 1009
10	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm). including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	46.44	Sqm	85.00	Rupees EightyFive Only	0 3947 3948
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	97362 97377
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY						
Name of work :- Restoration of rain damage on link road to Gondpur Jaichand km 0/00 to 0/800(SH:- C/o B/wall at RD 0/360.20to 0/373.20 -BHS)				Estimates cost:- Earnest Money:- Time Limit:-		99795/- Rs. 2000/- One Month.
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.80	Per Cubic metre.	160.00	Rupees one hundred sixty only	1248
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll	28.99	Per Cubic metre.	3300.00	Rupees three thousand three hundred only	95667
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614, 709, 1204, 3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	18.00	Each	160.00	Rupees One hundred only	2880
Note:-						
HP vide letter No.PBW(B)(17)/20212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt of HP vide letter No.PBW(B) A(3)/1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						
				Total:-		99795

Executive Engineer,
J.P.P.W.D. Division Haridwar
Distt. Una (H.P.)

Signature of Tenderer with seal

435

SCHEDULE OF QUANTITY

Estimated cost 9920997-74)
 Earnest money 2000
 Time limit One month

Name of work: Improvement of College infrastructure at SDWG Govt. College Beetan Tehsil Haroli Distt. Una (SH: C/O boundary wall)

Phase-I (Part 1)

SCHEDULE OF WORK / ITEM(S)						
S.No	Description of Work / Item(s)	Qty	Unit	RATE In		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	8.00	Per cubic metre	160.00	Rupees one hundred sixty only	1280
2	Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm) forty millimeter nominal size) mechanically mixed and curing complete excluding cost of form work in all work upto plinth level and breast wall including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.60	Per cubic metre	3350.00	Rupees three thousand three hundred fifty only	5360
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : three coarse sand): six graded crushed stone aggregate 20 mm(twenty millimetre) (twenty millimetre) nominal size) as directed by Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	8.00	Per cubic metre	3950.00	Rupees three thousand nine hundred fifty only	31600
4	Providing form work with steel plates 3.15mm (three point fifteen millimeter) thick welded with angle iron in frame of 30x30x5 mm (thirty into thirty into five millimeter) size so as to give a fair finish including centering shuttering strutting and propping etcetera with wooden battens and ballies for all heights of propping and centering below supporting floor to ceiling and removal of the same for insitu reinforcement and plain concrete work in foundation footing and bases of columns etcetera and mass concrete including carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	32.00	Per square metre	280.00	Rupees two hundred eighty only	8960
5	Providing and laying damp proof course 38mm (thirty eight millimeter) thick with cement concrete 1:2:4 (One cement: two sand: four graded crushed stone aggregate 12.5mm (twelve point five millimeter)nominal size) and curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	4.00	Per square metre	270.00	Rupees two hundred seventy only	1080
6	Applying a coat of hot bitumen (mexphalt 80/100 (eighty/hundred) or equivalent using 1.70 kg. (one point seventy kilogramme) per square meter on damp proof course after cleaning the surface with a piece of cloth lightly soaked with kerosene oil including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax sale tax, GST, labour cess or other taxes imposed by the Government.	4.00	Per square metre	100.00	Rupees one hundred only	400

7	Brick work with common burnt clay F P S (Non modular) bricks of class designation 7.5 in superstructure above plinth level upto all floor level /height in all shapes and size cement mortar 1:6(one cement: six sand) including curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana , toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	5.60	Per cubic metre	6950.00	Rupees six thousand nine hundred fifty only	38920
8	15mm (fifteen millimetre) cement plaster in single coat on rough side of brick/concrete/stone walls for interior plastering in all floor level/any height including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (eighty millimetre) in girth and finished even and smooth in cement mortar 1:6 (one cement : six sand) including curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana , toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	41.54	Per square metre	195.00	Rupees one hundred ninety five only	8100
9	Providing and laying cement concrete work grade M-20(M-twenty twenty) in retaining walls, return walls, walls (any thickness) including attached pillars, columns, piers, abutments, pillars, , posts, struts, buttresses, string or lacing courses, parapets,, coping, bed blocks, anchor blocks, plain windows sills, fillets, sunken floor etc. upto floor all level and curing complete including the cost of centering, shuttering and finishing including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana , toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	0.21	Per cubic metre	5550.00	Rupees five thousand five hundred fifty only	1166
10	Finishing walls with Acrylic Smooth exterior paint of required shade Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana , toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	41.54	Per Square metre	70.00	Rupees seventy only	2908
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018				Total	99774
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.					



Executive Engineer

Haroli Division

HP, PWD, Haroli

544

SCHEDULE OF QUANTITY

Estimated Cost 99875/-
Earnest Money 2000
Time limit One month

Name of work:- A/R & M/O on link road to Village Nangoli km 0/00 to 5/00, Panjawar Bathri road km 0/00 to 4/200, link road to village khad at RD km 0/00 to 3/500 , (SH:- Supplying and fixing of sign boards ,Painting on Bridges ,Parapets Bridges & Writing letters etc).

S No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Supplying and fixing direction and place identification sign board as per IRC:67 made of 1.5mm (one point five millimeter) thick MS sheeting vide Clause 1701.23 with area exceeding 0.90 sqm supported on 40mm dia MS pipe painted with red lead primer as approved drawing and and technical specification clause 1701(1200mmx900mm)including size board including carriage of material within all leads and lifts and other incidentals as per the direction of Engineer-in-charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.00	each	6200	Rupees six thousand two hundred only	43400
2	Painting steel work with Deluxe Multi surface paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including entire carriage of material within all leads and lifts and other incidentals as per the direction of Engineer-in-charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	15.12	sqm	80	Rupees eighty only	1210
3	Writing letter of figures on any surface with black japan paint including stops, commas, hyphen extra including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	20600.00	Per letter per centimeter height	1.75	Rupees one and seventy five paisa only	36050
4	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	137.25	sqm	10.00	Rupees ten only	1373

5	Providing and applying apex paint (two or more coats) on any surface with Asian paint, Nerolac, Burger at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat preparation of surface, etc. complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	137.25	sqm	130.00	Rupees one hundred thirty only	17843
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total	99875
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the					

Executive Engineer,
P.P.W.D. Division Haridwar
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Estimated Cost 99984/-
Earnest Money 2000
Time limit One month

Name of work:- A/R & M/O on link road Pandoga Barrier to Panjavar road km 0/0 to 9/0.
(SH:- Painting over bridges railing, parapets & Writing letters etc . at RD 0/250 ,2/438, 3/784).

S No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	676.67	sqm	10.00	Rupees ten only	6767
2	Providing and applying apex paint (two or more coats) on any surface with Asian paint, Nerolac, Burger at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat preparation of surface, etc. complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	676.67	sqm	130.00	Rupees one hundred thirty only	87967
3	Writing letter of figures on any surface with black japan paint including stops, commas, hyphen extra including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	3000.00	Per letter per centimeter height	1.75	Rupees one and seventy five paise only	5250
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)@ (17)2/0212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20				Total	99984
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractee , otherwise the tender will be rejected.					

Executive Engineer,
P.P.W.D. Division Haridwar
Distt. Una (H.P.)

Schedule of quantity

Name of work:- Construction of Boundary wall at Govt Sr.Sec. School Bhadsali Distt. Una .					Estimated Cost: Rs	
(Slt: C/O Boundary wall length =11.30 mtr.) Phase-IX					Time:-	One month
S.NO					Earnest Money:-	2000
DESCRIPTION					Rate in words	Amount
Qty	Unit	T.Rate				
6.78	Cum.	160.00	Rupees One Hundred Sixty Only	1085		
1.36	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	4488		
6.78	Cum	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	26103		
27.12	Sqm.	350.00	Rupees Three Hundred Fifty Only	9492		
3.39	Sqm.	284.20	Rupees Two Hundred EightyFour Paise Twenty Only	963		
3.39	Sqm.	95.85	Rupees NinetyFive Paise EightyFive Only	325		
6.14	Cum	6550.00	Rupees Six Thousand Five Hundred Fifty Only	40217		
				40224		

94362

₹ 94,377

One month

2000

no

8	15mm thick cement plaster in single coat on rough side of concrete stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and rounded angles not exceeding 80mm in girth and finished even in and smooth in cement mortar 1:4 (1 cement : 4 sand) including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government.	46.44	Sqm	210.00	Rupees Two Hundred Ten Only	9752- 9753
9	Providing & Laying Cement Concrete 1 : 2 : 4 (1 Cement : 2 Sand : 4 Graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work in :-String courses , coping, bed plates . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government.	0.22	Cum	4500.00	Rupees Four Thousand Five Hundred Only	990 1009
10	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm). including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government.	46.44	Sqm	85.00	Rupees EightyFive Only	3942 3948
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	97362- 97377
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

(51)

SCHEDULE OF QUANTITY

Estimated Cost 98927/-
 Earnest Money 2000/-
 Time limit One month

Name of work:- A/R & M/O on Una Rampur Haroli Palkwah Jaijon road km 0/00 to 23/00& Panjwar Bathri road Km 0/00 to 34/00 (SH:-Painting on rain shelter at near Swan Bridge ,Kangar & Rora)

S No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Finishing with Epoxy paint (two or more coats) on steel work at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government ... NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)(17)2/0212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)(A)(3)1/2020 dated 22.07.20	810.88	sqm	122.00	Rupees one hundred twenty two only	98927
					Total	98927
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractee, otherwise the tender will be rejected.					


 Executive Engineer,
 P.P.W.D. Division Haroli
 Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Estimated cost 99675
Earnest money 2000
Time limit One month

Name of work: Improvement of College infrastructure at SDWG Govt. College Beetan Tehsil Haroli Distt. Una (SH: C/O boundary wall) Phase-III

(CD) work

SCHEDULE OF WORK / ITEM(S)						
S.No	Description of Work / Item(s)	Qty	Unit	Figures	RATE In Words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.80	Per cubic metre	160.00	Rupees one hundred sixty only	1248
2	Providing and laying cement concrete 1:4:8 (one cement: four sand eight graded crushed stone aggregate 40mm) forty millimeter nominal size) mechanically mixed and curing complete excluding cost of form work in all work upto plinth level and breast wall including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.58	Per cubic metre	3350.00	Rupees three thousand three hundred fifty only	5293
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : three coarse sand): six graded crushed stone aggregate 20 mm (twenty millimetre) (twenty millimetre) nominal size) as directed by Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkana, toll tax, GST, labour cess or other taxes imposed by the Government.	8.00	Per cubic metre	3950.00	Rupees three thousand nine hundred fifty only	31600
4	Providing form work with steel plates 3.15mm (three point fifteen millimeter) thick welded with angle iron in frame of 30x30x5 mm (thirty into thirty into five millimeter) size so as to give a fair finish including centering shuttering strutting and propping etcetera with wooden battens and ballies for all heights of propping and centering below supporting floor to ceiling and removal of the same for insitu reinforcement and plain concrete work in foundation footing and bases of columns etcetera and mass concrete including carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	32.00	Per square metre	280.00	Rupees two hundred eighty only	8960
5	Providing and laying damp proof course 38mm (thirty eight millimeter) thick with cement concrete 1:2:4 (One cement two sand: four graded crushed stone aggregate 12.5mm (twelve point five millimeter) nominal size) and curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	4.00	Per square metre	270.00	Rupees two hundred seventy only	1080
6	Applying a coat of hot bitumen (mexphalt 80/100 (eighty/hundred) or equivalent using 1.70 kg. (one point seventy kilogramme) per square meter on damp proof course after cleaning the surface with a piece of cloth lightly soaked with kerosene oil including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	4.00	Per square metre	100.00	Rupees one hundred only	400

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damage on link road to Polian to Janani to providing R/wall at RD 3/070 to 3/090 RHS & U-shape drain at RD 2/140 to 2/183 RHS (SH: C/O R/wall at RD 3/070 to 3/080- RHS) Deposit work)

Estimates cost:-
Earnest Money:-
Time Limit:-

99474/-
Rs. 2000/-
One Month

S. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (hydraulic excavator) manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	8.40	Per Cubic metre	160.00	Rupees one hundred sixty only	1344
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed or broken stone aggregate 40mm (forty millimeter) nominal size in or under water/ ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802 B03 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	28.40	Per cubic metre	3300.00	Rupees three thousand three hundred only	93720
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709, 1204 3.7 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	9.00	Each	160.00	Rupees One hundred sixty only	1440
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204 3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	5.40	Per cubic metre	550.00	Rupees five hundred Fifty only	2970
Note:-	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No PBW(B)(X)17/20212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No PBW(B) A(3)/12020 dated 22.7.2020 & Govt. of HP vide letter No PBW(B) A(3) 1/2020-1 dated 7.10.2021				Total:-	99474
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Name of work :- Restoration of Rain damages on Pandoga to Pandoga Barrier road km 0/00 to 9/00 (SH:- C/o R/wall at RD 2/360.50 to 2/369.40)

Sl. No.	Description of work	Quantity	Unit	Figures	Estimated Cost	
					98581/-	2000/-
					Time limit	One month
					RATE In	AMOUNT
					Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	10.50	Per cubic metre	160.00	Rupees One hundred sixty only	1680
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana .toll tax, GST, labour cess or other taxes imposed by the Government.	27.32	Per cubic metre	3300.00	Rupees three thousand three hundred only	90156
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v) 20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614, 709, 1204, 3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	14.00	Each	160.00	Rupees One hundred sixty only	2240
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana .toll tax, GST, labour cess or other taxes imposed by the Government.	8.19	Per cubic metre	550.00	Rupees five hundred fifty only	4505
					Total:	98581
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(31/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
P.P.W.D. Division H
Distt. Una (H.P.)

475

55

551

Executive Engineer
Haroli Division
HP.PWD.,Haroli

Schedule of quantity

Name of work: - C/O link road Laluwal to Polian km. 0/00 to 3/400 Under 5054-MMSY (Deposit work).						Estimated Cost: Rs	₹ 98,792
						Time:-	One month
(SH: Providing & laying 20mm thick premix carpet at Rd. 1/698 to 2/035)						Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. i/c c/o material with in all leads and lift. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	13.90	cum	1300.00	Rupees One Thousand Three Hundred Only	18072	
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	240.96	sqm	55.00	Rupees FiftyFive Only	13253	
3	Providing, laying and rolling of open-graded premix carpet of 20 (Twenty) mm thickness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN static roller capacity, finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical Specification Clause 508.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	240.96	sqm	200.00	Rupees Two Hundred Only	48191	
4	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type A, Type B and Type C as per Technical Specification Clause 510. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	240.96	sqm	80.00	Rupees Eighty Only	19276	
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	98792	
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021						
	Percentage quoted rate in figures						
	Percentage quoted rate in words						
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Estimated Cost 99201
Earnest Money 2000
Time limit One month

Name of work:- A/R & M/O on Gondpur Turf Jai Chand road to Jhol Majra road Km 0/00 to 2/500, A/R & M/O on link road to village Gondpur Turf Jaichand Km 0/00 to 1/00 & Link road Umralli Beetan to Umralli Gahua Km 0/00 to 1/200 (SH: Painting work on parapets & culverts etc.)

S No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	698.60	Per square metre	10.00	Rupees one hundred thirty two only	6986
1	Providing and applying Apex paint (two or more coats) on any surface with Asian paint, Nerolac, Burger at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	698.60	Per square metre	132.00	Rupees one hundred thirty two only	92215
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)©(17)2/0212 dated 7.8.2018				Total	99201
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(311/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer
Haroli Division
HPPWD Haroli

453

98838

Schedule of quantity

Name of work:- Construction of Boundary wall at Govt Sr.Sec. School Bhadsali Distt. Una .						Estimated Cost: Rs	
(SH: C/O Boundary wall length =11.70 mtr.) Phase-III						Time:-	
						Earnest Money:-	
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words	Amount	
1	Excavation in foundation trenches etc. in earth work, lift upto 1.50 mtrs. stacking the excavated soil not more than 3 mtrs clear from the edge of the excavation and then returning the stacked soil in 15 cm layers when required in to plinths sides of foundations etc consolidating each deposited layer by ramming as watering and then disposing of all surplus excavated earth as directed with in all leads of 20 mtrs: Length of boundary wall pick work including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	7.02	Cum.	160.00	Rupees One Hundred Sixty Only	1123	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	1.40	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	4620 -4693	
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	7.02	Cum	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	27027	
4	Providing form work with steel plates 3.15mm thick welded with angle iron in frame 30x30x5mm. so as to give a fair finish including centering, shuftering, strutting and propping etc. with wooden battens and ballies, height of propping and centering below supporting floor to ceiling not exceeding 4 Mtrs. and removal of the same for insitu-reinforced concrete & plain concrete work in: including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	28.08	Sqm.	350.00	Rupees Three Hundred Fifty Only	9828	
5	Providing and laying damp proof course 38 mm thick cement concrete 1:2:4 (1 cement:2 sand:4 graded stone aggregates 12.5 mm nominal size) and curing complete. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	3.51	Sqm.	284.20	Rupees Two Hundred EightyFour Paise Twenty Only	998	
6	Applying coat of hot bitumen (Mexpahlt) 80/100 or equivalent) using 1.70 kg per sqm. on damp proof course after cleaning the surface with a piece of cloth lightly soaked with kerosene oil. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	3.51	Sqm.	95.85	Rupees NinetyFive Paise EightyFive Only	336	
7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand). including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	6.14	Cum	6550.00	Rupees Six Thousand Five Hundred Fifty Only	40217 40224	

48

8	15mm thick cement plaster in single coat on rough side of concrete stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and rounded angles not exceeding 80mm in girth and finished even in and smooth in cement mortar 1:4 (1 cement : 4 sand), including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	46.44	Sqm	210.00	Rupees Two Hundred Ten Only	9752-9753
9	Providing & Laying Cement Concrete 1 : 2 : 4 (1Cement : 2Sand : 4 Graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work in :-String courses , coping, bed plates . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malikhana , toll tax, GST, labour cess or other taxes imposed by the Government.	0.22	Cum	4500.00	Rupees Four Thousand Five Hundred Only	990-1009
10	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm). including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malikhana , toll tax, GST, labour cess or other taxes imposed by the Government.	46.44	Sqm	85.00	Rupees EightyFive Only	3947-3948
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	98838-98879
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Name of work :-Repair & Restoration work of road Baba Sidh Chano Temple to Mata Mandir Ward No 7.G.P. Badhera. (SH: C/O CC Pavement & Edge wall at Rd. 0/034.50 to 0/041.50) 49									
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Estimated Cost: Rs		Earnest Money:-		Amount
					Time:-		Rate in words	One month	
								2000	
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	25.20	CUM.	850.00			Rupees Eight Hundred Fifty Only		21420
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	35.28	CUM.	170.00			Rupees One Hundred Seventy Only		5998
3	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	2.10	CUM.	1150.00			Rupees One Thousand One Hundred Fifty Only		2415
4	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including, including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	10.92	CUM.	3400.00			Rupees Three Thousand Four Hundred Only		37128
5	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(i)nominal mix 1:1.5:3. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	3.15	CUM.	5600.00			Rupees Five Thousand Six Hundred Only		17640
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018						Total		84601
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021								
	Percentage quoted rate in figures								
	Percentage quoted rate in words								
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected								

Executive Engineer,
H.P.P.W.D. Division, H...

SCHEDULE OF QUANTITY									
50									
Name of work : Repair of pot hole on link road Nagnolia Harijan Basti Chappro Chhoti Khad Gujran Tarkhana Khuhi wala road Km 0/00 to 3/345 (SH; Patch work at RD 3/100 to 3/326)									
S. No.	Description of work	Quantity	Unit	Figures	Words	Estimated Cost	99887		
1	Providing , laying spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (pug mill) carriage of mixed material by tipper to site, laying in uniform layers in sub-base/ base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100KN (Eighty to hundred kilo newton) capacity to achieve the desired density including lighting barricading and maintenance of diversion etc. as per tables 400.11 & 400.12 and technical specification clause 406. including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana ,toll tax, GST, labour cess or other taxes imposed by the Government..	16.29	Per cubic metre	1400.00	Rupees One three hundred fifty only	Earnest Money	2000		
2	Providing and applying evenly a primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg (zero point seventy kilogram to one point zero kilogram) per square metre using mechanical means as per technical specification clause 502 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts. and other incidentals. The rate including octroi royalty, malkhana toll taxes, GST , labour cess or taxes imposed by the Government	217.13	Per square metre	55.00	Rupees Fifty five only	One month	AMOUNT		
3	Repair to pot holes and removal of loose material, firming of sides, cleaning of surface by providing tack coat with bitumen emulsion, 20mm thick premix carpet VG-30 and seal coat type B specification clause 1904.2.503 and 508.1 including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana ,toll tax, GST, labour cess or other taxes imposed by the Government..	217.13	Per square metre	300.00	Rupees Three hundred only		65139		
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)E(17/20212 dated 7.8.2018						Total:	99887		
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No.PBW(B) A(31/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021									
Percentage quoted rate in Figures									
Percentage quoted rate in words									
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.									

Executive Engineer
Haroli Division
HP.PWD., Haroli

457

H.P.F.W.D. Division Harold

Schedule of quantity

Name of work: - C/O link road Laluwal to Polian km. 0/00 to 3/400 Under 5054-MMSY (Deposit work).						Estimated Cost: Rs	₹ 99,672
						Time:-	One month
(SH: Providing & laying 20mm thick premix carpet at Rd. 2/035 to 2/375)						Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. i/c c/o material with in all leads and lift. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	14.03	cum	1300.00	Rupees One Thousand Three Hundred Only	18233	
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	243.10	sqm	55.00	Rupees FiftyFive Only	13371	
3	Providing, laying and rolling of open-graded premix carpet of 20 (Twenty) mm thickness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN static roller capacity, finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical Specification Clause 508..including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	243.10	sqm	200.00	Rupees Two Hundred Only	48620	
4	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type A, Type B and Type C as per Technical Specification Clause 510. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	243.10	sqm	80.00	Rupees Eighty Only	19448	
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	99672	
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021						
	Percentage quoted rate in figures						
	Percentage quoted rate in words						
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

462

SCHEDULE OF QUANTITY

Estimated Cost 99514
Earnest Money 2000
Time limit One month

Name of work:- A/R & M/O on Santoshgarh Tahlial Pollian Jaijoan road (H.P Boundary) Km 8/500 to 13/00 & A/R & M/O on Umralli Beetan road Km 0/00 to 1/350(SH: Painting work on parapets & culverts etc.)

S No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Removing dry, or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	700.80	Per square metre	10.00	Rupees one hundred thirty two only	7008
1	Providing and applying Apex paint (two or more coats) on any surface with Asian paint, Nerolac, Burger at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	700.80	Per square metre	132.00	Rupees one hundred thirty two only	92506
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)@ (17)2/0212 dated 7.8.2018				Total	99514
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the					

Executive Engineer
Haroli Division
HPPWD Haroli

Schedule of quantity

(SH: C/O Boundary wall length =11.50 mtr.) Phase-V

S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Estimated Cost: Rs	
						Time:-	One month
						Earnest Money:-	2000
1	Excavation in foundation trenches etc. in earth work, lift upto 1.50 mtrs. stacking the excavated soil not more than 3 mtrs clear from the edge of the excavation and then returning the stacked soil in 15 cm layers when required in to plinths sides of foundations etc consolidating each deposited layer by ramming as watering wall pick work. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	6.90	Cum.	160.00	Rupees One Hundred Sixty Only		1104
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	1.38	Cum.	3300.00	Rupees Three Thousand Three Hundred Only		4554
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specifications clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	6.90	Cum.	3850.00	Rupees Three Thousand Eight Hundred Fifty Only		26565
4	Providing form work with steel plates 3.15mm thick welded with angle iron in frame 30x30x5mm. so as to give a fair finish including centering, shuttering, strutting and propping etc. with wooden battens and ballies, height of propping and centering below supporting floor to ceiling not exceeding 4 Mtrs. and removal of the same for insitu-reinforced concrete & plain concrete work in: including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	27.60	Sqm.	350.00	Rupees Three Hundred Fifty Only		9660
5	Providing and laying damp proof course 38 mm thick cement concrete 1:2:4 (1 cement:2 sand:4 graded stone aggregates 12.5 mm nominal size) and curing complete. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	3.45	Sqm.	284.20	Rupees Two Hundred EightyFour Paise Twenty Only		980
6	Applying coat of hot bitumen (Mexphalt) 80/100 or equivalent) using 1.70 kg per sqm. on damp proof course after cleaning the surface with a piece of cloth lightly soaked with kerosene oil. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	3.45	Sqm.	95.85	Rupees NinetyFive Paise EightyFive Only		331
7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand), including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	6.14	Cum	6550.00	Rupees Six Thousand Five Hundred Fifty Only		40217 40224

98100

₹ 98,128

54

8	15mm thick cement plaster in single coat on rough side of concrete stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and rounded angles not exceeding 80mm in girth and finished even in and smooth in cement mortar 1:4 (1 cement : 4 sand). including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	46.44	Sqm	210.00	Rupees Two Hundred Ten Only	9752 9753
9	Providing & Laying Cement Concrete 1 : 2 : 4 (1Cement :2Sand :4 Graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work and reinforcement for reinforced cement concrete work in :-String courses, coping, bed plates . including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	0.22	Cum	4500.00	Rupees Four Thousand Five Hundred Only	990 1009
10	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm). including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	46.44	Sqm	85.00	Rupees EightyFive Only	3947 3948
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	98100 98128
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

Schedule of quantity

Name of work :- Repair & Restoration work of road Baba Sidh Chano Temple to Mata Mandir Ward No 7.G.P. Badhera. (SH: C/O CC Pavement & Edge wall at Rd. 0/026.10 to 0/034.50) <i>Handwritten: Badhera</i>						Estimated Cost: Rs	₹ 98,538
						Time:-	One month
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Earnest Money:-	2000
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (1/c equivalent design mix. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	30.24	CUM.	850.00	Rupees Eight Hundred Fifty Only		25704
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	24.79	CUM.	170.00	Rupees One Hundred Seventy Only		4214
3	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	2.52	CUM.	1150.00	Rupees One Thousand One Hundred Fifty Only		2898
4	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	13.10	CUM.	3400.00	Rupees Three Thousand Four Hundred Only		44554
5	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25 (I) nominal mix 1:1.5:3, including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	3.78	CUM.	5600.00	Rupees Five Thousand Six Hundred Only		21168
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018				Total		98538
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)(A)(3)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(3)/2020-1 Dated 07.10.2021						
	Percentage quoted rate in figures						
	Percentage quoted rate in words						
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

56

Tenderer with seal

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Name of work: - C/O link road Laluwal to Polian km. 0/00 to 3/400 Under 5054-MMSY (Deposit work).						Estimated Cost: Rs	₹ 99,378
(SH: Providing & laying 20mm thick premix carpet at Rd. 2/375 to 2/714)						Time:-	One month
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Earnest Money:-	2000
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. i/c c/o material with in all leads and lifts. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	13.98	cum	1300.00	Rupees One Thousand Three Hundred Only		18179
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	242.39	sqm	55.00	Rupees FiftyFive Only		13331
3	Providing, laying and rolling of open-graded premix carpet of 20 (Twenty) mm thickness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN static roller capacity, finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical Specification Clause 508.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	242.39	sqm	200.00	Rupees Two Hundred Only		48477
4	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type A, Type B and Type C as per Technical Specification Clause 510. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	242.39	sqm	80.00	Rupees Eighty Only		19391
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total		99378
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021						
	Percentage quoted rate in figures						
	Percentage quoted rate in words						
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Executive Engineer,
H.P.P.W.D. Division Haridwar
Distt. Una (H.P.)

463

SCHEDULE OF QUANTITY

S. No		Description of work	Quantity	Unit	RATE IN			Estimated Cost	
					Figures	Words	Amount	Earnest Money	Time limit
1		Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (pug mill) carriage of mixed material by tipper to site, laying in uniform layers in sub-base/ base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100KN (Eighty to hundred kilo newton) capacity to achieve the desired density including lighting barricading and maintenance of diversion etc. as per tables 400.11 & 400.12 and technical specifications clause 406, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	16.24	Per cubic metre	1400.00	Rupees One three hundred fifty only	22736	99590	One month
2		Providing and applying evenly a primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg (zero point seventy kilogram to one point zero kilogram) per square metre using mechanical means as per technical specification clause 502 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts, and other incidentals. The rate including octroi royalty, malikhana toll taxes, GST, labour cess or taxes imposed by the Government.	216.49	Per square metre	55.00	Rupees Fifty five only	11907		
3		Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen emulsion, 20mm thick premix carpet VG-30 and seal coat type B specification clause 1904.2.503 and 508.1 including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	216.49	Per square metre	300.00	Rupees Three hundred only	64947		
								Total:	99590
Percentage quoted rate in Figures									
Percentage quoted rate in words									
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.									

Executive Engineer
Haroli Division
HP.PWD., Haroli

457

Schedule of quantity

Name of work:- Balance work for restoration of rain damage on link road Boolgarh Bhadsali to The House of Sh. Beesham Singh G.P. Bhadsli Tehsil Haroli Distt. Una (HP) (Deposit work)							Estimated Cost: Rs	₹ 97,710/-
(SH: C/O R/wall Down stream side of culvert Rd. 0/008.50 to 0/017 RhS)							Time:-	One month
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Earnest Money:-	Amount	2000
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.29	Cum.	160.00	Rupees One Hundred Sixty Only		1326	
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	27.80	Cum.	3300.00	Rupees Three Thousand Three Hundred Only		91724/-	91740/-
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	15.00	nos	160.00	Rupees One Hundred Sixty Only		2400	
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.08	Cum.	550.00	Rupees Five Hundred Fifty Only		2244	
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018				Total		97710/-	97694/-
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021							
	Percentage quoted rate in figures							
	Percentage quoted rate in words							
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected							

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (HP)

480

60

Schedule of quantity

Name of work :-Repair & Restoration work of road Baba Sidh Chano Temple to Mata Mandir Ward No 7.G.P. Badhera. (SH: C/O CC Pavement & Edge wall at Rd. 0/017.50 to 0/026.10) <i>P/W</i>						Estimated Cost: Rs	
						Time:-	One month
						Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	30.96	CUM.	850.00	Rupees Eight Hundred Fifty Only	26316	
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	4.64	CUM.	170.00	Rupees One Hundred Seventy Only	789	
3	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	2.58	CUM.	1150.00	Rupees One Thousand One Hundred Fifty Only	2967	
4	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including, including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	13.42	CUM.	3400.00	Rupees Three Thousand Four Hundred Only	45614	
5	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(i) nominal mix 1:1.5:3. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	3.87	CUM.	5600.00	Rupees Five Thousand Six Hundred Only	21672	
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	97358	
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021						
	Percentage quoted rate in figures						
	Percentage quoted rate in words						
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Executive Engineer,

458

Schedule of quantity						
Name of work:- Construction of Boundary wall at Govt Sr. Sec. School Bhadsai Distt. Una .						
(SH: C/O Boundary wall length =10.00 mtr.) Phase-XII						
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words	Amount
1	Excavation in foundation trenches etc. in earth work, lift upto 1.50 mtrs. stacking the excavated soil not more than 3 mtrs clear from the edge of the excavation and then returning the stacked soil in 15 cm layers when required in to plinths sides of foundations etc consolidating each deposited layer by ramming as watering and then disposing of all surplus excavated earth as directed with in all leads of 20 mtrs: length of boundary wall pick work. Including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	6.00	Cum.	160.00	Rupees One Hundred Sixty Only	960
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size. Including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	1.20	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	3960
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802.803.1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. Including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	6.00	Cum	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	23100
4	Providing form work with steel plates 3.15mm.thick welded with angle iron in frame 30x30x5mm. so as to give a fair finish including centering, shuttering, strutting and propping etc. with wooden battens and ballies, height of propping and centering below supporting floor to ceiling not exceeding 4 Mtrs. and removal of the same for insitu-reinforced concrete & plain concrete work in: Including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	24.00	Sqm.	350.00	Rupees Three Hundred Fifty Only	8400
5	Providing and laying damp proof course 38 mm thick cement concrete 1:2:4 (1 cement:2 sand:4 graded stone aggregates 12.5 mm nominal size) and curing complete. Including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	3.00	Sqm.	284.20	Rupees Two Hundred EightyFour Paise Twenty Only	853
6	Applying coat of hot bitumen (Mespahlt) 80/100 or equivalent) using 1.70 kg per sqm. on damp proof course after cleaning the surface with a piece of cloth lightly soaked with kerosene oil. Including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	3.00	Sqm.	95.85	Rupees NinetyFive Paise EightyFive Only	288
7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand). Including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	5.96	Cum	6550.00	Rupees Six Thousand Five Hundred Fifty Only	39038 39048

90816

61

497

8	15mm thick cement plaster in single coat on rough side of concrete stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and rounded angles not exceeding 80mm in girth and finished even in and smooth in cement mortar 1:4 (1 cement : 4 sand). including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	44.84	Sqm	210.00	Rupees Two Hundred Ten Only	9416 9417
9	Providing & Laying Cement Concrete 1 : 2 : 4 (1Cement : 2Sand : 4 Graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work and reinforcement for reinforced cement concrete work in :-String courses, coping, bed plates . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government..	0.22	Cum	4500.00	Rupees Four Thousand Five Hundred Only	990 977
10	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 hr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm). including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government..	44.84	Sqm	85.00	Rupees EightyFive Only	3811 3812
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	90816 90785
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

697

SCHEDULE OF QUANTITY									
Name of work :- Restoration of Rain damages on Pandoga to Pandoga Barrier road km 0/00 to 9/00 (SH:- C/o R/wall at RD 2/325 to 2/333.60)									
Sl. No.	Description of work	Quantity	Unit	Figures	RATE IN		Estimated Cost	99582/-	
					Words	Amount		2000/-	One month
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	10.15	Per cubic metre	160.00	Rupees One hundred sixty only	1624			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	27.59	Per cubic metre	3300.00	Rupees three thousand three hundred only	91047			
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709, 1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	16.00	Each	160.00	Rupees One hundred sixty only	2560			
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	7.91	Per cubic metre	550.00	Rupees five hundred fifty only	4351			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				Total:	99582			
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20								
	Percentage quoted rate in Figures								
	Percentage quoted rate in words								
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.								

Executive Engineer,
P.P.W.D. Division Ha
Distt. Una (H)

474

Schedule of quantity

Name of work: - C/O link road Laluwal to Polian km. 0/00 to 3/400 Under 5054-MMSY (Deposit work).						Estimated Cost: Rs	₹ 99,085
						Time:-	One month
(SH: Providing & laying 20mm thick premix carpet at Rd. 3/052 to 3/390)						Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. i/c c/o material with in all leads and lift. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	13.94	cum	1300.00	Rupees One Thousand Three Hundred Only	18125	
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	241.67	sqm	55.00	Rupees FiftyFive Only	13292	
3	Providing, laying and rolling of open-graded premix carpet of 20 (Twenty) mm thickness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN static roller capacity, finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical Specification Clause 508..including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	241.67	sqm	200.00	Rupees Two Hundred Only	48334	
4	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type A, Type B and Type C as per Technical Specification Clause 510. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	241.67	sqm	80.00	Rupees Eighty Only	19334	
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	99085	
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021						
	Percentage quoted rate in figures						
	Percentage quoted rate in words						
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Name of work:- Balance work for restoration of rain damage on link road Boolgarh Bhadsali to The House of Sh. Beesham Singh G.P.					Estimated Cost: Rs	₹ 97,854
(SH: C/O R/wall Down stream side of culvert Rd. 0/00 to 0/008.50 Rhs)						97854
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:- Rate in words	One month 2000 Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.29	Cum.	160.00	Rupees One Hundred Sixty Only	1326
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	27.80	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	91740
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	16.00	nos	160.00	Rupees One Hundred Sixty Only	2560
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.08	Cum.	550.00	Rupees Five Hundred Fifty Only	2244
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	-97854
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B)(A)(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(31)/2020-1 Dated 07.10.2021					97854
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.P.W.D. Division Haroli

(65)

SCHEDULE OF QUANTITY

Name of work :- Restoration of Rain damages on Pandoga to Pandoga Barrier road km 0/00 to 9/00 (SH:- C/o R/wall at RD 2/333.60 to 2/342.30)							Estimated Cost	99335/-
							Earnest Money	2000/-
							Time limit	One month
Sl. No.	Description of work	Quantity	Unit	Figures	RATE In		AMOUNT	
					Words	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	10.27	Per cubic metre	160.00	Rupees One hundred sixty only		1643	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	27.50	Per cubic metre	3300.00	Rupees three thousand three hundred only		90750	
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v) 20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709, 1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	16.00	Each	160.00	Rupees One hundred sixty only		2560	
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	8.00	Per cubic metre	550.00	Rupees five hundred fifty only		4400	
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018					Total:	99353	
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(31)/2020 dated 22.07.20							
	Percentage quoted rate in Figures							
	Percentage quoted rate in words							
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.							

Executive Engineer,
I.P.P.W.D. Division Haridwar
Distt. Una (H.P.)

473/-

66

Schedule	
Name of work: - C/O link road Lauwal to Polian km. 0/00 to 3/400 Under S054-MMSY (Deposit work).	

66

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Not mandatory by the contractor, other wise the tender will be rejected

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damage on link road to Polian to Janani to providing R/wall at RD 3/070 to 3/090 RHHS & U-shape drain at RD 2/140 to 2/183 RHHS (SH: C/O R/wall at RD 3/080 to 3/090- RHHS) Deposit work)					
		Estimates cost:-		99204/-	
		Earnest Money:-		Rs. 2000/-	
		Time Limit:-		One Month.	
Description of work					
S. No.	Quantity	Unit	RATE In		AMOUNT
			Figures	Words	
1	8.40	Per Cubic metre	160 00	Rupees one hundred sixty only	1344
2	28.40	Per cubic metre	3300 00	Rupees three thousand three hundred only	93720
3	8.00	Each	160 00	Rupees One hundred sixty only	1280
4	5.20	Per cubic metre	550.00	Rupees One hundred fifty only	2860
Note:-				Total:-	99204

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Name of work: - C/O link road Laluwal to Polian km. 0/00 to 3/400 Under 5054-MMSY (Deposit work).							Estimated Cost: Rs	₹ 99,672
(SH: Providing & laying 20mm thick premix carpet at Rd. 1/020 to 1/360)							Time:-	One month
S.NO							Earnest Money:-	2000
DESCRIPTION							Rate in words	Amount
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. i/c c/o material with in all leads and lift. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	Qty	Unit	T.Rate			Rupees One Thousand Three Hundred Only	18233
		14.03	cum	1300.00				
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	Qty	Unit	T.Rate			Rupees FiftyFive Only	13371
		243.10	sqm	55.00				
3	Providing, laying and rolling of open-graded premix carpet of 20 (Twenty) mm thickness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN static roller capacity, finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical Specification Clause 508..including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	Qty	Unit	T.Rate			Rupees Two Hundred Only	48620
		243.10	sqm	200.00				
4	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type A, Type B and Type C as per Technical Specification Clause 510. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	Qty	Unit	T.Rate			Rupees Eighty Only	19448
		243.10	sqm	80.00				
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018						Total	99672
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021							
	Percentage quoted rate in figures							
	Percentage quoted rate in words							
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected							

Executive Engineer,

H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Name of work:- Construction of Boundary wall at Govt Sr.Sec. School Bhadsali Distt. Una .						Estimated Cost: Rs	₹ 98,505
(SH:- C/O Boundary wall length =11.60 mtr.) Phase-IV						Time:-	One month
						Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Excavation in foundation trenches etc. in earth work,lift upto 1.50 mtrs. stacking the excavated soil not more than 3 mtrs clear from the edge of the excavation and then returning the stacked soil in 15 cm layers when required in to plinths sides of foundations etc consolidating each deposited layer by ramming as watering and then disposing of all surplus excavated earth as directed with in allleads of 20 mtrs.Length of boundary wall pick work. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	6.96	Cum.	160.00	Rupees One Hundred Sixty Only	1114	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1.39	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	4587 4594	
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	6.96	Cum	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	26796	
4	Providing form work with steel plates 3.15mm.thick welded with angle iron in frame 30x30x5mm. so as to give a fair finish including centering, shuttering, strutting and propping etc. with wooden battens and ballies, height of propping and centering below supporting floor to ceiling not exceeding 4 Mtrs. and removal of the same for insitu-reinforced concrete & plain concrete work in: including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	27.84	Sqm.	350.00	Rupees Three Hundred Fifty Only	9744	
5	Providing and laying damp proof course 38 mm thick cement concrete 1:2:4 (1cement:2 sand:4 graded stone aggregates 12.5 mm nominal size) and curing complete. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	3.48	Sqm.	284.20	Rupees Two Hundred EightyFour Paise Twenty Only	1091, 989	
6	Applying coat of hot bitumen (Mexphalt) 80/100 or equivalent) using 1.70 kg per sqm. on damp proof course after cleaning the surface with a piece of cloth lightly soaked with kerosene oil. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	3.48	Sqm.	95.85	Rupees NinetyFive Paise EightyFive Only	334	
7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand). including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	6.14	Cum	6550.00	Rupees Six Thousand Five Hundred Fifty Only	40217 40224	

98572

4189

8	15mm thick cement plaster in single coat on rough side of concrete stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and rounded angles not exceeding 80mm in girth and finished even in and smooth in cement mortar 1:4 (1 cement : 4 sand). including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	46.44	Sqm	210.00	Rupees Two Hundred Ten Only	9752 9763
9	Providing & Laying Cement Concrete 1 : 2 : 4 (1Cement : 2Sand : 4 Graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work and reinforcement for reinforced cement concrete work in -String courses , coping, bed plates . including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	0.22	Cum	4500.00	Rupees Four Thousand Five Hundred Only	990 1009
10	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm). including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	46.44	Sqm	85.00	Rupees EightyFive Only	3947 3948
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018				Total	98572 98505
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.P.W.D.-Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Name of work :- Restoration of Rain damages on Pandoga to Pandoga Barrier road km 0/00 to 9/00 (SH- C/o R/wall at RD 2/342.50 to 2/351.50)

Sl. No.	Description of work	Quantity	Unit	Figures		Estimated Cost	99672
				Words	Amount		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	10.62	Per cubic metre	Rupees One hundred sixty only	1699		
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	27.63	Per cubic metre	Rupees three thousand three hundred only	91179		
3	Providing weepholes in brick masonry/ stone masonry plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614, 709, 1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	14.00	Each	Rupees One hundred sixty only	2240		
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	8.28	Per cubic metre	Rupees five hundred fifty only	4554		
				Total:	99672		
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018						
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20						
	Percentage quoted rate in Figures						
	Percentage quoted rate in words						
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Executive Engineer,
H.P.W.D. Division Ha
Distt. Una (H.P.)

472

Schedule of quantity

71

Name of work: - C/O link road Lalwal to Polian km. 0/00 to 3/400 Under 5054-MMSV (Deposit work).

(SH: Providing & laying 20mm thick premix carpet at Rd. 0/340 to 0/681)

S.NO	DESCRIPTION	Qty	Unit	T.Rate	Estimated Cost: Rs	
					Time:-	One month
					Earnest Money:-	2000
					Rate in words	Amount
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density i/c c/o material with in all leads and lift. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	14.07	cum	1300.00	Rupees One Thousand Three Hundred Only	18286
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	243.82	sqm	55.00	Rupees FiftyFive Only	13410
3	Providing, laying and rolling of open-graded premix carpet of 20 (Twenty) mm thickness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN static roller capacity, finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical Specification Clause 508..including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	243.82	sqm	200.00	Rupees Two Hundred Only	48763
4	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type A, Type B and Type C as per Technical Specification Clause 510. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	243.82	sqm	80.00	Rupees Eighty Only	19505
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018					
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures				Total	99964
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H/R)

SCHEDULE OF QUANTITY									
Name of work :- Restoration of Rain damages on Pandoga to Pandoga Barrier road km 0/00 to 9/00 (SH:- C/o R/wall at RD 2/351.50 to 2/360.50)									
Sl. No.	Description of work	Quantity	Unit	Figures	RATE In		Estimated Cost Earnest Money Time limit	99672 2000/- One month	AMOUNT
					Words	Words			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	10.62	Per cubic metre	160.00	Rupees One hundred sixty only				1699
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water/dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	27.63	Per cubic metre	3300.00	Rupees three thousand three hundred only				91179
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709. 1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	14.00	Each	160.00	Rupees One hundred sixty only				2240
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	8.28	Per cubic metre	550.00	Rupees five hundred fifty only				4554
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018				Total:			99672	
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)(A)(3)1/2020 dated 22.07.20								
	Percentage quoted rate in Figures								
	Percentage quoted rate in words								
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.								

Executive Engineer,
H.P.P.W.D. Division Haridwar
Distt. Una (H.P.)

471

Schedule of quantity

Name of work: - C/O link road Laluwal to Polian km. 0/00 to 3/400 Under 5054-MMSY (Deposit work).					Estimated Cost: Rs	₹ 99,378
(SH: Providing & laying 20mm thick premix carpet at Rd. 0/681 to 1/020)					Time:-	One month
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. i/c c/o material with in all leads and lift. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	13.98	cum	1300.00	Rupees One Thousand Three Hundred Only	18179
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	242.39	sqm	55.00	Rupees FiftyFive Only	13331
3	Providing, laying and rolling of open-graded premix carpet of 20 (Twenty) mm thickness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN static roller capacity, finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical Specification Clause 508.including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	242.39	sqm	200.00	Rupees Two Hundred Only	48477
4	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type A, Type B and Type C as per Technical Specification Clause 510. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	242.39	sqm	80.00	Rupees Eighty Only	19391
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018					Total	99378
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

Schedule of quantity

Schedule of quantity									
Name of work:- Construction of Boundary wall at Govt Sr.Sec. School Bhadsali Distt. Una .									
(SH: C/O Boundary wall length =11.20 mtr.) Phase-VIII									
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount			
1	Excavation in foundation trenches etc. in earth work, lift upto 1.50 mtrs. stacking the excavated soil not more than 3 mtrs clear from the edge of the excavation and then returning the stacked soil in 15 cm layers when required in to plinths sides of foundations etc consolidating each deposited layer by ramming as watering and then disposing of all surplus excavated earth as directed with in all leads of 20 mtrs: Length of boundary wall pick work. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	6.72	Cum.	160.00	Rupees One Hundred Sixty Only	1075			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	1.34	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	4422 4435			
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802.803.1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	6.72	Cum	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	25872			
4	Providing form work with steel plates 3.15mm thick welded with angle iron in frame 30x30x5mm. so as to give a fair finish including centering, shuttering, strutting and propping etc. with wooden battens and ballies, height of propping and centering below supporting floor to ceiling not exceeding 4 Mtrs. and removal of the same for insitu-reinforced concrete & plain concrete work in: including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	26.88	Sqm.	350.00	Rupees Three Hundred Fifty Only	9408			
5	Providing and laying damp proof course 38 mm thick cement concrete 1:2:4 (1 cement:2 sand:4 graded stone aggregates 12.5 mm nominal size) and curing complete. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	3.36	Sqm.	284.20	Rupees Two Hundred EightyFour Paise Twenty Only	955			
6	Applying coat of hot bitumen (Mexphalt) 80/100 or equivalent) using 1.70 kg per sqm. on damp proof course after cleaning the surface with a piece of cloth lightly soaked with kerosene oil. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	3.36	Sqm.	95.85	Rupees NinetyFive Paise EightyFive Only	322			
7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand). including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	6.14	Cum	6550.00	Rupees Six Thousand Five Hundred Fifty Only	40217 40224			

96960

(74)

8	15mm thick cement plaster in single coat on rough side of concrete stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and rounded angles not exceeding 80mm in girth and finished even in and smooth in cement mortar 1:4 (1 cement : 4 sand). including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	46.44	Sqm	210.00	Rupees Two Hundred Ten Only	9752 9753
9	Providing & Laying Cement Concrete 1 : 2 : 4 (1 Cement : 2 Sand : 4 Graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work and reinforcement for reinforced cement concrete work in -String courses , coping, bed plates . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	0.22	Cum	4500.00	Rupees Four Thousand Five Hundred Only	940 4009
10	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 hr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm). including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	46.44	Sqm	85.00	Rupees EightyFive Only	3947 3948
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018				Total	96960 97001
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


 Executive Engineer,
 H.P.W.D. Division Haroli
 Distt. Una (H.P.)

1493

SCHEDULE OF QUANTITY						
Name of work :- Restoration of rain damages on link road Harijan Basti to Ward 331 via Harinagar Panjanwal to 0/325) (SH-P/L 1:1.5:3 CC pavement in RD 0/315)						
Estimates cost:- 99895 Earnest Money:- Rs. 2000/- Time Limit:- One Month.						
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms. lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, melkhana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	11.78	Cum	160.00	Rupees one hundred sixty only	1885
2	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by mix in place method at OMC with tractor mount appropriate rovacator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORTD 2014 contained in para 2.2.3.6 and 3.7 of IRC SP 77-2008	8.40	Cum	1100.00	Rupees one thousand one hundred only	9240
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty millimeter) nominal size in or under water/ ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, melkhana toll tax, GST, labour cess or other taxes imposed by the Government.	12.90	Cum	3300.00	Rupees three thousand three hundred only	42570
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix M-25 crushed /broken stone aggregate 20mm (twenty millimeter) nominal size in or under water/ ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, melkhana toll tax, GST, labour cess or other taxes imposed by the Government.	8.40	Cum	5500.00	Rupees five thousand five hundred only	46200
Note:-	1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)(17)2/0212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B)(A)(3)1/2020 dated 22.07.20				Total:-	99895
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Schedule of quantity

Name of work:- Construction of Boundary wall at Govt Sr.Sec. School Bhadsali Distt. Una .		Estimated Cost: Rs		Time:-		Earnest Money:-	
(SH: C/O Boundary wall length =11.40 mtr.) Phase-X							
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Excavation in foundation trenches etc. in earth work, lift upto 1.50 mtrs. stacking the excavated soil not more than 3 mtrs clear from the edge of the excavation and then returning the stacked soil in 15 cm layers when required in to plinths sides of foundations etc consolidating each deposited layer by ramming as watering and then disposing of all surplus excavated earth as directed with in all leads of 20 mtrs:Length of boundary wall pick work. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	6.84	Cum.	160.00	Rupees One Hundred Sixty Only	1094	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1.37	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	4521 4574	
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	6.84	Cum	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	26334	
4	Providing form work with steel plates 3.15mm.thick welded with angle iron in frame 30x30x5mm. so as to give a fair finish including centring, shuttering, strutting and propping etc. with wooden battens and ballies, height of propping and centring below supporting floor to ceiling not exceeding 4 Mtrs. and removal of the same for insitu-reinforced concrete & plain concrete work in: Including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	27.36	Sqm.	350.00	Rupees Three Hundred Fifty Only	9576	
5	Providing and laying damp proof course 38 mm thick cement concrete 1:2:4 (1cement:2 sand:4 graded stone aggregates 12.5 mm nominal size) and curing complete. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	3.42	Sqm.	284.20	Rupees Two Hundred EightyFour Paise Twenty Only	972	
6	Applying coat of hot bitumen (Mexpfalt) 80/100 or equivalent) using 1.70 kg per sqm. on damp proof course after cleaning the surface with a piece of cloth lightly soaked with kerosene oil. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	3.42	Sqm.	95.85	Rupees NinetyFive Paise EightyFive Only	328	
7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand). including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	6.14	Cum	6550.00	Rupees Six Thousand Five Hundred Fifty Only	40217 40224	

97731

₹ 97,752

One month

2000

495

8	15mm thick cement plaster in single coat on rough side of concrete stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and rounded angles not exceeding 80mm in girth and finished even in and smooth in cement mortar 1:4 (1 cement : 4 sand), including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	46.44	Sqm	210.00	Rupees Two Hundred Ten Only	9752- 9753
9	Providing & Laying Cement Concrete 1 : 2 : 4 (1Cement :2Sand :4 Graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work and reinforcement for reinforced cement concrete work in :-String courses ,coping, bed plates , including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	0.22	Cum	4500.00	Rupees Four Thousand Five Hundred Only	990- 4609
10	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm). including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	46.44	Sqm	85.00	Rupees EightyFive Only	3947 3948
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) © (17) 2/20212 dated 07.08.2018				Total	97731 97752
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.P.W. Division Haroli
Distt. Una (H.P.)