Himachal Pradesh
Public Works Department
HP.PWD Division Shahpur Distt. Kangra (H.P)-176206
e-mail id: ee-shahpur-pwd@hp.gov.in
"NOTICE INVITING TENDERS"

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer Shahpur Division HP.PWD Shahpur on behalf of Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD (B&R) whose registration stood renewed as per revised rules and also registered under in H.P General Sales Tax Act 1968 so as to reach in his office on or before **27-11-2025 up to 11:00 AM.** and the same shall be opened on the same day at **11:30 AM.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable on **26-11-2025 up to 4:00** P.M and the application for issue of tender form shall be received on **25-11-2025** up to 12.00 noon.

The earnest money in the shape of NSC/FDR/Saving account of the Post office/ Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/incomplete tenders & tenders without earnest money will be summarily rejected. The offer of tender shall be kept open for 75 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit	Cost of tender form
1	Restoration of Rain damages on Charri to Bhitlu road Km 0/00 to 5/780.(S.H:-C/o RCC R/wall at Rd 4/650 to 4/655.	98,324.00	2,000.00	Two Months	350/-
2	Special Repir of Vetnary Hospital Gohju in Tehsil Shahpur at Distt Kangra Himachal Pradesh.(S.H:-Providing and Fixing perpainted sheet Back side.	99,923.00	2,000.00	Two Months	350/-
3	C/o Link raod Lam to Roun KM 0/00 to 2/100.(S.H:-Horing of JCB for formation cutting work.	97,900.00	2,000.00	One Month	350/-
4	Special Repir of Vetnary Hospital Gohju in Tehsil Shahpur at Distt Kangra Himachal Pradesh.(S.H:-Providing and Fixing Fencing in boundary wall Sanitary installation etc.	99,013.00	2,000.00	Two Months	350/-
5	Restoration of Rain damages in Chambi to Dharamshala road (MDR) Km 0/00 to 12/800.(S.H:-C/o Wire crate wall with C.C.Pusta at RD 11/852.70 to 11/854.	98,970.00	2,000.00	Two Months	350/-
6	A/R and M/O Charri to Bhitlu road km 0/00 to 5/780 . (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 0/00 to 1/00.	98,370.00	2,000.00	One Month	350/-
7	Restoration of Rain damages on Charri to Bhitlu road Km 0/00 to 5/780.(S.H:-C/o RCC R/wall at Rd 4/656 to 4/661.	97,617.00	2,000.00	Two Months	350/-
8	Special Repir of Vetnary Hospital Gohju in Tehsil Shahpur at Distt Kangra Himachal Pradesh.(S.H:-Providing and Fixing perpainted sheet front side.	99,692.00	2,000.00	Two Months	350/-
9	A/R and M/O Chambi to Dharamshala road (MDR-45) km 0/000 to 12/800. (S.H:-Clearing and Grubbing road land,C/O Earthen shoulder and Maintenance drain Between Km 0/00 to 1/800 .	99,861.00	2,000.00	One Month	350/-
10	A/R and M/O Charri to Bhitlu road km 0/00 to 5/780 . (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 1/00 to 2/00.	98,370.00	2,000.00	One Month	350/-
11	A/R and M/O Chambi to Dharamshala road (MDR-45) km 0/000 to 12/800. (S.H:-Clearing and Grubbing road land,C/O Earthen shoulder and Maintenance drain Between Km 10/700 to 12/800.	98,329.00	2,000.00	One Month	350/-
12	A/R and M/O Charri to Bhitlu road km 0/00 to 5/780 . (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 2/00 to 3/00.	98,370.00	2,000.00	One Month	350/-
13	Restoration to Rain Damage on Charri to Ghera Road km 0/000 to 8/555. (S.H:-C/o Unlined Drain & Berms between km 1/00 to 2/800.	97,865.00	2,000.00	One Month	350/-
14	A/R and M/O Charri to Bhitlu road km 0/00 to 5/780 . (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 3/00 to 4/00.	98,370.00	2,000.00	One Month	350/-
15	Restoration to Rain Damage on Charri to Ghera Road km 0/000 to 8/555. (S.H:-C/o Unlined Drain & Berms between km 3/00 to 4/800.	97,865.00	2,000.00	One Month	350/-
16	Restoration to Rain Damage on Charri to Bhitlu Road km 0/000 to 5/780.(S.H:-C/o Unlined Drain & Berms between km 1/200 to 3/00.	98,538.00	2,000.00	One Month	350/-
17	Restoration of Rain damages on on various roads under Darini section HP.PWD Darini Sub- Division.(S.H:-Hiring of Excavator cum loader for removal of slips on Darini to Jhaniyana and Darini Khurd Raod etc).	96,910.00	2,000.00	One Month	350/-

18	Restoration of Rain damages in Chambi to Dharamshala road (MDR) Km 0/00 to 12/800.(S.H:-C/o Wire crate wall with C.C.Pusta at RD 111/855 TO 11/856.50).	99,428.00	2,000.00	Two Month	350/-
19	A/R & M/O various roads under Shahpur sub Division (SH:- Hiring of excavator cum loader on Manai Bhandrella Mawa road 0/00 to 8/100)	99,000.00	2000.00	One Month	350/-
20	Restoration of Rain damages on various roads under Shahpur Sub division. (SH:- Hiring of excavator cum loader for Harnera Badanj Sidhpur tatwani road)	99,000.00	2000.00	One Month	350/-
21	Restoration of Rain damages on various roads under Shahpur Sub division. (SH:- Hiring excavator cum loader for Shahpur section)	99,000.00	2000.00	One Month	350/-
22	Restoration of Rain damages on various roads under Shahpur Sub division. (SH:- Hiring of rock breaker under Shahpur section)	99,200.00	2000.00	One Month	350/-
23	Restoration of Rain damages on various roads under Shahpur Sub division. (SH:- Hiring excavator cum loader for Dramman section)	99,000.00	2000.00	One Month	350/-
24	Restoration of Rain damages on various roads under Shahpur Sub division. (SH:- Hiring excavator cum loader for Harchakiyan section)	99,000.00	2000.00	One Month	350/-
25	Restoration of Rain damages on various roads under Shahpur Sub division. (SH:- Hiring excavator cum loader for Shahpur section)	99,000.00	2000.00	One Month	350/-

Certified that tender of above works are being called of urgent nature in public interest.

Terms & Conditions: -

1. The contractor/firm should be produce the attested copy of latest enlistment and renewal enlistment in HP.PWD, GST No. and EPF No. with the application falling which their application will not be entertained.
2. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
3. The Earnest Money for the above works should be required at the time of sale of tender forms.
4. The Contractor/Firms should be quoted percentage rate in the tender both in figures and in words failing which tender is likely to be rejected.
5. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.

Executive Engineer
Shahpur Division
HP.PWD Shahpur.
(on behalf of Governor of Himachal Pradesh)

No.PWD/SD/Tender/NIT/2025-26/- 7225-35 **Dated:** 19/11/25

Copy to following for information and necessary action:-

1. The Superintending Engineer 5th Circle HPPWD Palampur.
2. The Executive Engineer (IT) Nigam Vihar Shimla. He is requested to upload the same on the department website.
3. All the Assistant Engineer under this Division.
4. The Drawing/Accounts Branch in this office.
5. N.I.T Register.
6. Notice Board

Executive Engineer
Shahpur Division
HP.PWD Shahpur.

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98324.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Restoration of Rain damages on Charri to Bhitlu road KM 0/00 to 5/780.
SUB-HEAD :- Construction of RCC ~~Counter fort~~ R/wall at RD 4/650 to 4/655.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	4.95	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1733.00
2	Providing and fixing Dowl bar of 20 mm (Twenty milimetre) dia including drilling holes and plugging the bars with cement grout. as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royality, Malkana, toll tax, or any other taxes imposed by the Government.	5.90	380.95	Rupees Three Hundred Eighty And Paise Ninety Five Only	Per Running metre	2248.00
3	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royality, Malkana, toll tax, or any other taxes imposed by the Government.	9.10	7050.00	Rupees Seven Thousand Fifty Only	Per cubic metre	64155.00
4	Supplying fitting and placing HYSD bar reinforcement in Sub-structures complete as per drawings and MORTH technical specifications clause 1600 and 2200, including cutting bending, binding, Straightening and placing in position complete in all respect including the cost of binding, wire upto all heights and depths and as per direction and entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The rate is including Royality, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government.	255.40	95.00	Rupees Ninety Five Only	Per kilogram	24263.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
5	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):2(H)(One vertical Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in- charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	6.00	350.00	Rupees Three Hundred Fifty Only	Each	2100.00
6	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	4.50	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	3825.00
					TOTAL -	5924.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99923.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK : - Special repair of Vetnary Hospital Gohju in Tehsil Shahpur at Distt. Kangra Himachal Pradesh.

SUB-HEAD :- Providing and fixing perpainted sheet Back side.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
		3	4	5	6	7
1	2					
1	Providing and fixing 0.60mm (sixty millimetre) thick prepainted steel sheet (IS marked Z-120) of TATA Durashine/ sail over steel trussed in roofing with hot dipped metalic zinc coated sheet with top coat of regular modified polyster (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating of back coat of polyster of 5 (Five) microns over 5 (Five) microns primer coating including fixing with prepainted iron J or L hooks,bolts and nuts 6mm (six millimetre) diametres with prepainted limpet, rubber washers complete with all accessories as required as per specification, drawing and design including carriage of materials with in all leads, lifts and other incidentals as per the direction and entire satisfaction of Engineer-in-charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	18.35	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per square metre	24773.00
2	Steel work welded in built up sections of Tata/Sail composed in beams, joists, channels, angles, tees flats with connecting plates or angles, cleats as in trusses and trussed purlins, main and cross beams, hips, jack rafters, purlins connect to common rafter and like work including cutting hoisting fixing in position & applying a priming coat of red lead paint complete including entire carriage of material within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	715.71	105.00	Rupees One Hundred Five Only	Per Killogram	75150.00
					TOTAL :-	*99923.00*
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 97900.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : One Month

NAME OF C/o Link Road Lam to Roun Km 0/00 to 2/100.
SUB-HEAD : - Hiring of JCB for formation cutting work.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge.Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	89.00	1100.00	Rupees one thousand and or hundred only	Per Hour	97900.00
				TOTAL : -		97900.00
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99013.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Special repair of Vetnary Hospital Gohju in Tehsil Shahpur at Distt. Kangra Himachal Pradesh.
SUB-HEAD :- Providing and fixing fencing in Boundary wall Sanitary installation etc..

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. Made of G.I. wire of dia. 4 mm, outer dia not less than 5 mm in required colour and shade with 40x40x5 mm angle. complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	50.00	425.00	Rupees Four Hundred Twenty Five Only	Per square metre	21250.00
2	Providing and placing water tank of PVC (Poly venyl chloride) Sintex/Supreme/Finolex (Triple layer) ISI marked having capacity 500 (Five hundred) litres each with necessary fitting including over flow pipes, scour pipe, ball valve and with cover locking arrangement of good quality including providing pads of sizes as required good quality all complete as per specifications including entire carriage of material within all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	2.00	6150.00	Rupees Six Thousand One Hundred Fifty Only	Each	12300.00
3	Providing and fixing cancealed C.P. brass long body bib cock of continental series of Jaguar/ Classic series of Hindware/ Floral series of Cera/ Hindon series of Jal (heavy duty makes ISI marked) 15mm (Fifteen millimetre) as per specifications including entire carriage of material within all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	2.00	950.00	Rupees Nine Hundred Fifty Only	Each	1900.00
4	Providing and fixing polythelene aluminum polythelene (PE- AL-PE) composite pressure pipe U.V. stabilized with carbon block confirming to I.S. 15450-2004 of Kitec for water supply including clamps at appropriate spacing, cutting fixing and making good the walls etcetera; but excluding the cost of fittings (Internal work), including filling the joints with approved adhesive complete including entire carriage of materials within all leads lifts and other incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.1620 (20mm) twenty millimeter diameter pipe O.D. pipe	40.00	425.00	Rupees Four Hundred Twenty Five Only	Per Running Metre	17000.00

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
5	Providing and fixing stainless steel kitchen sink size 510 x1040 mm (Five hundred ten into One Thousand forty millimetre) with bowl depth 250 mm (two hundred fifty millimetre) of AMC unik / diamond approved standard ISI make with drain board and C.P. waste with C.I. or M.S. Brackets painted including cutting holes and making good the same but excluding fitting within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00	5750.00	Rupees Five Thousand Seven Hundred Fifty Only	Each	5750.00
6	15mm (Fifteen milimetres) thick cement plaster in single coat on rough and fair side of brick/concrete/stone walls for interior plastering upto all floor levels including arises internal rounded angles, chamfers and or rounded angles not exceeding 80mm (Eighty milimetres) in girth and finished even and smooth with cement mortar 1:6 (One cement isto six sand) within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	54.53	275.00	Rupees Two Hundred Seventy Five Only	Per square metre	14996.00
7	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, strubs, saplings and trees of girth upto 300mm removal of stumps of such trees cut earlier and disposal of unserviciable material and stacking of serviceable material to be used or auctioned upto a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness as per techanical specification clause 201 and as per direction of Engineer in charge with in all leads and lifts and other incidental. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	986.00	7.70	Rupees Seven And Paise Seventy Only	Per Cubic metre	7592.00
8	Providing and fixing 0.60mm (sixty millimetre) thick prepainted steel sheet (IS marked Z-120) of TATA Durashine/ sail over steel trussed in roofing with hot dipped metalic zinc coated sheet with top coat of regular modified polyster (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating of back coat of polyster of 5 (Five) microns over 5 (Five) microns primer coating including fixing with prepainted iron J or L hooks,bolts and nuts 6mm (six millimetre) diametres with prepainted limpet, rubber washers complete with all accessories as required as per specification, drawing and design including carriage of materials with in all leads, lifts and other incidentals as per the direction and entire satisfaction of Engineer-in-charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	13.50	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per square metre	18225.00
					TOTAL :-	99013.00
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPWD Shahpur

(24)

Sr no - 384 (5)

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98970.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Restoration of Rain Damages in Chambi to Dharamshala road (MDR) Km 0/00 to 12/800.
SUB-HEAD :- C/o Wire Crate wall with C.C.Pusta at RD 11/852.70 to 11/854. (under PDNA)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	5.15	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1803.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etctera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	6.55	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	35239.00
3	Providing and laying of boulder apron or gabin walls laid in wire crates with 5mm (Five millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone bounders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royality, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	17.95	3450.00	Rupees Three Thousand Four Hundred Fifty Only	Per cubic metre	61928.00
					TOTAL :-	98970.00
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98370.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK : - . **A/R and M/O Charri to Bhitlu road km 0/00 to 5/780 . (Under MMSRRY 2025-26).**

SUB-HEAD : - **Repair of Pot Hole / patch work between km 0/00 to 1/00.**

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer–in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government	*1.96*	*2250.00*	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	*4410.00*
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	295.10	*22.50*	Rupees Twenty Two And Paise Fifty Only	Per square metre	*6640.00*
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0~9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates usIng penetration grade bltumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfication of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	295.10	*295.90*	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	*87320.00*
					TOTAL :-	*98370.00*
	Quated Rate in Figure (%)	**(Amount to be quoted by the contractor in Figure)**				
	Quated Rate in Words (%)	**(Amount to be quoted by the contractor in words)**				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

NAME OF WORK :- Restoration of Rain damages on Charri to Bhitlu road KM 0/00 to 5/780.
SUB-HEAD :- Construction of RCC Counterfort R/wall at RD 4/656 to 4/661.

ESTIMATED COST: - ₹ 97617.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : Two Months

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	4.95	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1733.00
2	Providing and fixing Dowl bar of 20 mm (Twenty milimetre) dia including drilling holes and plugging the bars with cement grout. as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royality, Malkana, toll tax, or any other taxes imposed by the Government.	5.90	380.95	Rupees Three Hundred Eighty And Paise Ninety Five Only	Per Running metre	2248.00
3	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royality, Malkana, toll tax, or any other taxes imposed by the Government.	8.95	7050.00	Rupees Seven Thousand Fifty Only	Per cubic metre	63098.00
4	Supplying fitting and placing HYSD bar reinforcement in Sub-structures complete as per drawings and MORTH technical specifications clause 1600 and 2200, including cutting bending, binding, Straightening and placing in position complete in all respect including the cost of binding, wire upto all heights and depths and as per direction and entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The rate is including Royality, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government.	255.40	95.00	Rupees Ninety Five Only	Per kilogram	24263.00

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
5	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope I(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in- charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	7.00	350.00	Rupees Three Hundred Fifty Only	Each	2450.00
6	Back filling with granular material behind abutments, wing walls, return walls and retaning walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	4.50	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	3825.00
					TOTAL :-	*97617.00*
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

(8)

ESTIMATED COST: - ₹ 99692.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- **Special repair of Vetnary Hospital Gohju in Tehsil Shahpur at Distt. Kangra Himachal Pradesh.**

SUB-HEAD :- **Providing and fixing perpainted sheet front side.**

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
1	Providing and fixing 0.60mm (sixty millimetre) thick prepainted steel sheet (IS marked Z-120) of TATA Durashine/ sail over steel trussed in roofing with hot dipped metalic zinc coated sheet with top coat of regular modified polyster (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating of back coat of polyster of 5 (Five) microns over 5 (Five) microns primer coating including fixing with prepainted iron J or L hooks,bolts and nuts 6mm (six millimetre) diametres with prepainted limpet, rubber washers complete with all accessories as required as per specification, drawing and design including carriage of materials with in all leads, lifts and other incidentals as per the direction and entire satisfaction of Engineer-in-charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	20.25	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per square metre	27338.00
2	Steel work welded in built up sections of Tata/Sail composed in beams, joists, channels, angles, tees flats with connecting plates or angles, cleats as in trusses and trussed purlins, main and cross beams, hips, jack rafters, purlins connect to common rafter and like work including cutting hoisting fixing in position & applying a priming coat of red lead paint complete including entire carriage of material within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	689.09	105.00	Rupees One Hundred Five Only	Per Killogram	72354.00
					TOTAL :-	*99692.00*
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

(9)

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ **99861.00**
EARNEST MONEY : - ₹ **2000.00**
TIME LIMIT : **One Month**

NAME OF WORK **: -** **A/R and M/O Chambi to Dharamshala road (MDR-45) km 0/000 to 12/800.**

SUB-HEAD **: -** **Clearing and Grubbing road land,C/O Earthen shoulder and Maintenance drain Between Km 0/00 to 1/800 .**

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
1	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, strubs, saplings and trees of girth upto 300mm removal of stumps of such trees cut earlier and disposal of unserviciable material and stacking of serviceable material to be used or auctioned upto a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness as per techanical specification clause 201 and as per direction of Engineer in charge with in all leads and lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government	*0.50*	*22440.10*	Rupees Twenty Two Thousand Four Hundred Forty And Paise Ten Only	Per Hector	*11220.00*
2	C/O Shoulder (filling with fresh soil) Making up loss of material/ irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipment. The rate is including octroi, royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	4860.00	*7.35*	Rupees Seven And Paise Thirty Five Only	Per square metre	*35721.00*
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307.. The rate is including octroi, royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	1800.00	*29.40*	Rupees Twenty Nine And Paise Forty Only	Per Running metre	*52920.00*
					TOTAL : -	***99861.00***
	Quated Rate in Figure (%)	**(Amount to be quoted by the contractor in Figure)**				
	Quated Rate in Words (%)	**(Amount to be quoted by the contractor in words)**				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98370.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK : - A/R and M/O Charri to Bhitlu road km 0/00 to 5/780 . (Under MMSRRY 2025-26).
SUB-HEAD : - Repair of Pot Hole / patch work between km 1/00 to 2/00.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer–in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government	*1.96*	*2250.00*	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	*4410.00*
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	295.10	*22.50*	Rupees Twenty Two And Paise Fifty Only	Per square metre	*6640.00*
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0~9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates usIng penetration grade bltumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfication of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	295.10	*295.90*	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	*87320.00*
					TOTAL : -	*98370.00*
	Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)			
	Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)			

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ **98329.00**
EARNEST MONEY : - ₹ **2000.00**
TIME LIMIT : **One Month**

NAME OF WORK :- **A/R and M/O Chambi to Dharamshala road (MDR-45) km 0/000 to 12/800.**

SUB-HEAD :- **Clearing and Grubbing road land,C/O Earthen shoulder and Maintenance drain Between Km 10/700 to 12/800.**

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	2	3	4	5	6	7
1	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, strubs, saplings and trees of girth upto 300mm removal of stumps of such trees cut earlier and disposal of unserviciable material and stacking of serviceable material to be used or auctioned upto a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness as per techanical specification clause 201 and as per direction of Engineer in charge with in all leads and lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government	*0.53*	*22440.10*	Rupees Twenty Two Thousand Four Hundred Forty And Paise Ten Only	Per Hector	*11893.00*
2	C/O Shoulder (filling with fresh soil) Making up loss of material/ irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipment. The rate is including octroi, royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	3360.00	*7.35*	Rupees Seven And Paise Thirty Five Only	Per square metre	*24696.00*
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307.. The rate is including octroi, royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	2100.00	*29.40*	Rupees Twenty Nine And Paise Forty Only	Per Running metre	*61740.00*
					TOTAL :-	***98329.00***
	Quated Rate in Figure (%)	**(Amount to be quoted by the contractor in Figure)**				
	Quated Rate in Words (%)	**(Amount to be quoted by the contractor in words)**				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98370.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Charri to Bhitlu road km 0/00 to 5/780 . (Under MMSRRY 2025-26).
SUB-HEAD :- Repair of Pot Hole / patch work between km 2/00 to 3/00.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer–in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government	1.96	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	4410.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	295.10	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6640.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0~9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates uslng penetration grade bltumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfication of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	295.10	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	87320.00
					TOTAL :-	98370.00
	Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)			
	Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)			

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ **97865.00**
EARNEST MONEY : - ₹ **2000.00**
TIME LIMIT : **One Month**

NAME OF WORK : - **Restoration to Rain Damage on Charri to Ghera Road km 0/000 to 8/555.**
SUB-HEAD : - **C/o Unlined Drain & Berms between km 1/00 to 2/800.**

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
1	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, strubs, saplings and trees of girth upto 300mm removal of stumps of such trees cut earlier and disposal of unserviciable material and stacking of serviceable material to be used or auctioned upto a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness as per techanical specification clause 201 and as per direction of Engineer in charge with in all leads and lifts and other incidental.l The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government	*0.47*	*22440.10*	Rupees Twenty Two Thousand Four Hundred Forty And Paise Ten Only	Per Hector	*10547.00*
2	C/O Shoulder (filling with fresh soil) Making up loss of material/ irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipment. The rate is including octroi, royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	4680.00	*7.35*	Rupees Seven And Paise Thirty Five Only	Per square metre	*34398.00*
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307.. The rate is including octroi, royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	1800.00	*29.40*	Rupees Twenty Nine And Paise Forty Only	Per Running metre	*52920.00*
					TOTAL :-	***97865.00***
	Quated Rate in Figure (%)	**(Amount to be quoted by the contractor in Figure)**				
	Quated Rate in Words (%)	**(Amount to be quoted by the contractor in words)**				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98370.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Charri to Bhittu road km 0/00 to 5/780 . (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 3/00 to 4/00.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer–in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government	*1.96*	*2250.00*	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	*4410.00*
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kgs (Zero decimal two hundred Seventy five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	295.10	*22.50*	Rupees Twenty Two And Paise Fifty Only	Per square metre	*6640.00*
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0~9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfication of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	295.10	*295.90*	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	*87320.00*
					TOTAL :-	***98370.00***
	Quated Rate in Figure (%)	**(Amount to be quoted by the contractor in Figure)**				
	Quated Rate in Words (%)	**(Amount to be quoted by the contractor in words)**				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 97865.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- Restoration to Rain Damage on Charri to Ghera Road km 0/000 to 8/555.
SUB-HEAD :- C/o Unlined Drain & Berms between km 3/00 to 4/800.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
1	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, strubs, saplings and trees of girth upto 300mm removal of stumps of such trees cut earlier and disposal of unserviciable material and stacking of serviceable material to be used or auctioned upto a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness as per techanical specification clause 201 and as per direction of Engineer in charge with in all leads and lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government	*0.47*	*22440.10*	Rupees Twenty Two Thousand Four Hundred Forty And Paise Ten Only	Per Hector	*10547.00*
2	C/O Shoulder (filling with fresh soil) Making up loss of material/ irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipment. The rate is including octroi, royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	4680.00	*7.35*	Rupees Seven And Paise Thirty Five Only	Per square metre	*34398.00*
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307.. The rate is including octroi, royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	1800.00	*29.40*	Rupees Twenty Nine And Paise Forty Only	Per Running metre	*52920.00*
					TOTAL :-	***97865.00***
	Quated Rate in Figure (%)	**(Amount to be quoted by the contractor in Figure)**				
	Quated Rate in Words (%)	**(Amount to be quoted by the contractor in words)**				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98538.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- **Restoration to Rain Damage on Charri to Bhitlu Road km 0/000 to 5/780.**
SUB-HEAD :- **C/o Unlined Drain & Berms between km 1/200 to 3/00.**

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
1	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, strubs, saplings and trees of girth upto 300mm removal of stumps of such trees cut earlier and disposal of unserviciable material and stacking of serviceable material to be used or auctioned upto a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness as per techanical specification clause 201 and as per direction of Engineer in charge with in all leads and lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government	*0.50*	*22440.10*	Rupees Twenty Two Thousand Four Hundred Forty And Paise Ten Only	Per Hector	*11220.00*
2	C/O Shoulder (filling with fresh soil) Making up loss of material/ irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipment. The rate is including octroi, royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	4680.00	*7.35*	Rupees Seven And Paise Thirty Five Only	Per square metre	*34398.00*
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307.. The rate is including octroi, royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	1800.00	*29.40*	Rupees Twenty Nine And Paise Forty Only	Per Running metre	*52920.00*
					TOTAL :-	*98538.00*
	Quated Rate in Figure (%)	**(Amount to be quoted by the contractor in Figure)**				
	Quated Rate in Words (%)	**(Amount to be quoted by the contractor in words)**				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

(17)

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 96910.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : One Month

NAME OF Restoration of Rain damages on on various roads under Darini section HP.PWD Darini Sub- Division.
SUB-HEAD :- Hiring of Excavator cum loader for removal of slips on Darini to Jhaniyana and Darini Khurd Raod etc.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge.Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	88.10	1100.00	Rupees one thousand and or hundred only	Per Hour	96910.00
				TOTAL :-		96910.00
	Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)			
	Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)			

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

Sr no - 346 (18)

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99428.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Restoration of Rain Damages in Chambi to Dharamshala road (MDR) Km 0/00 to 12/800.

SUB-HEAD :- C/o Wire Crate wall with C.C.Pusta at RD 11/855 to 11/856.50. (under PDNA)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	5.75	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2013.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in 'or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etctera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	6.50	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	34970.00
3	Providing and laying of boulder apron or gabin walls laid in wire crates with 5mm (Five millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone bounders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royality, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	18.10	3450.00	Rupees Three Thousand Four Hundred Fifty Only	Per cubic metre	62445.00
					TOTAL :-	99428.00
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99000.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : One Month

NAME OF SUB-HEAD : - A/R & M/O various roads under Shahpur Sub- Division.
Hiring of Excavator cum loader on Manai Bhandrella Mawa road Km 0/00 to 8/100

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge.Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand and or hundred only	Per Hour	99000.00
				TOTAL : -		99000.00
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99000.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : One Month

NAME OF Restoration of Rain damages on various roads under Shahpur Sub- Division.
SUB-HEAD : - Hiring of Excavator cum loader for Harnera Badanj Sidhpur Tatwani road.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	2	3	4	5	6	7
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge.Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00 hr	1100.00	Rupees one thousand and or hundred only	Per Hour	99000.00
				TOTAL : -		99000.00
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

(21)

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99000.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : One Month

NAME OF Restoration of Rain damages on various roads under Shahpur Sub- Division.
SUB-HEAD : - Hiring of Excavator cum loader under Shahpur Section.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	2	3	4	5	6	7
1	Hiring of Excavator cum loader required for removal of slips, clearinguroad opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge.Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	*90.00*	*1100.00*	Rupees one thousand and or hundred only	Per Hour	*99000.00*
				TOTAL : -		*99000.00*
	Quated Rate in Figure (%)	i	(Amount to be quoted by the contractor in Figure)			
	Quated Rate in Words (%)	i	(Amount to be quoted by the contractor in words)			

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99200.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- **Repair and Restoration on various roads under HP.PWD Shahpur Sub- Division.**

SUB-HEAD :- **Hiring of rock Breaker under Shahpur Section.**

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Hiring of Rock Breaker having 2 to 4 tonne hammer capacity for removal of boulder slips,rock cutting for drains, removal of boulders from catchpits, opening of blocked drains due to boulders etc and other similar road works requiring breaking of rock and boulders on road in various reaches up to any height ,depth and disposal of material up to 20.00 meters lead in all kind and classification of soil including rocky portion as per direction and entire satisfactions of Engineer- in charge. The Rock Breaker should work minimum 8.00 hours daily. Any loss to the public property or any accident etc happened during the course of hiring period/execution of work, shall be the absolute responsibility of the Rock Breaker owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff will be provided by the owner. The repair, spare and watch and ward of Rock Breaker will also be born by the Contractor/Owner. The daily log book will be maintained at site which should be duly cerified by the Engineer in Charge. The rate is inclusive of GST and all other type taxes, royalities ete imposed by central or state government.	32.00	3100.00	Three Thousand One Hundred Only	Per Hour	99200.00
					TOTAL :-	***99200.00***
	Quated Rate in Figure (%)		**(Amount to be quoted by the contractor in Figure)**			
	Quated Rate in Words (%)		**(Amount to be quoted by the contractor in words)**			

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

(23)

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99000.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : One Month

NAME OF : Restoration of Rain damages on various roads under Shahpur Sub- Division.
SUB-HEAD : - Hiring of Excavator cum loader under Dramman section.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge.Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand and one hundred only	Per Hour	99000.00
					TOTAL : -	99000.00
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

(28)

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99000.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : One Month

NAME OF Restoration of Rain damages on various roads under Shahpur Sub- Division.
SUB-HEAD : - Hiring of Excavator cum loader under Harchakiyan section

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge.Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	*90.00*	*1100.00*	Rupees one thousand and or hundred only	Per Hour	*99000.00*
					TOTAL : -	*99000.00*
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99000.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : One Month

NAME OF: A/R & M/O various roads under Shahpur Sub- Division.
SUB-HEAD : - Hiring of Excavator cum loader under Shahpur section

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge.Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	*90.00*	*1100.00*	Rupees one thousand and or hundred only	Per Hour	*99000.00*
					TOTAL : -	*99000.00*
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur