

Himachal Pradesh
Public Works Department

No. PW-SD-I-CTR- Tender-NIT/2025-2026- 15121-22 Dated:- 13-11-2025

To


The Executive Engineer (IT Cell)
Nigam Vihar Shimla.

Subject :- Publication of Tender Notice.

Jai Hind


Enclosed please find herewith the tender Notice of work as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B)A(3)1/2024 dated Shimla-2 the 03-01-2024 and PWD-B-A0(3)/8/2025- 300858 dated 09-10-2025 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender & Schedule of Quantity and Certificate.


Executive Engineer,
Shimla Division No-1,
HPPWD, Shimla-3.

Copy forwarded to for further necessary action please.

1. The Superintending Engineer 4th Circle HPPWD Shimla .


Executive Engineer,
Shimla Division No-I.,
HPPWD., Shimla-3.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDERS**

Executive Engineer B&R Division No-I HPPWD Shimla for the following works on behalf of the Government of Himachal Pradesh from the eligible contractors enlisted in HPPWD, so as to reach in the office as per time schedule given below:-

- | | |
|--|-----------------------------------|
| 1. Date of receipt of application for tender forms:- | 21-11-2025 10:00 AM upto 12:00 PM |
| 2. Dated of Issue /sale of tender forms:- | 21-11-2025 12:00 PM upto 4:00 PM |
| 3. Date of receipt of tender:- | 22-11-2025 .up to 10:30 AM |
| 4. Date of opening of tender:- | 22-11-2025 up to 11:00 AM |

Sr. No.	Name of Work	Estimated cost	EMD(R s.)	Cost of Tender (Rs.)	Time Limit	Eligible class of Contractor
1	Restoation of Rain Damges on Shoghi mehli Junga Sadhupul road km. 12/375 to 48/925 (SH:- Constructono of Retaining wall at RD. 17/665 to 17/670).	498870/-	10000/-	350/-	30 days	Class-D
2	Restoation of Rain Damges on Shoghi mehli Junga Sadhupul road km. 12/375 to 48/925 (SH:- Constructono of Retaining wall at RD. 17/660.50 17/665).	497411/-	10000/-	350/-	30 days	Class-D

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest. The tender documents shall be issued only to those contractor/Firm who fulfill the following documents with the application.

- The valid enlistment/Registration of contractor in Appropriate Class.
- Permanent account No. (PAN NO).
- G.S.T No.
- Earnest Money in the shape of National saving certificate/time deposit account in the any of the post office in HP. F.D.R from any Nationalized Bank duly pleaded in favour of the Executive Engineer Shimla Division No-I HPPWD Shimla.
- The earnest & cost of tender form for the above works should be submitted with the application for the purchase of the tender form. The application received without earnest money & cost of tender form shall summarily be rejected.
- The officer of the tender shall remain valid up to 75 days after the opening of tender.
- Ambiguous/telephonic /conditional tenders or tender by fax/E mail shall not be considered and will be summarily be rejected.
- Executive Engineer reserve the right to reject or cancel any or all tenders without assigning any reasons.
- If the date given above happens to be holiday the same shall be processed on next working day.
- The Contractor/firms must quote their rates in words as well as in figures failing which EXN reserve the right to accept/reject any or all tenders.
- The tender forms shall not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.
- One contractor shall not have more than two major works in hand at a time.
- Work should be completed by the contractor within stipulated period.

Executive Engineer,
Shimla Division No-I.,
HPPWD. Shimla-3.

No.PW-SD-I/CB-Tender/2025-2026-
Copy forwarded to:-

15/23-35

Dated :- 13-11-2025

- Copy to the Deputy Commissioner Shimla Distt. Shimla.
- Copy to the Executive Engineer Shimla Division No-III HPPWD Shimla.
- Copy to the Sub Divisional Magistrate (U) Shimla.
- Copy to the Sub Divisional Magistrate (R) Shimla.
- Copy to Municipal committee Shimla Distt. Shimla.
- Copy to Block Development officer Mashobra Dsitt., Shimla.
- All the Assistant Engineers under this Division, HPPWD Shimla-3.
- Superintendent / HDM /DAO.
- Notice Board.

Executive Engineer,
Shimla Division No-I.,
HPPWD Shimla.

SCHEDULE OF QUANTITY


Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 4,98,870.00	
Name of Work :- Restoration of Rain Damages on Shoghi Mehli Junga Sadhupul road in Km. 12/375 to 48/925. (SH:- Construction of Retaining Wall at RD 17/665 to 17/670).						Earnest Money :- 10,000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting and disposal of earth work in by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site., according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	12.60	Cum	325.00	Rupees Three Hundred Twenty Five Only	Per Cubic Metre	4095.00
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required).All useful material such as stones, shingles aggregate and slates shall be properly stacked at site to the maximum possible extent in all leads and lifts through all modes of transportation the usefull stones as per the direction of the Engineer-in-Charge. Any loss to the public and private propriety during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	36.86	Cum	400.00	Rupees Four Hundred Only	Per Cubic Metre	14744.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement Mortar 1:5:10 (One cement: Five sand: Ten graded stone agg.40mm nominal size).	5.56	Cum	3800.00	Rupees Three Thousand Eight Hundred Only	Per Cubic Metre	21128.00

4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a) Cement Mortar 1:4:8(One cement:Four sand:Eight graded stone aggregate 20 mm(Twenty millimetre) nominal size).	94.59	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per Cubic Metre	435114.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Granular material.	17.17	Cum	1050.00	Rupees One Thousand Fifty Only	Per Cubic Metre	18029.00
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred milimetre) dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	32.00	Rmt	180.00	Rupees One Hundred Eighty Only	Per Running meter	5760.00
						Total	498870.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

T/S NO. 1482425 Dated 11/11/25 Amount. 5,13,836/-

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


Executive Engineer,
Shimla Division No.I,
HP PWD Shimla-3.

SCHEDULE OF QUANTITY


Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 4,97,411.00	
Name of Work :- Restoration of Rain Damages on Shoghi Mehli Junga Sadhupul road in Km. 12/375 to 48/925. (SH:- Construction of Retaining Wall at RD 17/660.50 to 17/665).						Earnest Money :- 10,000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting and disposal of earth work in by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site., according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	12.57	Cum	325.00	Rupees Three Hundred Twenty Five Only	Per Cubic Metre	4085.00
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required).All useful material such as stones, shingles aggregate and slates shall be properly stacked at site to the maximum possible extent in all leads and lifts through all modes of transportation the usefull stones as per the direction of the Engineer-in-Charge. Any loss to the public and private propriety during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	36.83	Cum	400.00	Rupees Four Hundred Only	Per Cubic Metre	14732.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement Mortar 1:5:10 (One cement: Five sand: Ten graded stone agg.40mm nominal size).	5.55	Cum	3800.00	Rupees Three Thousand Eight Hundred Only	Per Cubic Metre	21071.00

4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a) Cement Mortar 1:4:8(One cement:Four sand:Eight graded stone aggregate20 mm(Twenty milimetre) nominal size).	94.45	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per Cubic Metre	434470.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Granular material.	17.16	Cum	1050.00	Rupees One Thousand Fifty Only	Per Cubic Metre	18013.00
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred milimetre) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	28.00	Rmt	180.00	Rupees One Hundred Eighty Only	Per Running meter	5040.00
						Total	497411.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

T/S NO. 14822- Dated 11-11-25 Amount 5,12,333/-
23

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


Executive Engineer,
Shimla Division No.I,
HP PWD Shimla-3.