



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in

NO: PWD/BN/TA/NIT/2025-26/-
To

13340-45

Dated:-06.12.2025

**The Executive Engineer, (IT Cell),
Nirman Bhawan Nigam Vihar,
Shimla-2.**

Subject:- Publication of Tender Notice on the Departmental website.

Dear Sir,

Enclosed herewith is the Tender Notice for the work specified in the Notice Inviting tender (NIT). You are kindly requested to upload the same on the official website of the department in accordance with Notification No.PBW(B)A(3)1/2024 dated 03.01.2024, issued by the Secretary (PW) to the Government of Himachal Pradesh.

The works mentioned in the Notice Inviting Tender are urgent/emergent nature of works in public interest. Kindly ensure the prompt publication of the same on the website.

Encl: Notice Inviting Tender
& Schedule of Quantity.

Yours faithfully,


Executive Engineer
Baijnath Division
H.P.P.W.D. Baijnath

Copy forwarded for information to:-

1. The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
2. All the Assistant Engineers working under this Division.
3. The Drawing Branch of this office.
4. Notice Board.


Executive Engineer
Baijnath Division
H.P.P.W.D. Baijnath



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in

"NOTICE INVITING TENDER"


Sealed percentage rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.P.W.D., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **18.12.2025** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **17.12.2025** between **2.00 PM up to 4.30 P.M** and the application for issue of tender forms shall be received on **16.12.2025** up to **12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.P.W.D., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	R/D on Sakri to Deora Basti km 0/00 to 1/500 (SH: C/O B/wall at RD 0/840 to 0/847.40)	98,030/-	2,000/-	Rs.350/-	Two Months
2	Restoration of rain damages on Baijnath Bhattu Road km 0/00 to 6/00 (SH: C/O U-shape drain at RD 3/375 to 3/430)	99,820/-	2,000/-	Rs.350/-	Two Months
3	Restoration of Rain Damage on Holta Chadhiar Road km 56/00 to 75/00 (SH: Bush Cutting b/w RD 56/00 to 61/00 & 68/00 to 74/00)	76,160/-	1,600/-	Rs.350/-	One Month
4	Restoration of Rain Damages on Kangoo Da Paroh Salhera Road km 0/00 to 6/00 (SH: Bush cutting at RD 0/00 to 6/00)	40,320/-	800/-	Rs.350/-	One Month
5	Restoration of Rain Damage on Chobu Bhullana Road km 0/00 to 8/00 (SH: Bush cutting at RD 0/00 to 8/00)	71,680/-	1,500/-	Rs.350/-	One Month
6	Restoration of Rain Damage on Doli Khurad to Chordu Dhangore Road km 0/00 to 4/00 (SH: Bush cutting at RD 0/00 to 4/00)	35,840/-	800/-	Rs.350/-	One Month
7	Restoration of Rain Damage on Sagoor to Dhanag Including bridge over Binwa Khad at Khadiyal km 0/00 to 4/360 (SH: Construction of Protection work to Dhanag side Abutment in wire crates (Both side))	99,435/-	2,000/-	Rs.350/-	Two Months
8	Restoration of Rain Damages on Various Road Under Multhan Section (SH: Hiring of Hydraulic Excavator/JCB for removal of Snow/slips dressing of berms, filling depressions, clearance of drain and culvert)	99,000/-	2,000/-	Rs.350/-	One Month
9	Restoration of Rain Damages on Various Road Under Multhan Section (SH: Hiring of Hydraulic Excavator/JCB for removal of Snow/slips dressing of berms, filling depressions, clearance of drain and culvert)	99,000/-	2,000/-	Rs.350/-	One Month
10	R/D on various roads under Bir Sub Division HPPWD Baijnath (Multhan Section) (SH: Supplying and stacking of sand at shady/black ice locations after snow)	96,200/-	1,900/-	Rs.350/-	One Month
11	R/D on various roads Under Bir Sub-Division HPPWD Baijnath (SH: Supplying and stacking at site crushed stone agg. 63 to 45mm, 10 to 12mm, and sand) for patch work	99,795/-	2,000/-	Rs.350/-	Two Months

12	Restoration of Rain damage on Baijnath Chobin Balandar road Km 0/00 to 2/00 (SH: Painting and writing of village board, PMGSY boards, Direction and Place identification, rain Shelters and KM stone) (Under OFC)	95,297/-	2,000/-	Rs.350/-	Two Months
----	---	----------	---------	----------	------------

1. The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
2. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
3. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
4. Only two tenders form will be issued to the contractor/firm which may be noted.
5. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
6. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
7. The contractor shall have all required machinery such as Truck/Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
8. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
9. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
10. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.


 Executive Engineer
 Baijnath Division
 H.P. P.W.D. Baijnath
 For & On behalf of the Governor of H.P.

SCHEDULE OF QUANTITY

Name of work : R/D on sakri to Deora Basti km 0/00 to 1/500 . (SH: C/O B/wall at RD 0/840 TO 0/847.40)				Estimate Cost: 98,030.00/- Earnest Money: 2,000.00/- Time Limit : Two Months			
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs.	P
				Figures	Words		
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	5.55	Per Cum	290.00	Rupees Two Hundred & Ninety Only	1,610.00	
2	Providing and laying cement concrete 1:5:10 (one cement: five sand ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water / dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge . including carriage of material within all leads and lifts and other incidentals .. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	19.01	Per Cum	4950.00	Rupees Four Thousand Nine Hundred & Fifty Only	94,100.00	
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including entire carriage of materials within all leads and lifts and other incidentals.. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	8.00	Each	290.00	Rupees Two Hundred & Ninety Only	2,320.00	
Total						98,030.00	
Quoted rates Percentage in figures							
Quoted rates Percentage in words							

Executive Engineer
Bajnath Division
HPPWD Bajnath

2

SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on Bajinath Bhattu Road km 0/00 to 6/00 (S H :C/O U-shape Drain at RD 3/375 to 3/430 .				Estimate Cost: 99,820.00/- Earnest Money: 2,000.00/- Time Limit : Two Months			
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, chamber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, hauling out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	30.80	Per Cum	290.00	Rupees Two Hundred Ninety Only	8,932.00	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one part cement is to three sand is to six crushed stone agg. 20mm(forty millimetre) nominal size) in or under water and during complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	16.23	Per cubic metre	5600.00	Rupees Five Thousand Six Hundred Only	90,888.00	
Total			8			99,820.00	
Quoted rates Percentage in figures							
Quoted rates Percentage in words							

Executive Engineer
Bajinath Division
HPPWD Bajinath

3

SCHEDULE OF QUANTITY

Name of Work: - Restoration of Rain Damage on Holta Chadhiar Road km 56/00 to 75/00 .
(SH: Bush Cutting B/w RD 56/00 to 61/00 & 68/00 74/00)

Estimate Cost: 76,160.00
Earnest Money: 1,600.00
Time Limit : One Month

SCHEDULE OF WORKS

Sl. No.	Description of work	No.or Qty.	Unit	Rate to be entered by the		AMOUNT Rs.
				Figures	Words	
1	Clearing and grubbing road land in area of non-thorny jungle including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300 mm, removal of stumps of such trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150 mm in thickness as per Technical Specification Clause 201. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	34000.00	Per Sqm	2.24	Rupees Two And Paise Twenty Four Only	76,160.00
	Quated rates Percentage in figures					
	Quated rates Percentage in words					

Executive Engineer
Bajnath Division
HPPWD Bajnath

⑤

Estimate Cost: 40,320.00
Earnest Money: 800.00
Time Limit : One Month

Time Limit : One Month

SCHEDULE OF WORKS

Executive Engineer
Bajjnath Division
HPPWD Bajjnath

SCHEDULE OF QUANTITY

Name of Work: Restoration of Rain Damage on Chobu Bhullana Road km 0/00 to 8/00 .
(SH: Bush Cutting at RD 0/00 to 8/00)

Estimate Cost: 71,680.00
Earnest Money: 1,500.00
Time Limit : One Month

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Rate to be entered by the	AMOUNT
				Figures Words	Rs. P
1	Clearing and grubbing road land in area of non-thorny jungle including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300 mm, removal of stumps of such trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150 mm in thickness as per Technical Specification Clause 201. The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time.	32000.00	Per Sqm	2.24 Rupees Two And Paise Twenty Four Only	71,680.00
	Quoted rates Percentage in figures				
	Quoted rates Percentage in words				

Executive Engineer
Bajnath Division
HPPWD Bajnath

Name of Work: - Restoration of Rain Damage on Doli Khurad to Chordu Dhangore Road km 0/00 to 4/00
(SH: Bush Cutting at RD 0/00 to 4/00)

SCHEDULE OF QUANTITY

Estimate Cost: 35,840.00
Earnest Money: 800.00
Time Limit : One Month

SCHEDULE OF WORKS

Description of work

Sl. No.	Description of work	No. or Qty.	Unit	Rate to be entered by the Figures	Words	AMOUNT Rs. P
1	Clearing and grubbing road land in area of non-thorny jungle including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300 mm, removal of stumps of such trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150 mm in thickness as per Technical Specification Clause 201. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	16000.00	Per Sqm	2.24	Rupees Two And Paise Twenty Four Only	35,840.00
	Quoted rates Percentage in figures					
	Quoted rates Percentage in words					

Executive Engineer
Bajinath Division
HPPWD Bajinath

SCHEDULE OF QUANTITY

Name of work: Restoration of Rain Damage on Sagoor to Dhanag Including bridge over Binwa khadd at Khadiyal (SH : Construction of Protection work to Dhanag side Abutment in wire crates (Both Side))										km 0/00 to 4/360			Estimate Cost:99,435.00/- Earnest Money:2,000.00/- Time Limit : Two Months		
Sr. No.	i	Description of work	t	a	No. or Qty.	Unit	Rate			AMOUNT Rs. P					
							Figures	Words							
1		Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 390 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost.			17.88	Per Cubic metre	290.00	Rupees Two Hundred & Ninety Only		5,185.00					
2		Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire confirming to IS:280 and IS 4826 in 100mm x 100 mm mesh (woven diagonally) including 10 per extra for laps and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specifications clause 130# Including carriage of materials within all leads and lifts and other incidental. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."			32.50	Per Cubic metre	2900.00	Rupees Two Thousand Nine Hundred Only		94,250.00					
		Quoted rates Percentage in figures								99,435.00					
		Quoted rates Percentage in words													

Executive Engineer
 Baijnath Division
 HPPWD Baijnath

Estimated Cost: Rs 99,000.00
Earnest Money: Rs 2,000.00

Y
E
L

Executive Engineer
Bajjnath Division
HPPWD Bajjnath

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain Damages on Various Road Under Multhan section
(SH: Hiring of Hydraulic Excavator/JCB for removal of Snow/ slips dressing of road berms ,filling depressions , clearance of drain and culvert)

Estimated Cost:- Rs 99,000.00
Earnest Money:- Rs 2,000.00

SR. No.	Description of work	No. or Qty.	Unit	Time:- One Month		AMOUNT Rs. P
				In Figure	Rate Figures	
1	Hiring of Hydraulic Excavator/JCB cum loader having capacity of 0.9 Cum (zero point nine cubic meter) in working condition urgently required for removal of snow , slips Boulder and debris etc from road surface upto any height , depth and lead including slips, boulders in all kind and classification of soil including rocky portion and saturated soil due to non-availability of departmental machinery any loss to the public/ private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of the JCB/ Excavator owner which shall have to be fully compensated by the contractor in all cases. it should be ensure that the output of machine should not be less than 20 cum per hour The fuel and operational staff for JCB/ Excavator shall be borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer in charge. The rates are inclusive all taxes levy by the govt time to time including GST .	90.00	Per hour	1100.00	Rupees Eleven hundred only	99000.00
	Total:-					99000.00
	Quoted rates Percentage in figures					
	Quoted rates Percentage in words					


 Executive Engineer
 Bajinath Division
 HPPWD Bajinath

SCHEDULE OF QUANTITY

Name of Work: - R/D on various roads Under Bir Sub Division HPPWD Bajinath (Multhan Section)
(SH: Supplying and stacking of sand at shady/black ice locations after snow)

10

Estimate Cost: 96,200.00
Earnest Money: 1,900.00
Time Limit: Two Month

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Supply and stacking of fine aggregate sand of size greater than 0.06mm (zero decimal zero six millimeters) and shall consist of clean, hard, durable uncoated dry particles and shall be free from dust, soft or flaky material organic matter or other deleterious substances. The material shall be stacked at road side clear of carriage way and shoulders or on even ground as per instruction of Engineer-in-Charge. The aggregate shall pass 1.7mm sieve and retained on 180 micron sieve. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	52.00	Per Cubic metre	1,850.00	Rupees One Thousand Eight Hundred & Fifty Only	96,200.00	
	Total					96,200.00	
	Quated rates Percentage in figures						
	Quated rates Percentage in words						

Executive Engineer
Bajinath Division
HPPWD Bajinath

SCHEDULE OF QUANTITY

Name of Work: - R/D on various roads Under Bir Sub Division HPPWD Bajinath (SH: Supplying and stacking at site crushed stone agg. 63 to 45 mm, 10 to 12mm, and sand) for patch work							Estimate Cost: 99,795.00/- Earnest Money: 2000.00/- Time Limit : Two Month	
SCHEDULE OF WORKS								
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P		
				Figures	Words			
1	Supply and stacking of fine aggregate sand of size greater than 0.06mm (zero decimal zero six millimeters) and shall consist of clean, hard, durable uncoated dry particles and shall be free from dust, soft or flaky material organic matter or other deleterious substances. The material shall be stacked at road side clear of carriage way and shoulders or on even ground as per instruction of Engineer-in-Charge. The aggregate shall pass 1.7mm sieve and retained on 180 micron sieve. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	6.70	Per Cubic metre	1,850.00	Rupees One Thousand Eight Hundred & Fifty Only	12,395.00		
2	Supplying and stacking at site broken/crushed stone aggregate from hard stone of approved quarry 63mm to 45mm (sixty three to forty five millimeter) of disintegrated piece deleterious and organic matter from the approved quarry in specified stacks as per instruction of Engineer-in-Charge. The aggregates shall be free of elongated and flaky pieces, soft and disintegrated stones and vegetable and other deleterious matter. The aggregates shall be stacked in proper stacks of road side clear of carriage way and shoulders or on even ground as per the instruction of Engineer-in-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	44.50	Per Cubic metre	1,200.00	Rupees One Thousand Two Hundred Only	53,400.00		
3	Supply and stacking of crushed stone aggregate 12mm (twelve millimeter) and 10mm (ten millimeter) size consisting of angular, fragments of clean, hard, tough and durable rock. The aggregates shall be free of elongated and flaky pieces, soft and disintegrated stones and vegetable and other deleterious matter. The aggregates shall be stacked in proper stacks of road side clear of carriage way and shoulders or on even ground as per the instruction of Engineer-in-Charge. The proportion of the quantities of the material shall be as under:- a) Stone chippings 12mm (twelve millimeter) size passing 20mm (twenty millimeter) sieve and retained on 10mm (ten millimeter) sieve 0.18 cubic metre. Stone chippings 10mm (ten millimeter) size passing 12.5mm (twelve decimal five millimeters) sieve and retained on 6.30mm (six decimal three millimeters) sieve 0.09 cubic metre. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	20.00	Per Cubic metre	1,700.00	Rupees One Thousand Seven Hundred Only	34,000.00		
Total						99,795.00		
Quoted rates Percentage in figures								
Quoted rates Percentage in words								

Executive Engineer
Bajinath Division
HPPWD Bajinath

