



Office of the
Executive Engineer
Una Division, HP PWD Una
Tel: +911975226036,
E-mail: ee-una-hp@nic.in

No. PWU/CB//TA/Tender/2025-26/-
To

7018-26

Dated 04/12/2025

The Executive Engineer (IT) Cell,
Nirman Bhawan, Nigam Vihar,
Shimla-171002.

Subject: -


Regarding publication of Tenders Notice.

Sir,

"JAI HIND"

Enclosed please find herewith Tenders Notice along with Schedule of Quantities for uploading the same on Departmental website as per Notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B) A(3)1/2024 dated Shimla-2 the 03.01.2025 as the work mentioned in the Tender Notice are urgent in nature and in Public interest. This is for your kind information and necessary action at your end please.

DA:-As above.


Executive Engineer,
Bharwain, Division,
HPPWD, Bharwain


Copy along with its enclosures is forwarded to the following for favour of information please:-

1. The Superintending Engineer, 15th Circle, HPPWD, Una.
2. All the Assistant Engineer, working under this Division.
3. All the Head of Branches in this office.
4. Notice Board.


Executive Engineer,
Bharwain, Division,
HPPWD, Bharwain

Certificate

Certified that the tenders called vide this office letter
No.PWU/CB/TA/Tender Notice 2025-26 :- 7018-26 dated 04-12-2025
emergent nature and in Public interest.


Executive Engineer,
Bharwain, Division,
HPPWD, Bharwain

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDERS"

Sealed Percentage rate tender on PWD Form No. 6 & 8 are hereby invited by the Executive Engineer, Bharwain Division HPPWD Bharwain H.P. on behalf of Governor of H.P. for the following works from the approved and eligible contractors/ firms enlisted in PWD Department so as to reach in this office and opened as per time schedule given below. The offer of the tender will be kept open for 75 days from the date of opening of the tenders.

Date and time of receipt of applications for the tender form;- 10-12-2025(upto 04.00 P.M.)

Date of time issue/sale of tender forms against cash payment:- 11-12-2025(3.00 to 5.00 PM)

Date and time of receipt of tenders:- 12-12-2025 (upto 11.00 AM)

Date and time of opening of tenders:- 12-12-2025 at 11.30 AM

The earnest money in the shape of F.D.Rs if any of the Nationalized Bank in H.P. duly pledged in the favour of the Executive Engineer, Bharwain Division HPPWD Bharwain, will be received alongwith the applications for obtaining tender forms. The applications received without earnest money shall summarily be rejected. The Executive Engineer reserves the right to reject any tender without assigning any reason. The conditional / telegraphic tenders shall also be rejected. The scope of the work can be increased/ decreased without any Notice.

Sr. No	Name of work	Estimate Amount	Earnest Money	Time	Cost of tender	Eligible class of contractor
1	Restoration of rain damages on NH-70 to Panjoa Kalan road km 0/0 to 5/00 (SH:- Repair of Pot holes at various RDs. between km 0/0 to 2/500) Against Telecom Deposit.	99,949/-	2000	One Month	350/-	Class-C & D
2	Restoration of rain damages on NH-70 to Panjoa Kalan road km 0/0 to 5/00 (SH:- Repair of Pot holes at various RDs. between km 2/500 to 5/00) Against Telecom Deposit.	99,851/-	2000	One month	350/-	Class-C & D
3	Restoration of rain damages on Repoh Manjhar Suri Paloh road km 0/0 to 15/500 (SH:- Repair of Pot holes at various RDs between km 10/00 to 12/00) Against Telecom Deposit.	99,827/-	2000	One month	350/-	Class-C & D
4	Restoration of rain damages on Repoh Manjhar Suri Paloh road km 0/0 to 15/500 (SH:- Repair of Pot holes at various RDs between km 12/00 to 14/00) Against Telecom Deposit.	98,975/-	2000	One month	350/-	Class-C & D
5	Restoration of rain damages on link road from Govt. High School Suhin to Mandholi km 0/0 to 1/0 (SH:- Repair of Pot holes at various RDs between km 0/0 to 1/0) Against Telecom Deposit.	99,431/-	2000	One month	350/-	Class-C & D
6	Restoration of rain damages on Channi Devi to Chowar km 0/0 to 1/675 (SH:- Repair of Pot holes at various RDs between km 0/0 to 1/675) Against Telecom Deposit.	99,276/-	2000	One month	350/-	Class-C & D
7	Restoration of rain damages on Bagroo to Agriculture University Chak road km. 0/0 to 2/300 (SH:- Removal of slips, rain cuts and Unlined drain surface at RD 0/00 to 0/700) Section Nehri	98,900/-	2000	One month	350/-	Class-C & D
8	Restoration of rain damages on Bagroo to Agriculture University Chak road km. 0/0 to 0/700 (SH:- Removal of slips, rain cuts and Unlined drain surface at RD 0/800 to 1/200) Section Nehri	98,250/-	2000	One month	350/-	Class-C & D

TERM & CONDITIONS: -

1. The contractor/ firms should be registered as or/ dealer under HP Sales Tax Act, 1968 and also produce Sale Tax clearance certificate from the Excise and Taxation Department, GST No. and Permanent account No. (PAN No.).
 2. The intending contractors/ firms shall have to produce the copy of latest enlistment and renewal enlisted in HP: PWD.
 3. The contractor/firms are required to quote their rates clearly both in words as well as in figures, failing which the Executive Engineer reserve the right to accept/ reject any or all tenders.
 4. The conditional / ambiguous/ telegraphic tenders or tender by fax shall not entertain/ considered in any case
 5. No payment will be made to the contractor/ firms for damage caused by flood, rain, local disturbance, war, epidemic or either natural calamities during execution of work and no such claim on this account will be entertained.
 6. Security shall be released after 1 year from the date of completion of work provided no defect certificate is issued by the Engineer-in-charge.
 7. The Executive Engineer has right to accept or reject any or all the tender without assigning any reason.
 8. Any material left at site one month after completion of work shall become the property of the department and no payment shall be made to the contractor for the material.
 9. A sign Board ``Men at work / work in progress `` shall be placed `` by Contr. At least 200-150 meters ahead or places / roads where road are under repair / construction.
 10. The tender shall be issued to those contractors/ firms who have not more than two works in hand.
 11. Work should be completed by the contractor within stipulated period.
- DA Notice inviting tender / Schedule of Quantity and A Certificate.

Executive Engineer
Bharwain Division
HP: PWD, Bharwain..

Copy is forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP: PWD, Shimla-1.
2. The Chief Engineer, Hamirpur Zone, HP: PWD, Hamirpur.
3. The Superintending Engineer, 15th Circle, HPPWD, Una.
4. All the Assistant Engineers under this Division.
5. All the Head of the Branches in this office.
6. The Notice Board.


Executive Engineer
Bharwain Division
HP: PWD, Bharwain

Schedule of Quantity

Estimated Cost:- 99949/-
Earnest Money:- 2000/-
Time:- One Month

Name of Work:- Restoration of rain damages on NH-70 to Panjoa Kalan road km 0/0 to 5/00 (SH:- Repair of Pot holes at various RDs. between km 0/0 to 2/500) Against Telecom Deposit.

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
1	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads and lifts, laying in uniform layers in sub-base / base course on well prepared surface and compacting with vibratory roller of 8 (eight) to 10 (ten) tonne capacity to achieve the desired density, complete as per specifications and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	10.54	Cum	1650.00	Rs. One thousand six hundred fifty and paise zero only	Per cubic metre	17391
2	Providing and applying tack coat using bitumen emulsion @ 0.40 kg/sqm (at the rate of zero point forty kilogram per Square metre) conforming to IS:8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom and as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	140.50	Sqm	30.00	Rs. Thirty and paise zero only	Per Square metre	4215
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen VG-10 @ 3 kg per ten square metre, 20mm thick premix carpet with 0.27 cubic metre of stone aggregate mixed with bitumen VG-10 @ 14.6 kg (fourteen point six kilogram) per ten square metre and seal coat type B with 0.06 cubic metre fine aggregate mixed with bitumen VG-10 @ 6.8 kg (six point eight kilogram) per ten square metre of road surface as per specification Clause 1904.2 including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	265.57	Sqm	295.00	Rs. Two hundred ninety five and paise zero only	Per Square metre	78343
	Total						99949
	Percentage rate (Above or Below)						


 Executive Engineer,
 Bharwain Division,
 HPPWD, Bharwain.

Schedule of Quantity

Estimated Cost:- 99851/-
Earnest Money:- 2000/-
Time:- One Month

Name of Work:- Restoration of rain damages on NH-70 to Panjoa Kalan road km 0/0 to 5/00 (SH:- Repair of Pot holes at various RDs. between km 2/500 to 5/00) Against Telecom Deposit.

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
1	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads and lifts, laying in uniform layers in sub-base / base course on well prepared surface and compacting with vibratory roller of 8 (eight) to 10 (ten) tonne capacity to achieve the desired density, complete as per specifications and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	11.31	Cum	1650.00	Rs. One thousand six hundred fifty and paise zero only	Per cubic metre	18662
2	Providing and applying tack coat using bitumen emulsion @ 0.40 kg/sqm (at the rate of zero point forty kilogram per Square metre) conforming to IS:8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom and as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	150.80	Sqm	30.00	Rs. Thirty and paise zero only	Per Square metre	4524
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen VG-10 @ 3 kg per ten square metre , 20mm thick premix carpet with 0.27 cubic metre of stone aggregate mixed with bitumen VG-10 @ 14.6 kg (fourteen point six kilogram) per ten square metre and seal coat type B with 0.06 cubic metre fine aggregate mixed with bitumen VG-10 @ 6.8 kg (six point eight kilogram) per ten square metre of road surface as per specification Clause 1904.2 including carriage of materials within all leads and lifts and other incidentals . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	259.88	Sqm	295.00	Rs. Two hundred ninety five and paise zero only	Per Square metre	76665
Percentage rate (Above or Below)							
Total							99851

Executive Engineer,
Bharwain Division,
HPPWD, Bharwain.


Schedule of Quantity

Job No. 3

Estimated Cost:- 99827/-
Earnest Money:- 2000/-
Time:- One Month

Name of Work:- Restoration of rain damages on Repoh Manjhar Suri Paloh road km 0/0 to 15/500 (SH:- Repair of Pot holes at various RDs between km 10/00 to 12/00) Against Telecom Deposit.

Sub-Head and Items of work							
Sr. No.		Quantity	Rates in		Unit	Amount	
			Figures	Words			
1	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads and lifts, laying in uniform layers in sub-base / base course on well prepared surface and compacting with vibratory roller of 8 (eight) to 10 (ten) tonne capacity to achieve the desired density, complete as per specifications and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	9.77	1650.00	Rs. One thousand six hundred fifty and paise zero only	Per cubic metre	16121	
2	Providing and applying tack coat using bitumen emulsion @ 0.40 kg/sqm (at the rate of zero point forty kilogram per Square metre) conforming to IS:8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom and as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	130.25	30.00	Rs. Thirty and paise zero only	Per Square metre	3908	
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen VG-10 @ 3 kg per ten square metre , 20mm thick premix carpet with 0.27 cubic metre of stone aggregate mixed with bitumen VG-10 @ 14.6 kg (fourteen point six kilogram) per ten square metre and seal coat type B with 0.06 cubic metre fine aggregate mixed with bitumen VG-10 @ 6.8 kg (six point eight kilogram) per ten square metre of road surface as per specification Clause 1904.2 including carriage of materials within all leads and lifts and other incidentals . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	270.50	295.00	Rs. Two hundred ninety five and paise zero only	Per Square metre	79798	
Percentage rate (Above or Below)							
Total						99827	


 Executive Engineer,
 Bharwain Division,
 HPPWD, Bharwain.

Schedule of Quantity

Job No. 4

Estimated Cost:- 98975/-
Earnest Money:- 2000/-
Time:- One Month

Name of Work:- Restoration of rain damages on Repoh Manjhar Suri Paloh road km 0/0 to 15/500 (SH:- Repair of Pot holes at various RDs between km 12/00 to 14/00) Against Telecom Deposit.

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
1	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads and lifts, laying in uniform layers in sub-base / base course on well prepared surface and compacting with vibratory roller of 8 (eight) to 10 (ten) tonne capacity to achieve the desired density, complete as per specifications and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	10.90	Cum	1650.00	Rs. One thousand six hundred fifty and paise zero only	Per cubic metre	17985
2	Providing and applying tack coat using bitumen emulsion @ 0.40 kg/sqm (at the rate of zero point forty kilogram per Square metre) conforming to IS:8887, using emulsion pressure distributor including preparing the surface & charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	145.35	Sqm	30.00	Rs. Thirty and paise zero only	Per Square metre	4361
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen VG-10 @ 3 kg per ten square metre , 20mm thick premix carpet with 0.27 cubic metre of stone aggregate mixed with bitumen VG-10 @ 14.6 kg (fourteen point six kilogram) per ten square metre and seal coat type B with 0.06 cubic metre fine aggregate mixed with bitumen VG-10 @ 6.8 kg (six point eight kilogram) per ten square metre of road surface as per specification Clause 1904.2 including carriage of materials within all leads and lifts and other incidentals . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	259.76	Sqm	295.00	Rs. Two hundred ninety five and paise zero only	Per Square metre	76629
	Total						98975
	Percentage rate (Above or Below)						

Executive Engineer,
Bharwain Division,
HPPWD, Bharwain.


Schedule of Quantity

Job No. 5

Estimated Cost:- 99431/-
Earnest Money:- 2000/-
Time:- One Month

Name of Work:- Restoration of rain damages on link road from Govt. High School Suhin to Mandholi km 0/0 to 1/0 (SH:- Repair of Pot holes at various RDs between km 0/0 to 1/0) Against Telecom Deposit.

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
1	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads and lifts, laying in uniform layers in sub-base / base course on well prepared surface and compacting with vibratory roller of 8 (eight) to 10 (ten) tonne capacity to achieve the desired density, complete as per specifications and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	10.16	Cum	1650.00	Rs. One thousand six hundred fifty and paise zero only	Per cubic metre	16764
2	Providing and applying tack coat using bitumen emulsion @ 0.40 kg/sqm (at the rate of zero point forty kilogram per Square metre) conforming to IS:8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom and as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	135.45	Sqm	30.00	Rs. Thirty and paise zero only	Per Square metre	4064
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen VG-10 @ 3 kg per ten square metre, 20mm thick premix carpet with 0.27 cubic metre of stone aggregate mixed with bitumen VG-10 @ 14.6 kg (fourteen point six kilogram) per ten square metre and seal coat type B with 0.06 cubic metre fine aggregate mixed with bitumen VG-10 @ 6.8 kg (six point eight kilogram) per ten square metre of road surface as per specification Clause 1904.2 including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	266.45	Sqm	295.00	Rs. Two hundred ninety five and paise zero only	Per Square metre	78603
	Total						99431
	Percentage rate (Above or Below)						


 Executive Engineer,
 Bharwain Division,
 HPPWD, Bharwain.

Schedule of Quantity

Job No. 6

Name of Work:- Restoration of rain damages on Channi Devi to Chowar km 0/0 to 1/675 (SH:- Repair of Pot holes at various RDs between km 0/0 to 1/675) Against Telecom Deposit.

Estimated Cost:- 99276/-
Earned Money:- 2000/-
Time:- One Month

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
1	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads and lifts, laying in uniform layers in sub-base / base course on well prepared surface and compacting with vibratory roller of 8 (eight) to 10 (ten) tonne capacity to achieve the desired density, complete as per specifications and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	10.54	Cum	1650.00	Rs. One thousand six hundred fifty and paise zero only	Per cubic metre	17391
2	Providing and applying tack coat using bitumen emulsion @ 0.40 kg/sqm (at the rate of zero point forty kilogram per Square metre) conforming to IS:8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom and as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	140.55	Sqm	30.00	Rs. Thirty and paise zero only	Per Square metre	4217
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen VG-10 @ 3 kg per ten square metre, 20mm thick premix carpet with 0.27 cubic metre of stone aggregate mixed with bitumen VG-10 @ 14.6 kg (fourteen point six kilogram) per ten square metre and seal coat type B with 0.06 cubic metre fine aggregate mixed with bitumen VG-10 @ 6.8 kg (six point eight kilogram) per ten square metre of road surface as per specification Clause 1904.2 including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	263.28	Sqm	295.00	Rs. Two hundred ninety five and paise zero only	Per Square metre	77668
Percentage rate (Above or Below)							
Total							99276

Executive Engineer,
Bharwain Division,
HPPWD, Bharwain.

Schedule of Quantity

Estimated Cost:- 98900/-
Earnest Money:- 2000/-
Time:- One Month

Name of Work:- Restoration of rain damages on Bagroo to Agriculture University Chak road km. 0/0 to 2/300 (SH:- Removal of slips, rain cuts and Unlined drain surface at RD 0/00 to 0/700) Section Nehri

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material upto any lift and lead as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	750.00	Cubic metre	100.00	Rs. One hundred and paise zero only	Per cubic metre	75000
2	Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 250 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	100.00	Cubic metre	195.00	Rs. One hundred ninty five and paise zero only	Per cubic metre	19500
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions excavated material to be used in embankment at site with in any lead and lift as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the	110.00	Running metre	40.00	Rs. Fourty and paise zero only	Per running metre	4400
	Total Amount						98900
	Percentage rate (Above or Below)						



 Executive Engineer,
 Bharwain Division,
 HPPWD, Bharwain.

Schedule of Quantity

Estimated Cost:- 98250/-
Earnest Money:- 2000/-
Time:- One Month

Name of Work:- Restoration of rain damages on Bagroo to Agriculture University Chak road km. 0/0 to 0/700 (SH:- Removal of slips, rain cuts and Unlined drain surface at RD 0/800 to 1/200) Section Nehri

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
			Figures	Words			
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material upto any lift and lead as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	765.00	Cubic metre	100.00	Rs. One hundred and paise zero only	Per cubic metre	76500
2	Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 250 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	90.00	Cubic metre	195.00	Rs. One hundred ninety five and paise zero only	Per cubic metre	17550
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions excavated material to be used in embankment at site with in any lead and lift as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	105.00	Running metre	40.00	Rs. Fourty and paise zero only	Per running metre	4200
	Total Amount						98250
	Percentage rate (Above or Below)						


 Executive Engineer,
 Bharwain Division,
 HPPWD, Bharwain