



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

"NOTICE INVITING TENDERS"

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD, Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **12-12-2025** up to 11.00 AM. and the same shall be opened on the same day at **11.30 A.M.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on 11-12-2025 up to **4.00 P.M** and the application for issue of tender form shall be received on 11-12-2025 up to **1.00 PM**.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	Preparation of Forest diversion case under FCA, 1980 for the construction of Rud Panyali Lahar Chalaina Parmar nagar via Chowki road under Dheera Sub Division in Tehsil Dheera Distt. Kangra (HP) (SH:- Preparation of KML File and Geo Reference Digital map etc)	95,000/-	2000/-	Six Months	350/-
2	Preparation of Forest diversion case under FCA, 1980 for the construction of Parour Dheera Naura road under Dheera Sub Division in Tehsil Dheera Distt. Kangra (HP) (SH:- Preparation of KML File and Geo Reference Digital map etc)	95,000/-	2000/-	Six Months	350/-
3	Preparation of Forest diversion case under FCA, 1980 for the construction of Parour Dheera Naura road under Dheera Sub Division in Tehsil Dheera Distt. Kangra (HP) (SH:- Preparation of Revenue papers Forest Diversion Case under FCA, 1980 from km. 0/00 to 6/400)	90,624/-	1800/-	Three Months	350/-
4	Preparation of Forest diversion case under FCA, 1980 for the construction of Parour Dheera Naura road under Dheera Sub Division in Tehsil Dheera Distt. Kangra (HP) (SH:- Preparation of Revenue papers Forest Diversion Case under FCA, 1980 from km. 6/400 to 13/400)	99,120/-	2000/-	Three Months	350/-
5	Restoration of rain damages on Tamloh to Bharanta road (Under PDNA) (C/O Wire crate R/Wall at RD. 0/040 to 0/047050 & P/L Cement Concrete work in km. 0/750 to 0/872)	4,55,550/-	9100/-	Three month	350/-
6	C/O Ambulance road from GSSS to Bhagpuli GP Kiarwan Tehsil Dheera, Distt. Kangra (HP) (SH:- C/O Edge wall at RD. 0/210 to 0/232 RHS & P/LCC pavement work at R. 0/110 to 0/250) (DC Deposit SDP/2024/484)	1,97,160/-	3900/-	Three month	350/-

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm has to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.

Executive Engineer
Bhawarna Division
HPPWD Bhawarna

On behalf of Governor of Himachal Pradesh
Dated:- 5/12/25

No. PWD/BWD/TA/NIT/2025-26/

11201-10

Copy is forwarded to the following for information and necessary action:-

1. The Chief Engineer (KZ), HPPWD, Dharamshala.
2. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
3. All the Assistant Engineers under this Division.
4. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the departmental website.
5. The Drawing /Accounts Branch in this office.
6. Notice Board.


Executive Engineer,
Bhawarna Division,
HPPWD, Bhawarna.



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

CERTIFICATE

Certified that tender of works are being called of an emergent nature and for larger public interest so there is exigencies/ emergency in calling these tenders without press vide this office letter No. PWD/BWD/TA/NIT/2025-26-11201-10 dated: 5-12-2025.



Executive Engineer,
Bhawarna Division,
HPPWD. Bhawarna.

Schedule of Quantity

Name of work :- Preparation of forest diversion case under FCA, 1980 for the construction of construction of Rud Panyali Lahar Chailaina Parmar Nagar Via Chowki road Km 0/00 to 12/030 falling in under Dheera Sub Division in Tehsil Dheera, District Kangra. (H.P.) (H.P.) (SH:- Preparation of KML File and Geo Reference Digital map etcetra)

Estimated Cost :- Rs. 95,000/-
Earnest Money :- Rs. 2000/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Preparation of KML File and Geo Reference Digital map of proposed land and CA Area. Preparation of CA Scheme, Reclamation Plan, Cost Benefit Analysis, Muck Management, uploading Main Application Part I on Parivesh portal complete in all respect. Assistance to User Agency to attend the queries and clarification sought by MoEF. Submission of Stage I compliance report for obtaining Stage II Approval. Assistance to User Agency to make presentation for REC Meeting as required by MoEF. The Rates are inclusive of all equipments within all leads and lifts and other incidentals. The rate including octroi royalty, Malkana toll tax sale tax or other taxes imposed by the Government.	1.00	95000.00	Rupees Ninety Five Thousand Only	Job	95000.00
Total :-						95000.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

2

Name of work :- Preparation of forest diversion case under FCA, 1980 for the construction of Parour Dheera Naura road in Km 00/00 to 13/400 under Dheera Sub Division in Tehsil Dheera District Kangra. (H.P.) (SH:- Preparation of KML File and Geo Reference Digital map etcetra)

Estimated Cost :- Rs. 95,000/-
Earnest Money :- Rs. 2000/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Preparation of KML File and Geo Reference Digital map of proposed land and CA Area. Preparation of CA Scheme, Reclamation Plan, Cost Benefit Analysis, Muck Management, uploading Main Application Part I on Parivesh portal complete in all respect. Assistance to User Agency to attend the queries and clarification sought by MoEF. Submission of Stage I compliance report for obtaining Stage II Approval. Assistance to User Agency to make presentation for REC Meeting as required by MoEF. The Rates are inclusive of all equipments within all leads and lifts and other incidentals. The rate including octroi royalty, Malkana toll tax sale tax or other taxes imposed by the Government.	1.00	95000.00	Rupees Ninety Five Thousand Only	Job	95000.00
Quoted rates percentage in figures						
Quoted rates percentage in words						
Total :-						95000.00


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Preparation of forest diversion case under FCA, 1980 for the construction of Parour Dheera Naura road under Dheera Sub Division in Tehsil Dheera District Kangra. (H.P.). (SH:- Preparation of Revenue papers of Forest Diversion Case under FCA, 1980 from Km 0/00 to 6/400)

Estimated Cost :-Rs. 90,624/-
Earnest Money :- Rs. 1800/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Preparation of revenue paper for land acquire in the project, Layout Plan of the Project, Khassa wise detail of forest and non-forest both, enumeration list, village wise beneficiary information and Joint Inspection Report. Assistance to User Agency to procure DC Certificate for unavoidable and in-escapable and Certificate NFL for CA from Director Land Records, Shimla as per latest requirement of ministry of environment and forest conservation Govt. of India. The rate is including GST, octroi, royalty, Malkana, toll tax, sale tax or other taxes as imposed by the Government.	6,400	14160.00	Rupees Fourteen Thousand One Hundred Sixty Only	Per Kilometre	90624.00
Total:-						90624.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Preparation of forest diversion case under FCA, 1980 for the construction of Parour Dheera Naura road under Dheera Sub Division in Tehsil Dheera District Kangra. (H.P.), (SH:- Preparation of Revenue papers of Forest Diversion Case under FCA, 1980 from Km 6/400 to 13/400)

Estimated Cost :-Rs. 99,120/-
Earnest Money :- Rs. 2000/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Preparation of revenue paper for land acquire in the project, Layout Plan of the Project, Khasra wise detail of forest and non-forest both, enumeration list, village wise beneficiary information and Joint Inspection Report. Assistance to User Agency to procure DC Certificate for unavoidable and in-escapable and Certificate NFL for CA from Director Land Records, Shimla as per latest requirement of ministry of environment and forest conservation Govt. of India. The rate is including GST, octroi, royalty, Malkana, toll tax, sale tax or other taxes as imposed by the Government.	7.000	14160.00	Rupees Fourteen Thousand One Hundred Sixty Only	Per Kilometre	99120.00
					Total:-	99120.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Bhawana Division
 HP PWD Bhawana

Schedule of Quantity

5

Name of Work :- Restoration of rain damages on Tamlooh to Bharanta road. (Under PDNA)
(SH:- Construction of Wire crate R/wall at RD 0/040 to 0/047.50 & P/L Cement Concrete work in Km. 0/750 to 0/872).

Estimated Cost :-Rs. 4,55,550/-
Earnest Money :-Rs. 9100/-

Time Limit :- Three Months

S.No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	16.20	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	4050.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS-280 and IS-4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	32.40	2800.00	Rupees Two Thousand Eight Hundred Only	Per Cubic metre	90720.00
3	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.08	700.00	Rupees Seven Hundred Only	Per Cubic metre	4256.00
4	Construction of embankment with approved materials deposited at site from road way cutting and excavation from drains and foundations of other structures or other sources graded and compacted in 200mm(two hundred millimetres) thickness in every layers and compacted with three Wheel Road Roller 80-100 (eighty-hundred) KN static weight roller to meet the requirement of tables 300.1 and 300.2 as per M.O.R.D. technical specification Clause 301 and 1603.5 and as per the entire satisfaction and direction of the Engineer- In -Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.98	80.00	Rupees Eighty Only	Per Cubic metre	798.00

5	Providing, laying, Soling 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	2000.00	Rupees Two Thousand Only	Per Cubic metre	4000.00
6	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) in sub structure nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size using cement contents not less than 330 Kg (Three hundred thirty kilogram) per cubic metre on ground or under water and curing complete including pumping or boiling out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all height/ depths including cost of form work in open foundation as per drawing and MORD technical specification section 800, 900, 1200 including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	56.73	6200.00	Rupees Six Thousand Two Hundred Only	Per Cubic metre	351726.00
Total :-						
Quoted rates percentage in figures						455550.00
Quoted rates percentage in words						

Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work :- C/o Ambulance road from GSSS to Bhagpuri GP Kianwan Tehsil Dheera, Distt. Kangra (HP).
(SH:-C/O Edge Wall at Rd 0/210 to 0/232 RHS & P/L CC Pavement work at Rd 0/110 to 0/250). (DC Deposit) **500/2024/424.**

Estimated Cost :-Rs. 1,97,160/-
Earnest Money :-Rs. 3900/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimeter) nominal size in open foundation as per drawing and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203, including the cost of form work, curing complete and hauling of materials in all kinds of leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	31.80	6200.00	Rupees Six Thousand Two Hundred Only	Per Cubic metre	197160.00
Total :-						197160.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Executive Engineer
Bhawarna Division
HP PWD Bhawarna

