HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

E-Mail id-ee-bil2-hp@nic.in
Phone No.01978-222550

SHORT TERM TENDER NOTICE

Sealed items rates tender for the following works are hereby invited by the Executive Engineer, Bilaspur Division No.II, HP. PWD., Bilaspur (H.P) from the eligible contractors of the appropriates class registered in HP.PWD., as per revised enlistment rules so as to reach in the office undersigned on 16.12.2025 upto 10.30AM and will be opened on the same day at 11.00AM in the presence of intending contractors. The tender application will be received in this office alongwith cash payment on account of cost of tender form and the tender form can be had from this office on dated 15.12.2025 upto 12.30 PM. and will be sale on the same day at 4.00P.M.The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued to contractor on production of proof of enlistment, GST and Pan No.etc. Conditional tender and tender received without earnest money will be rejected straightway. The offer of the tender shall be kept open for 45 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT, other specifications and conditions of the tender can be seen by the contractors in the office of the undersigned on any working day during the office hours.

S. No.	Name of work	Estimated of cost	Earnest Money	Cost of form	Time limit
1	Restoration of Rain Damages on Swahan to Katirad Pangwana road Km.0/00 to 5/510(SH:- Hiring of Excavator cum rock breaker, Excavator cum loader/JCB & Tractor with trolley for removal of slis and dressing of Katcha road/Berms, clearance of drain at RD.0/00 to 2/00) for the year 2025-26 Job No.58	Rs.99,970/-	Rs.2,000/-	Rs.350/-	One Month
2	Restoration of Rain Damages on Swahan to Katirad Pangwana road Km.0/00 to 5/510(SH:- Hiring of Excavator cum rock breaker, Excavator cum loader/JCB & Tractor with trolley for removal of slis and dressing of Katcha road/Berms, clearance of drain at RD.2/00 to 3/00) for the year 2025-26 Job No.59	Rs.99,970/-	Rs.2,000/-	Rs.350/-	One Month
3	Restoration of Rain Damages on Swahan to Katirad Pangwana road Km.0/00 to 5/510(SH:- Hiring of Excavator cum rock breaker, Excavator cum loader/JCB & Tractor with trolley for removal of slis and dressing of Katcha road/Berms, clearance of drain at RD.3/00 to 4/00) for the year 2025-26 Job No.60	Rs.99,709/-	Rs.2,000/-	Rs.350/-	One Month
4.	Restoration of Rain Damages on link road Ghwandal to Sh.Naina Devi Ji Bus Stand Km.0/00 to 1/600(SH:-Hiring of Excavator cum loader/JCB & Tractor with trolley for removal of slips at RD.0/00 to 1/000) for the year 2025-26 Job No.23	Rs.98,994/-	Rs.2,000/-	Rs.350/-	One Month
5	Restoration of Rain Damages on link road Galwa to Challella road Km.0/00 to 4/765(SH:- Hiring of Excavator cum loader/JCB & Tractor with trolley for removal of slips at RD.0/00 to 2/000) for the year 2025-26 Job No.22	Rs.98,994/-	Rs.2,000/-	Rs.350/-	One Month
6	Restoration of Rain Damages on Sh.Naina Devi Ji Bhakra road Km 0/00 to 37/300(SH:-Hiring of Excavator cum loader/JCB & Tractor with trolley for removal of slips at RD.16/00 to 17/00) for the year 2025-26 Job No.24	Rs.99,849/-	Rs.2,000/-	Rs.350/-	One Month
7	Restoration of Rain Damages on Sh.Naina Devi Ji to Toba road Km.0/00 to 9/225 (SH:-Hiring of Hydraulic Excavator cum loader/JCB & Tractor with trolley for removal of slips at RD.7/00 to 9/225) for the year 2025-26 Job No.25.	Rs.99,849/-	Rs.2,000/-	Rs.350/-	One Month
8	Restoration of Rain Damages on Sh.Naina Devi Ji to Toba road Km.0/00 to 9/225 (SH:-Hiring of Hydraulic Excavator cum loader/JCB & Tractor with trolley for removal of slips at RD.4/900 to 6/000) for the year 2025-26 Job No.26.	Rs.99,849/-	Rs.2,000/-	Rs.350/-	One Month
9	Restoration of Rain Damages on Sh.Naina Devi Ji Bhakra road Km.0/00 to 37/300(SH:- Widening of road by Formation cutting at RD. 12/274.70 to 12/277.95)	Rs.98,922/-	Rs.2,000/-	Rs.350/-	One Month
10	Restoration of Rain Damages on Sh.Naina Devi Ji Bhakra road Km.0/00 to 37/300(SH:- Widening of road by Formation cutting at RD. 12/277.95 to 12/282.70)	Rs.99,275/-	Rs.2,000/-	Rs.350/-	One Month
11	A/R & M/O Residential Quarter at Police Station Kot Kehloor, Tehsil Sh.Naina Devi Ji,Distt.Bilaspur,HP(SH:-Providing and Fixing Door, Window and Distempering Painting etc)(Deposit work).	Rs.91,847/-	Rs.1,900/-	Rs.350/-	Three Months

Certified that tenders are being called for due to exigencies of works in the public interest.

Terms and Conditions:-

1. The Contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason.
3. The Contractor/firm must have his registration and GST No. The copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No.II, HP.PWD, Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be rejected straight way.
5. The contractor/ Firms are requested to insert the rate of each item both in words and in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.

No.PW/NBT/CB/Tender-State/EA-1/2025- 11614-19 Dated:- 9/12/25

Copy forwarded to the following for information and necessary action to:-

1. The Engineer-in-Chief, HP.PWD, Nirman Bhawan Nigam Vihar Shimla-2.
2. The Chief Engineer (HZ) HP.PWD., Hamirpur.
3. The Superintending Engineers,10th Circle, HP. PWD., Bilaspur.
4. The Executive Engineers (IT) O/o Engineer-in-Chief, HP.PWD., Shimla through email-eeict-pwd-shi@hp.gov.in & cc-pwd-hp@nic.in for uploading the same on HP.PWD web portal.
5. The Assistant Engineer,HP.PWD., Sub-Division Swarghat/ Sh.Naina Devi Ji.
6. Drawing Branch in this office/ Notice Board.

Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.

	SCHEDULE OF QUANTITY.			Estimated Cost:- Rs.=99,970 /-Only.			
				Earnest Money:- Rs.= 2,000/-Only.			
				Time:- One Month.			

Name of work :-Restoration of Rain Damages on Swahan to Katirad Pangwana road km 0/00 to 5/510 (SH:- Hiring of Excavator cum rock breaker ,Excavator cum loader/JCB & Tractor with trolley for removal of slips and dressing of katcha road/berms, clearance of drain at Rd 0/00 to 2/00) For the Year 2025-26 Job No.-58

S No.	Description of items.	Quantity		Rate In		Unit	Amou
				In Figure	In words.		
1	2	3	4	5	6	7	8
1	Hiring of Excavator cum rock breaker for removal of rocks in all kind of rocks such as soft or hard rock complete as per direction Engineer -in -Charge i/c P.O.L charges and other establishment requaied at site i.e operator. cleaner and staff and incidental charges i/c stacking of seveiceable material and disposal of un serviceable material in all lead and lifts as per direction and instruction of Engineer-in- charge.The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.00	Hours			Per Hours	
2	Providing one number Exacavator cum loader/JCB in good condition on hire bases at site of work for removal of slip.The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	65.00	Hours			Per Hours	
3	Providing one number Tractor with trolley in good condition. on hire basis having capacity of 3 to 5 tonne per trip for carriage of material i.e aggregate , soil , mud , boulders etc with in all leads and lifts as per direction of Engineer-In-Charge .The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.00	Hours			Per Hours	
	Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Exacavator cum rock breaker will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
2.1	The one number Exacavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
2.2	The One Number Tractor with trolley will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fullly responsible for any loss/damages to any private /Govt. Property during the execution of work						
	Total						

Executive Engineer,
Bilaspur Division No.
HP PWD, Bilaspur

	SCHEDULE OF QUANTITY.		Estimated Cost:- Rs.=99,970 /-Only.
			Earnest Money:- Rs.= 2,000/-Only.
			Time:- One Month.

Name of work :-Restoration of Rain Damages on Swahan to Katirad Pangwana road km 0/00 to 5/510 (SH:- Hiring of Excavator cum rock breaker ,Excavator cum loader/JCB & Tractor with trolley for removal of slips and dressing of katcha road/berms, clearance of drain at Rd 2/00 to 3/00) For the Year 2025-26 Job No.-59

S No.	Description of items.	Quantity		Rate In		Unit	Amount
				In Figure	In words.		
1	2	3	4	5	6	7	8
1	Hiring of Excavator cum rock breaker for removal of rocks in all kind of rocks such as soft or hard rock complete as per direction Engineer -in -Charge i/c P.O.L charges and other establishment requaied at site i.e operator. cleaner and staff and incidental charges i/c stacking of seveiceable material and disposal of un serviceable material in all lead and lifts as per direction and instruction of Engineer-in- charge.The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.00	Hours			Per Hours	
2	Providing one number Exacavator cum loader/JCB in good condition on hire bases at site of work for removal of slip.The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	65.00	Hours			Per Hours	
3	Providing one number Tractor with trolley in good condition. on hire basis having capacity of 3 to 5 tonne per trip for carriage of material i.e aggregate , soil , mud , boulders etc with in all leads and lifts as per direction of Engineer-In-Charge .The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.00	Hours			Per Hours	
	Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Exacavator cum rock breaker will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
2.1	The one number Exacavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
2.2	The One Number Tractor with trolley will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fullly responsible for any loss/damages to any private /Govt. Property during the execution of work						
	Total						

Executive Engineer,
Bilaspur Division No.
HP PWD., Bilaspur

	SCHEDULE OF QUANTITY.		Estimated Cost:- Rs.=99,709 /-Only.
			Earnest Money:- Rs.= 2,000/-Only.
			Time:- One Month.

Name of work :-Restoration of Rain Damages on Swahan to Katirad Pangwana road km 0/00 to 5/510 (SH:- Hiring of Excavator cum rock breaker ,Excavator cum loader/JCB & Tractor with trolley for removal of slips and dressing of katcha road/berms, clearance of drain at Rd 3/00 to 4/00) For the Year 2025-26 Job No.-60

S No.	Description of items.	Quantity		Rate In		Unit	Amount
				In Figure	In words.		
1	2	3	4	5	6	7	8
1	Hiring of Excavator cum rock breaker for removal of rocks in all kind of rocks such as soft or hard rock complete as per direction Engineer -in -Charge i/c P.O.L charges and other establishment requaied at site i.e operator. cleaner and staff and incidental charges i/c stacking of seveiceable material and disposal of un serviceable material in all lead and lifts as per direction and instruction of Engineer-in- charge.The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.00	Hours			Per Hours	
2	Providing one number Exacavator cum loader/JCB in good condition on hire bases at site of work for removal of slip.The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	61.00	Hours			Per Hours	
3	Providing one number Tractor with trolley in good condition. on hire basis having capacity of 3 to 5 tonne per trip for carriage of material i.e aggregate , soil , mud , boulders etc with in all leads and lifts as per direction of Engineer-In-Charge .The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.00	Hours			Per Hours	
	Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Exacavator cum rock breaker will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
2.1	The one number Exacavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
2.2	The One Number Tractor with trolley will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fullly responsible for any loss/damages to any private /Govt. Property during the execution of work						
	Total						

Executive Engineer,
Bilaspur Division No. 2
HA PWD, Bilaspur (H.P.)

	SCHEDULE OF QUANTITY.		Estimated Cost:- Rs.=98,994 /-Only.
			Earnest Money:- Rs.= 2,000/-Only.
			Time:- One Month.

Name of work :- Restoration of Rain damages on link road Ghwandal Sh. Naina Devi Ji Bus Stand km 0/00 to 1/600 (SH:- Hiring of Excavator cum loader/JCB & Tractor with trolle for removal of slips at Rd 0/00 to 1/000) For the Year 2025-26 Job No.-23

Sr No.	Description of items.	Quantity		Rate In		Unit	Amoun
				In Figure	In words.		
1	2	3	4	5	6	7	8
1	Providing one number Exacavator cum loader/JCB in good condition on hire bases at site of work for removal of slip.The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	62.00	Hours			Per Hours	
2	Providing one number Tractor with trolley in good condition. on hire basis having capacity of 3 to 5 tonne per trip for carriage of material i.e aggregate , soil , mud , boulders etc with in all leads and lifts as per direction of Engineer-In-Charge .The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	40.00	Hours			Per Hours	
	Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Exacavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
i)	The One Number Tractor with trolley will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fullly responsible for any loss/damages to any private /Govt. Property during the execution of work						
	Total						

Executive Engineer,
Bilaspur Division No.
HP PWD., Bilaspur (H.P.)

	SCHEDULE OF QUANTITY.		Estimated Cost:- Rs.=98,994 /-Only.
			Earnest Money:- Rs.= 2,000/-Only.
			Time:- One Month.

Name of work :- Restoration of Rain damages on link road Galwa to Challella road km 0/00 to 4/765 (SH:- Hiring of Excavator cum loader/JCB & Tractor with trolley for removal of slips at Rd 0/00 to 2/000) For the Year 2025-26 Job No.-22

Sr No.	Description of items.	Quantity		Rate In		Unit	Amoun
				In Figure	In words.		
1	2	3	4	5	6	7	8
1	Providing one number Exacavator cum loader/JCB in good condition on hire bases at site of work for removal of slip.The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	62.00	Hours			Per Hours	
2	Providing one number Tractor with trolley in good condition. on hire basis having capacity of 3 to 5 tonne per trip for carriage of material i.e aggregate , soil , mud , boulders etc with in all leads and lifts as per direction of Engineer-In-Charge .The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	40.00	Hours			Per Hours	
	Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Exacavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
i)	The One Number Tractor with trolley will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fullly responsible for any loss/damages to any private /Govt. Property during the execution of work						
	Total						

Executive Engineer,
Bilaspur Division No.
HPWD., Bilaspur (H

	SCHEDULE OF QUANTITY.		Estimated Cost:- Rs.=99,849 /-Only.
			Earnest Money:- Rs.= 2,000/-Only.
			Time:- One Month.

Name of work :- Restoration of Rain damages on Sh. Naina Devi Ji Bhakra road km 0/00 to 37/300 (SH:- Hiring of Excavator cum loader/JCB & Tractor with trolley for removal of slips at Rd 16/00 to 17/00) For the Year 2025-26 Job No.-24

Sr No.	Description of items.	Quantity		Rate In		Unit	Amount
				In Figure	In words.		
1	2	3	4	5	6	7	8
1	Providing one number Exacavator cum loader/JCB in good condition on hire bases at site of work for removal of slip.The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	67.00	Hours			Per Hours	
2	Providing one number Tractor with trolley in good condition. on hire basis having capacity of 3 to 5 tonne per trip for carriage of material i.e aggregate , soil , mud , boulders etc with in all leads and lifts as per direction of Engineer-In-Charge .The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	32.00	Hours			Per Hours	
	Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Exacavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
i)	The One Number Tractor with trolley will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fullly responsible for any loss/damages to any private /Govt. Property during the execution of work						
	Total						

Executive Engineer,
Bilaspur Division No. 2
HR PWD, Bilaspur (H.P.)

	SCHEDULE OF QUANTITY.		Estimated Cost:- Rs.=99,849 /-Only.
			Earnest Money:- Rs.= 2,000/-Only.
			Time:- One Month.

Name of work :- Restoration of Rain damages on Sh. Naina Devi Ji to Toba road km 0/00 to 9/225 (SH:- Hiring of Excavator cum loader/JCB & Tractor with trolley for removal of slips at Rd 7/00 to 9/225) For the Year 2025-26 Job No.-25

Sr No.	Description of items.	Quantity		Rate In		Unit	Amount
				In Figure	In words.		
1	2	3	4	5	6	7	8
1	Providing one number Exacavator cum loader/JCB in good condition on hire bases at site of work for removal of slip.The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	67.00	Hours			Per Hours	
2	Providing one number Tractor with trolley in good condition. on hire basis having capacity of 3 to 5 tonne per trip for carriage of material i.e aggregate , soil , mud , boulders etc with in all leads and lifts as per direction of Engineer-In-Charge .The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	32.00	Hours			Per Hours	
	Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Exacavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
i)	The One Number Tractor with trolley will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fullly responsible for any loss/damages to any private /Govt. Property during the execution of work						
	Total						

Executive Engineer,
Bilaspur Division No. 2
HR PWD., Bilaspur (H.P.)

	SCHEDULE OF QUANTITY.		Estimated Cost:- Rs.=99,849 /-Only.
			Earnest Money:- Rs.= 2,000/-Only.
			Time:- One Month.

Name of work :- Restoration of Rain damages on Sh. Naina Devi Ji to Toba road km 0/00 to 9/225 (SH:- Hiring of Excavator cum loader/JCB & Tractor with trolley for removal of slips at Rd 4/900 to 6/000) For the Year 2025-26 Job No.-26

Sr No.	Description of items.	Quantity		Rate In		Unit	Amount
				In Figure	In words.		
1	2	3	4	5	6	7	8
1	Providing one number Exacavator cum loader/JCB in good condition on hire bases at site of work for removal of slip.The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	67.00	Hours			Per Hours	
2	Providing one number Tractor with trolley in good condition. on hire basis having capacity of 3 to 5 tonne per trip for carriage of material i.e aggregate , soil , mud , boulders etc with in all leads and lifts as per direction of Engineer-In-Charge .The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	32.00	Hours			Per Hours	
	Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Exacavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
i)	The One Number Tractor with trolley will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fullly responsible for any loss/damages to any private /Govt. Property during the execution of work						
	Total						

Executive Engineer,
Bilaspur Division No. 2
HP PWD., Bilaspur (H.P.)

	SCHEDULE OF QUANTITY.	Estimated cost:- Rs.98,922/-Only.
		Earnest Money :- Rs. 2,000/- only
		Time:- One Month.

NAME OF WORK:- Restoration of Rain damages on Sh. Naina Devi Ji Bhakra road km 0/00 to 37/300 (SH:- Widening of road by Formation cutting at RD 12/274.70 to 12/277.95).

Sr	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification, 2014 Clause 300, 302.3.5 & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of material for filling in road way, camber ,embankments for grade improvements and disposal of all useful /surplus materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials tools equipments and execution shall be absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases as per direction of Engineer-in-Charges including carriage of materials within all leads and lifts.The rate including octori,royality , Malkana , toll tax, sale tax,Goods services tax or other taxes imposed by the Govt. A recovery of useful stone for 38.39 Cum (Thirty Eight point Thirty Nine). Cubic metre at the rate of Rs.300/- (Rs. Three hundred.) only shall be done on pro-rate basis in each running bill for this item including carriage of materials in all leads lifts as per the direction of the Engineer-in-Charge.	115.16	Cubic Metre			Per Cubic Metre	
	Total:-						

Executive Engineer,
Bilaspur Division No. 2,
HP PWD., Bilaspur (H.P.)

	SCHEDULE OF QUANTITY.	Estimated cost:- Rs.99,275/-Only.
		Earnest Money :- Rs. 2,000/- only
		Time:- One Month.

NAME OF WORK:- Restoration of Rain damages on Sh. Naina Devi Ji Bhakra road km 0/00 to 37/300 (SH:- Widening of road by Formation cutting at RD 12/277.95 to 12/282.70).

Sr	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification, 2014 Clause 300, 302.3.5 & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of material for filling in road way, camber ,embankments for grade improvements and disposal of all useful /surplus materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials tools equipments and execution shall be absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases as per direction of Engineer-in-Charges including carriage of materials within all leads and lifts.The rate including octori,royality , Malkana , toll tax, sale tax,Goods services tax or other taxes imposed by the Govt. A recovery of useful stone for 38.52 Cum (Thirty Eight point Fifty Two). Cubic metre at the rate of Rs.300/- (Rs. Three hundred) only shall be done on pro-rate basis in each running bill for this item including carriage of materials in all leads lifts as per the direction of the Engineer-in-Charge.	115.57	Cubic Metre			Per Cubic Metre	
	Total:-						

Executive Engineer,
Bilaspur Division No. 2
HP,PWD., Bilaspur (H.P.)

	SCHEDULE OF QUANTITY.	Estimated cost:- Rs.91,847/-Only.
		Earnest Money :- Rs.1,900/- Only.
		Time:- Three Months.

NAME OF WORK:- A/R & M/O Residential Quarter at Police Station Kot Kehloor, Tehsil Sh.Naina Devi Ji Distt. Bilaspur (HP) (SH:- Providing and Fixing Door, Window and Distempering Painting etc.) (Deposit work)

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within (50Fifty)metres lead Of area 3 sq. metres and below including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00	Nos.			Each	
2	Providing wood work in frames of doors, windows, clerestery windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately).Second class teak wood including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.15	Cubic metre.			Per Cubic Metre	
3	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in- charge. (Note:- But hinges and necessary screws shall be paid separately) Second class teak wood 35 mm (Thirty Five millimetre) thick shutters including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.31	Cubic metre.			Per Cubic Metre	
4	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete 300 x 16 mm (Three hundred into Sixteen Millimeter) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same .	2.00	Nos.			Each	
5	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 asper IS : 1868) transparent or dyed to required colour orshade, with necessary screws etc. complete including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same .						

i)	250x10 mm (Two hundred Fifty into Ten Millimeter)	4.00	Nos.			Each	
ii)	150x10 mm (One hundred fifty into Ten Millimeter)	2.00	Nos.			Each	
6	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 asper IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same .						
i)	125 mm (One Hundred twenty Five millimeter)	4.00	Nos.			Each	
ii)	100 mm (One Hundred millimeter)	2.00	Nos.			Each	
7	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm (one point four millimetre) in both directions with wire of dia 0.63 mm (zero point sixty Three millimetre), for doors, windows and clerestory windows with hinges and necessary screws with ISI marked M.S. pressed butt hinges bright finished of required size 35 mm (thirty five millimetre) thick shutters Second class teak wood including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same .	5.31	Square Meter			Per Square Meter	
8	Applying priming coat With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same .	9.55	Square Meter			Per Square Meter	
9	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same .	9.55	Square Meter			Per Square Meter	
10	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item) With float glass panes of 4.0 mm (four millimetre) thickness (weight not less than 10 kg/ sqm) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same .	5.00	Square Meter			Per Square Meter	

11	6 mm (six millmetre) plaster to ceiling in cement mortar 1:3(One Cement three sand) including carriage of materials , within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, royality, Malkana toll tax, Goods and Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.41	Square Metre			Per Square Metre	
12	White washing with lime to give an even shade old work two or more coats including carriage of materials , within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, royality, Malkana toll tax, Goods and Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	131.27	Square Metre			Per Square Metre	
13	Distempering with 1st quality acrylic distemper (ready made) of approved manufacturer and of required shade andcolour complete. as per manufacturer's specification one or more coats on old work. including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	479.74	Square Meter			Per Square Meter	
14	Finishing walls with water proofing cement paint of required shade Old work (one or more coats applied @ 2.20 kg/10 sqm) over priming coat of primer applied @ 0.80 litrs/10 sqm complete including cost of Priming coat including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	91.72	Square Metre			Per Square Metre	
	Total:-						

Executive Engineer,
Bilaspur Division No. 2,
HP PWD., Bilaspur (H.P.)