HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PWD/DPD/CB/EA-I/Tender/2025- 6005-06 Dated: - 22-12-2025

To

The Executive Engineer (IT Cell)
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject: - Publishing of tender Notice.

Sir,

Enclosed please find herewith tender notice of work as given in the Notice inviting Tender along with Schedule of Quantities for uploading the same on department website as per Notification No. Pr. Secy. (PW) to the Govt. of HP letter No. PBW (B) A (3) 1/2024 dated Shimla-2, the 03.01.2025 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ As above.

Executive Engineer,
Daulatpur Chowk Division,
HPPWD Daulatpur chowk.

Copy along with tender notice is forwarded to the Superintending Engineer, 15th Circle, HPPWD Una for information please.

DA/ As above.

Executive Engineer,
Daulatpur Chowk Division,
HPPWD Daulatpur chowk.

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed **Percentage rates** tenders on form 6 & 8 are hereby invited by the Executive Engineer Daulatpur Chowk Division, HPPWD, Daulatpur Chowk on behalf of Governor of HP for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach in this office and opened as per time schedule given below. The offer of the tender will be kept open for 75 days from the date of opening of the tenders.

Date and time of receipt of applications for the tender form : **29.12.2025 up to 05.00 PM**
Date and time of issue/Sale of tender forms against cash Payment : **30.12.2025 (03.00 PM to 5.00 PM)**
Date and time of receipt of tenders : **31.12.2025 up to 11.00 AM**
Date and time of opening of tenders : **31.12.2025 at 11.30 AM**

The tender forms will be issued against cash payment (non-refundable). The earnest money in the shape of NSC/Time Deposit/FDR of nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected.

Sr. No.	Name of Work	Estimated Cost	Earnest money	Time Limit	Cost of Form	Eligible Class of Contractor
1	Repair & Restoration of Rain Damages Link road NH-70 to Thaplan in G.P. Thaplan Km 0/0 to 8/300, (SH- Construction of Retaining wall between RD 8/280 to 8/320) Under PDNA 2023	324920.00	6500.00	Three Month	350-	Class-D
2	Repair & Restoration of Rain Damages link road Kalruhi To Athmah Km 0/0 to 4/600, (SH:- C/o PCC Drain & road Shoulder between RD 3/650 to 3/750 & 4/210 to 4/315) Under PDNA 2023	366913.00	7300.00	Three Month	350-	Class-D
3	Providing and installation of Computer system, UPS system and Printer in HPPWD Division office Daulatpur Chowk (Under IPH Deposit)	96450.00	2000.00	One Month	350-	Class-D
4	Repair & Restoration of Rain Damages link road Banne Di Hatti to Ghewat Bahed road from km. 0/0 to 4/520, (SH- Construction of Retaining wall between RD 3/455 to 3/475) Under PDNA 2023	499581.00	10000.00	Three Month	350-	Class-D
5	Repair & Restoration of Rain Damages Link road NH-70 to Thaplan in G.P. Thaplan Km 0/0 to 8/300, (SH- Construction of Retaining wall between RD 3/890 to 3/910) Under PDNA 2023	499680.00	10000.00	Three Month	350-	Class-D
6	Repair & Restoration of Rain Damages link road to Mohalla Kabirpanthi Tundkhari km. 0/0 to 1/800, (SH- Construction of Retaining wall between RD 0/535 to 0/550) Under PDNA 2023	438672.00	9000.00	Three Month	350-	Class-D

TERMS AND CONDITIONS: -

1. The contractor should produce a copy of enlistment/renewal letter at the time of application.
2. The contractor/firm shall have his registration and GST No. and copy of the same be attached with the application.
3. The earnest money for the above works should be submitted duly pledged in favour of Executive Engineer, Daulatpur Chowk Division, HPPWD Daulatpur chowk with the application for the purchase of tender forms. The application received without earnest money shall be summarily rejected.
4. The contractor/firms are required to insert the rate in words as well as in figures failing which Executive Engineer reserves the right to accept/rejects any or all tenders.
5. If any of the date mentioned above happens to be Local/Gazetted Holidays the same shall be process on next date.
6. The tender form will be issued to those contractors who have relevant machinery and equipment, list of which may be attached with their application along with proof of ownership of machinery/legal tie up.
7. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.

No. PWD/DPD/C-B-Tender/2025-5998-6004 Dt. 22-12-2025

Executive Engineer,
Daulatpur Chowk Division
HP.PWD Daulatpur Chowk.

PTO

No. PWD/DPD/CB-Tender/2025- 5998-6004 Dated: - 22-12-2025

Copy forwarded to the following for information and necessary action: -

1. The Engineer-in-Chief, HPPWD Nirman Bhawan Shimla.
2. The Chief Engineer (HZ) HPPWD Hamirpur.
3. The Superintending Engineer, 15th Circle, HPPWD Una.
4. All the Assistant Engineers working under this division.
5. Drawing Branch in this office.
6. Notice Board.

Sd/-

Executive Engineer,
Daulatpur Chowk Division
HP.PWD Daulatpur Chowk.

CERTIFICATE

Certified that tenders called vide this office letter No. PWD/DPD/CB-Tender/2025-5998-6004 dated 22-12-2025 are required to be carried out immediately being emergent nature of work in the public interest.

Executive Engineer,
Daulatpur chowk Division,
HPPWD Daulatpur Chowk.

Job No-01

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 324920/-
Earnest Money: Rs. 6500/-
Time Limit : Three Month

Name of Work:- Repair & Restoration of Rain Damages Link road NH-70 to Thaplan in G.P. Thaplan Km 0/0 to 8/300, (SH- Construction of Retaining wall between RD 8/280 to 8/320) Under PDNA 2023

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	28.000 Cubic metre	180.00	Rupees One Hundred Eighty Only	Per cubic metre	5040.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 25mm (twenty five millimeter) nominal size) for plain cement concrete in all heights/depths on ground or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, including cost of form work and curing complete in all type of structures like Retaining Walls & Breast Walls etcetera complete as per drawing and MORD technical specification section 800, 900, 1200 and 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	82.800 Cubic metre	3600.00	Rupees Three Thousand Six Hundred Only	Per cubic metre	298080.00
3	Providing weep holes in brick masonry/plain /reinforced concrete abutments, wing wall/ return wall, retaining walls and breast walls etcetra with 100mm (One Hundred millimeter) diamere PVC pipe make of D-Plast/Relpipe, working pressure not less then 4.50 Kg/Sq. cm. (four point five zero kilogram per square centimetre) , extending through the full width of the structure with slope of 1V:20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per the directions and entire satisfactions of Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	38.000 Number	220.00	Rupees Two Hundred Twenty Only	Each	8360.00
4	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification section 1200 and 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	19.200 Cubic metre	700.00	Rupees Seven Hundred Only	Per cubic metre	13440.00
	TOTAL					**324920.00**
	Quoted Rate in Figure		% above/below			
	Quoted Rate in Words					

Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Job No. 02

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 366913/-
Earnest Money: Rs. 7300/-
Time Limit : Three Months

Name of Work:- Repair & Restoration of Rain Damages link road Kalruhi To Athmah Km 0/0 to 4/600, (SH:- C/o PCC Drain & road Shoulder between RD 3/650 to 3/750 & 4/210 to 4/315) Under PDNA 2023

Sr. No.	Description of Item	Quantity		Rates in		Unit	Amount
				Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	46.63	Cubic metre.	180.00	Rupees One Hundred Eighty Only	Per cubic metre	8393.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, M-10 Grade (M-Ten) Nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20mm (Twenty millimeter) nominal size) in or under water in open foundations and the like for all types of structures, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, including cost of form work and curing complete as per drawing and MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	71.45	Cubic metre.	4000.00	Rupees Four Thousand Only	Per cubic metre	285800.00
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 25mm (twenty five millimeter) nominal size) for plain cement concrete in all heights/depths on ground or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, including cost of form work and curing complete in all type of structures like Retaining Walls & Breast Walls etcetera complete as per drawing and MORD technical specification section 800, 900, 1200 and 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	20.20	Cubic metre.	3600.00	Rupees Three Thousand Six Hundred Only	Per cubic metre	72720.00
					Total Amount		**366913.00**
	Quoted Rate in Figure			% above/below			
	Quoted Rate in Words						

Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Job No-03

BILL OF QUANTITY

Estimate Cost :- Rs.96450/-
Earnest Money :-Rs.2000/-
Time Limit :- One Month.

Name of work:- Providing and installation of Computer system, UPS system and Printer in HPPWD Division office Daulatpur Chowk (Under IPH Deposit)

Sr. No.	Description of Item	Quantity		Rate in		Unit	Amount
				Figures	Words		
1	Providing and installation of Computer system of Dell's Intel Core i5 Desktop Core™ 14th gen (8 GB DDR4/512 GB SSD/Windows 11 Home/23.8 Inch Screen/24-df1530in Bundle PC) with MS Office (Snow White, 409.3 mm x 497 mm x 235 mm, 5.85 Kg Monitor/Dell Wired Keyboard - KB216/USB optical mouse/ PL-antivirus 60 days updating (3 years comprehensive on site warranty) complete. The rates are inclusive octroi, royality, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	1.00	Number	78500.00	Rupees Seventy Eight Thousand Five Hundred Only	Each	78500.00
2	Providing and installation of Elnova: 650 VA offline UPS system (12Vx7AHx2 No.) with 25-30 Min battary backup 3 years warranty on UPS & 18 month on batteries from date of delievery. The rates are inclusive octroi, royality, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	1.00	Number	3150.00	Rupees Three Thousand One Hundred Fifty Only	Each	3150.00
3	Providing and installation of HP Laser HP Laser 1008a Printer, Single Function, Print, Hi-Speed USB 2.0, Up to 21 ppm, 150-sheet Input Tray, 100-sheet Output Tray, 10,000-page Duty Cycle, 1-Year Warranty, Black and White, 714Z8A. The rates are inclusive octroi, royality, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	1.00	Number	14800.00	Rupees Fourteen Thousand Eight Hundred Only	Each	14800.00
	TOTAL						**96450.00**
	Quoted Rate in Figure			% above/below			
	Quoted Rate in Words						

Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Job No-04

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 499581/-
Earnest Money: Rs. 10000/-
Time Limit : Three Month

Name of Work:- Repair & Restoration of Rain Damages link road Banne Di Hatti to Ghewat Bahed road from km. 0/0 to 4/520, (SH- Construction of Retaining wall between RD 3/455 to 3/475) Under PDNA 2023

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	34.560 Cubic metre	180.00	Rupees One Hundred Eighty Only	Per cubic metre	6221.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 25mm (twenty five millimeter) nominal size) for plain cement concrete in all heights/depths on ground or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, including cost of form work and curing complete in all type of structures like Retaining Walls & Breast Walls etcetera complete as per drawing and MORD technical specification section 800, 900, 1200 and 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	128.160 Cubic metre	3600.00	Rupees Three Thousand Six Hundred Only	Per cubic metre	461376.00
3	Providing weep holes in brick masonry/plain /reinforced concrete abutments, wing wall/ return wall, retaining walls and breast walls etcetra with 100mm (One Hundred millimeter) diamere PVC pipe make of D-Plast/Relpipe, working pressure not less then 4.50 Kg/Sq. cm. (four point five zero kilogram per square centimetre) , extending through the full width of the structure with slope of 1V:20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per the directions and entire satisfactions of Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	40.000 Number	220.00	Rupees Two Hundred Twenty Only	Each	8800.00
4	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification section 1200 and 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	33.120 Cubic metre	700.00	Rupees Seven Hundred Only	Per cubic metre	23184.00
	TOTAL					**499581.00**
	Quoted Rate in Figure	% above/below				
	Quoted Rate in Words					

Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Job No-05

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 499680/-
Earnest Money: Rs. 10000/-
Time Limit : Three Month

Name of Work:- Repair & Restoration of Rain Damages Link road NH-70 to Thaplan in G.P. Thaplan Km 0/0 to 8/300, (SH- Construction of Retaining wall between RD 3/890 to 3/910) Under PDNA 2023

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	32.000 Cubic metre	180.00	Rupees One Hundred Eighty Only	Per cubic metre	5760.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 25mm (twenty five millimeter) nominal size) for plain cement concrete in all heights/depths on ground or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, including cost of form work and curing complete in all type of structures like Retaining Walls & Breast Walls etcetera complete as per drawing and MORD technical specification section 800, 900, 1200 and 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	127.000 Cubic metre	3600.00	Rupees Three Thousand Six Hundred Only	Per cubic metre	457200.00
3	Providing weep holes in brick masonry/plain /reinforced concrete abutments, wing wall/ return wall, retaining walls and breast walls etcetra with 100mm (One Hundred millimeter) diamere PVC pipe make of D-Plast/Relpipe, working pressure not less then 4.50 Kg/Sq. cm. (four point five zero kilogram per square centimetre) , extending through the full width of the structure with slope of 1V:20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per the directions and entire satisfactions of Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	60.000 Number	220.00	Rupees Two Hundred Twenty Only	Each	13200.00
4	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification section 1200 and 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	33.600 Cubic metre	700.00	Rupees Seven Hundred Only	Per cubic metre	23520.00
	TOTAL					**499680.00**
	Quoted Rate in Figure	% above/below				
	Quoted Rate in Words					

Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Job No- 06

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 438672/-
Earnest Money: Rs. 9000/-
Time Limit : Three Month

Name of Work:- Repair & Restoration of Rain Damages link road to Mohalla Kabirpanthi Tundkhari km. 0/0 to 1/800, (SH- Construction of Retaining wall between RD 0/535 to 0/550) Under PDNA 2023

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	26.400 Cubic metre	180.00	Rupees One Hundred Eighty Only	Per cubic metre	4752.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 25mm (twenty five millimeter) nominal size) for plain cement concrete in all heights/depths on ground or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, including cost of form work and curing complete in all type of structures like Retaining Walls & Breast Walls etcetera complete as per drawing and MORD technical specification section 800, 900, 1200 and 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	113.250 Cubic metre	3600.00	Rupees Three Thousand Six Hundred Only	Per cubic metre	407700.00
3	Providing weep holes in brick masonry/plain /reinforced concrete abutments, wing wall/ return wall, retaining walls and breast walls etcetra with 100mm (One Hundred millimeter) diamere PVC pipe make of D-Plast/Relpipe, working pressure not less then 4.50 Kg/Sq. cm. (four point five zero kilogram per square centimetre) , extending through the full width of the structure with slope of 1V:20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per the directions and entire satisfactions of Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	39.000 Number	220.00	Rupees Two Hundred Twenty Only	Each	8580.00
4	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification section 1200 and 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	25.200 Cubic metre	700.00	Rupees Seven Hundred Only	Per cubic metre	17640.00
	TOTAL					**438672.00**
	Quoted Rate in Figure	% above/below				
	Quoted Rate in Words					

Executive Engineer,
HPPWD Division,
Daulatpur Chowk