

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PWD/DEH/CB/Tender/2025.26-
To

9817-25

Dated 27/12/2023

The Executive Engineer (IT Cell)
HPPWD Nirman Bhawan Nigam Bihar
HPPWD Shimla

Subject:- Tender Notice

Sir,

Enclosing Kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on Department website as per notification of Principal Secretary (PW) to the Govt. of HP vide No ; PWD/(B) A(3) 1/2024 dated 03.01.2024 as the works mentioned in the inviting tender are urgent in nature and public interest

Executive Engineer,
Dehra Division HP.PWD.,
Dehra.

Copy to the F.C-cum- Secretary (PW) to the Govt. of Himachal Pradesh Shimla -
2 for favour of information please.

Copy to the Engineer-in-Chief HPPWD Shimla for information please.
information please.
Copy to the Chief Engineer (KZ) HPPWD Dharamshala for favour of

information please.
Copy to the Superintending Engineer Dehra Circle HPPWDD ehra for favour of

Copy to Notice Board

Copy to All the head of Branches

Copy to All the Contractors working under Dehra Division

Executive Engineer,
Dehra Division HPPWD.,
Dehra.

H. P. P.W.D. TENDER

Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Dehra Division HPPWD., Dehra on behalf of the Governor of HP for the following works from the approved and eligible contractors (C&D Class) enlisted in HPPWD.

TENDER SCHEDULE:

- | | |
|---|-------------------------|
| 1. Date and time of receipt of application for tender form: | 02.01.2026 upto 1.00 PM |
| 2. Date and time of issue of tender form: | 03.01.2026 upto 1.00 PM |
| 3. Date and time of receipt of tenders: | 03.01.2026 upto 5.00 PM |
| 4. Date and time of opening of tenders: | 03.01.2026 at 11.30 AM |

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dehra Division HPPWD Dehra must accompany with each tender.

Job No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
1	Restoration of Rain Damages on Nehranpukhar to Kasba Kohasan Road km.0/00 to 2/00 (SH:- Construction of cement concrete pavement with Toewall on Khad Portion at RD. 1/175 to 1/205) PDNA	Rs.495270/-	Rs.10,000/-	Three Months	Rs 350/-
2	Restoration of Rain Damages on Nehranpukhar to Kasba Kohasan Road km.0/00 to 2/00 (SH:- Construction of cement concrete pavement with Toewall on Khad Portion at RD. 1/206 to 1/236) PDNA	Rs.495270/-	Rs.10,000/-	Three Months	Rs 350/-
3	Restoration of Rain Damages on Nehranpukhar to Kasba Kohasan Road km.0/00 to 2/00 (SH:- Construction of cement concrete pavement with Toewall on Khad Portion at RD. 1/237 to 1/260 & Catchpit for Hume Pipe Culvert at RD. 0/370 & 0/470).PDNA	Rs.299723/-	Rs.6,000/-	Three Months	Rs 350/-
4	Restoration of Rain Damages on Kaloha Pragpur Nehranpukhar Dhaliara Dadasiba Road km. 9/00 to 22/200 (SH:- Providing and Laying 80mm thick Interlocking Paver Block at RD. 18/090 to 18/130)	Rs.472952/-	Rs.10,000/-	Three Months	Rs 350/-
5	Restoration of Rain Damages on Kaloha Pragpur Nehranpukhar Dhaliara Dadasiba Road km. 9/00 to 22/200 (SH:- Providing and Laying 80mm thick Interlocking Paver Block at RD. 15/252.50 15/295)	Rs.499431/-	Rs.10000/-	Three Months	Rs 350/-
1.	The contractors/firms should possess the following documents(Photocopy to be attached with the application):				
(i)	Copy of Registration/Latest renewal of enlistment.				
(ii)	PAN (Permanent Account No.)				
(iii)	Registration under GST No.				
(iv)	EPF(Employee Provident Fund Account No.)				
(v)	The proof ownership/hire/lease, buying of required machinery for micro surfacing works.				
2	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case.				
3	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).				
4	The offer of the tender shall remain valid upto 30 days after the opening.				


Executive Engineer
HPPWD Division Dehra
Distt Kangra H.P

on behalf of Governor of Himachal Pradesh
HIM LOK SAMPARK

360

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.495270.00
Earnest Money :- Rs. 10000.00
Time Limit :- Three Months.

Name of work:- Restoration of Rain Damages on Nehranpukhar to Kasba Kohasan Road km.0/00 to 2/00 (SH:- Construction of cement concrete pavement with Toewall on Khad Portion at RD. 1/175 to 1/205) PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	84.00 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	24,360.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkhana, GST, toll tax or any other taxes imposed by the Government.	16.50 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	66,825.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated plain/reinforced cement concrete Grade-M-25 (M-Twenty five) nominal mix 1:1.5:3 (One cement isto one and half sand isto three graded crushed stone aggregate 20mm (Twenty millimeter) nominal size <i>in open foundation</i> as per drawing and MORD technical specification clause 802, 803, 1202 and 1203 including the cost of form work and curing complete but excluding cost of reinforcement for reinforced concrete work as per satisfaction and direction of Engineer-in-Charge, including carriage of materials up to all leads, lifts. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	16.50 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	1,13,025.00
4	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-10 (M-Ten) nominal mix 1:3:6 (One cement isto three sand isto six graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water <i>in open foundation</i> for all type of structure and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900 and 1200 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, Toll tax or any other taxes imposed by the Government.	58.80 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	2,91,060.00
		TOTAL				4,95,270.00
		% Above/below				
		Quoted Amount in Figures				
		Quoted Amount in Words				

Proccedure Billed by quantity surveyor
8/9/2017/10/2 49153701

 Executive Engineer,
 Dehra Division,
 PWD Dehra

361

PERCENTAGE BILL OF QUANTITY

Name of work:-

Restoration of Rain Damages on Nehranpukhar to Kasba Kohasan Road km.0/00 to 2/00 (SH:- Construction of cement concrete pavement with Toewall on Khad Portion at RD. 1/206 to 1/236).PDNA

Estimate Cost :- Rs.495270.00

Earnest Money :- Rs.10,000.00

Time Limit :- Three Months.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	84.00 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	24,360.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	16.50 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	66,825.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated plain/reinforced cement concrete Grade-M-25 (M-Twenty five) nominal mix 1:1.5:3 (One cement isto one and half sand isto three graded crushed stone aggregate 20mm (Twenty millimeter) nominal size <i>in open foundation</i> as per drawing and MORD technical specification clause 802, 803, 1202 and 1203 including the cost of form work and curing complete but excluding cost of reinforcement for reinforced concrete work as per satisfaction and direction of Engineer-in-Charge, including carriage of materials up to all leads, lifts. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	16.50 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	1,13,025.00
4	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-10 (M-Ten) nominal mix 1:3:6 (One cement isto three sand isto six graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water <i>in open foundation</i> for all type of structure and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900 and 1200 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, Toll tax or any other taxes imposed by the Government.	58.80 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	2,91,060.00
TOTAL						4,95,270.00
% Above/below						
Quoted Amount in Figures						
Quoted Amount in Words						

Accepted by BILU 29/08/2015
 9/8/2015/15/2 495270/-

Executive Engineer,
 Dehra Division,
 HPPWD Dehra

362

PERCENTAGE BILL OF QUANTITY

Name of work:- Restoration of Rain Damages on Nehranpukhtar to Kasba Kohasan Road km. 0/00 to 2/00 (SH:- Construction of cement concrete pavement with Toe wall on Khad Portion at RD. 1/237 to 1/260 & Catchpit for Hume Pipe Culvert at RD. 0/370 & 0/470). PDNA

Estimate Cost :- Rs.299723.00
Earnest Money :- Rs. 6,000.00
Time Limit :- Three Months.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	35.64 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	10,336.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkhana, GST, toll tax or any other taxes imposed by the Government.	13.19 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	53,420.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-10 (M-Ten) nominal mix 1:3:6 (One cement isto three sand isto six graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water <i>in open foundation</i> for all type of structure and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900 and 1200 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, Toll tax or any other taxes imposed by the Government.	47.67 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	2,35,967.00
	TOTAL					2,99,723.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

*100% correct by 24/09/2024 checked
8/09/2024 to 24/09/2024*

[Signature]
Executive Engineer,
Dehra Division,
HPPWD Dehra

363

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs 472952.00
 Earnest Money :-Rs. 10000.00
 Time Limit :- Three Month.

Name of work:- Restoration of Rain Damages on Kaloha Pragpur Nehrampukhar Dhaliara Dadasiba Road km. 9/00 to 22/200 (SH:- Providing and Laying 80mm thick Interlocking Paver Block at RD. 18/090 to 18/130) PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	30.00 Cubic meter	290.00	Rupees Two Hundred Ninety Only	Per Cubic meter	8,700.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (fourty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	28.00 Cubic meter	4050.00	Rupees Four Thousand Fifty Only	Per Cubic meter	1,13,400.00

Sr. No.	Description of item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water in open foundation for all types of structure and the like in solid causeway and Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government	5.94 Cubic meter	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic meter	34,452.00
4	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 80 mm of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	280.00 Square meter	1130.00	Rupees One Thousand One Hundred Thirty Only	Square meter	3,16,400.00
Total						4,72,952.00
		% Above/below				
		Quoted Amount in Figures				
		Quoted Amount in Words				

Executive Engineer,
Dehra Division,
AHPWD Dehra

Per cost Bill 294475 checked
9/10/2019 472952/-

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs 499431.00
Earnest Money :-Rs. 10000.00
Time Limit :- Three Month.

Name of work:- Restoration of Rain Damages on Kaloha Pragpur Nehranpukhar Dhaliara Dadasiba Road km. 9/00 to 22/200 (SH:- Providing and Laying 80mm thick Interlocking Paver Block at RD. 15/252.50 15/295)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	31.88 Cubic meter	290.00	Rupees Two Hundred Ninety Only	Per Cubic meter	9,244.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (fourty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	29.75 Cubic meter	4050.00	Rupees Four Thousand Fifty Only	Per Cubic meter	1,20,488.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water in open foundation for all types of structure and the like in solid causeway and Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government	5.78 Cubic meter	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic meter	33,524.00
4	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 80 mm of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	297.50 Square meter	1130.00	Rupees One Thousand One Hundred Thirty Only	Square meter	3,36,175.00
Total						4,99,431.00
		% Above/below				
		Quoted Amount in Figures				
		Quoted Amount in Words				

Percentage/3442 quantity checked & approved for Rs 499431/-

Executive Engineer,
Dehra Division,
CHPPWD Dehra