HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PWD/DEH/CB/Tender/2025.26- 9798- 9810 Dated 27/12/2025

To

The Executive Engineer (IT Cell)
HPPWD Nirman Bhawan Nigam Bihar
HPPWD Shimla

Subject:- **Tender Notice**

Sir,

Enclosing Kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on Department website as per notification of Principal Secretary (PW) to the Govt. of HP vide No ; PWD/(B) A(3) 1/2024 dated 03.01.2024 as the works mentioned in the inviting tender are urgent in nature and public interest

Executive Engineer,
Dehra Division HP.PWD.,
Dehra

Copy to the F.C-cum- Secretary (PW) to the Govt. of Himachal Pradesh Shimla - 2 for favour of information please.

Copy to the Engineer-in-Chief HPPWD Shimla for information please.

Copy to the Chief Engineer (KZ) HPPWD Dharamshala for favour of information please.

Copy to the Superintending Engineer Dehra Circle HPPWDD Dehra for favour of information please.

Copy to Notice Board

Copy to All the head of Branches

Copy to All the Contractors working under Dehra Division

Executive Engineer,
Dehra Division HPPWD.,
Dehra.

H. P. P.W.D. TENDER

Sealed item rate tenders on the form 6&8 are invited by the **Executive Engineer Dehra Division HPPWD., Dehra** on behalf of the Governor of HP for the following works from the approved and eligible contractors (C&D Class) enlisted in HPPWD.

TENDER SCHEULE:

1. Date and time of receipt of application for tender form: 07.01..2026 upto 1.00 PM
2. Date and time of issue of tender form: 08.01.2026 upto 5.00 PM
: 3 Date and time of receipt of tenders: 09.01.2026 upto 11.00 AM
4 Date and time of opening of tenders: 09.01.2026 at 11.30 AM

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dehra Division HPPWD Dehra must accompany with each tender.

Job No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
1	Restoration of Rain Damages on Bankhandi to Haripur Road km.0/00 to 8/00 (SH:- Construction of V-shape drain at Rd. 1/700 to 1/872) PDNA	Rs.498766/-	Rs.10,000/-	Three Months	Rs 350/-
2	Restoration of Rain Damages on Bankhandi to Haripur Road km.0/00 to 8/00 (SH:- Construction of V-shape drain at Rd. 1/875 to 1/935 & 2/300 to 2/412) PDNA	Rs.498766/-	Rs.10,000/-	Three Months	Rs 350/-
3	Restoration of Rain Damages on Bankhandi to Paisa Road km. 0/00 to 6/800 (SH:- Providing and Laying 80mm thick Interlocking Paver Block at RD.3/700 to 3/800)	Rs.497292/-	Rs.10,000/-	Three Months	Rs 350/-
4	Restoration of Rain Damages on Bankhandi to Paisa Road km. 0/00 to 6/800 (SH:- Providing and Laying 80mm thick Interlocking Paver Block at RD.3/800 to 3/900)	Rs.497292/-	Rs.10,000/-	Three Months	Rs 350/-
5	Restoration of rain damages on Bankhandi to Kherian road Km 0/0 to 4/000 (SH:- Providing and Laying 80mm thick Interlocking Paver Block at RD.0/810 to 0/850 & 2/330 to 2/370) PDNA	Rs.499271/-	Rs.10,000/-	Three Months	Rs 350/-
6	Restoration of rain damages on Bankhandi to Kherian road Km 0/0 to 4/000 (SH:- Construction of V-Shape drain at RD. 0/00 to 1/00) PDNA	Rs.495083/-	Rs.10,000/-	Three Months	Rs 350/-
7	Restoration of Rain Damages on Khabli to Miyoli Road km.0/00 to 3/500 (SH:-C/o R/wall at Rd.2/780 to 2/800, Edge wall with drain at Rd. 2/800 to 2/840 & B/wall at RD. 2/900 to 2/930) .PDNA	Rs.485334/-	Rs.10,000/-	Three Months	Rs 350/-
8	Restoration of Rain Damages on Khabli to Miyoli Road km.0/00 to 3/500 (SH:-C/o Edge wall with drain at Rd. 2/660 to 2/760) .PDNA	Rs.474887/-	Rs.10,000/-	Three Months	Rs 350/-
9	Restoration of rain damages on Jawalamukhi Dehra Jawali Raja Ka Talab road in Km 4/0 to 39/180 (SH:- Construction of Edge wall at RD. 17/050 to 17/130) .PDNA	Rs.464016/-	Rs.10,000/-	Three Months	Rs 350/-

10	Restoration of Rain Damages on Kaloha Pragpur Nehranpukhar Dhaliara Dadasiba Road km. 9/00 to 22/200 (SH:- Providing and Laying 80mm thick Interlocking Paver Block at RD. 15/210 to 15/252.50)	Rs.499431/-	Rs.10,000/-	Three Months	Rs 350/-

1.	The contractors/firms should possess the following documents(Photocopy to be attached with the application):
(i)	Copy of Registration/Latest renewal of enlistment.
(ii)	PAN (Permanent Account No.)
(iii)	Registration under GST No.
(iv)	EPF(Employee Provident Fund Account No.)
(v)	The proof ownership/hire/lease, buying of required machinery for micro surfacing wor
2	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case.
3	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).
4	The offer of the tender shall remain valid upto 30 days after the opening.

Executive Engineer
HPPWD Division Dehra
Distt Kangra H.P
on behalf of Governor of Himachal Pradesh
HIM LOK SAMPARK

365

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 4,98,766.00
Earnest Money :- Rs. 10,000.00
Time Limit :- Three Months.

Name of work:- Restoration of rain damages on Bankhandi to Haripur road Km 0/0 to 8/000 (SH:- Construction of V-Shape drain at RD. 1/700 to 1/872). Under PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	46.44 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	13,468.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation of all type of structure like Drains, etcetera including pumping or bailing out water/dewatering (surface and sub soil water) removal of the slush which may arise at the time of laying under water, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 or as per direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	98.04 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	4,85,298.00
	Total					**4,98,766.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage Bill & quantity checked & approved for Rs 498766/-only

Executive Engineer,
Dehra Division,
HPPWD Dehra.

366

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 4,98,766.00
Earnest Money :- Rs. 10,000.00
Time Limit :- Three Months.

Name of work:- Restoration of rain damages on Bankhandi to Haripur road Km 0/0 to 8/000 (SH:- Construction of V-Shape drain at RD. 1/875 to 1/935 & 2/300 to 2/412). Under PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	46.44 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	13,468.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation of all type of structure like Drains, etcetera including pumping or bailing out water/dewatering (surface and sub soil water) removal of the slush which may arise at the time of laying under water, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 or as per direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	98.04 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	4,85,298.00
	Total					**4,98,766.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage Bill Quantity checked & approved for
4,98,766/- Rs

Executive Engineer,
Dehra Division.

367

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs 497292.00
Earnest Money :-Rs. 10000.00
Time Limit :- Three Month.

Name of work:- Restoration of Rain Damages on Bankhandi to Paisa Road km. 0/00 to 6/800 (SH:- Providing and Laying 80mm thick Interlocking Paver Block at RD.3/700 to 3/800)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	15.50 Cubic meter	290.00	Rupees Two Hundred Ninety Only	Per Cubic meter	4,495.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (fourty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	21.53 Cubic meter	4050.00	Rupees Four Thousand Fifty Only	Per Cubic meter	87,197.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water in open foundation for all types of structure and the like in solid causeway and Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government	15.50 Cubic meter	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic meter	89,900.00
4	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 80 mm of M-30 grade with approved color design and pattern in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, toll tax, sale tax ,GST or any other taxes imposed by the Government.	287.00 Square meter	1100.00	Rupees One Thousand One Hundred Only	Square meter	3,15,700.00
						4,97,292.00
	Total	% Above/below				
		Quoted Amount in Figures				
		Quoted Amount in Words				

Percentage Bill Quantity checked & approved to Rs 497292/- only

Executive Engineer,
Dehra Division,
HPPWD Dehra

368

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs 497292.00
Earnest Money :-Rs. 10000.00
Time Limit :- Three Month.

Name of work:- Restoration of Rain Damages on Bankhandi to Paisa Road km. 0/00 to 6/800 (SH:- Providing and Laying 80mm thick Interlocking Paver Block at RD.3/800 to 3/900) PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	15.50 Cubic meter	290.00	Rupees Two Hundred Ninety Only	Per Cubic meter	4,495.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (fourty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	21.53 Cubic meter	4050.00	Rupees Four Thousand Fifty Only	Per Cubic meter	87,197.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water in open foundation for all types of structure and the like in solid causeway and Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government	15.50 Cubic meter	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic meter	89,900.00
4	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 80 mm of M-30 grade with approved color design and pattern in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, toll tax, sale tax ,GST or any other taxes imposed by the Government.	287.00 Square meter	1100.00	Rupees One Thousand One Hundred Only	Square meter	3,15,700.00
	Total					4,97,292.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage Below & quantity checked & approved/
Rs 497292/- only

Executive Engineer,
Dehra Division,
HPPWD Dehra

369

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 4,99,271.00
Earnest Money :- Rs. 10,000.00
Time Limit :- Three Months.

Name of work:- Restoration of rain damages on Bankhandi to Kherian road Km 0/0 to 4/000 (SH:- Providing and Laying 80mm thick Interlocking Paver Block at RD.0/810 to 0/850 & 2/330 to 2/370) PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	16.88 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	4,895.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	20.48 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	82,944.00
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation of all type of structure like Drains, etcetera including pumping or bailing out water/dewatering (surface and sub soil water) removal of the slush which may arise at the time of laying under water, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 or as per direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	6.00 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	29,700.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
4	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water in open foundation for all types of structure and the like in solid causeway and Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government	14.04 Cubic meter	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic meter	81,432.00
5	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 80 mm of M-30 grade with approved color design and pattern in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, toll tax, sale tax ,GST or any other taxes imposed by the Government.	273.00 Squarem etre	1100.00	Rupees One Thousand One Hundred Only	Per Squarem etre	3,00,300.00
	Total					**4,99,271.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage BOQ quantity checked & approx for Rs 499271/- only.

Executive Engineer,
Dehra Division,
HPPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 4,95,083.00
Earnest Money :- Rs. 10,000.00
Time Limit :- Three Months.

Name of work:- Restoration of rain damages on Bankhandi to Kherian road Km 0/0 to 4/000 (SH:- Construction of V-Shape drain at RD. 0/00 to 1/00) PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	140.25 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	40,673.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation of all type of structure like Drains, etcetera including pumping or bailing out water/dewatering (surface and sub soil water) removal of the slush which may arise at the time of laying under water, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 or as per direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	91.80 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	4,54,410.00
	Total					4,95,083.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage Bill & quantity checked & approved for Rs 495083/- only

Executive Engineer,
Dehra Division,
HPPWD Dehra.

371

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.485334.00
Earnest Money :- Rs.10,000.00
Time Limit :- Three Months.

Name of work:- Restoration of Rain Damages on Khabli to Miyoli Road km.0/00 to 3/500 (SH:-C/o R/wall at Rd.2/780 to 2/800, Edge wall with drain at Rd. 2/800 to 2/840 & B/wall at RD. 2/900 to 2/930) .PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	***Earth work in excavation in foundation for all types of structures*** such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	67.20 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	19,488.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, toll tax or any other taxes imposed by the Government.	65.52 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	2,65,356.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-10 (M-Ten) nominal mix ***1:3:6*** (One cement isto three sand isto six graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water ***in open foundation*** for all type of structure and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900 and 1200 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, Toll tax or any other taxes imposed by the Government.	34.20 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	1,69,290.00
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	60.00 Number	250.00	Rupees Two Hundred Fifty Only	Each	15,000.00
5	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	21.60 Cubic metre	750.00	Rupees Seven Hundred Fifty Only	Per Cubic metre	16,200.00
	TOTAL					**4,85,334.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage Bill Quantity checked & approved for Rs 485334/- only

Executive Engineer,
Dehra Division,
HPPWD Dehra

372

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.474887.00
Earnest Money :- Rs.10,000.00
Time Limit :- Three Months.

Name of work:- Restoration of Rain Damages on Khabli to Miyoli Road km.0/00 to 3/500 (SH:-C/o Edge wall with drain at Rd. 2/660 to 2/760) .PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	***Earth work in excavation in foundation for all types of structures*** such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	63.18 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	18,322.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-10 (M-Ten) nominal mix ***1:3:6*** (One cement isto three sand isto six graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water ***in open foundation*** for all type of structure and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900 and 1200 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, Toll tax or any other taxes imposed by the Government.	88.70 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	4,39,065.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	70.00 Number	250.00	Rupees Two Hundred Fifty Only	Each	17,500.00
	TOTAL					**4,74,887.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage Bill & quantity checked & approved Rs 4,74,887/- (Rupees)

Executive Engineer,
Dehra Division,
HPPWD Dehra

373

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.464016.00
Earnest Money :- Rs.10,000.00
Time Limit :- Three Months.

Name of work:- Restoration of rain damages on Jawalamukhi Dehra Jawali Raja Ka Talab road in Km 4/0 to 39/180 (SH:- Construction of Edge wall at RD. 17/050 to 17/130) .PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	***Earth work in excavation in foundation for all types of structures*** such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	38.40 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	11,136.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, toll tax or any other taxes imposed by the Government.	109.60 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	4,43,880.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	36.00 Number	250.00	Rupees Two Hundred Fifty Only	Each	9,000.00
	TOTAL					**4,64,016.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage Bill & quantity checked & approved for Rs 464016/- only

Executive Engineer,
Dehra Division,
HPPWD Dehra

374

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs 499431.00
Earnest Money :-Rs. 10000.00
Time Limit :- Three Month.

Name of work:- **Restoration of Rain Damages on Kaloha Pragpur Nehranpukhar Dhaliara Dadasiba Road km. 9/00 to 22/200 (SH:- Providing and Laying 80mm thick Interlocking Paver Block at RD. 15/210 to 15/252.50)**

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	31.88 Cubic meter	290.00	Rupees Two Hundred Ninety Only	Per Cubic meter	9,244.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (fourty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	29.75 Cubic meter	4050.00	Rupees Four Thousand Fifty Only	Per Cubic meter	1,20,488.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water in open foundation for all types of structure and the like in solid causeway and Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government	5.78 Cubic meter	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic meter	33,524.00
4	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 80 mm of M-30 grade with approved color design and pattern in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, toll tax, sale tax ,GST or any other taxes imposed by the Government.	297.50 Square meter	1130.00	Rupees One Thousand One Hundred Thirty Only	Square meter	3,36,175.00
	Total					4,99,431.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage Bldg quantity checked & approved
for Rs 499431/-

Executive Engineer,
Dehra Division,
HPPWD Dehra