

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
No.PW-SRDD-CB-CTR-NIT-2025-26-15337-371

Dated:- 3-12-2025

To

The Executive Engineer (IT Cell),
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- **Notice Inviting Tender for uploading the same on departmental website.**

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office for uploading the same on departmental website as per notification Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW-BFO(2)/3/2024-284016 dated Shimla-2 the 09-09-2025 as the works mentioned in the tender Notice are urgent in nature and in public interest.

Encl:-Copy of NIT

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhami
Ph. 0177-2790534

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-
3. The Superintending Engineer, 4th Circle, HPPWD., Shimla-3.
4. All the Superintending Engineer, in HPPWD. (SZ)
5. The Deputy Commissioner Shimla Distt. Shimla.
6. The Sub Divisional Magistrate Shimla.
7. All the Executive Engineers in HPPWD, (SZ).
8. All the Assistant Engineer, working under this division.
9. All the heads of the branches in this office.
10. Notice Board.

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhami
Ph. 0177-2790534

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Shimla Rural Division H.P.P.W.D. Dhami on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Services Tax Act, 2017 so as to reach in this office on before **12.12.2025 up to 11:30 AM** and the same shall be opened on the same day at **12:00 P.M.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **11.12.2025 up to 5.00 PM** and the application for issue of tender form shall be received on **10.12.2025 up to 4:00 PM.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Shimla Rural Division HPPWD Dhami must be accompanied with the application for tender documents. Please not any exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No.	Name of Work	Estimated Cost (In Rs.)	EMD	Time	Cost of Form
1	R/R damages on Badmain to Ghaini road Km. 0/00 to 6/500 (SH:- C/O R/Wall at Rd. 0/705 to 0/715).	229888/-	4600/-	One month	Rs.350/-
2	R/R damages on Bhagar to Jagehdi road Km. 0/00 to 8/600 (SH:- Removal of slips at various Rds between Km. 0/00 to 8/600).	495934/-	10000/-	One month	Rs.350/-
3	R/R damages on Nehra Bhukho road Km. 0/00 to 8/00 (SH:- C/O R/Wall in between Km. 6/370 to 6/383).	476452/-	10000/-	One month	Rs.350/-
4	Preparation of DPR under sub division Jutogh: (i) C/O Kufridhar to village Sanol Sanog Km. 0/00 to 2/170. (2) C/O link road to village Kafled Km. 0/00 to 1/075. (3) Kiarti Goshala to Mashobra road Km. 0/00 to 1/760. (4) C/O Ghanahatti to Tikkari road Km. 0/00 to 5/350 and (5) C/O Rahel to Shilli road Km. 0/00 to 1/670).	438750/-	9000/-	One month	Rs.350/-
5	R/R damages on Chaba Makarcha road Km. 0/00 to 1/500 (SH: C/O R/Wall at Rd. 0/480 to 0/495).	336440/-	10000/-	One month	Rs.350/-
6	R/R damages on Badmain Ghaini road Km. 0/00 to 6/500 (SH: C/O R/Wall at Rd. 3/210 to 3/223).	222539/-	4500/-	One month	Rs.350/-
7	R/R damages on badmain-Basantpur road Km. 0/00 to 7/00 (SH: Dismantling of unsafe R/Wall at Rd. 5/970 to 5/985).	341723/-	7000/-	One month	Rs.350/-

8	R/R damages on badmain-Basantpur road Km. 0/00 to 7/00 (SH: Removal of slips/Landslide at various Rds.).	149963/-	3000/-	One month	Rs.350/-
9	R/R damages on Hiranagar Sharog road Km. 0/00 to 5/500 (SH: Channelization of culvert discharge and removal of land slide at Rd. 0/080 to 0/085).	444482/-	9200/-	One month	Rs.350/-
10	R/R damages on Gharog Nalta road Km. 0/00 to 7/00 (SH: Removal of slips & C/O B/Wall in B/W Km. 5/640 to 5/675).	464800/-	9000/-	One month	Rs.350/-
11	Geological investigation for construction of Govt. Polytechnic at Basanpur Tehsil Dunni Distt. Shimla, H.P.	294920/-	6000/-	One month	Rs.350/-
12	R/R damages on Dhanpur Sandoa road Km. 0/00 to 8/100 (SH: C/O B/Wall in B/W Km. 4/285 to 4/304). PCC.	426402/-	8600/-	One month	Rs.350/-
13	Restoration of Rain Damages on Hiranagar Sharog road km.0/00 to 5/500 (SH:- C/O R/Wall at Rd. 0/670 to 0/681).	467472/-	9000/-	One month	Rs.350/-
14	C/O link road from Kufridhar to Shanol road Km. 0/00 to 2/120 (SH: C/O C. D. in Km. 1/850 with wing wall).	496365/-	10000/-	One Month	Rs. 350/-
15	C/O link road from Kufridhar to Shanol road Km. 0/00 to 2/120 (SH: C/O W-Wall in Km. 1/841.65 to 1/847.65& 1/852.35 to 1/858.35).	479766/-	10000/-	One Month	Rs. 350/-
16	C/O link road from Kufridhar to Shanol road Km. 0/00 to 2/120 (SH: C/O C. D. in Km. 0/280 with wing wall).	204126/-	4000/-	One Month	Rs. 350/-
17	R/R damages on Bangora Kalihatti Bastigunana road Km. 0/00 to 11/675 (SH: C/O R/Wall in B/W Km. 10/645 to 10/655).	365481/-	7000/-	One month	Rs.350/-
18	C/O link road from Shoghi Mehli road to Village Bhog (SH: C/O RCC Box Culvert (1x1. Mtr.) at Rd. 0/735).	460900/-	10000/-	One Month	Rs. 350/-
19	C/O link road from Shoghi Mehli road to Village Bhog (SH: C/O RCC Box Culvert (1x1. Mtr.) at Rd. 0/840).	460900/-	10000/-	One Month	Rs. 350/-
20	A/R & M/O Tutikandi Sheelgaon via Kiari road Km. 0/00 to 3/870 (SH: C/O B/Wall at Rd. 3/765 to 3/780 for supporting playground).	280906/-	5700/-	One Month	Rs. 350/-
21	R/R damages on Bag to Kangri road Km. 0/00 to 7/250 (SH: C/O wire crate B/wall at Rd. 5/970 to 6/000).	358386/-	7200/-	One month	Rs.350/-
22	C/O Chailly Khurd road Km. 0/00 to 1/350 (SH: C/O R/Wall in between Km. 0/290 to 0/300).	303059/-	6000/-	One Month	Rs. 350/-
23	C/O Chailly Khurd road Km. 0/00 to 1/350 (SH: C/O R/Wall in between Km. 1/270 to 1/282).	363930/-	7000/-	One Month	Rs. 350/-
24	A/R & M/O Slapper-Tattapani-Sunni-Luhri road, portion Km. 86/000 to 104/000 (SH: C/O R/Wall in between Km. 96/075 to 96/102).	449392/-	10000/-	One Month	Rs. 350/-
25	R/R damages on Sal to Karyali road Km. 0/00 to 3/00 (SH: C/O B-Wall at Km.0/710 to 0/740) (PCC).	405824/-	8200/-	One month	Rs.350/-
26	R/R damages on Paughatti to Shal Chanog road Km. 0/00 to 7/330 (SH: C/O R-Wall at Rd. 7/140 to 7/148.50).	463161/-	9000/-	One month	Rs.350/-
27	Restoration of Rain Damages on Ghanahatti Kalihatti Arki road km.0/00 to 8/060 (SH:- C/O R/Wall at Rd. 0/060 to 0/070).	283820/-	6000/-	One month	Rs.350/-
28	Restoration of Rain Damages on Khel ka Chaura to Baggi road km.10/00 to 11/500 (SH:- C/O R/Wall at Rd. 11/150 to 11/170).	351423/-	7000/-	One month	Rs.350/-
29	R/R damages on Dargi Macharyana Judloo road Km. 0/00 to 11/900 (SH: C/O R-Wall at Rds. 0/720 to 0/733).	492892 /-	10000/-	One Month	Rs.350/-
30	R/R damages on Galog Nehra Okhroo road Km. 0/00 to 11/135 (SH: C/O R-Wall at Rds. 2/396 to 2/408).	306039 /-	6000/-	One Month	Rs.350/-

31	Restoration of Rain Damages on Hiranagar Sharog road km.0/00 to 5/500 (SH:-Channelization of culvert discharge with wire crate at Rd. 0/080 to 0/085).	344056/-	6900/-	One month	Rs.350/-
32	R/R damages on link road to Totu bazaar Km. 0/00 to 1/020 (SH: C/O R-Wall at Rds. 0/013 to 0/028).	455258 /-	9000/-	One Month	Rs.350/-
33	R/R damages on Kufridhar Rain shelter to village Kufridhar G.P. Ghanahatti in Km. 0/00 to 0/645 (SH: C/O R-Wall at Rds. 0/000 to 0/023).	302466/-	6000/-	One Month	Rs.350/-
34	A/R & M/O Shimla Nalagarh road Km. 7/00 to 22/000 (SH: Repair of earthen shoulder, Trimming of grass and clearing of drain in Km. 10/00 to 22/000).	496800 /-	10000/-	One Month	Rs.350/-
35	R/R damages on Ambulance road from Taradevi Malog Zalgi road Km. 0/00 to 0/470 (SH: Providing and fixing steel railing in Km. 0/00 to 0/200) (Balance work).	186913 /-	3800/-	One Month	Rs.350/-
36	R/R damages on Shoghi Mehli road Km. 0/00 to 12/375 (SH: C/O B-Wall at Rds. 6/765 to 6/775).	175731 /-	3600/-	One Month	Rs.350/-
37	R/R damages on Shoghi Mehli road Km. 0/00 to 12/375 (SH: C/O R-Wall at Rds. 4/100 to 4/117.50).	499718 /-	10000/-	One Month	Rs.350/-
38	R/R damages on Shoghi Mehli road Km. 0/00 to 12/375 (SH: C/O B-Wall at Rds. 4/585 to 4/600 and 4/510 to 4/525).	395475 /-	8000/-	One Month	Rs.350/-
39	A/R & M/O Paoghatti to Shal chanog road Km. 0/00 to 7/330 (SH: Maintenance /clearing of drain, Trimming fo Grass and white wash in Km. 0/00 to 7/330).	245242 /-	5000/-	One Month	Rs.350/-
40	R/R damages on Chorti to Pahal road Km. 0/00 to 4/500 (SH: C/O B-Wall at Rds. 3/060 to 3/080).	259810 /-	5000/-	One Month	Rs.350/-

Followings documents should be attached with the application for tenders:-

- The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.

Executive Engineer
Shimla Rural Division
H.P.P.W.D. Dharni

Certificate

Certified that the tenders called vide this notice inviting tender for 40 (Fourty) jobs are due to exigencies/emergency of works in the larger public interest.


Executive Engineer
Shimla Rural Division
H.P.P.W.D. Dharni

Schedule Of Quantity

Name Of Work :- R/R damages on Badmain to Ghaini Road Km. 0/00 to 6/500
(SH:- C/O R/wall at RD 0/705 to 0/715)

Estimated Cost:- 2.29,888.00
Earnest Money:- 10,000.00
Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	14.60	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	5205
2	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand : 8 graded stone aggregate 20mm nominal size) and curing complete excluding the cost of form work in Foundation and plinth. including carriage of material The rate including octroi, royalty, Malkana toll tax, GST or any other taxes input or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	46.70	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	214820
3	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pie extending through the full with of the structures with slop of 1 (V):20(H) towards drawing face complete as per drawing and technical specification clauses 614.709.1204.3.7	24.00	Rmt.	190.00	Rupees One Hundred Ninety Only	Per running Metre	4560
4	Back filling filling behind abutment wing wall and retaining wall and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I. Including carriage of material within all leads and lifts.	6.30	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	5303
Total Rs.							229888
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhami. 

SCHEDULE OF QUANTITY

Name of Work: - Restoration of rain damages on Bhagar to Jagehdi road km 0/00 to 8/600 (SH:- Removal of slip in various Rds. Between km. 0/00 TO 8/600)

Estimated Cost: - Rs 495934 /- only
Earnest Money : - Rs. 10000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures	5		
1	2	3	4	5	6	7
1	Removal of land slide slip clearance in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops, & disposal of cut material / unserviceable materials upto dumping site arranged by the contractor at his own risk & cost with in all leads and lifts as per direction of Engineer-in-Charge & technical specification 302.3.5 and 1611.	3237.17 Cum	153.20	Rupees One Hundred Fifty Three and Paise Twenty Only	Per cubic metre	495934.00
0					Total:	495934.00

Amount Quoted by the Contractor in Percentage **Rs.**

Executive Engineer
Shimla Rural Division
HPPWD, Dharni

Name of Work:- Restoration of rain damages on Nehra Bhukho Road Km. 0/00 to 8/00 (Sh: Construction of Retaining wall in between Km. 6/370 to 6/383)

SCHEDULE OF QUANTITY

Estimated Cost - Rs 476452 /- only
Earnest Money : - Rs 10000 /-only
Time - One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount
1	2	3	4	5	6
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	17.16 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre 4005.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	19.63 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre 6998.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	95.03 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre 437138.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	46.80 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre 7956.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	24.18 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre 20355.00
0				Total:	476452.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

SCHEDULE OF QUANTITY						
Name of Work:- Preparation of DPR under Sub Division Jutogh : (i) CONSTRUCTION OF KUFRIDHAR TO VILLAGE SANOL SANOG. KM 0/00 TO 2/170, (2) CONSTRUCTION OF LINK ROAD TO KAFLED. KM 0/00 TO 1/075, (3) KIARTI GOSHALA TO MASHOBRA ROAD KM 0/00 TO 1/760, (4) CONSTRUCTION OF GHANAHATTI TO TIKKARI ROAD. KM 0/00 TO 5/350 and (5) CONSTRUCTION OF RAHAL TO SHILLY ROAD. KM 0/00 TO 1/670)				Estimated Cost - Rs 438750 /- only		
				Earnest Money : - Rs 9000 /-only		
				Time: - One Month		
S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
1	2	3	4	5	6	7
1	Preparation of Detailed Project Report of which includes following provision as mentioned below :- i) Topography survey by digital total station with two second accuracy showing all features on survey plan like trees, culverts, bridges, electric poles, telephone poles, hand pumps, school, Habitants villages etc. ii) Draw cross-sections at 15m intervals, L-sections and calculate the quantity of earthwork in standard format of autocad showing all layers of pavement components as applicable. iii) Preparation of survey plan showing all details as per MORD guidelines and specifications. If any correction/amendment will be desired by the office the same may be corrected as desired and directed by the Engineer-In-Charge complete in all respect. After approval of the same from the head office the same should be submitted in three fair copies and soft copy as per the requirement of this office and upto entire satisfaction of Engineer-In-Charge including all type of incidental charges.	12.03 Km.	30000.00	Rupees Thirty Thousand Only	Per Kilometer	360750.00
2	CBR test including gain size analysis, atterbergs limit, proctor compaction and CBR value upto the entire satisfaction of Engineer-In-Charge including all type of incidental charges.	26.00 Sample	3000.00	Rupees Three Thousand Only	Per Sample	78000.00
0					Total:	438750.00

Amount Quoted by the Contractor in Percentage	Rs.
---	-----

Note : (i) All the material will procured by the contractor him self.


Executive Engineer,
Shimla Rural Division,
HPPWD, Dhamsi

Schedule Of Quantity						Estimated Cost:- 3,36,440.00	
Name Of Work :- Restoration of Rain Damages on Chaba Makarcha road km. 0/00 to 1/500 (SH:- C/O R/Wall at Rd. 0/480 to 0/495)						Earnest Money:- 7500.00	
S.No Description of Work						Time:- One Months.	
1	2	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
		3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings including carriage of material within all leads and lifts.	19.50	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	4551
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	8.10	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2888
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand : 8 graded stone aggregate 20mm nominal size) and curing complete excluding the cost of form work in Foundation and plinth. including carriage of material The rate including octroi, royalty, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	65.33	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	300518
4	Back filling filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I. Including carriage of material within all leads and lifts.	24.75	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	20835
5	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pie extending through the full width of the structures with slop of 1 (V):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7	40.25	Rmt.	190.00	Rupees One Hundred Ninety Only	Per running Metre	7648
Total Rs.							336440
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhami.

Schedule Of Quantity						Estimated Cost:- 2,22,539.00	
Name Of Work :- Restoration of Rain Damages on Badmain Ghani road km. 0/00 to 6/500 (SH:- C/O R/wall at Rd 3/210 to 3/223)						Earnest Money:- 4500.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	12.22	Per cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	2852
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	5.07	Per cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1807
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand : 8 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form work in Foundation and plinth. including carriage of material The rate including octroi, royalty, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	43.29	Per cum	4700.00	Rupees Four Thousand Seven Hundred Only	Per cubic metre	203463
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pie extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7	27.50	Rmt.	190.00	Rupees One Hundred Ninety Only	Per running Metre	5225

5	Back filling filling behind abutment wing wall and retaning wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I.Including carriage of material within all leads and lifts.	10.92	Per cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	9192
	Total Rs.						222539
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhamsi. 

SCHEDULE OF QUANTITY

Name of work:- RRD on Badmain-Basantpur road km 0/000 to 7/000. (SH:- Dismantling of unsafe R/wall at RD 5/970 to 5/985)

Estimated cost:- 341,723.00

Earnest money:- 7000.00

Time:- One Month

Sr. No.	Description	Qty.	Unit	Rate in figure.	Rate in word.	Amount.
1	Demolishing cement concrete manually/ by mechanical means including disposal of material upto 10.00 kilometres lead & as per direction of Engineer - in charge. Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix).	286.20	Per cum	1194.00	Rupees One Thousand one hundred ninety four Only	341723.00
					Total:-	341723.00

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dham

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of Rain Damage on Removal of Slips/ Landslide at Various R.Ds Badmain Basantpur Road km 0/000 to 7/000 (SH:-						Estimated cost:-	149,963.00
						Earnest money:-	3000.00
						Time:-	One Month
Sr. No.	Description	Qty.	Unit	Rate in figure.	Rate in word.	Amount.	
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in all kind of soil/ ordinary rock by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	672.30	Per Sqm	223.06	Rupees Two Hundred Twenty Three and Paise six only	149963	
					Total:-	149963.00	
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
 Shimla Rural Division,
 HP,PWD, Dhani.

Schedule Of Quantity						Estimated Cost:- 4,44,482.00	
Name of Work :- Restoration of Rain Damages on Hiranagar Sharog road km 0/00 to 5/00 (SH:- Channelization of Culvet Discharge and removal of land slide at Rd. 0/080 to 0/085)						Earnest Money:- 9,200.00	
						Time:- One Months.	
Sr.No	Description of Work	No.of Qty.		Rate		Unit	Amount
1	2	3	4	5	6	7	8
				In figures	In words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	11.25	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	4011
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four milimeter) dia GI wire conforming to IS 280 (two hundred eighty) and IS.4826 (four thousand eight hundred twenty six) in 100 mm x 100 mm (one hundred into one hundred milimeter) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogramme) each as per drawing and technical specifications clause 1301, (one thousand three hundred one) including carriage of all labour equipment and material to various location through all modes of transportation in all leads lifts all incidental charge.	46.88	Cum	3620.00	Rupees Three Thousand Six Hundred Twenty Only	Per Cubic metre	169706
3	Removal of Inad slides / slips clearance, Removal of land slide in hilly area in ordinary Rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a all leads and lifts as per technical specification 302.3.5 and 1611 and as per the direction of Engineer in Charge.	660.00	Cum	410.25	Rupees Four Hundred Ten and Paise Twenty Five Only	Per Cubic metre	270765
	Total Rs.						444482
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami

SCHEDULE OF QUANTITY

Time -
Rate
figures

Amount Quoted by the Contractor in Percentage

Rs.

Executive Engineer
Shimla Rural Division
HPPWD, Dhamsi

Schedule Of Quantity

Name Of Work :- Geological Investigation for Construction of Govt. Polytechnic at Basantpur Tehsil Suni Distt Shimla HP

Estimated Cost:- 2,94,920.00
 Earnest Money:- 6,000.00
 Time:- One Months.

S.No	Description of Work	No. of Qty.	Rate		Unit	Amount
			In figures	In words		
1	Sub Soil Investigation in all type of soil/strata by drilling of bore holes of Nx Size 75 mm dia for investigation of soil rock conditions at site of work including mobilization and de- mobilization for drilling shifting of machinery to bore site making platform and water arrangement for drilling. The scope of work includes preservation of core including relevant tests and submission of geotechnical report of comlex site of work including carriage of materials within all leads and lift as per the direction of Engineer-in Charge.	40.40	Rmt	7300.00	Rupees Seven Thousand Three Hundred Only	Per running metre
	Total Rs.					294920
	Amount Quoted by the Contractor in Percentage					
	Note :- All the material will procured by the contractor him self					

Executive Engineer,
 Shimla Rural Division,
 HP, PWD, Dhami

Schedule Of Quantity							Estimated Cost:- 4,26,402.00
Name of Work :- Restoration of Rain damages on Dhanpur Sandoa road km. 0/00 to 8/100 (SH:- C/O B/wall at km. 4/285 to 4/304) (PCC)							Earnest Money:- 8,600.00
							Time:- One Months.
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
1	2	3	4	5	In figures	In words	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited) all earth work in cutting/excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings including carriage of material within all leads and lifts	12.73	Cum	199.00		Rupees One Hundred Ninety Nine Only	2533
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	36.29	Cum	356.50		Rupees Three Hundred Fifty Six and Paise Fifty Only	12937
3	Providing and laying concrete Mechanically mixed and vibrated nominal mix 1:4:8 (one cement: four sand: eight graded stone aggregate 20mm nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and hauling of materials in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	82.84	Cum	4800.00		Rupees Four Thousand Eight Hundred Only	397632
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pie extending through the full with of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7	70.00	No	190.00		Rupees One Hundred Ninety Only	13300
Total Rs.							426402
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhanpur

Name of Work:- Restoration of Rain Damages Hiranagar Sharog Road Km. 0/00 to 5/500 (Sh: Construction of Retaining wall at Rd. 0/670 to 0/681)

SCHEDULE OF QUANTITY

Estimated Cost - Rs 467472 /- only
Earnest Money - Rs 9000 /-only
Time - One Month

S. No.	Sub head and items of work	Qty	Rate figures	Unit	Amount		
1	2	3	4	5	6		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603 1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	15.84	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	3697.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	18.48	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	6588.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	95.81	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	440726.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	38.00	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	6460.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204 3 8 (I) Granular material. Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	11.88	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	10001.00
0					Total:		467472.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Name of Work:- Construction of Link Road from Kufridhar to Shanol Road Km. 0/00 to 2/120 (Sh: Construction of C.D. in Km. 1/850 with wing wall)

SCHEDULE OF QUANTITY

Estimated Cost - Rs 496365 /- only
Earnest Money - Rs 10000 /-only
Time - One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount
1	2	3	4	5	6
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603 1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	40.34 Cum	233 40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre 9415 00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203, P.C.C grade M 10, (i) C.C. 1:3:6 20 mm nominal mix (Twenty Milimetre size) concrete mix , including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	26.49 Cum	5000 00	Rupees Five Thousand Only	Per cubic metre 132450 00
3	Providing and laying reinforced cement concrete pipe NP2 as per design in single Row. Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108. (c) 900 mm dia	15.00 Rmt.	3616 00	Rupees Three Thousand Six Hundred Sixteen Only	Per Running Metre 54240 00
4	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	63.26 Cum	4600 00	Rupees Four Thousand Six Hundred Only	Per cubic metre 290996 00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	6.30 Cum	841 80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre 5303 00
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	23.30 Rmt.	170 00	Rupees One Hundred Seventy Only	Per Running Metre 3961 00
0					Total: 496365.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhamsi

Name of Work:- Construction of Link Road from Kufridhar to Shanol Road Km. 0/00 to 2/120 (Sh: Construction of W-Wall in Km. 1/841.65 to 1/847.65 & 1/852.35 to 1/858.35)

SCHEDULE OF QUANTITY

Estimated Cost - Rs 479766 /- only
Earnest Money - Rs 10000 /-only
Time - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	34.56 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	8066.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	85.92 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	30630.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	91.68 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	421728.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material. Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	12.96 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	10910.00
5	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification. Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	49.60 Rmt	170.00	Rupees One Hundred Seventy Only	Per Running Metre	8432.00
0					Total:	479766.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhamsi

Name of Work:- Construction of Link Road from Kufridhar to Shanol Road Km. 0/00 to 2/120 (Sh: Construction of C.D. in Km. 0/280 with wing wall)

SCHEDULE OF QUANTITY

Estimated Cost - Rs 204126 /- only
Earnest Money - Rs 4000 /-only
Time - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
1	2	3	4	5	6	7
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	49.85 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	17772.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203, P.C.C grade M 10, (i) C.C. 1:3:6 20 mm nominal mix (Twenty Milimetre size) concrete mix , including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	15.05 Cum	5200.00	Rupees Five Thousand Two Hundred Only	Per cubic metre	78260.00
3	Providing and laying reinforced cement concrete pipe NP2 as per design in single Row. Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 (c) 900 mm dia	7.50 Rmt.	3616.00	Rupees Three Thousand Six Hundred Sixteen Only	Per Running Metre	27120.00
4	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	15.83 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	72818.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204 3 8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	6.72 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	5657.00
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	14.70 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	2499.00
0					Total:	204126.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Name of Work:- Restoration of rain damages on Bangora Kalihatti Bastigunana Road Km. 0/00 to 11/675 (Sh: Construction of R-wall in between Km. 10/645 to 10/655)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 365481 /- only
Earnest Money: - Rs. 7000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount
1	2	3	4	5	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	13.20 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre 3081.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	15.10 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre 5383.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	73.10 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre 336260.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	30.00 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre 5100.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	18.60 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre 15657.00
0				Total:	365481.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhani

Schedule Of Quantity						Estimated Cost:- 4,60,900.00	
Name Of Work :- C/O link road from Shoghi Mehli Road to village Bhog. (SH:-						Earnest Money:- 10,000.00	
C/O RCC Box Culvert (1x 1. mtr) at Rd. 0/735)						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
1	2	3	4	In figures	In words	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	29.55	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	10535
2	Plain/ reinforced cement concrete in sub structure as per drawing and technical specification clauses 802,804,805, 806,807,1202 and 1204 PCC M-15 (1:2.5:5) including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	38.84	Cum	6750.00	Rupees Six Thousand Seven Hundred Fifty Only	Per Cubic metre	262170
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. Grade M-10 Nominal mix 1:3:6 (1 cement :3sand :6graded stone agg)including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	2.00	Cum	5600.00	Rupees Five Thousand Six Hundred Only	Per Cubic metre	11200
4	Providing and laying Precast Box Culvert having Size 1000x1000x150 mm with M35+ Grade concrete in a computer controlled weigh batch, using a water cement ratio of 0.2-0.35 , Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	7.50	Rmt	21830.00	Rupees Twenty One Thousand Eight Hundred Thirty Only	Per running metre	163725
5	Back filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I.Including carriage of material within all leads and lifts.	8.40	Cum	1150.00	Rupees One Thousand One Hundred Fifty Only	Per Cubic metre	9660
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	19.00	Nos	190	Rupees One Hundred Ninety Only	Each	3610
Total Rs.							460900
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD. Dham.

Draft Schedule Of Quantity						Estimated Cost:- 4,60,900.00	
Name Of Work :- C/O link road from Shoghi Mehli Road to village Bhog. (SH:- C/O RCC Box Culvert (1x 1. mtr) at Rd. 0/840)						Earnest Money:- 10,000.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
1	2	3	4	In figures	In words	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	29.55	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	10535
2	Plain/ reinforced cement concrete in sub structure as per drawing and technical specification clauses 802,804,805, 806,807,1202 and 1204 PCC M-15 (1:2.5:5) including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	38.84	Cum	6750.00	Rupees Six Thousand Seven Hundred Fifty Only	Per Cubic metre	262170
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. Grade M-10 Nominal mix 1:3:6 (1 cement :3sand :6graded stone agg.)including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	2.00	Cum	5600.00	Rupees Five Thousand Six Hundred Only	Per Cubic metre	11200
4	Providing and laying Precast Box Culvert having Size 1000x1000x150 mm with M35+ Grade concrete in a computer controlled weigh batch, using a water cement ratio of 0.2-0.35 , Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	7.50	Rmt	21830.00	Rupees Twenty One Thousand Eight Hundred Thirty Only	Per running metre	163725
5	Back filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I.Including carriage of material within all leads and lifts.	8.40	Cum	1150.00	Rupees One Thousand One Hundred Fifty Only	Per Cubic metre	9660
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	19.00	Nos	190	Rupees One Hundred Ninety Only	Each	3610
Total Rs.							460900

DNIT Approved for Rs. 4,60,900.00 /- only (Rupees Four lacs Sixty Thousand Nine Hundred) Only for the year 2025-26 entred for DNIT Reg.
Sr.No. 552

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Schedule Of Quantity						Estimated Cost:- 2,80,906.00	
Name Of Work :- A/R & M/O Tutikandi Sheelgaon via Kiari Road km. 0/00 to 3/870 (SH:- C/O Breast wall at Rd 3/765 to 3/780 for Supporting Playground)						Earnest Money:- 5,700.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
1	2	3	4	In figures	In words	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	16.20	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic metre	3781
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	24.30	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	8663
3	Providing and Laying cement concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause 802, 803, 1202 & 1203 in Cement Concrete 14:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	57.37	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per Cubic metre	263902
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	24.00	No	190.00	Rupees One Hundred Ninety Only	Each	4560
Total Rs.							280906
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhani

Schedule Of Quantity						Estimated Cost:- 3,58,386.00	
Name Of Work :- R/R Damages on Bag to Kangri road km 0/00 to 7/250.(SH:- C/O Wire crate B/wall at Rd 5/970 to 6/000)						Earnest Money:- 7,200.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
1	2	3	4	In figures	In words	7	8
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	36.00	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	12834
2	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I. wire conforming to IS:280 and IS: 4826 in 100mmx100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25Kg each as per drawing and technical specifications Clause 1301 including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	93.90	Cum	3680.00	Rupees Three Thousand Six Hundred Eighty Only	Per Cubic metre	345552
Total Rs.							358386
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Name of Work:- Construction of Chailly Khurd Road Km. 0/00 to 1/350 (Sh: Construction of R-wall in between Km. 0/290 to 0/300)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 303059 /- only
Earnest Money : - Rs. 6000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	14.40 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	3361.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	16.80 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	5989.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	60.75 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	279450.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	30.40 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	5168.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	10.80 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	9091.00
0					Total:	303059.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Name of Work:- Construction of Chailly Khurd Road Km. 0/00 to 1/350 (Sh: Construction of R-wall in between Km. 1/270 to 1/282)

SCHEDULE OF QUANTITY

Estimated Cost - Rs 363930 /- only
Earnest Money : - Rs 7000 /-only
Time - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	17.28 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	4033.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	20.16 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	7187.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	72.90 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	335340.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification. Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	38.00 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	6460.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	12.96 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	10910.00
0					Total:	363930.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Schedule Of Quantity						Estimated Cost:- 4,49,392.00	
Name Of Work :- A/R & M/O Slapper -Tattapani-Sunni-Luhri road , Portion km. 86/000 to 104/000 (SH:- C/o R/wall in between km. 96/075 to 96/102)						Earnest Money:- 10,000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	26.46	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per Cubic metre	5266
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	21.87	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	7797
3	Providing and laying concrete for plain reinforcement concrete in open foundation & plinth complete as per drawing and technical specification clause 802, 803, 1202 & 1203 including carriage of materials as per the directions of Engineer-in-charge. (i) Cement Concrete 1:3:6 nominal mix (1 Cement 3 sand: 6 graded crushed stone aggregate 20mm nominal size).	79.92	Cum	5200.00	Rupees Five Thousand Two Hundred Only	Per Cubic metre	415584
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	41.00	No	190.00	Rupees One Hundred Ninety Only	Each	7790
5	Back filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I.Including carriage of material within all leads and lifts.	15.39	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per Cubic metre	12955
Total Rs.							449392
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer.
Shimla Rural Division.
HP.PWD. Dhami.

Schedule Of Quantity						Estimated Cost:- 4,05,824.00	
Name Of Work :- Restoration of Rain Damages on Sal to Karyali road km. 0/00 to 3/00 (SH:- C/o B/wall at km 0/710 to 0/740) (PCC)						Earnest Money:- 8,200.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	23.10	Cum	193.55	Rupees One Hundred Ninety Three and Paise Fifty Five Only	Per Cubic metre	4471
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	13.50	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	4813
3	Providing and Laying cement concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause 802, 803, 1202 & 1203 in Cement Concrete 14:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	78.60	Cum	4900.00	Rupees Four Thousand Nine Hundred Only	Per Cubic metre	385140
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification. Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	60.00	No	190.00	Rupees One Hundred Ninety Only	Each	11400
Total Rs.							405824
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP.PWD, Dharmu

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain Damages on Paughatti to Shal Chanog Road Km. 0/00 to 7/330 (Sh: Construction R-wall at Rd. 7/140 to 7/148.50)

Estimated Cost - Rs 463161 / only
Earnest Money - Rs 9000 / only

S. No.	Sub head and items of work	Qty		Rate figures	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	10.20	Cum	233.40	Per cubic metre	2381.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer in Charge	30.60	Cum	356.50	Per cubic metre	10909.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	93.03	Cum	4600.00	Per cubic metre	427938.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 (i) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	20.40	Cum	841.80	Per cubic metre	17173.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge	28.00	Rmt	170.00	Per Running Metre	4760.00
0					Total:	463161.00
Amount Quoted by the Contractor in Percentage						Rs.

Note : (i) All the material will procured by the contractor him self.

**Executive Engineer,
Shirga Rural Division,
UPPWO, Dhule**

SCHEDULE OF QUANTITY

Name of Work:- Restoraton of rain damages on Ghanahatti Kalihatti Arki Road Km. 0/00 to 8/060 (Sh: Construction of R-wall at Rd. 0/060 to 0/070)

Estimated Cost: - Rs 283820 /- only
Earnest Money : - Rs. 6000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
			4	5		
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	16.20 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	3781.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	19.40 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	6916.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	56.80 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	261280.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	6.90 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	5808.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	35.50 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	6035.00
0					Total:	283820.00

Amount Quoted by the Contractor in Percentage	Rs.
--	------------

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Name of Work:- Restoration of rain damages on Khel Ka Chaura to Baggi Road Km. 10/00 to 11/500 (Sh: Construction of R-wall at Rd. 11/150 to 11/170)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 351423 /- only
Earnest Money : - Rs. 7000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603 1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	8.80 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	2054.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	28.80 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	10267.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	70.96 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	326416.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	7.80 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	6566.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	36.00 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	6120.00
0					Total:	351423.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Name of Work:- Restoration of Rain Damages on Dargi Macharyana Judloo Road Km. 0/00 to 11/900 (Sh: Construction of Retaining wall at Rd. 0/720 to 0/733)

SCHEDULE OF QUANTITY

Estimated Cost - Rs 492892 /- only
Earnest Money - Rs 10000 /-only
Time - One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount
1	2	3	4	5	6
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	17.16 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre 4005.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	19.63 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre 6998.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	97.85 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre 450110.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	24.18 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre 20355.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	67.20 Rmt	170.00	Rupees One Hundred Seventy Only	Per Running Metre 11424.00
0				Total:	492892.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Name of Work:- Restoration of Rain Damages Galog Nehra Okhroo Road Km. 0/00 to 11/135 (Sh: Construction of Retaining wall at Rd. 2/ 396 to 2/408)

SCHEDULE OF QUANTITY

Estimated Cost - Rs 306039 /- only
Earnest Money - Rs. 6000 /-only
Time - One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount
1	2	3	4	5	6
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	14.28 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre 3333.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	22.18 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre 7907.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	61.17 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre 281382.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8. (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	8.87 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre 7467.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	35.00 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre 5950.00
0					
				Total:	306039.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Schedule Of Quantity						Estimated Cost:- 3,44,056.00	
Name of Work :- Restoration of Rain Damages on Hiranagar Sharog road km 0/00 to 5/00 (SH:- Channelization of Culvet Discharge with wire crate at Rd. 0/080 to 0/085)						Earnest Money:- 6,900.00	
						Time:- One Months.	
Sr.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
		3	4	5	6	7	8
1	2						
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	13.13	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	4681
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four milimeter) dia GI wire conforming to IS 280 (two hundred eighty) and IS.4826 (four thousand eight hundred twenty six) in 100 mm x 100 mm (one hundred into one hundred milimeter) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogramme) each as per drawing and technical specifications clause 1301, (one thousand three hundred one) including carriage of all labour equipment and material to various location through all modes of transportation in all leads lifts all incidental charge.	93.75	Cum	3620.00	Rupees Three Thousand Six Hundred Twenty Only	Per Cubic metre	339375
							344056
	Total Rs.						
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Link Road Totu Bazzar Km. 0/00 to 1/020 (Sh: Construction of Retaining wall at Rd. 0/013 to 0/028)

Estimated Cost: - Rs 455258 /- only
Earnest Money - Rs. 9000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount	
1	2	3	4	5	6	
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603 1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	21.60 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	5041.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	25.20 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	8984.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	91.13 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	419198.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	49.40 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	8398.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	16.20 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	13637.00
0					Total:	455258.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain Damages Kufridhar Rain shelter to village Kufridhar G.P. Ghanahatti in Km. 0/00 to 0/645
(Sh: Construction of Retaining wall at Rd. 0/00 to 0/023)

Estimated Cost - Rs 302466 /- only
 Earnest Money - Rs 6000 /-only
 Time - One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount
1	2	3	4	5	6
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	12.42 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre 2899.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge	21.39 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre 7626.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	59.80 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre 275080.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	11.73 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre 9874.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	41.10 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre 6987.00
0				Total:	302466.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD, Dhamsi

SCHEDULE OF QUANTITY

Name of Work:- Annual Repair & Maintenance of Shimla Nalagarh Road Km. 7/00 to 22/000 (Sh:Repair of earthen shoulder, Trimming of Grass and Clearing of Drain in Km. 10/00 to 22/000)

Estimated Cost: - Rs 496800 /- only
Earnest Money : - Rs. 10000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
1	2	3	4	5	6	7
1	Maintenance of Earthen shoulder (stripping of excess soil) , Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 as per the direction of Engineer-in-Charge.	14400.00 Sqm	16.50	Rupees Sixteen and Paise Fifty Only	Per Square Meter	237600.00
2	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907 including carriage of material upto all leads and lifts as per the direction of Engineer-in-charge.	12000.00 Rmt.	4.00	Rupees Four Only	Per Running Meter	48000.00
3	Trimming of grass and weeds from shoulder / berms and disposing off the same to suitable locations as per technical specifications clause 1914 including carriage of material within all leads and lifts as per the directions of Engineer-in-charge.	52800.00 Sqm	4.00	Rupees Four Only	Per Square Meter	211200.00
0.00					Total:	496800.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dharmi

Schedule Of Quantity

Name Of Work :- Restoration of Rain on Ambulance road from Taradevi Malog Zalgi road km 0/00 to 0/470 (SH:- Providing and fixing steel railing in Km 0/00 to 0/200 (Balance work)

Estimated Cost:- 1,86,913.00

Earnest Money:- 3,800.00

Time:- One Month.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge	13.33	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	4752
2	Providing and laying cement concrete 1:2:4 (one cement: Two Sand: four graded stone Agg 20mm size) for plain/reinforced concrete in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 Including carriage of material within leads and lifts	21.58	Cum	5900.00	Rupees Five Thousand Nine Hundred Only	Per Cubic metre	127322
3	Structural Steel work welded in built up sections/ framed work, including hoisting, fixing in position and applying a priming coat of Sproved steel (a) In gratings, frames, guard bar, ladder, railings, kels, gates and similar works. The rate includes, octroi, Malkhana Tall tax, Goods and Service Tax, building and other construction worker welfare cess royalty or any other tax, levy or cess in respect of hul for or output by this contract shall be payable by the contractor Government shall not entertain any claim whatsoever in this pect of the same	519.80	Kg	105.50	Rupees One Hundred Five and Paise Fifty Only	Per Killogram	54839
Total Rs.							186913
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhamsi

Schedule Of Quantity						Estimated Cost:- 1,75,731.00	
Name Of Work :- Restoration of Rain Damages on Shoghi Mehli road km 0/00 to 12/375 (SH:- C/O B/wall at Rde 6/765 to 6/775)						Earnest Money:- 3,600.00	
						Time:- One Month.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
1	2	3	4	In figures	In words	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	21.30	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic metre	4971
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	3.90	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	1390
3	Providing and Laying cement concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 14:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	36.20	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per Cubic metre	166520
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	15.00	Nos	190.00	Rupees One Hundred Ninety Only	Each	2850
Total Rs.							175731
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dham

Schedule Of Quantity						Estimated Cost:- 4,99,718.00	
Name Of Work :- Restoration of Rain, or Shoghi Mehli road km 0/00 to 12/380 (SH:- SH:- C/O R/wall at Rd 4/100 to 4/117.50)						Earnest Money:- 10,000.00	
						Time:- One Month.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
1	2	3	4	In figures	In words	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge	11.03	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic metre	2574
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	41.48	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	14788
3	Providing and Laying cement concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 14:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	94.85	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per Cubic metre	455280
4	Back filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I. Including carriage of material within all leads and lifts	24.68	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per Cubic metre	20776
5	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	35.00	Nos	180.00	Rupees One Hundred Eighty Only	Each	6300
Total Rs.							499718
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhamsi.

Schedule Of Quantity						Estimated Cost:- 3,95,475.00	
Name Of Work :- Restoration of Rain Damages on Shoghi Mehli Bypass Road km 0/00 to 12/375 (SH:- C/O B/wall at Rd 4/585 to 4/600 and 4/510 to 4/525)						Earnest Money:- 8,000.00	
						Time:- One Month.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
1	2	3	4	In figures	In words	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	30.00	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic metre	7002
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	21.30	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	7593
3	Providing and Laying cement concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 14:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	78.00	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per Cubic metre	374400
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	36.00	Nos	180.00	Rupees One Hundred Eighty Only	Each	6480
Total Rs.							395475
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dharm.

SCHEDULE OF QUANTITY

Name of Work:- Annual Repair & Maintenance of Paoghatti to Shal Chanog Km. 0/00 to 7/330 (Sh: Maintenance / clearing of drain, Trimming of Grass and white wash in Km. 0/00 to 7/330)

Estimated Cost: - Rs 245242 /- only
Earnest Money : - Rs. 5000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount	
1	2	3	4	5	6	
1	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907 including carriage of material upto all leads and lifts as per the direction of Engineer-in-charge.	8035.00 Rmt.	4.00	Rupees Four Only	Per Running Meter	32140.00
2	Trimming of grass and weeds from shoulder / berms and disposing off the same to suitable locations as per technical specifications clause 1914 including carriage of material within all leads and lifts as per the directions of Engineer-in-charge.	33747.00 Sqm	4.00	Rupees Four Only	Per Square Meter	134988.00
3	White washing with lime on undecorated wall surface two coats to give an even shade includign throughly brooming the surface to remove all dirt dust mortar dirt and other foreign matter including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	3254.75 Sqm	24.00	Rupees Twenty Four Only	Per Square Meter	78114.00
0.00					Total:	245242.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dharni

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain Damages on Chorti to Pahal Road Km. 0/00 to 4/500 (Sh: Construction of Breast wall at Rd.3/060 to 3/080)

Estimated Cost: - Rs 259810 /- only
Earnest Money : - Rs. 5000 /-only
Time - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	10.80 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	2521.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	24.80 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	8841.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	52.00 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	239200.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	54.40 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	9248.00
0					Total:	259810.00

Amount Quoted by the Contractor in Percentage	Rs.
--	------------

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhami