OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG
PH: 01907-222229 Fax: 222229 , e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2024- 10267 Dated:- 11-12-2025

To

The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2.

Subject :- Regarding publication of Tender on departmental site.

With reference to the notification issued by the Secretary(PW) to the Government of Himachal Pradesh No. P BW(B)A(3)1/2024 dated 03.01.2024 and PBW-B-F0(2)/3/2024-284016 dated 18.07.2025, enclosed please find herewith the copy of Notice Inviting Tender for the loading on departmental web-site as

Certified that the works mentioned in the Tender Notice are urgent in nature and in coordination with the Disaster Management Act, 2005 Section 24 (i).

Encl:- As above.

Executive Engineer,
B&R Division,
HP PWD Karsog

OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG
PH: 01907-222229 Fax: 222229 , E-mail : ee-kar-hp@nic.in

Notice inviting tender

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **20.12.2025 upto 11.00** AM and shall be opened on the same day at **12.00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 19.12.2025** for which the application should reach in this office **upto 1.00 PM 19.12.2025.**

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening o f tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	R/R damages on Chholdhar Panout Dehra road Km. 0/00 to 3/00 (SH:- Removal of slips, C/o unlined drain and maintenance of berm at	99,225/-	2,000/-	One month	350/-
2	R/R damages on link road from Kelodhar to Doghra in GP Richhni Km. 0/00 to 1/700 (SH:- Removal of slips at various RDs in Km. 0/00 to 1/700)	99,762/-	2,000/-	Two month	350/-
3	R/R damages on Karsog Kunhu road KM. 0/00 to 10/00 (SH:- Removal of slips, maintenance of berms & C/o unlined drain in Km. 0/00 to 10/00)	99,498/-	2,000/-	Two months	350/-
4	R/R damages on Kao Kanda road via Narol (SH:- Removal of slips in KM. 0/00 to 3/00)	98,532/-	2,000/-	Two month	350/-
5	A/R & M/O Rest House at Karsog Distt. Mandi H.P. (SH:- Providing and supplying of 8 seater dining table including chair for rest house Karsog)	99,200/-	2,000/-	One month	350/-
6	A/R & M/O Rest House at Karsog Distt. Mandi H.P. (SH:- Providing and supplying of Easy Seating Chair and 12mm thick glass top for dining table for Rest House Karsog)	99,500/-	2,000/-	One month	350/-
7	R/R damages on link road to village Dachhain Km. 0/00 to 2/500 (SH:- Protection work for abutment of slab culvert at RD 1/435) Job No. 3	99,106/-	2,000/-	One month	350/-

8	R/R damages on Chndi Dachhain road Km. 0/00 to 8/435 (SH:- P/L 900 mm dia Hume pipe at RD 6/210)	96,638/-	2,000/-	One month	350/-
9	R/R damages on Kelodhar Chhatri road Km. 0/00 to 19/00, Sainj Sainjeli via Gannu road Km. 0/00 to 5/500, Seri Shout road KM. 0/00 to 19/00 (SH:- Hiring of Air Compressor for blasting) under PDNA	98,952/-	2,000/-	One month	350/-
10	R/R damages on Bhanthal Punni road KM. 0/00 to 3/00 (SH:- Removal of slips and maintenance of berms in KM. 1/500 to 3/00)	99,528/-	2,000/-	One month	350/-
11	R/R damages on Latheri Khdkan road Km. 0/00 to 2/00 (SH:- C/o unlined drain and maintenance of berm in KM. 0/00 to 2/00)	99,721/-	2,000/-	One month	350/-
12	R/R damages on Seri Shout road Km. 0/00 to 19/00 (SH:- Removal of land slide slips and maintenance of earthen shoulders at various RDs in Km. 16/00 to 19/00)	99,339/-	2,000/-	One month	350/-
13	R/R damages on Seri Shout road Km. 0/00 to 19/00 (SH:- Removal of land slide slips and maintenance of earthen shoulders at various RDs in Km. 10/00 to 13/00)	99, 977/-	2,000/-	One month	350/-
14	R/R damages on Kotlu Katanda road Km. 0/00 to 19/00 (SH:- removal of slips and maintenance of berms in Km. 9/00 to 19/00)	99,634/-	2,000/-	One month	350/-
15	R/R damages on Kotlu Katanda road Km. 0/00 to 19/00 (SH:- Removal of slips and maintenance of berms in Km. 0/00 to 9/00)	99,715/-	2,000/-	One month	350/-
16	R/R damages on Punni Naswar road Km. 0/00 to 3/300 (SH:- C/o unlined drain and maintenance of berm at various RDs) under PDNA 2023	97,182/-	2,000/-	One month	350/-
17	R/R damages on Lalag to Kalehni road Km. 0/00 to 6/00 (SH:- C/o maintenance of berm in KM. 0/00 to 3/00) under PDNA 2023	97,875/-	2,000/-	One month	350/-
18	R/R damages on Rela to Saryogi via Badghat in GP Sanarli Km. 0/00 to 3/00(SH:- Removal of slips, C/o unlined drain and maintenance of berms in Km. 0/00 to 1/500)	99,924/-	2,000/-	One month	350/-
19	R/R damages on Rela to Saryogi via Badghat in GP Sanarli Km. 0/00 to 3/00(SH:- Removal of slips, C/o unlined drain and maintenance of berms in Km. 0/500 to 3/00)	99,345/-	2,000/-	One month	350/-
20	R/R damages on Khaneol to Sidh Chausi road Km. 0/00 to 7/00 (SH:- Removal of slips and maintenance of earthen shoulders at various RDs in Km. 0/00 to 2/500)	99,704/-	2,000/-	One month	350/-
21	R/R damages on Khaneol to Sidh Chaasi road Km. 0/00 to 7/00 (SH:- Removal of land slide and maintenance of earthen shoulders at various RDs in Km. 3/00 to 5/00)	99,827/-	2,000/-	One month	350/-
22	R/R damages on Kelodhar Chhatri road Km. 0/00 to 19/00 (SH:- Removal of land slide slips and maintenance of earthen shoulders at various RDs	99,229/-	2,000/-	One month	350/-

	in Km. 10/00 to 14/00)				
23	R/R damages on Karsog to Kanda road KM. 0/00 to 10/00 (SH:- Maintenance of berms and C/o unlined drain in KM. 0/00 to 10/00)	99,420/-	2,000/-	One month	350/-

TERMS & CONDITIONS:-

1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act.
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
9. As per Govt. Notification **PW/CTR/32-20Genl Inst-CPWD/2020-37996-38095 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.**

Executive Engineer
B&R Division
HPPWD Karsog

No. PW-E-Tender-NIT/2025-26- 10241-46 Dated:- 11-12-2025

1. All the Assistant Engineers, working under this Division.
2. Copy to Drawing & Account Branch.
3. Notice board of this office.

Executive Engineer,
B&R Division,
HP PWD Karsog

Percentage Schedule of Quantity

Estimated Cost	99225
Earnest Money	2000
Time	One month

Name of Work:- R/R Damages on Chhouldhar Panout Dehra road Km. 0/00 to 3/00(SH:- Removal of slips, C/O unlined drain & Maintenance of bjerm at various RD's)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Construction of unlined surface drain of average cross-section area 0.20 sqm in soil specified line grade, level and dimension. Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	675.00	Per Running Meter	23.80	16065.00	Rupees Sixteen Thousand Sixty Five and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	3780.00	Per Square Meter	22.00	83160.00	Rupees Eighty Three Thousand One Hundred Sixty and Paise Zero Only
					99225.00	
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	99762
Earnest Money	2000
Time	Two Months

Name of Work:- R/R Damages on Link road from Kelodhar to Doghra in G.P. Richni Km 0/00 to 1/700(SH:- Removal of land slide slips at various RD's in km 0/00 to 1/700).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST	Toatal Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	831.35	Per Cubic Meter	120.00	99762.00	Rupees Ninety Nine Thousand Seven Hundred Sixty Two and Paise Zero Only
Total in Figures					**99762.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	99498
Earnest Money	2000
Time	Two Months

Name of Work:- R/R Damages on Karsog Kunhu road Km. 0/00 to 10/00(SH:- Removal of slips, Maintenance of berms & C/O Unlined drain in Km 0/00 to 10/00),

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Removal of land slide slip clearance Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lift upto 1.5 m (one point five metre) and lead upto 1000m (one thousand metre) as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	801.90	Per Cubic Meter	120.00	96228.00	Rupees Ninety Six Thousand Two Hundred Twenty Eight and Paise Zero Only
2	Construction of unlined surface drain of average cross-section area 0.20 sqm(zero point twenty square metre) in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	150.00	Per Running Meter	21.80	3270.00	Rupees Three Thousand Two Hundred Seventy and Paise Zero Only
					99498.00	
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	98532
Earnest Money	2000
Time	Two Months

Name of Work:- R/R Damages on Kao Kanda road via Narol (SH:- Removal of slips in Km 0/00 to 03/00),

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Removal of land slide slip clearance Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lift upto 1.5 m (one point five metre) and lead upto 1000m (one thousand metre) as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	739.35	Per Cubic Meter	120.00	88722.00	Rupees Eighty Eight Thousand Seven Hundred Twenty Two and Paise Zero Only
2	Construction of unlined surface drain of average cross-section area 0.20 sqm(zero point twenty square metre) in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	450.00	Per Running Meter	21.80	9810.00	Rupees Nine Thousand Eight Hundred Ten and Paise Zero Only
					98532.00	
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99200
Earnest Money 2000
Time One Month

Name of Work:- A/R & M/O Rest House at Karsog Tehsil Karsog Distt. Mandi (HP) (SH:- Providing and supplying of 8 seater dinning table including chair for rest house Karsog)

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Providing and supplying of dinning table frame made of metal teak wood legs I shade of 85 x 85 mm (eighty five into eighty five millimeter) in comination with 25 mm Sq. (twenty five millimeter squre) and 65 x 25 mm (sixty five into twenty five millimeter) rectangular pipe on top. the top made of 25 mm (twenty five millimeter) thick teak wood, the bale frame duly painted and polished in walnut wooden shade dinning chair frame made of teak wood in combination of 1.1/4 " sq, 1" sq having 32 (thirty two) density50 mm (fifty millimeter) chusionon seat frame made of soft wood provided with 75 mm x 18 mm (seventy five millimeter into eighteen millimeter) wood strip on top duly fitted with pipe fram and below wooden strip having cushioned back frame made with teak wood and chusion with 35 mm (thirty five millimeter) both seat and back upholstered with best qualtiy upholstered cloth and as per direction of Engineer-in-Charge including of carriage of materail within all leads, lifts and other incidentals.	1.00	Each	99200.00	99200.00	Rupees Ninety Nine Thousand Two Hundred and Paise Zero Only
					99200.00	
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99500
Earnest Money 2000
Time One Month

Name of Work:- A/R & M/O Rest House at Karsog Tehsil Karsog Distt. Mandi (HP) (SH:- Providing and supplying of Easy seating chair and 12 mm thick glass top for dinning table for est house karsog)

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Providing and supplying of Easy seating chair wiuth seat, size 450 x 450 mm (four hundred fifty into four hundred fifty millimeter) and having teak wood designer arms and frame made in combination of 1.1/4" sq. , 1" sq. having 32 (thirty two density) density 50 mm (fifty millimeter) chusionon seat frame made of soft wood provided with 75 mm x 18 mm (seventy five millimeter into eighteen millimeter) wood stip on toip duly fitted with pipe frame and below wooden strip having cushioned back frame made with teak wood and chusion with 35 mm both seat and back upholstered with best quality upholstered clothand as per direction of Engineer-in-Charge including of carriage of materail within all leads, lifts and other incidentals.	11.00	Each	7500.00	82500.00	Rupees Eighty Two Thousand Five Hundred and Paise Zero Only
2	Providing and fixing 12 mm (twelve millimeter) thick Glass top 8" x 4" (eight inch into four inch) Dinning table and as per direction of Engineer-in-Charge including of carriage of materail within all leads, lifts and other incidentals.	1.00	Each	17000.00	17000.00	Rupees Seventeen Thousand and Paise Zero Only
					99500.00	
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99106
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Link road to Village Dachhain Km. 0/00 to 2/500 (SH:- Protection work for abutment of slab culvert at RD 1/435) Job No.3

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Providing and laying concrete for plain/rainforcement concrete 1:2:4 (one cement : two sand : four graded stone aggregae) in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	10.44	Per Cubic Meter	7036.00	73456.00	Rupees Seventy Three Thousand Four Hundred Fifty Six and Paise Zero Only
2	Supplying and placing HYSD bars reinforcement(Fe 415) in substructure complete as per drawing and specification clasue 1002, 1005, 1010 & 1202 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	270.00	Per Kilo Gram	95.00	25650.00	Rupees Twenty Five Thousand Six Hundred Fifty and Paise Zero Only
Total in Figures					99106.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 96638
Earnest Money 2000
Time One Month

ame of Work:-R/R Damage on Chindi Dachhain Road Km 0/00 to 8/435 (SH:- P/L 900 mm dia Hume pipe at RD 6/210)

r. No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	38.25	Per Cubic Metre	390.20	14925.00	Rupees Fourteen Thousand Nine Hundred Twenty Five and Paise Zero Only
2	Providing and laying Reinforced Cement Conrete Pipe NP2 for culverts on first classs bedding of granular material in single row including fixing collar with cement mortor 1:2 but excluding excavation protection works, back filling, concrete and masonry work in head walls and parapets Clause 1106. as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	15.00	Per Runnig Metre	5447.50	81713.00	Rupees Eighty One Thousand Seven Hundred Thirteen and Paise Zero Only
otal in Figures					96638.00	
uoted Rate in Figures			Select		0.00	
uoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98952
Earnest Money 2000
Time One Month

Name of work : - R/R Damage on Kelodhar Chhhatri Road Km 0/00 to 19/00, Sainj Sainjali via. Gannu Road Km 0/00 to 5/500, Seri Shout Road Km 0/00 to 19/00. (SH.:- Hiring of air Compressor for Blasting) under PDNA

Sr.No.	Sub-Head and items of works.	Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all Taxes including GST in Rs.	Total Amount with all Taxes including GST in Rs. in Words
1	Hiring of air compressor with tractor and jack hammer for hole cutting in all kind of soil fuel ,oil lubricants and wages of operating staff, any repair during operation and shifting of machinery from on place to other, required location will be carried out by the owner on his own risk and cost .Actually working hours will be deployed at any location as desired by the Engineer-in charge.Any loss to the public/private property or any accidents etc. should be the absolute responsibility of the owner/contractor which shall have to be fully compensated by him in all cases. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	21.00	Per Day	4712.00	98952.00	Rupees Ninety Eight Thousand Nine Hundred Fifty Two and Paise Zero Only
	Total in Figures				**98952.00**	
	Quoted Rate in Figures					
	Quoted Rate in Words					

Executive Engineer
Karsog Division
HPPWD Karsog

Percentage Schedule Of Quantity

Estimated Cost 99528
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Bhanthal Punni Road Km. 0/00 to 3/00 (SH:- Removal of Slips & Maintenance of berm in Km 1/500 to 3/0).

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Toatal Amount	Toatal Amount with all taxes including GST In
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	372.15	Per Cubic Metre	120.00	44658.00	Rupees Forty Four Thousand Six Hundred Fifty Eight and Paise Zero Only
2	Construction of unlined surface drain of average cross-section area 0.20 sqm in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	600.00	Per Running Metre	23.80	14280.00	Rupees Fourteen Thousand Two Hundred Eighty and Paise Zero Only
3	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	1845.00	Per Square Metre	22.00	40590.00	Rupees Forty Thousand Five Hundred Ninety and Paise Zero Only
Total in Figures					**99528.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99721
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Latheri Khadkan road Km 0/00 to 2/00 (SH:- C/O unlined drain & maintenance of berm in Km 0/00 to 2/00).

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	296.11	Per Cubic Meter	120.00	35533.00	Rupees Thirty Five Thousand Five Hundred Thirty Three and Paise Zero Only
2	Construction of unlined surface drain of average cross-section area 0.20 sqm(zero point twenty square metre) in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per direction of Engineer- in -charge with in all lead and lifts and other incidentals.	570.00	Per Running Meter	23.80	13566.00	Rupees Thirteen Thousand Five Hundred Sixty Six and Paise Zero Only
3	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto 1000m (one thousand metre) as per technical specification clause 1903 as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	2301.00	Per Square Meter	22.00	50622.00	Rupees Fifty Thousand Six Hundred Twenty Two and Paise Zero Only
					99721.00	
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	99339
Earnest Money	2000
Time	One Month

Name of Work:- R/R Damages on Seri Shout road Km 0/00 to 19/00(SH:- Removal of land slide slips & Maintanace of Earthen Shoulders at various RD's in km 16/00 to 19/00).

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	646.20	Per Cubic Meter	120.00	77544.00	Rupees Seventy Seven Thousand Five Hundred Forty Four and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto 1000m (one thousand metre) as per technical specification clause 1903 as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	997.50	Per Square Meter	21.85	21795.00	Rupees Twenty One Thousand Seven Hundred Ninety Five and Paise Zero Only
					99339.00	
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	99977
Earnest Money	2000
Time	One Month

Name of Work:- R/R Damages on Seri Shout road Km 0/00 to 19/00(SH:- Removal of land slide slips & Maintanace of Earthen Shoulders at various RD's in km 10/00 to 13/00).

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	737.55	Per Cubic Meter	120.00	88506.00	Rupees Eighty Eight Thousand Five Hundred Six and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto 1000m (one thousand metre) as per technical specification clause 1903 as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	525.00	Per Square Meter	21.85	11471.00	Rupees Eleven Thousand Four Hundred Seventy One and Paise Zero Only
					99977.00	
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	99634
Earnest Money	2000
Time	One Month

Name of Work:- R/R Damages on Kotlu Katanda road Km. 0/00 to 19/00 (SH:- Removal of slips and Maintenance of berms in Km 9/00 to 19/00).

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Removal of land slide slip clearance Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lift upto 1.5 m (one point five metre) and lead upto 1000m (one thousand metre) as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	726.33	Per Cubic Meter	120.00	87160.00	Rupees Eighty Seven Thousand One Hundred Sixty and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto 1000m (one thousand metre) as per technical specification clause 1903 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals	567.00	Per Square Meter	22.00	12474.00	Rupees Twelve Thousand Four Hundred Seventy Four and Paise Zero Only
					99634.00	
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	99715
Earnest Money	2000
Time	One Month

Name of Work:- R/R Damages on Kotlu Katanda road Km. 0/00 to 19/00 (SH:- Removal of slips and Maintenance of berms in Km 0/00 to 9/00).

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Removal of land slide slip clearance Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lift upto 1.5 m (one point five metre) and lead upto 1000m (one thousand metre) as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	739.38	Per Cubic Meter	120.00	88726.00	Rupees Eighty Eight Thousand Seven Hundred Twenty Six and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto 1000m (one thousand metre) as per technical specification clause 1903 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals	499.50	Per Square Meter	22.00	10989.00	Rupees Ten Thousand Nine Hundred Eighty Nine and Paise Zero Only
Total in Figures					99715.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	**97182**
Earnest Money	**2000**
Time	**One Month**

Name of Work:-R/R Damage on Punni Naswar road Km. 0/00 to 3/30 (SH :- C/O unlined drain and Maintenance of berm at various RD's)Under PDNA 2023.

Sr. No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Construction of unlined surface drain of average cross-section area 0.20 sqm in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	675.00	Per Running Metre	21.80	14715.00	Rupees Fourteen Thousand Seven Hundred Fifteen and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	3748.50	Per Square Metre	22.00	82467.00	Rupees Eighty Two Thousand Four Hundred Sixty Seven and Paise Zero Only
Total in Figures					97182.00	
Quoted Rate in Figures			Select		**0.00**	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	97875
Earnest Money	2000
Time	One Month

Name of Work:-R/R Damage on Lalag to Kalehni road Km. 0/00 to 6/00 (SH :- C/O Maintenance of berm in Km 0/00 to 3/0) Under PDNA 2023.

Sr. No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Construction of unlined surface drain of average cross-section area 0.20 sqm in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	675.00	Per Running Metre	21.80	14715.00	Rupees Fourteen Thousand Seven Hundred Fifteen and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	3780.00	Per Square Metre	22.00	83160.00	Rupees Eighty Three Thousand One Hundred Sixty and Paise Zero Only
					97875.00	
Total in Figures			Select		0.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99924
Earnest Money 2000
Time One Month

ame of Work:- R/R Damages on Rela to Saryog via Badghat in G.P. Sanarli Km 0/00 to 3/00(SH:- Removal of slips,C/O Unlined drain & Maintenance of Berms in Km 0/00 to 1/500).

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	367.20	Per Cubic Meter	120.00	44064.00	Rupees Forty Four Thousand Sixty Four and Paise Zero Only
2	Construction of unlined surface drain of average cross-section area 0.20 sqm(zero point twenty square metre) in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	600.00	Per Running Meter	23.80	14280.00	Rupees Fourteen Thousand Two Hundred Eighty and Paise Zero Only
3	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto 1000m (one thousand metre) as per technical specification clause 1903 as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	1890.00	Per Square Meter	22.00	41580.00	Rupees Forty One Thousand Five Hundred Eighty and Paise Zero Only
					99924.00	
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99345
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Rela to Saryog via Badghat in G.P. Sanarli Km 0/00 to 3/00(SH:- Removal of slips,C/O Unlined drain & Maintenance of Berms in Km 1/500 to 3/00).

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	430.80	Per Cubic Meter	120.00	51696.00	Rupees Fifty One Thousand Six Hundred Ninety Six and Paise Zero Only
2	Construction of unlined surface drain of average cross-section area 0.20 sqm(zero point twenty square metre) in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	255.00	Per Running Meter	23.80	6069.00	Rupees Six Thousand Sixty Nine and Paise Zero Only
3	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto 1000m (one thousand metre) as per technical specification clause 1903 as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	1890.00	Per Square Meter	22.00	41580.00	Rupees Forty One Thousand Five Hundred Eighty and Paise Zero Only
					99345.00	
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	99704
Earnest Money	2000
Time	One Month

Name of Work:- R/R Damages on Khaneol to Sidh Chausi road Km 0/00 to 7/00(SH:- Removal of land slide slips & Maintenance of Earthen Shoulders at various RD's in Km 0/00 to 2/500).

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Removal of land slide slip clearance Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lift upto 1.5 m (one point five metre) and lead upto 1000m (one thousand metre) as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	661.26	Per Cubic Meter	120.00	79351.00	Rupees Seventy Nine Thousand Three Hundred Fifty One and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto 1000m (one thousand metre) as per technical specification clause 1903 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals	931.50	Per Square Meter	21.85	20353.00	Rupees Twenty Thousand Three Hundred Fifty Three and Paise Zero Only
					99704.00	
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	99827
Earnest Money	2000
Time	One Month

Name of Work:- R/R Damages on Khaneol to Sidh Chausi road Km 0/00 to 7/00(SH:- Removal of land slide slips & Maintenance of Earthen Shoulders at various RD's in Km 3/00 to 5/00).

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Removal of land slide slip clearance Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lift upto 1.5 m (one point five metre) and lead upto 1000m (one thousand metre) as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	613.94	Per Cubic Meter	120.00	73673.00	Rupees Seventy Three Thousand Six Hundred Seventy Three and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto 1000m (one thousand metre) as per technical specification clause 1903 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals	1197.00	Per Square Meter	21.85	26154.00	Rupees Twenty Six Thousand One Hundred Fifty Four and Paise Zero Only
					99827.00	
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 99229
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Kelodhar Chhatri Road Km. 0/00 to 19/00 (SH:- Removal of land Slide Slips & Maintenance of Earthen Shoulders at various RD's *in* Km 10/00 to 14/00).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Toatal Amount	Toatal Amount with all taxes including GST In
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	597.48	Per Cubic Metre	120.00	71698.00	Rupees Seventy One Thousand Six Hundred Ninety Eight and Paise Zero Only
3	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	1260.00	Per Square Metre	21.85	27531.00	Rupees Twenty Seven Thousand Five Hundred Thirty One and Paise Zero Only
Total in Figures					**99229.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	99420
Earnest Money	2000
Time	One Month

Name of Work:- R/R Damages on Karsog to Kanda road Km. 0/00 to 10/00(SH:- Maintenance of Berms & C/O Unlined drain in Km 0/00 to 10/00)

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Removal of land slider in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	367.20	Per Cubic Meter	120.00	44064.00	Rupees Forty Four Thousand Sixty Four and Paise Zero Only
2	Construction of unlined surface drain of average cross-section area 0.20 sqm(zero point twenty square metre) in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	375.00	Per Running Meter	23.80	8925.00	Rupees Eight Thousand Nine Hundred Twenty Five and Paise Zero Only
3	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto 1000m (one thousand metre) as per technical specification clause 1903 as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	2110.50	Per Square Meter	22.00	46431.00	Rupees Forty Six Thousand Four Hundred Thirty One and Paise Zero Only
					99420.00	
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.