OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG
PH: 01907-222229 Fax: 222229 , e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2024- 9835 Dated:- 3-12-2025

To

The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2.

Subject :- Regarding publication of Tender on departmental site.

With reference to the notification issued by the Secretary(PW) to the Government of Himachal Pradesh No. P BW(B)A(3)1/2024 dated 03.01.2024 and PBW-B-F0(2)/3/2024-284016 dated 18.07.2025, enclosed please find herewith the copy of Notice Inviting Tender for the loading on departmental web-site as

Certified that the works mentioned in the Tender Notice are urgent in nature and in coordination with the Disaster Management Act, 2005 Section 24 (i).

Encl:- As above.

Executive Engineer,
B&R Division,
HP PWD Karsog

OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG
PH: 01907-222229 Fax: 222229 , E-mail : ee-kar-hp@nic.in

Notice inviting tender

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **15.12.2025 upto 11.00** AM and shall be opened on the same day at **12.00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 12.12.2025** for which the application should reach in this office **upto 1.00 PM 12.12.2025**.

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening o f tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	R/R damages on Alsindi to Tattapani via Dhundan road KM. 0/00 to 5/00 (SH:- ROFD at various RDs between Rd 1/540 to 1/585) under PDNA 2023	4,95,886/-	10,000/-	One month	350/-
2	R/R damages on Alsindi to Tattapani via Dhundan road KM. 0/00 to 5/00 (SH:- ROFD at various RDs between RD 0/00 to 0/20) under PDNA 2023	4,81,757/-	9,700/-	One month	350/-
3	R/R damages on Mamail to Mehandi road KM. 0/00 to 19/00 (SH:- C/o R/wall at RD 11/960 to 11/970 and 12/325 to 12/340) under PDNA	4,77,035/-	9,500/-	One month	350/-
4	R/R damages on Mamail to Mehandi road KM. 0/00 to 19/00 (SH:- C/o B/wall at RD 11/680 to 11/695 and C/o unlined drain surface and removal of slips at Km. 11/00 to 13/00) under PDNA	4,67,950/-	9,400/-	One month	350/-
5	R/R damages on Rikki Bahan Gadhiman road KM. 0/00 to 5/00 (SH:- Maintenance of berm & C/o unlined drain in KM. 0/00 to 5/00)	4,89,051/-	9,800/-	One month	350/-
6	R/R damages on Alsindi to Dhundan via Dhundan road Km. 0/00 to 5/00 (SH:- ROFD at various RDs between KM. 0/00 to 1/800)	4,89,982/-	9,800/-	One month	350/-
7	R/R damages on Alsindi to Dhundan via Dhundan road Km. 0/00 to 5/00 (SH:- ROFD at various RDs between KM. 1/960 to 2/600)	4,71,110/-	9,800/-	One month	350/-

8	R/R damages on Sarahan Haripur road Km. 0/00 to 10/00 (SH:- Removal of slips & C/o unlined drain in Km. 0/00 to 10/00) under PDNA	4,90,399/-	9,900/-	One month	350/-
9	R/R damages on Karsog to Parlog road Km. 0/00 to 19/00 (SH:- C/o U-shape drain at Km. 0/00 to 0/075) under PDNA	4,75,911/-	9,600/-	One month	350/-
10	R/R damages on Shimla Mandi via Tattapani road Km. 55/500 to 90/00 (SH:- Removal of land slide slips at various RDs between Km. 65/00 to 90/00) under PDNA 2023	4,92,396/-	9,900/-	One month	350/-
11	R/R damages on Alsindi to Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:- ROFD at various RDs between RD 2/630 to 2/700) under PDNA 2023	4,82,444/-	9,700/-	One month	350/-
12	R/R damages on Shakelar Mahog via Navidhar road Km. 0/00 to 9/00 (SH:- Removal of slips and maintenance of earthen shoulders and C/o unlined surface drain at various RDs in Km. 0/00 to 9/00) under PDNA 2023	4,85,615/-	9,800/-	One month	350/-

TERMS & CONDITIONS:-

1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act.
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
9. As per Govt. Notification **PW/CTR/32-20Genl Inst-CPWD/2020-37996-38095 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.**

Executive Engineer
B&R Division
HPPWD Karsog

No. PW-E-Tender-NIT/2025-26- 9829-34 Dated:- 3-12-2025

1. All the Assistant Engineers, working under this Division.
2. Copy to Drawing & Account Branch.
3. Notice board of this office.

Executive Engineer,
B&R Division,
HP PWD Karsog

e

Percentage Schedule of Quantity

Estimated Cost 495886
Earnest Money 10000
Time One Month

Name of Work:- R/R Damages on Alsindi to Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:- ROFD at various RDs between RD 1/540 to 1/585)Under PDNA 2023.

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of **208.18** cubic metre @ Rs. 300/- per cubic metre amounting to Rs. **62454/-** only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	1486.96	Per Cubic Meter	333.49	495886.00	Rupees Four Lakhs Ninety Five Thousand Eight Hundred Eighty Six and Paise Zero Only
Total in Figures					495886.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	481757
Earnest Money	9700
Time	One Month

Name of Work:- R/R Damages on Alsindi to Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:- ROFD at various RD's between RD 0/00 to 0/020) Under PDNA 2023.

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall berexcavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of **230.97** cubic metre @ Rs. 300/- per cubic metre amounting to Rs. **69291/-** only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	1332.55	Per Cubic Meter	361.53	481757.00	Rupees Four Lakhs Eighty One Thousand Seven Hundred Fifty Seven and Paise Zero Only
					481757.00	
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 477035
Earnest Money 9600
Time One Month

Name of Work:- R/R Damages on Mamail to Mehandi road Km 0/00 to 19/00 (SH:- C/O R/Wall at RD 11/960 to 11/970 and 12/325 to 12/340) Under PDNA.

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stemps and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	51.00	Per Cubic Meter	355.00	18105.00	Rupees Eighteen Thousand One Hundred Five and Paise Zero Only
2	Providing concrete for plain/reinforced concrete 1:4:8 (one cement : four course sand : eight graded stone aggregate) 25 mm (twenty five millimeter) nominal size mechanical mixed and vibrated in open foundations complete as per drawings and technical specifications MORD Clause 802, 803, 1202 & 1203 and curing complete includingg the cost of form work or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	74.48	Per Cubic Meter	5500.00	409640.00	Rupees Four Lakhs Nine Thousand Six Hundred Forty and Paise Zero Only
3	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals	22.50	Per Cubic Meter	1460.95	32871.00	Rupees Thirty Two Thousand Eight Hundred Seventy One and Paise Zero Only
4	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall,return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drewing face complete as per drawing and technical specification clause 614,709,1204.3.7 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	44.00	Each	373.15	16419.00	Rupees Sixteen Thousand Four Hundred Nineteen and Paise Zero Only
Total in Figures					**477035.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	467950
Earnest Money	9400
Time	One Month

Name of Work:- R/R Damages on Mamail to Mehandi road Km 0/00 to 19/00 (SH:- C/O B/Wall at RD 11/680 to 11/695 and C/O unlined drain surface and removal of slips at Km 11/00 to 13/00) Under PDNA.

Sr.No.	1 Sub-Head and items of worksI	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stemps and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	33.75	Per Cubic Meter	355.00	11981.00	Rupees Eleven Thousand Nine Hundred Eighty One and Paise Zero Only
2	Providing concrete for plain/reinforced concrete 1:4:8 (one cement : four course sand : eight graded stone aggregate) 25mm (twenty five millimeter) nominal size mechanical mixed and vibrated in open foundations complete as per drawings and technical specifications MORD Clause 802, 803, 1202 & 1203 and curing complete includingg the cost of form work or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	52.31	Per Cubic Meter	5500.00	287705.00	Rupees Two Lakhs Eighty Seven Thousand Seven Hundred Five and Paise Zero Only
3	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals	10.80	Per Cubic Meter	1460.95	15778.00	Rupees Fifteen Thousand Seven Hundred Seventy Eight and Paise Zero Only
4	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall,return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drewing face complete as per drawing and technical specification clause 614,709,1204.3.7 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	28.00	Each	373.15	10448.00	Rupees Ten Thousand Four Hundred Forty Eight and Paise Zero Only
5	Construction of unlined surface drain of average cross-section area 0.20 sqm(zero point twenty square metre) in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	1800.00	Per Running Meter	21.80	39240.00	Rupees Thirty Nine Thousand Two Hundred Forty and Paise Zero Only
6	Removal of land slide slip clearance Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lift upto 1.5 m (one point five metre) and lead upto 1000m (one thousand metre) as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	856.65	Per Cubic Meter	120.00	102798.00	Rupees One Lakh Two Thousand Seven Hundred Ninety Eight and Paise Zero Only
Total in Figures					**467950.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	489051
Earnest Money	9800
Time	One Month

Name of Work:-R/R Damage on Rikki Bahan Gadhimaan Road Km 0/00 to 5/00 (SH:- Maintenance of berm & C/O unlined drain in km 0/0 to 5/0). Under PDHA

Sr. No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Construction of unlined surface drain of average cross-section area 0.20 sqm in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	4500.00	Per Running Metre	21.80	98100.00	Rupees Ninety Eight Thousand One Hundred and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	17770.50	Per Square Metre	22.00	390951.00	Rupees Three Lakhs Ninety Thousand Nine Hundred Fifty One and Paise Zero Only
					489051.00	
Total in Figures			Select		**0.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost	489982.00
Earnest Money	9800
Time	One Month

Name of Work:- R/R Damages on Alsindi to Tattapani via Dhudan road Km 0/00 to 5/00 (SH:- ROFD at various RD's between Km 0/00 to 1/800). (Under PDNA)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Toatal Amount with	Toatal Amount with all taxes including GST In Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of **234.92** cubic metre @ Rs. 300/- per cubic metre amounting to Rs. **70476/-** only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1355.30	Per Cubic Metre	361.53	489982.00	Rupees Four Lakhs Eighty Nine Thousand Nine Hundred Eighty Two and Paise Zero Only
Total in Figures					**489982.00**	
Quoted Rate in Figures					0.00	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	471110
Earnest Money	9500
Time	One Month

Name of Work:- R/R Damages on AlsIndi to Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:- ROFD at various RD's between Km 1/960 to 2/600)Under PDNA.

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road tospecified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of **225.87**cubic metre @ Rs. 300/- per cubic metre amounting to Rs. **67761/-** only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	1303.10	Per Cubic Meter	361.53	471110.00	Rupees Four Lakhs Seventy One Thousand One Hundred Ten and Paise Zero Only
Total in Figures					**471110.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	490399
Earnest Money	9900
Time	One Month

Name of Work:- R/R Damages on Sarahan Haripur road Km. 0/00 to 10/00(SH:- Removal of slips & C/O unlined drain in Km 0/00 to 10/00)Under PDNA

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	2434.16	Per Cubic Meter	120.00	292099.00	Rupees Two Lakhs Ninety Two Thousand Ninety Nine and Paise Zero Only
2	Construction of unlined surface drain of average cross-section area 0.20 sqm(zero point twenty square metre) in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	2550.00	Per Running Meter	23.80	60690.00	Rupees Sixty Thousand Six Hundred Ninety and Paise Zero Only
3	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto 1000m (one thousand metre) as per technical specification clause 1903 as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	6255.00	Per Square Meter	22.00	137610.00	Rupees One Lakh Thirty Seven Thousand Six Hundred Ten and Paise Zero Only
					490399.00	
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 475911
Earnest Money 9600
Time Six Months.

Name of Work:- R/R Damages on Karsog to Parlog road Km. 0/00 to 19/00 (SH:- C/O U-Shape drain at km. 0/00 and 0/075) Under PDNA

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Demolishing cement concerte manually/by mechanical means including disposal of material with 50 Mtr. (fifty meters) lead and as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	3.74	Per Cubic Meter	1642.85	6144.00	Rupees Six Thousand One Hundred Forty Four and Paise Zero
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to any lead dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 50 depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	15.66	Per Cubic Meter	483.95	7579.00	Rupees Seven Thousand Five Hundred Seventy Nine and Paise Zero Only
3	Providing concrete for plain/reinforced concrete M-10 grade 1:3:6 (one cement : three course sand : six graded crushed stone aggregate) 40 mm (forty millimeter) nominal size for mechanically mixed and vibrated in open foundation and plinths or similar work complete as per drawing and technical specifications MORD Clause 802, 803,1202 & 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	2.61	Per Cubic Meter	5976.25	15598.00	Rupees Fifteen Thousand Five Hundred Ninety Eight and Paise Zero Only
4	Providing and laying reinforcement cement concrete 1:1.5:3 (one cement : one point five course sand : three graded stone aggregate) 25 mm (twenty five millimeter) nominal size in super structure as per drawing and technical specification clause1401 and as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals.	9.45	Per Cubic Meter	9116.30	86149.00	Rupees Eighty Six Thousand One Hundred Forty Nine and Paise Zero Only
5	Supplying and placing HYSD bars reinforcement(Fe 415) in substructure complete as per drawing and specification clasue 1002, 1005, 1010 & 1202 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	0.44	Per Tonne	84402.45	37137.00	Rupees Thirty Seven Thousand One Hundred Thirty Seven and Paise
6	Steel work welded in built up sections,trusses and framed work,including cuttig hoisting,fixing in postions and applying a priming coat of red lead paint.as per diection of engineer in charge with in all lead and lifts and other incidentals.	2171.28	Per Kilogram	148.90	323304.00	Rupees Three Lakhs Twenty Three Thousand Three Hundred Four and Paise Zero Only
					475911.00	
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 492396
Earnest Money 9900
Time One Month

Name of Work:- R/R Damages on Shimla Mandi Via Tattapani road KM 55/500 to 90/00 (SH:- Removal of land slide slips at various RD's between KM 65/000 to 90/00) under PDNA-2023

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Removal of land slide slip clearance Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lift upto 1.5 m (one point five metre) and lead upto 1000m (one thousand metre) as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	4103.30	Per Cubic Meter	120.00	492396.00	Rupees Four Lakhs Ninety Two Thousand Three Hundred Ninety Six and Paise Zero Only
Total in Figures					492396.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	482444
Earnest Money	9700
Time	One Month

Name of Work:- R/R Damages on Alsindi to Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:- ROFD at various RDs between RD 2/630 to 2/700)Under PDNA 2023.

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of **231.31** cubic metre @ Rs. 300/- per cubic metre amounting to Rs. **69393/-** only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	1334.45	Per Cubic Meter	361.53	482444.00	Rupees Four Lakhs Eighty Two Thousand Four Hundred Forty Four and Paise Zero Only
					482444.00	
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 485615
Earnest Money 9800
Time One Month

Name of Work:- R/R Damages on Shakelar Mahog Via Navidhar Road Km. 0/00 to 9/00 (SH:- Removal of Slips & Maintenance of Earthen Shoulders & C/O unlined surface drain at various RD's in Km 0/00 to 9/00). Under PDNA 2023

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Toatal Amount	Toatal Amount with all taxes including GST In
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	2470.35	Per Cubic Metre	120.00	296442.00	Rupees Two Lakhs Ninety Six Thousand Four Hundred Forty Two and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	5145.00	Per Square Metre	21.85	112418.00	Rupees One Lakh Twelve Thousand Four Hundred Eighteen and Paise Zero Only
3	Construction of unlined surface drain of average cross-section area 0.20 sqm in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	3225.00	Per Running Metre	23.80	76755.00	Rupees Seventy Six Thousand Seven Hundred Fifty Five and Paise Zero Only
					485615.00	
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.