

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PWN-CB-Tender/2025-26- 5902-08
To

Dated:- 03/12/2025


The Executive Engineer (IT Cell),
Nigam Vihar, H.P.P.W.D., Shimla-2.
cc-pwd-hp@nic.in

Subject:-

Publication of Tender Notice.


Enclosed please find herewith the Notice Inviting Tender to be opened on 10.12.2025 for uploading on department website as per notification Secy.(PW) to the Govt. of H.P. No.PBW(B)A(3)1/2024 dated Shimla-2 the 03.01.2024 and further No.PWD-B-A0(3)/8/2025-300858 dt.9.10.25 as the work mentioned in the notice is urgent nature and public interest.

Encl:- As above.


Executive Engineer,
B & R Division,
HPPWD., Nahan

Copy forwarded to the following for information & n/a to:-

1. The Engineer-in-Chief, HP.PWD., Shimla.
2. The Chief Engineer (SZ), HP.PWD., Shimla.
3. The Superintending Engineer, 12th Circle, HP.PWD., Nahan please.
4. All the Assistant Engineers under this division.
5. All Head of Branches of this office.
6. The Notice Board.


Executive Engineer,
B & R Division,
HPPWD., Nahan

Himachal Pradesh
Public Works Department
Notice inviting Tender

Sealed percentage rate tender on form PWD 6 & 7 are invited by the Executive Engineer Nahan, Division HP, PWD on behalf of Governor of Himachal Pradesh for the following works from the approved and eligible contractors enlisted in HP PWD, so as to reach in this office as per time schedule given below.

- | | |
|---|--------------------------|
| 1. Date of receipt of application of tenders forms.:- | 09.12.2025 upto 11:00 AM |
| 2. Date of issue/ sale of tender Forms.:- | 10.12.2025 upto 10.30 AM |
| 3. Date of receipt of tender | 10.12.2025 at 11:00 AM |
| 4. Date of opening of tender:- | 10.12.2025 at 12:00 Noon |

Sr. No.	Name of Work	Estimated Cost (in ₹)	Earnest Money (in ₹)	Time Limit	Cost of Tender Form (in ₹)
1	Preparation of detailed project report, detailed estimate/working estimate on detailed analysis of rate of various works of roads works & building works estimates under Nahan Division.	95000/-	2000/-	02 Month	350/-
2	Preparation of detailed project report, detailed estimate/working estimate on detailed analysis of rate of various works of building work estimates under Nahan Division)	95000/-	2000/-	02 Month	350/-
3	Repair & Maintenance of HPPWD Rest House Dadahu. (Sh:- Repair of Sofa Set etc.)	88000/-	1800/-	01 Month	350/-
4	R/R damages on Jalal Bridge to Shiru Maila road km 0/00 to 4/275 (SH:- Removal of slips at RD 1/00 to 2/00)	98600/-	2000/-	02 Month	350/-
5	R/R Damages on Jalal Bridge to Shiru Maila Raod km 0/00 to 4/275 (Sh:- Removal of slips at RD 3/00 to 4/275)	98260/-	2000/-	02 Month	350/-
6	R/R Damages on link road from Banethi to Dagjar km 0/00 to 6/500 (Sh:- Removal of slips at RD 3/00 to 6/500)	98796	2000/-	02 Month	350/-
7	R/R Damages on link road from Bedaghat to Gaunth km 0/00 to 5/00 (SH:- Removal of slips at RD 1/500 to 3/00)	98141	2000/-	02 Month	350/-
8	R/R Damages to Jabbal Kanoti Upper Surla Kathana road km 0/00 to 5/200 (Sh:- C/O R/wall at RD 2/240 to 2/257) PDNA-2023	492606/-	10000/-	02 Month	350/-
9	C/O Govt. High School Building at Dhayli Tehsil Dadahu Distt. Sirmour H.P. (SH:- Floor Tiles) Part-2	99733/-	2000/-	02 Month	350/-
10	C/O Govt. High School Building at Dhayli Tehsil Dadahu Distt. Sirmour H.P. (SH:- Tiles & Other Miscellaneous work) Part-4	92360/-	2000/-	02 Month	350/-
11	C/O GHS Building at Malgaon, TehsilNahan, Distt. Sirmour (HP) (SH:- C/O Wire gauge & Glass panes of Door & Window etc.)	97713/-	2000/-	02 Month	350/-
12	C/O GHS Building at Malgaon, TehsilNahan, Distt. Sirmour (HP) (SH:- P/F Sanitary items & other miscellaneous work).	98924/-	2000/-	02 Month	350/-

CERTIFICATE:-It is certified thatthe tenders of above works are of exigency/ emergent nature in public interest.

Terms & Conditions:-

- The Contractors/ Bidders must submit copy of their Permanent Income Tax Account Number/ GST Number/ EPF No. along with the application for tender.
- The Earnest money for the above works should be submitted with applications for the purchase of the tender documents.
- The Contractors/Firms should attach copy of the Registration/ Renewal with the application.
- The contractor/ bidder should quote his rates both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
- Conditional and telegraphic tender shall not be accepted and rejected straightway. Tender received after due date and time will be rejected

6. The tender documents shall be issued to only those contractors who do not have more than two works in hand in any HPPWD Circle/ Division worth Rs. 1.00 Crore each or above.
7. The offer shall remain valid up to 75 days.
8. The provisions of guidelines issued vide the Principal Secretary (PW) to the Govt. of HP, Shimla vide notification No. PBW(B)A(3)1/2020 dated Shimla-2 the 22nd July, 2020 regarding adoption of CPWD works manual 2019 & other publication of CPWD in HPPWD shall also be applicable.
9. The Executive Engineer reserves the right to accept / reject any tender/applications or all tenders without assigning any reasons.


Executive Engineer,

Nahan Division,
HPPWD Nahan.

Estimated cost :-

Rs. 95,000 /-
Rs. 2,000 /-

SCHEDULE OF QUANTITY

Name of work :- Preparation of detailed project report, detailed estimate/working estimate on detailed analysis of rate of various works of Roads works & building works estimates under Nahan Division.

Estimated cost :- Rs. 95,000 /-
Earnest Money :- Rs. 2,000 /-
Time :- Two months.


S.No.	Sub-head & item of works	Quantity	Unit	Rate in		Amount
				Figure	Words	
1	Preparation of following detailed project report, detailed estimate & working estimates & DNIT on detailed analysis of rates of various works under roads and building works under Nahan Division including drawings complete in all respect & submission to the same to higher office for approval If any correction/ammendment will be desired by the head office the same may be corrected as desired & directed by the Engineer-in-Charge and complete in all respect. After approval the same from the head office should be submitted with soft copy. Road works & building works (Nahan Sub-Division) :- 1 Working estimate & DNIT for the construction of ink road from Sainwala Jhamiria Bogria Jamanwala Charuwala Kotla Km. 0/0 to 11/500 (Under Nabard) 2 C/O Type-II, Type-III & Type-IV residence quarter for NGO's Grade-II to Police Station SV & ACB at Nahn, District Sirmour (HP).	2.00 Job	Job	47500.00	Rs. Fourty seven thousand five hundred only.	95000
Total :-						95000

Quoted rates in figure (+/ -) (..... %)

Quoted rates in words (+/ -). %

Opened By Me.....
Cutting.....
Over Writting.....
Erasing.....
Condition.....

E.E.


Executive Engineer,
Nahan Division, HP.PWD.,
Nahan.

SCHEDULE OF QUANTITY

Name of work :- Preparation of detailed project report, detailed estimate/working estimate on detailed analysis of rate of various works of building work estimates under Nahan Division).


Estimated cost :- Rs. 95,000 /-
Earnest Money :- Rs. 2,000 /-
Time :- Two months.

S.No.	Sub-head & item of works	Quantity	Unit	Rate in		Amount
				Figure	Words	
1	Preparation of following detailed project report,detailed estimate & working estimates & DNIT on detailed analysis of rates of various works under building under Nahan Division including drawings complete in all respect & submission to the same to higher office for approval If any correction/ammendment will be desired by the head office the same may be corrected as desired & directed by the Engineer-in-Charge and complete in all respect. After approval the same from the head office should be submitted with soft copy. Building works (Dadahu Sub-Division) :- 1 Detailed estimate for the construction of Tehsil Office building at Dadahu, District Sirmour (HP) 2 Detailed estimate for the construction of Degree college building Shri Renuka Ji at Dadahu, District Sirmour (HP) .	2.00 Job	Job	47500.00	Rs. Fourty seven thousand five hundred only.	95000
Total :-						95000

Quoted rates in figure (+/ -) (..... %)
Quoted rates in words (+/ -) %

Opened By Me.....
Cutting.....
Over Writing.....
Erasing.....
Condition.....

E.E.


Executive Engineer,
Nahan Division, HP.PWD.,
Nahan.

3

SCHEDULE OF QUANTITY

Name of Work:- Repair & Maintenance of HPPWD Rest House Dadahu. (SH:- Repair of Sofa Set etc.)				Estimated cost :- Rs. 88,000/- only		
				Earnest Money:- Rs. 1,800/-		
				Time:- One Month		
1	Repair of Sofa set i.e. change of Matters, Jute etc. including all leads and carriage of materials and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	11.00	Each	5000.00	Rs. Five Thousand & Paise Nil only	55000.00
2	Repair of Sofa Chair i.e. change of Matters, Jute, Cloth etc. including all leads and carriage of materials and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	7.00	Each	3000.00	Rs. Three Thousand & Paise Nil only	21000.00
3	Repair of Dining Chairs i.e. change of matters, Jute cloth etc. including all leads and carriage of materials and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	6.00	Each	2000.00	Rs. Two Thousand & Paise Nil only	12000.00
Total						88000.00

Quoted Rate in Figure (+/-) (.....%)

Quoted Rate in Words (+/-) (.....%)

Condition:-

1 Rate should be quoted for all heights including all leads and lift.

2 The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Opened By Me.....
Cutting.....
Over Riding.....
Erasing.....
Condition.....

E.E.

Executive Engineer,
HP.PWD., Division
Nahan.

(4)

SCHEULE OF QUANTITY

Name of Work:-R/R Damages on Jalal Bridge to Shiru Maila road km 0/00 to 4/275 (SH: Removal of slips at RD 1/00 to 2/00)				Estimated cost :- Rs. 98,600/- only		
				Earnest Money:- Rs. 2,000/-		
				Time:- Two Months.		
1	Removal of land slide/slips in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611 including all leads, lifts and carnage of materials complete as per entire satisfaction of the Engineer in Charge	1160.00	Per Cubic metre	85.00	Rs. Eighty Five & paise Nil only	98600.00
Total						98600.00

Quoted Rate in Figure (+/-) (.....%)

Quoted Rate in Words (+/-) (.....%)

Condition -

1 Rate should be quoted for all heights including all leads and lift.

2 The contractor shall procure all the materials conforming to of MORTH at his own risk and cost.

Operated By: M/s.....


Cutting.....

Over Writing.....

Erasing.....

Condition.....

E.E.


 Executive Engineer,
 HP.PWD., Division
 Nahan.

5

SCHEDULE OF QUANTITY

Name of Work:-R/R Damages on Jalal Bridge to Shiru Maila road km 0/00 to 4/275 (SH: Removal of slips at RD 3/00 to 4/275)

Estimated cost :- Rs. 98,260/- only		
Earnest Money:- Rs. 2,000/-		
Time:- Two Months.		
85.00	Rs. Eighty Five & paise Nil only	98260.00
Total		98260.00

1	Removal of land slide/slips in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge	1156.00	Per Cubic metre
---	---	---------	-----------------


Quoted Rate in Figure (+/-) (.....%)
 Quoted Rate in Words (+/-) (.....%)

Condition:-

- 1 Rate should be quoted for all heights including all leads and lift.
- 2 The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Opened By Me.....
 Cutting.....
 Over Writing.....
 Erasing.....
 Condition.....

E.E.


 Executive Engineer,
 HP PWD, Division
 Nahan.

6

SCHEDULE OF QUANTITY

Name of Work:-R/R Damages on link road from Banethi to Dagjar km 0/00 to 6/500 (SH: Removal of slips at RD 3/00 to 6/500)

			Estimated cost :- Rs. 98,796/- only		
			Earnest Money:- Rs. 2,000/-		
			Time:- Two Months.		
1	Removal of land slide/slips in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge.	1162.30	Per Cubic metre	85.00	Rs. Eighty Five & paise Nil only
Total					98796.00

Quoted Rate in Figure (+/-) (.....%)

Quoted Rate in Words (+/-) (.....%)

Condition:-

- 1 Rate should be quoted for all heights including all leads and lift
- 2 The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Opened By Me.....
Cutting.....
Over Writing.....
Erasing.....
Condition.....

E.E.

Executive Engineer,
HP.PWD., Division
Nahan.

7

7

SCHEDULE OF QUANTITY						
Name of Work:-R/R Damages on link road from Bedaghat to Gaunth km 0/00 to 5/00 (SH: Removal of slips at RD 1/500 to 3/00)						
1	Removal of land slide/slips in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611 including all leads lifts and carnage of materials complete as per entire satisfaction of the Engineer in Charge	1154.60	Per Cubic metre	Estimated cost :- Rs. 98,141/- only		
				Earnest Money:- Rs. 2,000/-		
				Time:- Two Months.		
				85.00	Rs. Eighty Five & paise Nil only	98141.00
Total						98141.00


Quoted Rate in Figure (+/-) (.....%)

Quoted Rate in Words (+/-) (.....%)

Quoted Rate in Figure (+/-) (.....%)
Quoted Rate in Words (+/-) (.....%)

- Condition:-
- 1 Rate should be quoted for all heights including all leads and lift
 - 2 The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Checked By: M.
Cutting.....
Over Writing.....
Erasing.....
Condition.....


Executive Engineer,
HP.PWD., Division
Nahan.

E.E.

8

SCHEDULE OF QUANTITY

Name of work:- R/R Damages to Jabbal Kanoti Upper Suria Kathana road km. 0/00 to 5/200. (SH:- C/o R/wall at RD 2/240 to 2/257) PDNA				Estimated Cost Rs.4,92,606.00/-	
				Earnest Money: Rs. 10,000/-only	
				Time:- Two Months	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge	32.640	Per cubic metre	300.00	Rs.Three hundred & Paise nil only 9792.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement: four sand: eight crushed aggregates) including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	100.470	Per Cubic metre	4211.30	Rs.Four Thousand Two Hundred Fifty & Paise Nil Only 423109.00
4	Providing weep holes in bricks/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia PVC pipe extended through the full width of the structure with slope of 1 vertical and 20 in horizontal towards drawing face complete as per specification clause 614.709.1204.3.7 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	45.000	Per Each	270.00	Rs. Two Hundred Seventy Two & Paise Nil only 12150.00
5	Back filling behind abutment wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular materials as per HP PWD . specification 1990 of Volume-1 (one) including carriage of all labour equipment & materials to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-charge	36.720	Per Cubic metre	1149.00	Rs.One Thousand One Hundred Forty Nine & Paise Nil Only. 42191.00
5	Construction of Embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of table 300.1 and 300.2 as per technical specification clause 301.5	54.400	Per cubic metre	98.60	Rs. Ninety eight & paise sixty only 5364.00
Total					492606.00

Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) (-----%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Opened By Me.....
Cutting.....
Over Writing.....
Erasing.....
Condition.....

E.E.

Executive Engineer
Nahan Division,
HP.PWD, Nahan

SCHEDULE OF QUANTITY

Name of work:- C/o Govt. High School Building at Dhayli Tehsil Dadahu Distt. Sirmour H.P. (SH:- Floor Tiles) Part 2				Estimated Cost Rs.99,733/-		
				Earnest Money: Rs. 2,000/- only		
				Time:- Two Months		
Sr.No	Sub Head and item of work	Qty	Unit	Rate		Amount
				Figure	Words	
1	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete including carriage of all labour equipment & materials to various location through all leads , lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	72.52	Per Square metre	1375.25	Rs. One Thousand Three Hundred Seventy Five & Paise Twenty Five Only	99733.00
	Total					99733.00

Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) (.....%)

Condition :-

- 1 Rate should be quoted for all heights including all leads and lift.
- 2 The contractor shall procure all the materials conforming to the specifications.
- 3 of MORTH at his own risk and cost.

Opened By Me.....
Cutting.....
Over Writing.....
Erasing.....
Condition.....

Executive Engineer
Nahan Division,
HP.PWD, Nahan

E.E.

SCHEDULE OF QUANTITY

Name of work:- C/o Govt. High School Building at Dhayli Tehsil Dadahu Distt. Sirmour HP(SH:- Tiles & Other Miscellaneous work) Part -4

Estimated Cost Rs.92,360/-

Earnest Money: Rs. 2,000/- only

Time:- Two Months

Sr.No	Sub Head and item of work	Qty	Unit	Rate		Amount
				Figure	Words	
1	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete. including carriage of all labour equipment & materials to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	84.77	Per Square metre	820.00	Rs. Eight Hundred Twenty & Paise Nil Only	69511.00
2	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete including carriage of all labour equipment & materials to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	10.36	Per Square metre	1375.25	Rs. One Thousand Three Hundred Seventy Five & Paise Twenty Five Only	14248.00
3	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100mm (one hundred millimeter) sand cast Iron P or S trap, 10 litre (ten litre) low level white PVC flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required complete including carriage of materials in all leads and lifts and as directed by the Engineer in Charge: White Vitreous china Orissa pattern W.C. pan of size 580mm x 440mm (five hundred eighty millimeter X four hundred forty millimeter) with integral type foot rests	2.00	Per Each	4300.30	Rs. Four Thousand Three Hundred & Paise Thirty Only	8601.00
Total:						92360.00

Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Opened By Me.....
Cutting.....
Over Writing.....
Erasing.....
Condition.....

E.E.

Executive Engineer
Nahan Division,
HP.PWD, Nahan

SCHEDULE OF QUANTITY

11

Name of work:- C/O GHS Building at Malgaon ,Tehsil Nahan,Distt sirmour (HP) (SH:- C/O Wire gauge & Glass panes of Door & Window etc).				Estimated Cost Rs.97,713/-	
				Earnest money: Rs. 2000/-	
				Time:- Two Months	
Sr.No	Sub Head and item of work	Qty	Unit	Rate	Amount
1	Providing & Fixing fly proof wire gauge to windows, clerestory windows & door with mild steel flat 15*3 mm (fifteen into three milimetre) & nut & bolts complete. Galvanised mild steel wire gauge with 0.63 mm dia wire and 1.4 mm aperture on both sides including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer in Charge.	26.55	Per Square metre	1434.25	Rs. One Thousand Four Hundred Thirty Four & Paise Twenty Five Only.
2	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with 4mm (four milimetre) thick glass panes including carriage of materials in all leads and lifts and as directed by the Engineer in charge.	26.55	Per cubic metre	847.55	Rs. Eight Hundred Forty Seven & Paise Fifty Five Only.
3	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank. including carriage of materials in all leads and lifts and as directed by the Engineer in charge.	2000	Litre	8.80	Rs. Eight & Paise Eighty Only.
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal Mix 1:4:8 including carriage of materials in all leads and lifts and as directed by the Engineer in charge.	2.05	Per cubic metre	4211.30	Rs. Four Thousand Two Hundred Eleven & Paise Thirty Only.
5	Eathwork in excavation for structures in all depths as per drawing and technical specification for rural roads August 2004 clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable material. including carriage of materials in all leads and lifts and as directed by the Engineer in charge.	36.3	Per cubic metre	300.00	Rs. Three Hundred & Paise Nil Only.
Total					97713.00

Quoted Rate in Figure (+/-) (.....%)

Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Opened By Me.....
 Cutting.....
 Over Written.....
 Drawing.....
 Condition.....

E.E.

Executive Engineer
 Nahan Division,
 HP PWD, Nahan

12

SCHEDULE OF QUANTITY

Name of work:- C/O GHS Building at Malgaon, Tehsil Nahan, Distt sirmour (HP) (SH:- P/F Sanitary items & other miscellaneous work).					Estimated Cost Rs.98,924/-	
					Earnest money: Rs. 2000/-	
					Time:- Two Months	
Sr.No	Sub Head and item of work	Qty	Unit	Rate		Amount
1	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required W.C. pan with ISI marked white solid plastic seat and lid including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer in Charge.	2	Each	4330.20	Rs.Four Thousand Three Hundred Thirty & Paise Twenty Only.	8660.00
2	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: White Vitreous china Orissa pattern W.C.pan of size 580x440 mm with integral type foot rests including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer in Charge.	2	Each	4490.75	Rs.Four Thousand Four Hundred Ninety & Paise Seventy Five Only.	8982.00
3	spreaders with unions and clamps (all in C.P. brass) with waste fitting as per IS : 2556, C.I. trap with outlet grating and other couplings in C.P. brass, including painting of fittings and cutting and making good the walls and floors wherever required Single half stall urinal with 5 litre P.V.C. automatic flushing cistern including carnage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer in Charge.	2	Each	6776.80	Rs.Six Thousand Seven Hundred Seventy Six & Paise Eighty Only.	13554.00
4	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls whereverWhite Vitreous China Flat back wash basin size 550x 400 mm with single 15 mm C.P. brass pillar tap require White Vitreous China Flat back wash basin size 550x 400 mm with single 15 mm C P brass pillar tap, including carnage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer in Charge.	4	Each	2089.70	Rs.Two Thousand Eighty Nine & Paise Seventy Only.	8359.00
5	Providing and fixing water closet squatting pan (Indianand fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C P brass screws and washers complete including carnage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer in Charge.	4	Each	1009.90	Rs.One Thousand Nine & Paise Ninety Only.	4040.00
6	Providing and fixing C P Brass Cock of approved quality conforming to is 8931,complete including carnage of materials in all leads and lifts and as directed by the Engineer in Charge 15mm Nominal bore	25	Each	500.00	Rs.Five Hundred & Paise Nil Only.	12500.00
7	Providing and fixing C P brass stop cock (concealed) of standard design and of approved make conforming to IS 8931 15 mm nominal bore	6	Each	606.25	Rs.Six Hundred Six & Paise Twenty Five Only.	3638.00
8	Providing and fixing in position pre-cast R C C manhole cover and frame of required shape and approved quality Square shape 450 mm internal dimensions	1	Each	1002.2	Rs One Thousand Two & Paise Twenty Only.	1002.00
9	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS 13592 Type A, including jointing with seal ring conforming to IS 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 75 mm diameter	25.00	Per Running Meter	165.15	Rs One Hundred Sixty Five & Paise Fifteen Only	4129.00
10	Providing and fixing water closet squatting brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour 450 mm long towel rail with total length of 495 mm, 78 mm wide and effective height of 88 mm weighing not less than 170gms	4	each	415.15	Rs Four Hundred Fifteen & Paise Fifteen Only	1661.00

11	Providing and fixing PTMT liquid soap container 109 mm wide, 125 mm high and 112 mm distance from wall of standard shape with bracket of the same materials with snap fittings of approved quality and colour, weighing not less than 105 gms.	4	Each	158.55	Rs. One Hundred Fifty Eight & Paise Fifty Five Only.	634.00
12	Providing and fixing PVC plain bend ISI marked including fixing with approved adhesive etc. complete 75mm dia including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer in Charge.	10	Each	75.00	Rs. Seventy Five & Paise Nil Only.	750.00
13	Providing and fixing PVC collars ISI marked including fixing with approved adhesive etc. complete 75mm dia including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer in Charge.	10	Each	10.00	Rs. Ten & Paise Nil Only.	100.00
14	Providing and fixing bright finished brass tower bolts (barrel type) with necessary screws etc. complete 150x10 mm	125	Each	228.15	Rs. Two Hundred Twenty Eight & Paise Fifteen Only.	28519.00
15	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete 300x16 mm	10	Each	239.60	Rs. Two Hundred Thirty Nine & Paise Sixty Only.	2396.00
Total						98924.00

Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) (.....%)


Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

Opened By Me.....
Cutting.....
Over Writing.....
Erasing.....
Condition.....

E.E.


Executive Engineer
Nahan Division,
HP.PWD, Nahan