

**Himachal Pradesh
Public Works Department**

No. PWP/Agr. Asstt./Tender/2025/ 13986-96

Dated/ 6-12-2025

To

The Executive Engineer (IT Cell),
Nirman Bhawan Nigam Vihar Shimla-2
Himachal Pradesh Shimla -2.

Subject:- Publication of Tender Notice.

Enclosed please find herewith Tender Notice of works as given in the Notice inviting Tenders alongwith schedule of quantities for uploading on departmental website as per Notification Secretary (PW) to the Govt. of HP letter NO. PBW (B) A (3) 1/2024 dated Shimla -03.01.2025

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in Public interest.

DA/ Stated as above

Executive Engineer
Palampur Division
HPPWD Palampur


Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

1. The Superintending Engineer, 5th Circle, HPPWD., Palampur.
2. The Drawing /Accounts Branch in this office.
3. All Assistant Engineers working under this division.
4. Notice Board.

Executive Engineer
Palampur Division
HPPWD Palampur

CERTIFICATE

Certified that the tenders invited vide this office
NIT No. PWP/ Agr. Asstt/ NIT/ 2025/- 13986-96
Dated 06-12-2025 are urgent in nature and in public interest.


Executive Engineer
Palampur Division
HPPWD Palampur

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
'NOTICE INVITING TENDERS'**

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P for the following work from the approved and eligible contractors enlisted in HP.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **17.12.2025** up to 11.00 AM. And the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on 16.12.2025 up to 4.00 P.M and the application for issue of tender form shall be received 15.12.2025 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S. No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	Preparation of Forest Diversion case under FCA, 1980 for the construction of link road from Bhagotla Dharer Rajnali Km 0/00 to 3/777 under Gopalpur Sub-Division in Tehsil Palampur Distt. Kangra (HP) (SW:- Preparation of Forest Diversion case under FCA, 1980)	Rs. 95,000.00	Rs. 1,900.00	Two Month
2	Preparation of Forest Diversion case under FCA, 1980 for the construction of link road from Bhagotla Dharer Rajnali Km 0/00 to 3/777 and Lugri Bhatti Kandi road KM 0/00 to 3/249 under Gopalpur Sub-Division in Tehsil Palampur Distt. Kangra (HP) (SW:- Preparation of Revenue paper for Forest Diversion case under FCA, 1980)	Rs. 99,488.00	Rs. 2,000.00	Two Month
3	Restoration of rain damages on Dharaman Rajehar GwalTikkar road to Kapen (SW:- Hiring of JCB)	Rs. 98,900.00	Rs.2,000.00	Three Month
4	Restoration of Rain damages on Dharer Rajnali Bhagotla road KM 0/00 to 4/500 (SH:- Providing and laying of G-II on various RD's between 1/500 to 4/500)	Rs. 99,855.00	Rs. 2,000.00	Two Month
5	R/D on Kandi Thalla Malenta road KM 0/00 to 4/500 (SW:- Hiring of JCB for removal of slip & clearance of drain from Km 0/00 to 4/500)	Rs. 98,900.00	Rs. 2,000.00	Two Month
6	Restoration of rain damages on Patti to Dohal road Km 0/00 to 0/500 (SW:- C/o R/Wall at RD 0/470 to 0/473.10 (Deposit))	Rs. 49,171.00	Rs. 1,000.00	Two Month
7	Link road Cinema Hall Bye Pass to Ghuggar Tanda road (SW:- C/o V-Shape drain cum Edge wall RD 0/139 to 0/171.80 (MC Deposit))	Rs. 99,110.00	Rs. 2,000.00	Three Months
8	Link road Cinema Hall Bye Pass to Ghuggar Tanda road (SW:- C/o V-Shape drain cum Edge wall RD 0/096 to 0/129 (MC Deposit))	Rs. 99,713.00	Rs. 2000.00	Three Months
9	Link road from Snow View Colony to Join Suggar road (SW:- Repair of Pot holes (MMSRRY) at RD 0/250 to 0/500)	Rs. 99,645.00	Rs. 2,000.00	Three Months
10	Link road from Bindraban Differpatt Goswami Awadi Sughar Bandla Tea Estate Jersey Farm road Km 0/000 to 2/00 (SW:- Repair of Pot Holes (MMSRRY))	Rs. 99,536.00	Rs. 2,000.00	Three Months
11	Link road from SSB Chowk Bandla to Village Sughar Aima (SW:- Repair of Pot holes (MMSRRY))	Rs. 99,029.00	Rs. 2,000.00	Three Months
12	Link road from Snow View Colony to Join Suggar road (SW:- Repair of Pot holes (MMSRRY) at RD 0/000 to 0/250)	Rs. 98,995.00	Rs. 2,000.00	Three Months

13	Renovation of Rain damages on Dharamshala Yol Dadh Palampur Road (MDR- 78) Under Gopalpur Sub-Division (SW:- Painting and writing letters in KM Stones and bridges etc)	Rs. 99,950.00	Rs. 2,000.00	Two Months
14	C/o New School Building Library & Examination Hall at GSSS Palampur (SW:- Chiseling/ Wedging out of Rock)	Rs. 93,905.00	Rs. 1,900.00	Three Months
15	Repair of RRD on link road to Tambar KM 0/00 to 0/700 (SW:- Providing and laying CC Pavement at RD 0/200 to 0/235) (SDRF)	Rs. 99,225.00	Rs. 2,000.00	Two Months
16	C/o Cow Shed at Kudan Dehal PO Jia Tehsil Palampur Distt. Kangra HP (SW:- C/o U-shape drain for Urine waste & Steel for Animal Tie Anchor work (Deposit)	Rs. 98,826.00	Rs. 2,000.00	Two Months
17	C/o Cow Shed at Kudan Dehal PO Jia Tehsil Palampur Distt. Kangra HP (SW:- Providing Fixing Glass panes in Ventilators, Doors & Steel over Khurli (Deposit)	Rs. 97,520.00	Rs. 2,000.00	Two Months
18	C/o Dharamshala Dadh Palampur Holta Chadiyar road Km 0/00 to 40/500 (MDR-78) (SW:- C/o U-Shape drain at various RDs between KM 15/00 to 20/500 (Deposit from EE Bhawarna)	Rs. 99,200.00	Rs. 2,000.00	Two Months
19	C/o Dharamshala Dadh Palampur Holta Chadiyar road Km 0/00 to 40/500 (MDR-78) (SW:- Dressing of berms at various RDs between KM 15/00 to 20/500 (Deposit from EE Bhawarna)	Rs. 99,828.00	Rs. 2,000.00	Two Months
20	Restoration of Rain damages on Parour Lahla Gopalpur Rakh Ghamrota Jyuen Sukeri Kandi Bandla Palampur road KM 0/00 to 33/00 (SW:- C/o R/Wall at RD 11/190 to 11/200)	Rs. 99,376.00	Rs. 2,000.00	Two Months
21	Balance work of road from Village Rakh to Ustehar KM 0/00 to 0/600 (SW:- C/o Edge wall slab over Kuhal & CC Pavement in Path (MNP)	Rs. 51,101.00	Rs. 1,100.00	Two Months
22	C/o Jeepable road from Main road to Sh. Partap Chand House Mohal GP Upper Dadh (SH:- Providing and laying CC Pavement (VKVNY Deposit)	Rs. 98,438.00	Rs. 2,000.00	Two Months
23	Restoration of Rain damages on Dharamshala Yol Dadh Holta Chadiyar Sandhole road at KM 33/00 to 40/000 (SW:- Providing and laying 1:3:6 etc)	Rs. 99,100.00	Rs. 2,000.00	Three Months
24	C/o road from Anil Kumar House to Sh. Pritam Chand house Ward No. 2 (SW:- C/o R/Wall (Deposit)	Rs. 98,627.00	Rs. 2,000.00	Three Months
25	C/o Pucca Path from Sh. Paras Ram House towards Smt. Beena Devi house Ward No. 1 in GP Sungal (SW:- C/o CC Pavement at RD 0/000 to 0/042 (Deposit)	Rs. 48,195.00	Rs. 1,000.00	Three Months
26	Chowki Patwar Khana to Rajpur Kalu-Di-Hatti Kesar Bag Colony road KM 0/00 to 2/130 (SW:- C/o U-shape drain from RD 2/030 to 2/063 (MC Deposit)	Rs. 99,099.00	Rs. 2,000.00	Three Months
27	Chowki Patwar Khana to Rajpur Kalu-Di-Hatti Kesar Bag Colony road KM 0/00 to 2/130 (SW:- C/o U-shape drain from RD 2/063 to 2/095.50 (MC Deposit)	Rs. 97,629.00	Rs. 2,000.00	Three Months
28	Restoration of Rain damages on Dharaman to Spedu at RD 0/000 to 5/000 (SW:- C/o B/Wall Pusta at RD 4/758 to 4/770)	Rs. 98,533.00	Rs. 2,000.00	Three Months
29	Restoration of Rain damages on Dharaman to Spedu at RD 0/000 to 5/000 (SW:- C/o B/Wall at RD 4/770 to 4/783.80))	Rs. 99,581.00	Rs. 2,000.00	Three Months
30	Restoration of Rain damages on Yol Dadh Palampur road 27/000 to 33/000 (SW:- C/o B/Wall from RD 29/225 to 29/234.35)	Rs. 99,761.00	Rs. 2,000.00	Three Months

31	Restoration of Rain damages on link road from Khalet to Sidhpur Sarkari road (SW:- C/o R/Wall from RD 2/113.60 to 2/150)	Rs. 97,015.00	Rs. 2,000.00	Three Months
32	Construction of SDRF HQ Campus at Bagora Palampur Tehsil Palampur Distt. Kangra (HP) (SW:- Topographical Survey Contour Plan)	Rs. 98,070.00	Rs. 2,000.00	Three Months
33	C/o Jeepable road from Sham Lal House to Suresh Kumar house Ward No. 1 GP Band Vihar (Deposit) (SW:- Providing and laying Interlocking Paver Block at RD 0/000 to 0/022)	Rs. 99,365.00	Rs. 2,000.00	Three Months
34	C/o R/Wall to Protect the land of Sh. Sanjay Kumar S/o Sh. Ramesh Ward No. 5 GP Thalla Uarla (SW:- C/o R/Wall (Deposit))	Rs. 74,561.00	Rs. 1,500.00	Two Months

Terms & Conditions-

Following documents should accompany the application for tenders.

1. G.S.T. No.
2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years

Executive Engineer
Palampur Division
HPPWD Palampur

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITIES						
Name of work:- Preparation of forest diversion case under FCA, 1980 for the construction of link road from Bhagotla Dharer Rajnalli Km 0/00 to 3/777 under Gopalpur Sub Division in Tehsil Palampur, Distt. Kangra H.P. (SH:- Preparation of Forest Diversion Case under FCA,1980).		Quantity	Estimated cost Rs.		Unit	95000.00
			Earnest Money Rs.			1900.00
			Time Limits			Two Months
			Rate			Amount
Sr. No.	Description of Item	In Figures	In Word		Job	
1	Preparation of KML File and Geo Reference Digital map of proposed land and CA Area. Preparation of CA Scheme, Reclamation Plan, Cost Benefit Analysis, Muck Management, uploading Main Application Part I on Parivesh portal complete in all respect. Assistance to User Agency to attend the queries and clarification sought by MoEF. Submission of Stage I compliance report for obtaining Stage II Approval. Assistance to User Agency to make presentation for REC Meeting as required by MoEF. The Rates are inclusive of all equipments within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1.000				
Total						

Executive Engineer,
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- Preparation of forest diversion case under FCA, 1980 for the construction of link road from Bhagotla Dharer Rajnali Km 0/00 to 3/777 & Link road Lugri Bhatti Kandi road Km 0/00 to 3/249 under Gopalpur Sub Division in Tehsil Palampur, Distt. Kangra H.P. (SH):- Preparation of Revenue paper for Forest Diversion Case under FCA, 1980).					Estimated cost Rs.	99488.00
					Earnest Money Rs.	2000.00
					Time Limits	Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Preparation of revenue paper for land acquire in the project, Layout Plan of the Project, Khassa wise detail of forest and non-forest both, enumeration list, village wise beneficiary information and Joint Inspection Report, Assistance to User Agency to procure DC Certificate for unavoidable and in-escapable and Certificate NFL for CA from Director Land Records, Shimla as per latest requirement of ministry of environment and forest conservation Govt. of India The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	7.026			Per Kilometre	
	Total					


 Executive Engineer,
 Palampur Division
 HP PWD Palampur

Drafts Schedule of Quantity

Name of Work :- Restoration of rain damages on Dharman rajehar Gwalitkiker road to Kapen

(S.W.) :- Hiring of JCB

Estimated Cost :- Rs. 98,900/-
Earnest Money :- Rs. 2000/-

Time limit : Three Months.

Sl. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Hiring of J.C.B (Excavator -Cum -Loader) including P.O.L. charges, shifting charges and other ancillary equipments as required at site of work for removal of slips. The disposal of this un-serviceable material has to be done in the required width of the road to avoid damages to the properties of the people or in case any damage took place, the contractor is liable for it. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-in -Charge including all leads and lifts.	86.00	1150.00	Rupees One Thousand One Hundred Fifty Only	Per Hour	98900.00
					Total :-	98900.00

Drafts Schedule of quantity Checked and approved for Rs. 98,900/- only
Rupees Ninety Eight Thousand Nine Hundred Only

Executive Engineer
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Dharer Rajnali Bhagotla road Km 0/00 to 4/500. (SH:- Providing and Laying of G-II on various Rd's between 1/500 to 4/500).				Estimated cost Rs.		99855.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	44.38			Per cubic metre	

Executive Engineer
 Palampur Division
 HP PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- R/D on Kandi Thalla Malenta road Km 0/00 to 4/500.(SH:- Hiring of JCB for removal of slip & clearance of drain from Km 0/00 to 4/500).

		Estimated cost Rs.		98900.00
		Earnest Money Rs.		2000.00
		Time Limits		Two Months
Sr. No.	Description of Item	Quantity	Rate	
			In Figures	In Word
1	Hiring of JCB (Excavator-Cum-Loader) including P.O.L. charges shifting charges and other ancillary equipments as per required at site of work for removal of slips. The disposal of this un-serviceable material has to be done in the required width of the road to avoid damages to the properties of the people or in case any damage intook place, the contractor is liable for it. The work shall have to be carried out as per ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	86.00		Per Hour
			Unit	
			Amount	
			Total	

Executive Engineer,
Palampur Division
H.P. PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Patti to Dohal road Km 0/00 to 0/500. (SH:- C/o R/wall at Rd 0/470 to 0/473.10). Deposit 0.50 Lacs				Estimated cost Rs.	
				Earnest Money Rs.	
				Time Limits	
Sr. No.	Description of Item	Quantity	Rate		Unit
			In Figures	In Word	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	3.47			Per cubic metre
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	10.23			Per cubic metre.
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	6.00			Each
4	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC: 78 & 2200. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	3.72			Per cubic metre
				Total	


 Executive Engineer,
 Palampur Division
 HP.PWD Palampur

Schedule of Quantity

Work :- Link Road Cinem Hall Bye Pass to Ghuggar Tanda Road

Sub Work :- C/O V-shape drain cum edge wall Rd 0/139 to 0/171.80(MC Deposit)

Estimate Cost :- Rs. 99,110/-

Earnest Money :- Rs. 2000/-

Time Limit :- Three months

S. No	Description of Item	Quantity		Rate		Unit	Amount Rupees
				In figure	In Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantiam of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	23.62	Cubic metre			Per Cubic metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government .	19.68	Cubic metre			Per Cubic metre	
Total :-							


Executive Engineer,
Palampur Division,
HPPWD Palampur

Schedule of Quantity

Name of Work :- Link Road Cinem Hall Bye Pass to Ghuggar Tanda Road
Sub Work :- C/O V-shape drain cum edge wall Rd 0/096 to 0/129(MC Deposit)

Estimate Cost :- Rs. 99,713/-
Earnest Money :- Rs. 2000/-
Time Limit :- Three months

S. No	Description of Item	Quantity		Rate		Unit	Amount Rupees
				In figure	In Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	23.76	Cubic metre			Per Cubic metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government..	19.80	Cubic metre			Per Cubic metre	
Total :-							

Executive Engineer,
Palampur Division,
HPPWD Palampur

Schedule of Quantity

Line of Work :- Link Road from Snow View Colony to Join Suggar Road
Sub Work :- Repair of Pot Holes (MMSRRY) RD 0/250 to 0/500

Estimate Cost :- Rs. 99,645/-
Earnest Money :- Rs. 2000/-
Time Limit :- Three months

S. No	Description of Item	Quantity		Rate		Unit	Amount Rupees
				In figure	In Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm(twenty millimetres) thick pre-mix carpet and seal coat type B specification Clause 1904.2.503 and 508.1. including carriage of materials, within all leads, lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, sale tax or any other taxes imposed by the Government.	254.38	Square metre			Per Square metre	
2	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, Malkana, tolltax, sale tax or other taxes imposed by the Government.	5.72	Cubic metres			Per Cubic metre.	
Total :-							

Executive Engineer,
Palampur Division,
HPPWD Palampur

Schedule of Quantity

of Work :- Link Road from Binderaban Differpatt Goswami Awadi Sugar Bundla tea Estate Jersey Farm roadKm.0/000 to 2/000
 Work :- Repair of Pot Holes (MMSRRY)

Estimate Cost :- Rs. 99,536/-
 Earnest Money :- Rs. 2000/-

Time Limit :- Three months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rupees
			In figure	In Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm(twenty millimetres) thick pre-mix carpet and seal coat type B specification Clause 1904.2.503 and 508.1. including carriage of materials, within all leads, lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, sale tax or any other taxes imposed by the Government.	254.06			Per Square metre	
2	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, Malkana, tolltax, sale tax or other taxes imposed by the Government.	5.72			Per Cubic metre.	
Total :-						

Executive Engineer,
 Palampur Division,
 HPPWD Palampur

of Work :- Link Road from SSB Chowk Bandla to Village Sugar Aima
Work :- - Repair of Pot Holes (MMSRRY)

Schedule of Quantity

Estimate Cost :- Rs. 99,029/-
Earnest Money :- Rs. 2000/-
Time Limit :- Three months

11

S. No	Description of Item	Quantity		Rate		Unit	Amount Rupees
				In figure	In Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimetres) thick pre-mix carpet and seal coat type B specification Clause 1904.2.503 and 508.1. including carriage of materials, within all leads, lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, sale tax or any other taxes imposed by the Government.	252.77	Square metre			Per Square metre	
2	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, Malkana, tolltax, sale tax or other taxes imposed by the Government.	5.69	Cubic metres			Per Cubic metre.	
Total :-							

Executive Engineer,
Palampur Division,
HPPWD Palampur

Schedule of Quantity

Name of Work :- Link Road from Snow View Colony to Join Suggar Road
Sub Work :- Repair of Pot Holes (MMSRRY) RD 0/000 to 0/250

Estimate Cost :- Rs. 98,995/-
Earnest Money :- Rs. 2000/-

Time Limit :- Three months

S. No	Description of Item	Quantity		Rate		Unit	Amount Rupees
				In figure	In Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm(twenty millimetres) thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including carriage of materials, within all leads, lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, sale tax or any other taxes imposed by the Government.	252.67	Square metre			Per Square metre	
2	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, Malkana, tolltax, sale tax or other taxes imposed by the Government.	5.69	Cubic metres			Per Cubic-metre.	
Total :-							

Executive Engineer,
Palampur Division,
HPPWD Palampur

13

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Dharamshala Yol Dadh Palampur road (MDR-78) under Gopalpur Sub Division, (SH:- Painting & writing letters in Km Stones & bridges etc.),					Estimated cost Rs.		99950.00
					Earnest Money Rs.		2000.00
					Time Limits		Two Months
Sr. No.	Description of Item	Quantity	In Figures	In Word	Rate		Amount
					In Figures	In Word	
1	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	35.00				Per square metre	
2	Writing letters or figures on any surface with black japan paint (stops,comas,hyphens and the like not to be measured and paid separately) Indian(letters/figures) . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	30000.00				Per letter per cm. height	
3	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. New work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	280.00				Per square metre.	
Total							

Executive Engineer,
Palampur Division
HP PWD Palampur.

Schedule of Quantity

Line of Work :- C/O New School building Library & Examination Hall at GSSS Palampur
 Sub Work :- Chiselling/ Wedging out of Rock

Estimate Cost :- Rs. 93,905/-
 Earnest Money :- Rs. 1900/-
 Time Limit :- Three months

S. No	Description of Item	Quantity		Rate		Unit	Amount Rupees
				In figure	In Words		
1	Excavation in foundations, trenches etc., in earth work, lift upto 1.50 Metres stacking the eacavated soil not more than 3 metres clear from the edge of the excavation and then returning the stacked soil in 15cm. layers, when required in to plinths sides of foundations etc., consolidating each deposited layer by ramming and watering and then disposing of all surplus excavated earth as directed with in a lead of 20 metres.Chiselling/wedging out of rock where blasting is prohibited in Hard Rock. controlled chiselling in the campus of School building. Recovery of stones to the tune of 18.43 cubic metre (Eighteen decimal four three) quantity @ Rs.300/- (Rupees three hundred) per cubic metre shall be effected from the contractor's running bills on pro-rata basis as per actual quantity executed. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him in all cases.	122.88	Cubic metre			Per Cubic metre	
					Total :-		

Executive Engineer,
 Palampur Division,
 HPPWD Palampur

SCHEDULE OF QUANTITY

Name of work:- Repair of RRD on Link road to Tamber Km 0/00 to 0/700. (SH:- Providing & Laying C.C. Pavement at Rd 0/200 to 0/235). **SDRF**

0/200 to 0/235). SDRF						
Department of Road on Link road to Lamber Km 0/00 to 0/700. (SH):- Providing & Laying C.C. Pavement at Rd						
Sr. No.	Description of Item	Quantity	Estimated cost Rs.		99225.00	
			Earnest Money Rs.		2000.00	
			Time Limits		Two Months	
1	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	15.75	In Figures	In Word	Unit	Amount
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur.

SCHEDULE OF QUANTITY

Name of work:- C/o Cow Shed at Kudan Dehal P.O. Jia Tehsil Palampur Distt. Kangra H.P. (SH:- C/o U-Shape drain for Urine waste & steel for Animal tie Anchor work). **Deposit**

Urine waste & steel for Animal tie Anchor work), Deposit							Estimated cost Rs.	
							Earnest Money Rs.	
Sr. No.	Description of Item	Quantity	Rate		Unit	Time Limits		
			In Figures	In Word		Two Month	Amount	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	15.48			Per cubic metre		98826.00	
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arrisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	11.72			Per cubic metre.		2000.00	
3	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	351.26			Per Kilogram			
4	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	74.65			Per Kilogram			
	Total							

Executive Engineer,
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Cow Shed at Kudan Dehal P.O. Jia Tehsil Palampur Distt. Kangra H.P. (SH:- P/F Glass panes in ventilators, Doors & Steel over Khurli). Deposit				Estimated cost Rs.		97520.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing & fixing 4.00 mm thick glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	60.92			Per Square Metre	
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.60			Per cubic metre	
3	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	0.60			Per cubic metre.	
4	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	450.00			Per Kilogram	
	Total					

Executive Engineer,
Palampur-Division
HP.PWD Palampur.

SCHEDULE OF QUANTITY						
Name of work:- C/o Dharamshala Dadh Palampur Holta Chadhiar road Km 0/00 to 40/500 (MDR-78). (SH):- C/o U-Shape Drain at various Rd's between Km 15/00 to 20/500). Deposit from E.E. Bhawarna						
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
			Time Limits			Two Months
			Earnest Money Rs.			2000.00
			Estimated cost Rs.			99200.00
1	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government .	1600.00			Per Running metre	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Dharamshala Dadh Palampur Holta Chadhiar road Km 0/00 to 40/500 (MDR-78). (SH:- Dressing of berms at various Rd's between Km 15/00 to 20/500). Deposit from E.E. Bhawarna					Estimated cost Rs.	99828.00
					Earnest Money Rs.	2000.00
					Time Limits	Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Maintenance of Earthen shoulder (filling with fresh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government .	1692.00			Per square metre.	
	Total					

Executive Engineer,

Palampur Division

HP PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Parour Lahla Gopalpur Rakh Ghamrota Jyven Sukeri Kandi Bandla Palampur Road Km 0/00 to 33/00. (SH:- C/o R/wall at Rd 11/190 to 11/200).		Estimated cost Rs.		99376.00
		Earnest Money Rs.		2000.00
		Time Limits		Two Months
		Quantity	In Figures	In Word
Sr. No.	Description of Item	Quantity	In Figures	In Word
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	7.20		Per cubic metre
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge: as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	21.60		Per cubic metre.
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	16.00		Each
				Total

Executive Engineer
Palampur Division
HP PWD Palampur.

(21)

SCHEDULE OF QUANTITY						
Name of work:- Balance work of road from village Rakh to Usthehar Km 0/00 to 0/600. (SH:- C/o edge wall slab over kahal & C.C. Pavement in path). MNP						
			Estimated cost Rs.		51101.00	
			Earnest Money Rs.		1100.00	
			Time Limits		Two Months	
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	2.77			Per cubic metre	
2	Providing and laying Plain/reinforced cement concrete in substructure R.C.C grade M 20 (1:2:4) nominal mix complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	6.79			Per cubic metre.	
3	Supplying, fitting, and placing HYSD bar reinforcement in superstructure complete as per drawing and technical specifications Clauses 1002, 1010 and 1202 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	0.06			Per Metric Tonne	
4	Steel work welded in built up section Trusses and Framed work including cutting, hoisting, fixing in position and applying a priming coat of red lead paint in grating, framed guard, bar ladders railing bracket and similar works as per direction of engineer in charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	21.35			Per Kilogramme	
			Total			

Executive Engineer
Palampur Division
HP PWD Palampur

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY							98438.00
Name of work:- C/o Jeppable road from main road to Sh. Partap Chand House Mohal G.P. Upper Dadh. (SH:- Providing and Laying C.C. Pavement). VKVNY Deposit 1.00 Lacs					Estimated cost Rs.		
					Earnest Money Rs.		2000.00
					Time Limits		Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	15.75			Per cubic metre.		
	Total						

Executive Engineer,
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work:- Restoration of rain damages on Dharamshala Yol Dadh Holta Chadhar sandhole road at Km. 33/000 to 40/000
S.W.:-P/L 1:3:6 etc.

Work No. 23

Estimated Cost :- Rs. 99,100/-

Earnest Money :- Rs. 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50m. (average lead 25 m) as per Technical Specification Clause 307. Manual means, as per the Directions of Engineer-in-Charge including carriage of materials, with in all leads, lifts and other incidental.	1280.00	Running metre			Per Running metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government..	4.20	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
Palampur Division
H.P.PWD Palampur

Schedule of Quantity

Estimated Cost :- Rs. 98,627/-
 Earnest Money :- Rs. 2000/-
 Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construct of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	8.42	Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specifications section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	20.83	Cubic metre			Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	6.00	Numbers			Each	
4	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	7.47	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
 Palampur Division
 H.P.PWD Palampur

Schedule of Quantity

Name of Work:- C/O Pucca path from Sh. Paras Ram house towards Smt. Beena Devi house Ward No. 1 in GP Sungal
S.W.-:C/O CC Pavement at RD 0/000 to 0/042. (Deposit)

Work No. 25

Estimated Cost :- Rs. 48,195/-
Earnest Money :- Rs.1000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per Direction of Engineer -in -charge i/c carriage of materials within all leads,lifts and other incidentals by Manual Means.The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	3.78			Per Cubic metre.	
2	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203. includingthe cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	6.30			Per Cubic metre.	
					Total :-	

Executive Engineer
Palampur Division
H.P.PWD Palampur

Schedule of Quantity

Name of Work:- Chowki Patwar Khana to Rajpur Kalu-Di-Hatti kesar Bag Colony Road Km. 0/000 to 2/130
(S. W. :- C/O U-shape drain from RD 2/030 to 2/063(MC Deposit)

Estimated Cost :- Rs.99,099/-

Earnest Money :- Rs. 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	19.80	Cubic metre			Per Cubic metre	
2	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203. includingthe cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax or any other taxes imposed by the Government.	14.85	Cubic metres			Per Cubic metre.	
						Total :-	

Executive Engineer
Palampur Division
H.P.PWD Palampur

Work No. 27

Name of Work:- Chowki Patwar Khana to Rajpur Kalu-Di-Hatti kesar Bag Colony Road Km. 0/000 to 2/130
(S. W. :- C/O U-shape drain from RD 2/063 to 2/095.50(MC Deposit))

Estimated Cost :- Rs.97,629/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months.

Schedule of Quantity

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	19.50			Per Cubic metre	
2	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203. includingthe cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	14.63			Per Cubic metre.	
					Total :-	

Executive Engineer
Palampur Division
H.P.PWD Palampur

Schedule of Quantity

Work of Work:- Restoration of rain damages on Dharman to speedu at RD. 0/000 to 5/000

S.W:- C/O B/wall Pusta at RD 4/758 to 4/770

Work No. 28

Estimated Cost :- Rs. 98,533/-

Earnest Money :- Rs. 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	21.91	Cubic metre			Per Cubic metre	
2	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	16.00	Numbers			Each	
						Total :-	

Executive Engineer
Palampur Division
H.P.PWD Palampur

Schedule of Quantity

Name of Work:- Restoration of rain damages on Dharman to specu at RD. 0/000 to 5/000
B/wall at RD 4/770 to 4/783.80

S.W:-6/0

Work No. 29

Estimated Cost :- Rs. 99,581/-

Earnest Money :- Rs. 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	16.56	Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	22.08	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
Palampur Division
H.P.PWD Palampur

Schedule of Quantity

Name of Work:- Restoration of rain damages on Yol Dadh Palampur road 27/000 to 33/000
S.W.:- C/O B/wall from RD 29/225 to 29/234.35

Work No. 30

Estimated Cost :- Rs. 99,761/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of sumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	6.36	Cubic metre			Per Cubic metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government..	20.10	Cubic metre			Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204,307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	13.00	Numbers			Each	
						Total :-	

Executive Engineer
Palampur Division
H.P.PWD Palampur

Schedule of Quantity

Estimated Cost :- Rs. 97,015/-
 Earnest Money :- Rs. 2000/-
 Time limit : Three Months.

Name of Work:- Restoration of rain damages on link road from Khalet to Sidhpur Sarkari road
 S.W.:- C/O R/wall from RD 2/113.60 to 2/150

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	7.30	Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	21.06	Cubic metre			Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	7.00	Numbers			Each	
4	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	3.71	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
 Palampur Division
 H.P.PWD Palampur

Schedule of Quantity
Name of Work:- Construction of SDRF HQ Campus at Bagora Palampur, Distt. Kangra (Himachal Pradesh)
S.H.:- Topographical Survey Contour Plan)

Estimated Cost :- Rs. 98,070/-

Earnest Money :- Rs. 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Topographical Survey Contour Plan SDRF HQ Campus at Bagora Palampur and submitted the test result complete in all respect. The rate is including GST, toll tax, sale tax or other taxes imposed by the Government.	26868.48			Per Square Metre	
					Total :-	

Executive Engineer
Palampur Division
H.P. PWD Palampur

Schedule of Quantity

Work :- C/O Jeepable road from Sham Lal house to Suresh Kumar house W. No. 1 G.P. Band Vihar (Deposit)
P/L interlocking paver blocks at RD 0/000 to 0/022

Work No. **33**

Estimated Cost :- Rs. 99,365/-
Earnest Money :- Rs. 2000/-

Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	3.00	Cubic metres			Per Cubic metre.	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	67.58	Square Metre			Per square metre	
3	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix, P.C.C grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802, 803, 1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	1.00	Cubic metre			Per Cubic metre	
						Total :-	


Executive Engineer
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o R/wall to protect the land of Sh. Sanjay kumar S/o Sh. Ramesh ward No. 5 GP Thalla Uarla. (SH:- C/o R/wall). Deposit 0.75 Lacs

74561.00

1500.00

Two Months

Estimated cost Rs.

Earnest Money Rs.

Time Limits

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	8.75			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1:5:10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall. Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	16.77			Per cubic metre	
			Total			

Executive Engineer,
Palampur Division
HP PWD Palampur