



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Telephone No: 01782-233017

e-mail: ee-ram-hp@nic.in

No. PW/ RMP/TA-I/Publication/2025-
To

~~8909-10~~
8911-12,


Dated:- 18/12/25

→ The Executive Engineer (IT Cell),
Nigam Bihar, H.P. Shimla-2.

Subject:- Publication of tender Notice.

Enclosed please find herewith the tender Notice of various works as given in the tender inviting tender for uploading on department website as per notification Special Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2024 dated 03 January 2024 as the works mentioned in the tender Notice are urgent nature and public interest.

DA: - As above.

Executive Engineer,
B&R Division HPPWD,
Rampur. 



HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

Telephone No: 01782-233017
e-mail: ee-ram-hp@nic.in

NOTICE INVITING TENDER

Sealed item rate tender(s) on PWD form No. 6 & 8 are hereby invited by the Executive Engineer, B&R Division, HPPWD, Rampur Distt. Shimla (HP) on behalf of the Governor of H.P. for the following works from registered contractors in HP.PWD (B&R) in appropriate class so as to reach in this office on **02.01.2026** upto 10:30 A.M. and will be opened on the same day at 11:00 A.M. in the presence of contractors or their authorized representative who wish to be present at that time. The application for obtaining the tender form will be received on **01.01.2026** between 10:00 A.M. to 2:00 P.M. The tender form can be had from this office against cash payment (Non-refundable) on **01.01.2026** between 02:00 PM to 5:00 PM.

The earnest money in the shape of National Saving Certificate/Time Deposit Account/ Saving Account of the Post office in Himachal Pradesh duly pledged in favour of the Executive Engineer, B&R Division, HP. PWD, Rampur Bushahr Distt. Shimla H.P. must accompany with the tender form. Ambiguous/Telegraphically/conditional tenders or tender by FAX shall not be entertained/considered in any case. The tenders without earnest money shall summarily be rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer, B&R Division, HP.PWD, Rampur Bushahr reserve the right to reject/accept any offer of tender without assigning any reasons.

Sr. No.	Name of work	Estimated cost	Earnest money	Cost of tender form	Time limit
1	R/R damages on Palzara to Payee road Km. 0/000 to 8/000 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips, dressing of road side drain/culverts etc. at various RDs)	98,750/-	2,000/-	350/-	One month
2	R/R damages on Sunda Jaguni Sanei road Km. 0/000 to 7/150 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips, dressing of road side drain/culverts etc. at various RDs)	98,750/-	2,000/-	350/-	One month
3	R/R damages on Rattanpur Uchi Shah Dofda road Km. 0/000 to 16/780 (SH:- Hiring of Dumper for carriage of debris/muck from RD 10/135 to 10/225) Job-1)	96,000/-	2,000/-	350/-	One month
4	Rattanpur Uchi Shah Dofda road Km. 0/000 to 16/780 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips, dressing of muck from RD 10/135 to 10/225)	98,750/-	2,000/-	350/-	One month
5	R/R damages on Shanadhar Shraikoti road Km. 0/000 to 8/200 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips, dressing of Katcha road surface/berms and cleaning of road side drain/culverts in Km. 5/000 to 8/200)	98,750/-	2,000/-	350/-	One month
6	R/R damages on Badrash Brandli road Km. 0/000 to	98,750/-	2,000/-	350/-	One

	34/090 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips, cleaning of road side drain/culverts etc. at various RDs in Km. 27/000 to 34/090)				month
7	R/R damages on various roads in Rampur Section under Rampur Sub Division (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips, dressing of berms and clearance of road side drain at various RDs)	98,750/-	2,000/-	350/-	One month
8	R/R damages on Racholi Dansa Lalsa road Km. 0/000 to 14/000 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of slips, clearance of road side drain on various RDs)	98,750/-	2,000/-	350/-	One month
9	R/R damages on Lalsa Shandal Bahlidhar road Km. 0/000 to 9/500 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips, cleaning of road side drain/culverts etc. at various RDs in Km. 0/000 to 6/000)	98,750/-	2,000/-	350/-	One month
10	R/R damages on various roads in Nogli Section under Rampur Sub Division (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips, at various RDs)	98,750/-	2,000/-	350/-	One month
11	R/R damages on various roads in Taklech-II Section under Taklech Sub Division (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips, at various RDs)	98,750/-	2,000/-	350/-	One month
12	R/R damages on Rohru Sungri Bahli Taklech Nogli road Km. 27/000 to 80/000 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips, at RD 36/000 to 45/000)	98,750/-	2,000/-	350/-	One month
13	R/R damages on various roads in Deothi Section under Taklech Sub Division (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips, at various RDs)	98,750/-	2,000/-	350/-	One month
14	R/R damages on various roads in Bahli Section under Taklech Sub Division (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips, at various RDs)	98,750/-	2,000/-	350/-	One month
15	R/R damages on various roads in Taklech-I Section under Taklech Sub Division (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips, at various RDs)	98,750/-	2,000/-	350/-	One month
16	R/R damages on various roads in Deothi Section under Taklech Sub Division (SH:- Supplying and stacking at site approved crushed sand at various RDs)	98,800/-	2,000/-	350/-	One month
17	Hiring of Backhoe loader and Dumper in HRTC road for loading and carriage of landslide/muck to the dumping site and GBSSS Rampur for loading and carriage of land side on stairs to the dumping site)	41,000/-	1,000/-	350/-	One month
18	R/R damages on various roads in Dansa Section under Rampur Sub Division (SH:- Supplying and	97,500/-	2,000/-	350/-	One month

	stacking at site approved crushed sand at various RDs)				
19	R/R damages on various roads in Sarahan Section under Sarahan Sub Division (SH:- Hiring of Tipper for removal of slips and debris)	98,800/-	2,000/-	350/-	One month
20	R/R damages on Rampur Gaura Mashnoo Jeori road Km. 0/000 to 61/000 (Portion 52/000 to 61/000) (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips, dressing of Katcha road surface/berms and cleaning of road side drain/culverts etc. at various RDs)	98,750/-	2,000/-	350/-	One month
21	R/R damages on Nanan Dharali road Km. 0/000 to 4/000 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips, dressing of Katcha road surface/berms and cleaning of road side drain/culverts etc. at various RDs)	98,750/-	2,000/-	350/-	One month
22	R/R damages on Manglad Runpoo road Km. 0/000 to 6/400 and Kinoo Bhagawat road Km. 0/000 to 7/750 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips, dressing of Katcha road surface/berms and cleaning of road side drain/culverts etc. at various RDs)	98,750/-	2,000/-	350/-	One month
23	R/R damages on Bajwa Bridge to Village Bajwa Km. 0/000 to 3/000 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips, dressing of Katcha road surface/berms and cleaning of road side drain/culverts etc. at various RDs)	98,750/-	2,000/-	350/-	One month
24	R/R damages on Kinoo Bhagawat road Km. 0/000 to 7/750 (SH:- Hiring of Tipper for removal of slips and debris at various RDs)	98,800/-	2,000/-	350/-	One month
25	R/R damages on Jeori Nawaroo Bonda road Km. 0/000 to 6/790 (SH:- Supplying and stacking at site approved crushed sand at various RDs)	98,800/-	2,000/-	350/-	One month
26	R/R damages on Labana Sadana road Km. 0/000 to 8/000 and Pajidhar Chandi Branda road Km. 0/000 to 10/000 (SH:- Supplying and stacking at site approved crushed sand at various RDs in Ganvi Labana Sadana and Pajidhar Chandi Branda)	98,800/-	2,000/-	350/-	One month
27	R/R damages on Rampur Gaura Mashnoo Jeori Sarahan road Km. 0/000 to 61/000 (Portion 52/000 to 61/000)(SH:- Supplying and stacking at site approved crushed sand at various RDs)	98,800/-	2,000/-	350/-	One month
28	R/R on damages Chasni Mandhog road Km. 0/000 to 3/300 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips on various RDs)	98,800/-	2,000/-	350/-	One month
29	R/R damages on Shanadhar Shraikoti road Km. 0/000 to 8/200 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips, dressing of berms, cleaning of road side drain/culverts in Km. 0/000 to 5/000)	98,750/-	2,000/-	350/-	One month
30	R/R damages on Racholi Dansa Lalsa road Km.	98,750/-	2,000/-	350/-	One

	0/000 to 14/000 (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips, cleaning of road side drain/culverts etc. at various RDs in Km. 7/000 to 14/000)				month
31	R/R damages on Keo Koot Kinf road Km. 0/000 to 13/500 (SH:- Hiring of tipper for removal of slips/debris at various RDs)	98,000/-	2,000/-	350/-	One month
32	R/R damages on Mashnoo Taklech road Km. 0/000 to 48/000 (portion Km. 0/000 to 12/000) (SH:- Deployment/Hiring of JCB/Excavator-cum-loader for removal of snow/slips, dressing of Katcha road surface/berms and cleaning of road side drain/culverts etc. at various RDs)	98,750/-	2,000/-	350/-	One month
33	C/O Dust Bin Shed in MGMSC Khaneri Tehsil Rampur Distt. Shimla H.P. (SH:- C/O Dust Bin)	69,952/-	1,500/-	350	10 days

Terms and conditions:-

1. The contractors/firms are required to quote their rates clearly both in words as well as in figures, failing which the tender is liable to be rejected.
2. The contractor will produce show their enlistment/renewal documents at the time of obtaining tender form.
3. Latest Income tax and sale tax clearance certificates as well as Pan Number and GST number must be attached with the application failing which tender documents will not be issued.
4. The tender forms will be issued to only those contractors who have not more than two works in hand in any of HP.PWD. Circles.
5. The contractor will have to submit the proof. of registration under Employees Providing Funds & Miscellaneous provision Act. 1952 at the time of tender. Failure to observe this condition shall render the tender of the contractor liable to summary rejection.

Executive Engineer,
Rampur Division (B&R),
HPPWD, Rampur Bsr.

No: - RMP/Tender/2025 - 8918-19.

Dated:- 18-12-2025

Copy forwarded for information:-

1. The Superintending Engineer 11th Circle HPPWD, Shimla.
2. Copy to Notice Board.

Executive Engineer,
Rampur Division (B&R),
HPPWD, Rampur Bsr.

SCHEDULE OF QUANTITY

Name of Work:- R/R damages on Palzara to Payee road km 0/000 to 8/00 .

(SH:- Deployment/Hiring of JCB/Excavator-cum loader for removal of snow/ slips, cleaning of road side drain/culverts etc at various Rds)

Estimated cost :- **98,750.00**
 Earnest money :- **2,000.00**
 Time allowed:- **OneMonth**

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for eath cutting/excavation/filling/ removal of snow/slips and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour			

H
 Executive Engineer,
 Rampur Division (B&R)
 P.P.W.D., Rampur.

SCHEDULE OF QUANTITY

Name of Work:- R/R damages on Sunda Jaguni sanei road km 0/000 to 7/150.
(SH:- Deployment/Hiring of JCB/Excavator-cum loader for removal of snow/ slips, cleaning of road side drain/culverts etc at various Rd's)

Estimated cost :-
Earnest money :-
Time allowed:-

98,750.00
2,000.00
OneMonth

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for eath cutting/excavation/filling/ removal of snow/slips and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour			

Executive Engineer,
Rampur Division (B&R)
H.P.W.D., Rampur.


SCHEDULE OF QUANTITY

Name of Work:- R/R Damages on Rattanpur Uchi Shah Dofda road Km 0/00 to 16/780

(SH:- Hiring of Dumper for carriage of debris/muck from Rd 10/135 to 10/225), job-1

Estimated cost :-
Earnest money :- 2,000.00
Time allowed:- One month

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of dumper of heavy Commercial Vehical category for carriage of earth /debris / boulder and other construction materials from various location etc. Including wages of tipper driver 1 cleaner including P.O.L. Any repair /damaged during work will be absulte responsibility of the contractor/ on onwer tipper has to work at least eight hours per day, only actual working days shall be accounted for to payment. No payment will be made of holidays as well as on holidays if there is no work to the entire satisfaction of Engineer-in-charge.	12.00	Per Day			
	Total:-					


 Executive Engineer,
 Rampur Division (B&R)
 PWD, Rampur.

SCHEDULE OF QUANTITY

Name of Work:- R/R Damages on Rattanpur Uchi Shah Dofda KM 0/000 to 16/780.

(SH:- Deployment/Hiring of CB/Excavator-cum loader for loading,dressing of muck from Rd 10/135 to 10/225).

Estimated cost :- **98,750.00**
 Earnest money :- **2,000.00**
 Time allowed:- **One Month**

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for earth cutting/excavation/ filling/slips and clearance of blocked side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge	79.00	Per hour			
Total:-						

Executive Engineer,
 Rampur Division (B&R)
 P.PWD, Rampur.

SCHEDULE OF QUANTITY

Name of Work:- R/R damages on Shanadhar Shaikkoti road Km 0/00 to 8/200.
(SH:- Deployment/Hiring of JCB/Excavator-cum loader for removal of snow/ slips, dressing of katcha road surface/berms and cleaning of road side drain/culverts in Km 5/00 to 8/200)

Estimated cost :- **98,750.00**
Earnest money :- **2,000.00**
Time allowed:- **One Month**

Sr. No	Description of items		Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
	1	2	3	4	5	6	7
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for earth cutting/excavation/filling/ removal of snow/slips and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.		79.00	Per hour			

H
Executive Engineer,
Rampur Division (B&R)
B.P.W.D., Rampur.

SCHEDULE OF QUANTITY

Estimated cost :- **98,750.00**
 Earnest money :- **2,000.00**
 Time allowed:- **One Month**

Name of Work:- R/R damages on Badrash Brandli road km 0/000 to 34/090 .
 (SH:- Deployment/Hiring of JCB/Excavator-cum loader for removal of snow/ slips, cleaning of road side drain/culverts etc at various Rd's intKm 27/00 to 34/090)

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for eath cutting/excavation/filling/ removal of snow/slips and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour			

Executive Engineer,
 Rampur Division (B&R)
 A.P.W.D., Rampur.

SCHEDULE OF QUANTITY

Name of Work:- R/R damages on various roads in rampur Section under Rampur Sub Division.
(SH:- Deployment/Hiring of JCB/Excavator-cum loader for removal of snow/slips, dressing of berms and clearance of road side drain in various roads under Rampur section)

Estimated cost :- **98,750.00**
Earnest money :- **2,000.00**
Time allowed:- **OneMonth**

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for removal of slow/slips and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	3	Per hour	79.00		

Executive Engineer,
Rampur Division (B&R)
HP.PWD., Rampur.

SCHEDULE OF QUANTITY

Name of Work:- R/R damages on Racholi Dansa lalsa road Km 0/00 to 14/00.
(SH:- Deployment/Hiring of JCB/Excavator-cum loader for removal of slips,clearance of road side drain on various Rds)

Estimated cost :- **98,750.00**
Earnest money :- **2,000.00**
Time allowed:- **OneMonth**

Sr. No	Description of Items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for removal of snow/slips and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour			

H
Executive Engineer,
Rampur Division (B&R)
P.W.D., Rampur.

SCHEDULE OF QUANTITY

Estimated cost :- **98,750.00**
 Earnest money :- **2,000.00**
 Time allowed:- **OneMonth**

Name of Work:- R/R damages on Lalsa Shandal ballidhar road km 0/000 to 9/500 .

(SH:- Deployment/Hiring of JCB/Excavator-cum loader for removal of snow/ slips, cleaning of road side drain/culverts etc at various Rd's in Km 0/00 to 6/00)

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for eath cutting/excavation/filling/ removal of snow/slips and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour			


Executive Engineer,
 Rampur Division (B&R)
 PWD., Rampur.

SCHEDULE OF QUANTITY

Name of Work:- R/R damages on various roads in Nogli Section under Rampur Sub-Division
(SH:- Deployment/Hiring of JCB/Excavator-cum loader for removal of snow/ slips, at various Roads)

Estimated cost :- **98,750.00**
Earnest money :- **2,000.00**
Time allowed:- **OneMonth**

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for eath cutting/excavation/filling/ removal of snow/slips and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour			


Executive Engineer,
Rampur Division (B&R)
P.P.W.D., Rampur.

SCHEDULE OF QUANTITY

Name of Work:- R/R damages on various roads in Takleeh-11 Section under Takleeh Sub Division.
(SH:- Deployment/Hiring of JCB/Excavator-cum loader for removal of slips on various roads)

Estimated cost :- **98,750.00**
Earnest money :- **2,000.00**
Time allowed:- **OneMonth**

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for removal of snow/slips and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour			

Executive Engineer,
Rampur Division (B&R)
P.P.W.D., Rampur.

SCHEDULE OF QUANTITY

Name of Work:- R/R damages on Rohru Sungri Bahl Takleeh Noghi road Km 27/00 to 80/00 .
(SH:- Deployment/Hiring of JCB/Excavator-cum loader for removal of slips at Km 36.00 to 45/00

Estimated cost :- **98,750.00**
Earnest money :- **2,000.00**
Time allowed:- **OneMonth**

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for removal of snow/slips and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair / breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper / truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour			

H
Executive Engineer,
Rampur Division (B&R)
B&RWD., Rampur.

SCHEDULE OF QUANTITY

Name of Work:- R/R damages on various roads in Deothi Section under Takleth Sub Division.
(SH:- Deployment/Hiring of JCB/Excavator-cum loader for removal of slips on various roads)

Estimated cost :- **98,750.00**
Earnest money :- **2,000.00**
Time allowed:- **OneMonth**

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for removal of snow/slips and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour			

Executive Engineer,
Rampur Division (B&R)
P.P.WD., Rampur.

SCHEDULE OF QUANTITY

Estimated cost :- **98,750.00**
 Earnest money :- **2,000.00**
 Time allowed:- **One Month**

Name of Work:- R/R damages on various roads in Bahli Section under Takeleh Sub Division.

(SH:- Deployment/Hiring of JCB/Excavator-cum loader for removal of snow/slips at various roads)

Sr. No	Description of Items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for removal of snow/slips and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour			

Executive Engineer,
 Rampur Division (B&R)
 P.P.WD., Rampur.

SCHEDULE OF QUANTITY

Name of Work:- R/R damages on various roads in Taklech-1 Section under Taklech Sub Division.
(SH:- Deployment/Hiring of JCB/Excavator-cum loader for removal of slips on various roads)

Estimated cost :- **98,750.00**
Earnest money :- **2,000.00**
Time allowed:- **One Month**

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for removal of snow/slips and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour			

H
Executive Engineer,
Rampur Division (B&R)
PP PWD, Rampur.

SCHEDULE OF QUANTITY

Estimated cost :- 98,800.00
 Earnest money :- 2,000.00
 Time allowed:- OneMonth

Name of Work:- R/R damages on various roads under Deothi Section under Takleth Sub-Division
 (SH :- Supplying and stacking at site approved crushed sand at various RD's on various roads).

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	2	3	4	5	6	7
1	Supplying and stacking at site of approved crushed sand consisting of natural sand, hard, durable, clean, and free from adherent coatings, organic impurities, or any deleterious materials. The item includes cost of all operations such as collection, royalty, loading, unloading, mechanical transportation, all leads and lifts, and proper stacking at site complete as per the directions of Engineer-in-charge	76.00	Per Cubic Metre			
	Total:-					

H
 Executive Engineer,
 Rampur Division (B&R)
 P.P.W.D., Rampur.

SCHEDULE OF QUANTITY

Name of Work:- Hiring of Backhoe loader and Dumper in HRTC road for loading and carriage of landslide/muck to the dumping site and GBSSS Rampur Bsr. For loading and carriage of land slide on stairs to the dumping site)

Estimated cost **41,000.00**
 Earnest money **1,000.00**
 Time allowed:-
 One month

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
		3	4	5	6	7
1	Hiring of dumper of heavy Commercial Vehical category for carriage of earth /debris / boulder and other construction materials from various location etc. Including wages of tipper driver 1 cleaner including P.O.L. Any repair /damaged during work will be absolute responsibility of the contractor/ on owner tipper has to work at least eight hours per day, only actual working days shall be accounted for to payment. No payment will be made of holidays as well as on holidays if there is no work to the entire satisfaction of Engineer-in-charge.	12.00	Per Day			
2	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for earth cutting/excavation/ filling/slips and clearance of blocked side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	399.00	Per hour			
Total:						

Executive Engineer,
 Rampur Division (B&R)
 P.PWD., Rampur.

SCHEDULE OF QUANTITY

Estimated cost :- 97,500.00

Earnest money :-	2,000.00
------------------	----------

Time allowed:- OneMonth

Name of Work:- R/R damages on various roads in Dansa Section under Rampur Sub-Division (SH :-Supplying and stacking at site approved crushed sand at various Roads)	v
--	---

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	2	3	4	5	6	7
1	Supplying and stacking at site of approved crushed sand consisting of natural sand, hard, durable, clean, and free from adherent coatings, organic impurities, or any deleterious materials. The item includes cost of all operations such as collection, royalty, loading, unloading, mechanical transportation, all leads and lifts, and proper stacking at site complete as per the directions of Engineer-in-charge	76.00	Per Cubic Metre			
					Total:-	

Executive Engineer,
Rampur Division (B&R)
P.P.WD., Rampur.

SCHEDULE OF QUANTITY

Estimated cost :-

98,800.00

Earnest money :-

2,000.00

Time allowed:-

OneMonth

Name of Work:- R/R damages on various roads in Sarahan Section under Sarahan Sub-Division

(SH :- Hiring of Tipper for removal of slips and debris).

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1		3	4	5	6	7
1	Hiring of tipper of Light Commercial Vehical category for carriage of earth /debris / boulder and other construction materials from various location etc. Including wages of tipper driver 1 cleaner including P.O.L. Any repair /damaged during work will be absulte responsibility of the contractor/ on owner tipper has to work at least eight hours per day, only actual working days shall be accounted for to payment. No payment will be made of holidays as well as on holidays if there is no work to the entire satisfaction of Engineer-in-charge.	19.00	Per Day			
					Total:-	

Executive Engineer,
Rampur Division (B&R)
~~HP PWD~~, Rampur.

~~QHP~~ P.W.D., Rampur.

SCHEDULE OF QUANTITY

Estimated cost :- **98,750.00**
 Earnest money :- **2,000.00**
 Time allowed :- **One Month**

Name of Work:- R/R damages on Rampur Gaura Mashnoo Jeori road km 0/000 to 61/000 (Portion 52/000 to 61/000) in Tehsil Rampur Distt. Shimla
 (SH:- Deployment/Hiring of JCB/Excavator-cum loader for removal of snow/ slips, dressing of Katcha road surface/berms and cleaning of road side drain/culverts etc at various Rd's)

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for eath cutting/excavation/filling/ removal of snow/slips and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour			

H
 Executive Engineer,
 Rampur Division (B&R)
 P.P.W.D., Rampur.

SCHEDULE OF QUANTITY

Name of Work:- R/R damages on Nanan Dharali road km 0/000 to 4/000 in Tehsil Rampur Distt. Shimla

(SH:- Deployment/Hiring of JCB/Excavator-cum loader for removal of snow/ slips, dressing of katcha road surface/berms and cleaning of road side drain/culverts etc at various Rd's)

Estimated cost :- **98,750.00**
 Earnest money :- **2,000.00**
 Time allowed:- **One Month**

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for eath cutting/excavation/filling/ removal of snow slips and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour			

11
 Executive Engineer,
 Rampur Division (B&R)
 P.W.D., Rampur.

SCHEDULE OF QUANTITY

Estimated cost :- **98,750.00**
 Earnest money :- **2,000.00**
 Time allowed:- **One Month**

Name of Work:- R/R damages on Manglad Rumpoo road km 0/000 to 6/400 and Kinoo Bhagawat road km 0/000 to 7/750

(SH:- Deployment/Hiring of JCB/Excavator-cum loader for removal of snow/ slips, dressing of katcha road surface/berms and cleaning of road side drain/culverts etc at various Rd's)

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for earth cutting/excavation/filling/ removal of snow slips and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour			

H
 Executive Engineer,
 Rampur Division (B&R)
 P.W.D., Rampur.

SCHEDULE OF QUANTITY

Name of Work:- R/R damages on Bajwa Bridge to Village Bajwa km 0/000 to 3/000

(SH:- Deployment/Hiring of JCB/Excavator-cum loader for removal of snow/ slips, dressing of katcha road surface/berms and cleaning of road side drain/culverts etc at various Rd's)

Estimated cost :- **98,750.00**
 Earnest money :- **2,000.00**
 Time allowed:- **OneMonth**

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for eath cutting/excavation/filling/ removal of snow slips and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour			

H
 Executive Engineer,
 Rampur Division (B&R)
 PWD., Rampur.

SCHEDULE OF QUANTITY

98,800.00

2,000.00

OneMonth

Name of Work:- R/R damages on Kinoo Bhagawat road Km 0/00 to 7/750 in Kinoo Section under Sarahan Sub-Division (SH :- Hiring of Tipper for removal of slips and debris).

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of tipper of Light Commercial Vehical category for carriage of earth /debris / boulder and other construction materials from various location etc. Including wages of tipper driver 1 cleaner including P.O.L. Any repair /damaged during work will be absulte responsibility of the contractor/ on owner tipper has to work at least eight hours per day, only actual working days shall be accounted for to payment. No payment will be made of holidays as well as on holidays if there is no work to the entire satisfaction of Engineer-in- charge.	19.00	Per Day			
					Total:-	

Executive Engineer,
Rampur Division (B&R)
~~MP.PWD~~, Rampur.

SCHEDULE OF QUANTITY

98,800.00

2,000.00

OneMonth

Name of Work:- R/R damages on Jeori Nawaroo Bonda road Km 0/00 to 6/790 in Jeori Section under Sarahan Sub-Division (SH :-Supplying and stacking at site approved crushed sand at various RDs under Jeori Nawaroo Bonda road).

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of tipper of Light Commercial Vehical category for carriage of earth /debris / boulder and other construction materials from various location etc. Including wages of tipper driver 1 cleaner including P.O.L. Any repair /damaged during work will be absulte responsibility of the contractor/ on owner tipper has to work at least eight hours per day, only actual working days shall be accounted for to payment. No payment will be made of holidays as well as on holidays if there is no work to the entire satisfaction of Engineer-in-charge.	76.00	Per Cubic Metre			
					Total:-	

Executive Engineer,
Rampur Division (B&R)
HP&WD., Rampur.

SCHEDULE OF QUANTITY

Estimated cost :- **98,800.00**
 Earnest money :- **2,000.00**
 Time allowed:- **One Month**

Name of Work:- R/R damages on Labana Sadana road Km 0/00 to 8/000 and Pajidhar Chandī Branda road km 0/000 to 10/000 in Ganvi Section under Sarahan Sub-Division
 (SH :- Supplying and stacking at site approved crushed sand at various RD's in Ganvi Labana Sadana and Pajidhar Chandī Branda)

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	1	2	3	4	5	6
1	Supplying and stacking at site of approved crushed sand consisting of natural sand, hard, durable, clean, and free from adherent coatings, organic impurities, or any deleterious materials. The item includes cost of all operations such as collection, royalty, loading, unloading, mechanical transportation, all leads and lifts, and proper stacking at site complete as per the directions of Engineer-in-charge	76.00	Per Cubic Metre			7
					Total:-	

Executive Engineer,
 Rampur Division (B&R)
 H.P.W.D., Rampur.

SCHEDULE OF QUANTITY

Name of Work:- R/R damages on Rampur Gaura Mashnoo Jeori Sarahan road Km 0/00 to 61/000 (Portion:- 52/000 to 61/000) in Jeori Section under Sarahan Sub-Division

Estimated cost :- 98,800.00
Earnest money :- 2,000.00
Time allowed:- OneMonth

(SH :- Supplying and stacking at site approved crushed sand at various RD's under R G M T S road).

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	1	3	4	5	6	7
1	Supplying and stacking at site of approved crushed sand consisting of natural sand, hard, durable, clean, and free from adherent coatings, organic impurities, or any deleterious materials. The item includes cost of all operations such as collection, royalty, loading, unloading, mechanical transportation, all leads and lifts, and proper stacking at site complete as per the directions of Engineer-in-charge	76.00	Per Cubic Metre			
					Total:-	

Executive Engineer,
Rampur Division (B&R)
P.P.W.D., Rampur.


SCHEDULE OF QUANTITY

Name of Work:- R/R damages on Chasni Mandhog road Km 0/00 to 3/300

(SH:- Deployment/Hiring of JCB/Excavator-cum loader for removal of slips at various Rds)

Estimated cost :- **98,750.00**
 Earnest money :- **2,000.00**
 Time allowed:- **OneMonth**

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for removal of snow/slips and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair / breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour			


 Executive Engineer,
 Rampur Division (B&R)
 P.P.W.D., Rampur.

SCHEDULE OF QUANTITY

Name of Work:- R/R damages on Shanadhar Shraikoti road km 0/000 to 8/200 .
(SH:- Deployment/Hiring of JCB/Excavator-cum loader for removal of snow/ slips, dressing of berms, cleaning of road side drain/culverts in Km 0/00 to 5/00)

Estimated cost :- 98,750.00
Earnest money :- 2,000.00
Time allowed:- One Month

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for earth cutting/excavation/filling/ removal of snow/slips and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour			

Executive Engineer,
Rampur Division (B&R)
P.W.D., Rampur.

SCHEDULE OF QUANTITY

Estimated cost :- 98,750.00
 Earnest money :- 2,000.00
 Time allowed:- One Month

Name of Work:- R/R damages on racholi Dansa lalsa road km 0/000 to 14/00 .

(SH:- Deployment/Hiring of JCB/Excavator-cum loader for removal of snow/ slips, cleaning of road side drain/culverts etc at various Rds in Km 7/00 to 14/00)

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for earth cutting/excavation/filling/ removal of snow/slips and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour			


Executive Engineer,
 Rampur Division (B&R)
 M.P. WD., Rampur.

SCHEDULE OF QUANTITY

Name of Work:- R/R damages on Keo Koot Kinf road km 0/000 to 13/500 in Ganvi Section under Sarahan Sub-Division
(SH :- Hiring of Tipper for removal of slips and debris).

Estimated cost :- 98,800.00
Earnest money :- 2,000.00
Time allowed:- OneMonth

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of tipper of Light Commercial Vehical category for carriage of earth /debris / boulder and other construction materials from various location etc. Including wages of tipper driver 1 cleaner including P.O.L. Any repair /damaged during work will be absulte responsibility of the contractor/ on onwer tipper has to work at least eight hours per day, only actual working days shall be accounted for to payment. No payment will be made of holidays as well as on holidays if there is no work to the entire satisfaction of Engineer-in-charge.	19.00	Per Day			
					Total:-	


Executive Engineer,
Rampur Division (B&R)
P.P. WD., Rampur.

SCHEDULE OF QUANTITY

Name of Work:- R/R damages on Mashnoo Takleeh road km 0/000 to 48/000 (Portion 0/000 to 12/000)
(SH:- Deployment/Hiring of JCB/Excavator-cum loader for removal of snow/ slips, dressing of katcha road surface/berms and cleaning of road side drain/culverts etc at various Rd's)

Estimated cost :- **98,750.00**
Earnest money :- **2,000.00**
Time allowed:- **OneMonth**

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Hiring of earth cutting/excavating machinery of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for eath cutting/excavation/filling/ removal of snow slips and clearance of side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinery from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.	79.00	Per hour			

H
Executive Engineer,
Rampgr Division (B&R)
P.P.W.D., Rampur.

SCHEDULE OF QUANTITY

Name of work:- Construction of Dust Bin Shed in MGMSC Khaneri Tehsil Rampur Distt. Shimla (H.P.) (Sub Head :- C/O Dust Bin)

Estimated cost :- 69,952.00
 Earnest money :- 1,500.00
 Time allowed:- Ten Days

Sr. No	Description of items	Quantity	Unit	Rate (In figure)	Rate (In Word)	Amount
1	Earth work in excavation for structure in all depth as per drawing and technical specification Clause 305-1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable material . All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion damage to hill side water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiselling and wedging out of rock(where blasting is prohibited) as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	2.03	Per Cubic meter			
2	P/L Cement concrete 1:4:8 (one cement : four sand : eight graded stone aggregate twenty five millimeter nominal size)for plain/ reinforced concrete work in open foundation complete as per drawing and technical specification Clauses 802,803,1202& 1203. including all leads and lifts as per directions of Engineer in Charge.	1.42	Per Cubic metre			
3	Steel work welded in built up section/framed work,including cutting hoisting,fixing in position and applying a priming coat of approved steel primer using structural steel etc.as required In grating,grames,guard bar,ladder,railing,brackets gates and other similar work, including all leads and lifts as per directions of Engineer in Charge.	387.35	Per Kg.			
4	Providing and fixing 0.60 mm thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regularmodified polyester(RNP) organic coating of 20 microns over 5 microns primer coating of back coat of polyester of 5 microns over 5 microns primer coating including fixinf with prepainted iron j or L hooks bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete . including all leads and lifts as per directions of Engineer in Charge.	7.80	Per Square metre			
5	Providing and fixing ridges or hips 60cmover all with 0.45mm thick prepainted steel sheet of TATA DURASHINE .in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20 microns over 5 microns primer coating + back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron j or L hooks, bolts & nuts 6mm dia & prepainted G.I. limpet and bitumen washers complete with all accessories as required as per the direction of Engineer-in-Charge.	3.90	Per Running metre			
Total:-						

Executive Engineer,
 Rampur Division (B&R)
 PWD, Rampur.