



Office of the
Executive Engineer
Una Division, HP PWD Una
Tel: +911975226036,
E-mail: ee-una-hp@nic.in

No.PWU/CB/TA/Tender/2025-26:-

8054-8060

Dated :- 30/12/25

To

The Executive Engineer (IT) Cell,
Nirman Bhawan, Nigam Vihar,
Shimla-171002.

Subject: -


Regarding publication of Tenders Notice.

Sir,

"JAI HIND"

Enclosed please find herewith Tenders Notice along with Schedule of Quantities for uploading the same on Departmental website as per Notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B) A(3)1/2024 dated Shimla-2 the 03.01.2025 as the work mentioned in the Tender Notice are urgent in nature and in Public interest. This is for your kind information and necessary action at your end please.

DA:-As above.


Executive Engineer,
Una, Division,
HPPWD, Una


Copy along with its enclosures is forwarded to the following for favour of information please:-

1. The Superintending Engineer, 15th Circle, HPPWD, Una.
2. All the Assistant Engineer, working under this Division.
3. All the Head of Branches in this office.
4. Notice Board.

Executive Engineer,
Una, Division
HPPWD, Una

Certificate

Certified that the tenders called vide this office letter
No.PWU/CB/T-I/2025-26:- 8041-8053 dated-30-12-2024 emergent nature and in Public
interest.


Executive Engineer,
Una Division, HP:PWD,
Una

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDERS

Sealed percentage rate tender on PWD Form No. 6 & 8 are hereby invited by the Executive Engineer, Una Division HPPWD Una H.P. on behalf of Governor of H.P. for the following works from the approved and eligible contractors/ firms enlisted in PWD Department so as to reach in this office or before **08.01.2026 upto 11.00 A.M.** and will be opened on the same day at **11.30 A.M.** in presence of the intending contractor s or their authorized representatives who may like to be present. If it happened be holiday on the day of opening of tender the same will be opened on next working day at the same time. The application for obtaining the tender forms will be received latest by **05.01.2026 at 10.00 AM upto 10.30 AM** against cash payment (non-refundable) and the tender form can be had from this office upto **06.01.2026** during the office hours.

The earnest money in the shape of F.D.Rs if any of the Nationalized Bank in H.P. duly pledged in the favour of the Executive Engineer, Una Division HPPWD Una , will be received alongwith the applications for obtaining tender forms. The applications received without earnest money shall summarily be rejected. The Executive Engineer reserves the right to reject any tender without assigning any reason. The conditional / telegraphic tenders shall also be rejected. The scope of the work can be increased/ decreased without any Notice. The offers of the tender (s) shall be kept open for 75 days from the date of opening the tender(s).

Sr. No.	Name of work	Estimated cost	Earnest Money	Time Limit	Cost of tender	Eligible class of contractor
1	2	3	4	5	6	7
1	A/R & M/O Type-II Qtr No. 4 & 5 Pooled accommodation at Rakkar Colony Distt. Una H.P (SH: Repair of wood work, Distempering painting etc.)	99,647/-	2,000/-	One Month	350/-	Class-C & D
2	A/R & M/O Residential building Una (SH: P/L Painting and other repair work in Type-IV residence and boundary wall in DC Colony Una	99,141/-	2,000/-	One Month	350/-	Class-C & D
3	A/R & M/O residential building Una (SH: Providing painting and other repair work of type IV Qtr. No.7	99,679/-	2000/-	One Month	350/-	Class-C & D
4	A/R & M/O residential building at Una (SH: Providing and laying water proofing in type-III Qtr. No.11 and 15 in DC colony Una)	99,684/-	2,000/-	One Month	350/-	Class-C & D
5	A/R & M/O residential building at Una (SH: Painting and other repair work in SDM residence in DC Colony (Phase-I)	99,953/-	2,000/-	One Month	350/-	Class-C & D
6	A/R & M/O residential building at Una (SH: Painting and other repair work in SDM residence in DC Colony (Phase-II)	99,954/-	2,000/-	One Month	350/-	Class-C & D
7	A/R & M/O residential building at Una (SH: repair of plaster, painting and other maintenance for type-III qtr. No. 14 and 20 DC Colony Una	99,859/-	2,000/-	One Month	350/-	Class-C & D
8	A/R & M/O Type-III Qtr No.4& 6 HPPWD at Rakkar Colony Distt. Una H.P (SH: Repair of wood work, Distempering painting etc.	98,586/-	2,000/-	One Month	350/-	Class-C & D
9	A/R & M/O LIG Qtr No. 90 to 95 Pooled accommodations at Rakkar Colony Distt. Una (H.P) (SH: Repair of wood work, Distempering painting etc.)	99,737/-	2,000/-	One Month	350/-	Class-C & D
10	A/R & M/O LIG Qtr No. 94 to 95 Pooled accommodations at Rakkar Colony Distt. Una (H.P) (SH: Providing and laying R/wall)	98,293/-	2,000/-	One Month	350/-	Class-C & D
11	A/R & M/O residential building at Una (SH: Providing and laying roof treatment and other repair in District attorney and ACJM residence).	99,708/-	2,000/-	One Month	350/-	Class-C & D
12	A/R & M/O residential building at Una (SH: Painting and toilet repair at police chowki sadar Una at old Mini Secretariat)	99,922/-	2,000/-	One Month	350/-	Class-C & D

K. Subramanian

13	A/R & M/O residential building at Una (SH: Providing and laying outer repair type-III building Qtr No. 9 to 20 in DC Colony Una (H.P).)	99,839/-	2,000/-	One Month	350/-	Class-C & D
14	A/R & M/O LIG 104 Quarters Pooled accommodations at Rakkar Colony Distt. Una (H.P) (SH: Repair of wood work, Distempering painting etc.)	99,944/-	2,000/-	One Month	350/-	Class-C & D
15	A/ & M/O LIG 104 & 108 Quarters Pooled accommodation at Rakkar Colony Distt. Una (H.P) (SH:- Repair of tile works etc.)	99,641/-	2,000/-	One Month	350/-	Class-C & D
16	Repair & maintenance of HPPWD, residential building at Jalgran Tehsil & Distt. Una (SH:- P/L interlock pavers along residence)(Part-I)	99,749/-	2,000/-	One Month	350/-	Class-C & D
17	Repair & maintenance of HPPWD, residential building at Jalgran Tehsil & Distt. Una (SH:- P/L interlock pavers along residence)(Part-II)	99,382/-	2,000/-	One Month	350/-	Class-C & D
18	Repair & maintenance of HPPWD, residential building at Jalgran Tehsil & Distt. Una (SH:- P/L interlock pavers along residence)(Part-III)	99,355/-	2,000/-	One Month	350/-	Class-C & D
19	Repair & maintenance of HPPWD, residential building at Jalgran Tehsil & Distt. Una (SH:- P/L interlock pavers along residence)(Part-IV)	99,912/-	2,000/-	One Month	350/-	Class-C & D
20	A/R & M/O Type-LIG Qtr. No.91 & 92 Pooled accommodation at Rakkar Colony Una (SH:- Repair of roof with water proofing compound etc)	99,550/-	2,000/-	One Month	350/-	Class-C & D
21	A/R & M/O Type-LIG Qtr. No.93 & 94 Pooled accommodation at Rakkar Colony Una (SH:- Repair of roof with water proofing compound etc)	99,548/-	2,000/-	One Month	350/-	Class-C & D
22	A/R & M/O Type-LIG Qtr. No.95 & 96 Pooled accommodation at Rakkar Colony Una (SH:- Repair of roof with water proofing compound etc)	99,545/-	2,000/-	One Month	350/-	Class-C & D
23	A/R & M/O Type-LIG Qtr. No.97 & 98 Pooled accommodation at Rakkar Colony Una (SH:- Repair of roof with water proofing compound etc)	99,646/-	2,000/-	One Month	350/-	Class-C & D
24	A/R & M/O Type-LIG Qtr. No.99 & 100 Pooled accommodation at Rakkar Colony Una (SH:- Repair of roof with water proofing compound etc)	99,644/-	2,000/-	One Month	350/-	Class-C & D
25	A/R & M/O Type-LIG Qtr. No.101 & 102 Pooled accommodation at Rakkar Colony Una (SH:- Repair of roof with water proofing compound etc)	99,641/-	2,000/-	One Month	350/-	Class-C & D
26	A/R & M/O Type-LIG Qtr. No.103 & 104 Pooled accommodation at Rakkar Colony Una (SH:- Repair of roof with water proofing compound etc)	99,598/-	2,000/-	One Month	350/-	Class-C & D
27	A/R & M/O Type-LIG Qtr No. 120 & 121 pooled accommodation at Rakkar Colony Una (SH:- Repair of roof with water proofing compound etc)	99,732/-	2,000/-	One Month	350/-	Class-C & D
28	A/R & M/O Type-LIG Qtr No. 105 & 106 pooled accommodation at Rakkar Colony Una (SH:- Repair of roof with water proofing compound etc)	99,598/-	2,000/-	One Month	350/-	Class-C & D
29	A/R & M/O Type-LIG Qtr No. 107 & 108 pooled accommodation at Rakkar Colony Una (SH:- Repair of roof with water proofing compound etc)	99,593/-	2,000/-	One Month	350/-	Class-C & D

30	A/R & M/O Type-LIG Qtr No. 109 & 110 pooled accommodation at Rakkar Colony Una (SH:- Repair of roof with water proofing compound etc)	99,742/-	2,000/-	One Month	350/-	Class-C & D
31	A/R & M/O Type-LIG Qtr No. 116 & 117 pooled accommodation at Rakkar Colony Una (SH:- Repair of roof with water proofing compound etc)	99,737/-	2,000/-	One Month	350/-	Class-C & D
32	A/R & M/O Type-LIG Qtr No. 118 & 119 pooled accommodation at Rakkar Colony Una (SH:- Repair of roof with water proofing compound etc)	99,735/-	2,000/-	One Month	350/-	Class-C & D
33	A/R & M/O Pooled accommodation Quarter No.27 Type-III residential building at Rakkar Distt. Una (SH:- C/o Car shed size 3.50x3.00 with structural steel and repainted steel sheet etc.	82,583/-	2,000/-	One Month	350/-	Class-C & D
34	A/R & M/O residential building for in DC Colony Una (SH:- Providing painting outside and DC residence (Part-I)	98,402/-	2,000/-	One Month	350/-	Class-C & D
35	A/R & M/O residential building for in DC Colony Una (SH:- Providing painting outside and DC residence (Part-II)	98,886/-	2,000/-	One Month	350/-	Class-C & D
36	A/R & M/O residential building for in DC Colony Una (SH:- Providing painting outside and DC residence (Part-III)	96,960/-	2,000/-	One Month	350/-	Class-C & D
37	Repair & Maintenance of Non-residential Building at Una Distt. Una (SH:- Providing services out sources basis of One No. Supervisor/work inspector for Period of five month i.e. 1st January 2026 to May 2026	95,020/-	2,000/-	One Month	350/-	Class-C & D
38	Repair & maintenance of office of Assistant Engineer HPPWD Sub Division No.IUna at DC Colony Una (HP) (SH: P/L painting and other repair etc (Part-I)	99,666/-	2,000/-	One Month	350/-	Class-C & D
39	A/R & M/O Non-residential building at Una (SH:- Repair of CCTV surveillance system of CP PLUS with IP quality at circle office Una (H.P)	82,185/-	2,000/-	One Month	350/-	Class-C & D
40	Repair & maintenance of office of Assistant Engineer HPPWD Sub Division No.IUna at DC Colony Una (HP) (SH: P/L water proofing etc (part-II)	99,750/-	2,000/-	One Month	350/-	Class-C & D
41	Restoration of rain damage to Path from the house of Dr.Attri etc. to house of Shri Ram Murti in Ward No. 1 in Village Arniala Upper MC Una (SH: Providing and laying interlocking paver blocks km 0/0 to 0/040) (Under VKVNY (MLALAD)	99,608/-	2,000/-	One Month	350/-	Class-C & D
42	C/o Path near the house of ShriBalram etc. in Village Lalsingi MC Una Tehsil & Distt. Una (SH:- P/L interlocking paver blocks km 0/027 to 0/054) (Under VKVNY(MLALAD)	99,935/-	2,000/-	One Month	350/-	Class-C & D
43	C/o Path near the house of ShriBalram etc. in Village Lalsingi MC Una Tehsil & Distt. Una (SH:- P/L interlocking paver blocks km 0/0 to 0/027) Under VKVNY (MLALAD)	99,981/-	2,000/-	One Month	350/-	Class-C & D
44	Restoration of rain damages on link road Charatgarh to Sasan road near the house of Pooran Chand km 0/0 to 1/200 (SH:P/L 80mm thick interlocking paver in Rd 0/493.50 to 0/507.20)(Under deposit VKVNY (MLALAD)	82,330/-	2,000/-	One Month	350/-	Class-C & D

45	Restoration of rain damages on link road Charatgarh to Sasan road near the house of Pooran Chand km 0/0 to 1/200 (SH:P/L 80mm thick interlocking paver in Rd 0/521.10 to 0/535.92) (Under deposit VKVNY (MLALAD)	89,162/-	2,000/-	One Month	350/-	Class-C & D
46	Restoration of rain damages on link road to village BharolianKhurd Km 0/0 to 2/0 (SH: P/L CC interlocking paver block at Rd 0/574 to 0/586)	99,393/-	2,000/-	One Month	350/-	Class-C & D
47	Restoration of damages occurred due to laying of OFC in various roads under Mehatpur Sub-Division No.II HPPWD Mehatpur (SH:- Providing fixing and art Painting information boards etc) (Rakkar Section)	99,741/-	2,000/-	One Month	350/-	Class-C & D
48	Restoration of damages occurred due to laying of OFC in various roads under Mehatpur Sub-Division No.II HPPWD Mehatpur (SH:- Providing fixing and art Painting information boards etc) (Santoshgarh Section)	99,546/-	2,000/-	One Month	350/-	Class-C & D
49	Restoration of damages occurred due to laying of OFC in various roads under Mehatpur Sub-Division No.II HPPWD Mehatpur (SH:- Painting and art painting of ordinary Km stones 200 mtrs . Stones and information sign boards etc) (Mehatpur section)	99,825	2,000/-	One Month	350/-	Class-C & D
50	Restoration of damages occurred due to laying of OFC in various roads under Mehatpur Sub-Division No.II HPPWD Mehatpur (SH:- Providing fixing and art Painting information boards etc) (Mehatpur Section)	99,643/-	2,000/-	One Month	350/-	Class-C & D
51	Restoration of rain damages Bangarh Nangran road to Ghalore Chowk upto Punjab Boundary Km 0/0 to 2/500 Tehsil & Distt. Una (H.P) (SH:- C/o R/wall at RD 2/450 to 2/455) (Deposit work)	99,223/-	2,000/-	One Month	350/-	Class-C & D
52	Restoration of rain damages Bangarh Nangran road to Ghalore Chowk upto Punjab Boundary Km 0/0 to 2/500 Tehsil & Distt. Una (H.P) (SH:- C/o R/wall at RD 2/455 to 2/460) (Deposit work)	99,053/-	2,000/-	One Month	350/-	Class-C & D
53	Improvement of Vulnerable Spots on Old Hoshiarpur road Km 0/0 to 4/330 (SH: Providing and reacting crash barrier at Rd 3/870 to 3/892 (LHS)	89,116/-	2000/-	One Month	350/-	Class-C & D
54	Improvement of Vulnerable Spots on Old Hoshiarpur road Km 0/0 to 4/330 (SH: Providing and reacting crash barrier at Rd 3/810 to 3/832 (RHS)	89,138/-	2000/-	One Month	350/-	Class-C & D
55	M/T on link road Village Malukpur to Binewal Govt. Sr. Sec. School in Village Majara Sucha Singh etc. from Punna to Saint Soldger School , Badsehda to peer Sathan IPH Scheme, Village Sanoli to Mahinder Singh etc. C/o link road Shani Dev Temple to Punjab Border, Widening & Strengthening of roads in village Fatehpur and C/o link road to house of Bakshi Ram from Km -0/00 to km 2/500 under NABARD (SH:- Preparation of working Estimate and DNIT).	85,000/-	2,000/-	One Month	350/-	Class-C & D
56	Repair& maintenance of Behdala Jankour via Abada Barana road km 0/0 to 4/600 Tehsil & Distt. Una (SH: C/O R/Wall along road from RD 0/934.85 to 0/945.50) Under MDPE Deposit	99,997/-	2,000/-	One Month	350/-	Class-C & D

57	Repair & maintenance of Behdala Jankour via Abada Barana road km 0/0 to 4/600 Tehsil & Distt. Una (SH: C/O R/Wall along road from RD 0/945.50 to 0/956.15) Under MDPE Deposit	99,827/-	2,000/-	One Month	350/-	Class-C & D
58	Annual repair & Maintenance on Various roads in Basoli under Sub-Division No.I HPPWD Una HPPWD. (SH:- Hiring of excavator Cum Loader clearance of earthen Shoulders and road side drains etc.	99,000/-	2,000/-	One Month	350/-	Class-C & D
59	Annual repair & Maintenance on Various roads in Basoli under Sub-Division No.I HPPWD Una HPPWD. (SH:- Hiring of excavator Cum Loader clearance of earthen Shoulders and road side drains etc.	99,000/-	2,000/-	One Month	350/-	Class-C & D
60	Repair and maintenance of link road to village Galua (SH:- Providing and fixing grating on drain at fixing grating on drain at RD 0/0 to 0/013) Under OFC Deposit	97,681/-	2,000/-	One Month	350/-	Class-C & D
61	Repair and maintenance of link road to village Galua (SH:- Providing and fixing grating on drain at fixing grating on drain at RD 0/026 to 0/039) Under OFC Deposit	97,848/-	2,000/-	One Month	350/-	Class-C & D
62	Repair and maintenance of link road to village Galua (SH:- Providing and fixing grating on drain at fixing grating on drain at RD 0/013 to 0/026) (Under OFC Deposit) (Under OFC Deposit)	98,234/-	2,000/-	One Month	350/-	Class-C & D
63	A/R & M/O link road to Village Lower Arniala km 0/0 to 1/0 (SH: P/F CC interlocking paver blocks at Rd 0/040 to 0/083 (Right side berms)	98,493/-	2000/-	One Month	350/-	Class-C & D
64	A/R & M/O to link road from Jhalera to Una via lower Lalsingi Km 0/0 to 4/340 (SH:- Providing and marking strip lines 100mm at Rd 1/605 to 2/415)(Under OFC deposit).	93,960/-	2000/-	One Month	350/-	Class-C & D
65	A/R & M/O to link road from Jhalera to Una via lower Lalsingi Km 0/0 to 4/340 (SH:- Providing and marking of rumble strip lines 100mm at RD 0/0 to 0/800)(Under OFC deposit)	92,800/-	2000/-	One Month	350/-	Class-C & D
66	A/R & M/O Santoshgarh Mehatpur road Km 0/0 to 7/0 (Under road safety) (SH:- Providing and marking of edge line, rumble strip lines and Zehra crossing at junction & near to school Hospital etc. at RD 5/500 to 5/965)	99,876/-	2000/-	One Month	350/-	Class-C & D
67	A/R & M/O Santoshgarh Mehatpur road Km 0/0 to 7/0 (Under road safety) (SH:- Providing and marking of edge line, rumble strip lines and Zehra crossing at junction & near to school Hospital etc. at RD 5/975 to 6/410)	99,737/-	2000/-	One Month	350/-	Class-C & D
68	A/R & M/O Santoshgarh Mehatpur road Km 0/0 to 7/0 (Under road safety) (SH:- Providing and marking of edge line, rumble strip lines and Zehra crossing at junction & near to school Hospital etc. at RD 6/425 to 6/990)	99,992/-	2000/-	One Month	350/-	Class-C & D
69	Repair & maintenance of link road DehlanBehdala Km 0/0 to 2/060 (SH:- P/L 80mm thick interlocking paver in Rd 1/660 to 1/684.50) Both side shoulders Under MDPE Deposit	99,941/-	2000/-	One Month	350/-	Class-C & D

70	Repair & maintenance of link road Dehlan Behdala Km 0/0 to 2/060 (SH:- P/L 80mm thick interlocking paver in Rd 1/684.50 to 1/709) Both side shoulders Under MDPE Deposit	99,932/-	2000/-	One Month	350/-	Class-C & D
71	Restoration of rain damage on 120 metre span bridge on Una Santoshgarh road at Rd 1/760(SH:- Channelization of Khad on upstream side of Rampur bridge 1/760 at Middle of the Khad)	99,726/-	2,000/-	One Month	350/-	Class-C & D
72	Restoration of rain damage on 120 metre span bridge on Una Santoshgarh road at Rd 1/760(SH:- Channelization of Khad on upstream side of Rampur bridge 1/760 RHS Upstream)	99,726/-	2,000/-	One Month	350/-	Class-C & D

TERM & CONDITIONS:-

1. The contractor/ firms should be registered as or/ dealer under HP Sales Tax Act, 1968 and also produce Sale Tax clearance certificate from the Excise and Taxation Department.
2. The intending contractors/ firms shall have to produce the copy of latest enlistment and renewal enlisted in HP: PWD.
3. The contractor/firms are required to quote their rates clearly both in words as well as in figures, failing which the Executive Engineer reserve the right to accept/ reject any or all tenders.
4. The conditional / ambiguous/ telegraphic tenders or tender by fax shall not entertain/ considered in any case
5. No payment will be made to the contractor/ firms for damage caused by flood, rain, local disturbance, war, epidemic or either natural calamities during execution of work and no such claim on this account will be entertained.
6. Security shall be released after 1 year from the date of completion of work provided no defect certificate is issued by the Engineer-in-charge.
7. The Executive Engineer has right to accept or reject any or all the tender without assigning any reason.
8. Any material left at site one month after completion of work shall become the property of the department and no payment shall be made to the contractor for the material.
9. A sign Board "Men at work / work in progress" shall be placed " by Contr. At least 200-150 meters ahead of places / roads where road are under repair / construction.
10. The contractor should be personally present for submission of application from 10.00 AM to 10.30 AM for purchase of tender form. No application will be accepted after 10.30 AM.
11. Contactor cannot submit application for more than two works/ Jobs.

K. S. Dabur
Executive Engineer

Una Division, HP: PWD, Una.

On behalf of Governor of H.P.

No. PWU/CB/T-1/2025-26:-

8041-8053

Dated:-

30-12-2025

Copy is forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP: PWD, Shimla-1.
2. The Chief Engineer, Hamirpur Zone, HP: PWD, Hamirpur.
3. The Superintending Engineer, 15th Circle Una.
4. All the Assistant Engineers under this Division.
5. The Deputy Commissioner, Una.
6. The Sub Divisional Officer (C), Una.
7. The District Treasury Officer, Una.
8. The Block Development Officer, Una.
9. The Municipality, Una.
11. All the Head of the Branches in this office.
12. The Notice Board.

Executive Engineer,
Una Division, HP:PWD,
Una


(99)

①

SCHEDULE OF QUANTITY						Estimated Cost	99647/-
Name of work : A/R & M/O Type-II Qtr No.4 & 5 Pooled accomodation at Rakkar Colony Distt. Una H.P(S.H. :- Repair of Wood work, Distemping painting etc.)						Earnest Money	2000/-
						Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Providing wood work in frames of doors, windows,clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately.(Sal wood)including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.092	Per cubic metre	95000.00	Rupees Ninety five thousand only	8740	
2	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, including panelling , all complete as per direction of Engineer-incharge Kiln seasoned and chemically treated sheesham wood 30 mm thick shutters including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.12	Per square metre	4000.00	Rupees Four thousand only	32480	
3	Providing and fixing wire gauge shutters using galvanised M.S. wire gauge of I.S. gauge of average width of aperture 1.4mm both side direction with wire of dia 0.63 mm for doors, windows and celerestory windows i/c bright finished black enamelled iron hinges with necessary screws. Hollock woods 30 mm thick including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	6.92	Per square metre	3000.00	Rupees Three thousand only	20760	
4	Removing dry or oil bound by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including carriage of material within all leads and lifts.	323.34	Per square metre	7.00	Rupees Seven only	2263	
5	Providing and applying white cement based putty of average thickness 1 mm, of approved brand andmanufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of material within all leads and lifts and other incidentials.The rate Includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	97.00	Per square metre	60.00	Rupees Sixty only	5820	
6	Distemping with oil bound washable distemper of 13.41.1 New work (two or more coats) over and including water thinnable priming coat with cement primer.Including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	323.34	Per square metre	60.00	Rupees Sixty only	19400	
7	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade. Two or more coats on new work.including carriage of material within all leads and lifts and other incidentials.The rate Includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	104.14	Per square metre	65.00	Rupees Sixty five only	6769	

6

8	Renewing glass panes with wooden fillets wherever necessary float glass panes of nominal thickness 4mm including carriage of material within all leads and lifts.	0.83	Per square metre	500.00	Rupees Five hundred only	415
9	Providing and fixing CP brass angle valve for basin for basin mixer and geyser points of approved quality conforming to IS: 8931 15mm nominal bore including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	2.00	each	550.00	Rupees Five hundred fifty only	1100
10	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931: 15 mm nominal bore including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	2.00	each	500.00	Rupees Five hundred only	1000
11	Providing and fixing ball valve (brass) of approved quality high or low pressure with plastic floats complete 15mm nominal bore including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	2.00	each	450.00	Rupees Four hundred fifty only	900
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)A(17)2/0212 dated 7.8.2018				Total:	99647
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer
 Una Divn. HP. P.W.
 Una

67

2

SCHEDULE OF QUANTITY

Estimated cost 99141/-

Earnest money 2000/-

Time limit One month

Name of Work: A/R & M/O Residential building Una (SH: P/L Painting and other repair work in Type IV residence and boundary wall in DC colony Una

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Repair to plaster in patches of 2.50sqm and under 10 to 15mm thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20mtr. with Cement mortar 1:5 (1cement:5sand)including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	15.12	Per square metre	160.00	Rupees One hundred sixty only	2419
2	Applying birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops dust loose materials and other foreign matter sand paperd smooth to give final matt finish to the surface complete including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	82.85	Per square metre	60.00	Rupees Sixty only	4971
3	Distempering (two coat) with oil bound washable distemper of approved brand and manufacture and of required shade on decorated wall surfaces to give an even shade after thoroughly brushing the surface clean of all grease dirt,loose,pieces of scales and also including preparing the surface even and sand papered smooth i Including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	371.57	Per square metre	65.00	Rupees Sixty five only	24152
4	Finishing wall with weather proof exterior grade emulsion of approved design (Aplexultima) or its euivalent on undecorated wall surface (two coats) to give an even shade and final finish after throughly cleaning the surface to remove all dirt,dust and other foreign matter etcetra including sand paper smooth complete including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	435.18	Per square metre	85.00	Rupees Eighty five only	36990
5	Providing and fixing glazing with glass panes of 4mm thickness (weight not less than 10kg/sqm.)including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government	1.610	Per square metre	850.00	Rupees Eight hundred fifty only	1369

6

6	Providing and fixing 12mm thick wooden flooring tile including cost of adhesive of approved quality including carriage of materials with all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	17.20	Per square metre	1700.00	Rupees One thousand seven hundred only	29240
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				G.Total	99141
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer
 Una Divn.HP.PWB
 Una


3

SCHEDULE OF QUANTITY						
Name of work :A/R & M/O residential building Una (SH: Providing painting and other repair work of type IV qtr. No.7)						
					Estimated Cost	99679/-
					Earnest Money	2000/-
					Time limit	one month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing and fixing 40mm (forty millimetre)thick second class deodar wood wire gauge shutters using galvanised M.S. wire gauge of I.S. gauge designation 85G with wire of dia 0.58mm for doors, windows and clerestory windows including first class deodar wood ornamental beading 20 mm X 12.5 mm (twenty into twelve point five millimetre)section including bright finished black enamelled iron butt hinges with necessary screws including carriage of materials with all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1.20	Per square metre	2800.00	Rupees Two thousand eight hundred only	3360
2	Providing and fixing 18mm thick HDHMR board covered with lamination on both side including cutting of board as per required size and tapes, fevicol, nails and all other necessary arrangements to fix the boards on wall for panneling and for ward robe etcetra as per direction of Engineer-incharge including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.80	Per square metre	1780.00	Rupees One thousand seven hundred eighty only	3204
3	Providing and fixing flush door shutters decorative type core of block board construction with frames of first class hard wood and well matched class indian teak plyvneering with vertical grains or cross bends and face veneering omn both faces of shutters 35mm thick including black enammeled MS butt hinges including carrige of materials with all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1.20	Per square metre	3500.00	Rupees Three thousand five hundred only	4200
4	Providing and fixing decorative high pressure laminated sheet of plain/ wood grain in gloss/matt/suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS: 2046 Type S, including cost of adhesive of approved quality 1mm thick including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	6.20	Per square metre	850.00	Rupees Eight hundred fifty only	5270
5	Providing and fixing bright finished brass helical door spring(Superior quality) including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.00	each	415.00	Rupees Four hundred fifteen only	415

6	Providing and fixing 150mm bright finished floor brass door stopper with rubber cushion, necessary brass screws etc. to suit shutter thickness complete including entire carriage of material within all leads and lifts and other incidentials .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.00	each	215.00	Rupees Two hundred fifteen only	430
7	Providing and fixing aluminium handles anodized transparent or dyed to required colour or shade with necessary screws etc. complete including carriage of materials in all leads and lifts. (125mm) including entire carriage of material within all leads and lifts and other incidentials .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	4.00	each	95.00	Rupees Ninety five only	380
8	Providing and fixing aluminium tower bolts (Barrel type) anodized transparent or dyed to required shade and colour with screws etc.200 x 10mm including entire carriage of material within all leads and lifts and other incidentials .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	4.00	each	120.00	Rupees One hundred twenty only	480
9	Painting two coat(excluding priming coat)on wood and wood based surfaces with enamel paint to given and even shade including cleaning of all dirt,dust and other foreign matter sand papering and stoppingincluding entire carriage of material within all leads and lifts and other incidentials .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	20.84	Per square metre	65.00	RupeesSixty only	1355
10	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops dust loose material and foreign matter sand papered smooth to give final matter finish to the surface complete including carriage of materials within all leads ad lifts.The rate includes octroi,royalty,Malkhana Toll tax , goods service tax,labour cess or other taxes imposed by the Government	85.73	Per square metre	60.00	Rupees Sixty only	5144
11	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats)including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	85.73	Per square metre	60.00	Rupees Sixty only	5144


6

12	Providing and fixing APP (Atactic Polypropylene Polymer) modified prefabricated five layer 2 mm thick water proofing membrane , black finished reinforced with glass fibre matt consisting of a coat of bitumen primer for bitumen membrane @ 0.40 litre/sqm by the same membrane manufacture of density at 25°C, 0.87 -0.89 kg/ litre and viscosity 70' - 160 cps. Over the primer coat the layer of membrane shall be laid using Butane torch and sealing all joints etc., and preparing the surface complete. The vital physical and chemical parameters of the membrane shall be as under : Joint strength in longitudinal and transverse direction at 23°C as 350/300 N/ 5 cm. Tear strength in longitudinal and transverse direction as 60/80N. Softening point of membrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D - 5147. The laying of membrane shall be got done through the authorised applicator of the manufacture of membrane 3mm including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	108.15	Per square metre	650.00	Rupees Six hundred fifty only	70298
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				G.Total	99679
	2) The rates shall be including of all types of taxes including GST etetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate In Figures					
	Percentage quoted Rate In Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer
 Una Divn.HP. PWD,
 Una

9

SCHEDULE OF QUANTITY							
						Estimated Cost	99684/-
Name of work :A/R & M/O residential building at Una (SH: Providing and laying water proofing in type-III Qtr. No.11 and 15 in D.C. Colony Una)						Earnest Money	2000/-
						Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer, 3 mm thickwater proofing membrane, black finished reinforced withglass fibre matt consisting of a coat of bitumen primerfor bitumen membrane @ 0.40 litre/sqm by thesame membrane manufactured of density at 25°C, 0.87 -0.89 kg/litre and viscosity 70 - 160 cps. Over the primercoat the layer of membrane shall be laid using butanetorch and sealing all joints etc., and preparing thesurface complete. The vital physical and chemicalparameters of the membrane shall be as under : Jointstrength in longitudinal and transverse direction at 23°Cas 350/300 N/5 cm. Tear strength in longitudinal andtransverse direction as 60/80N. Softening point ofmembrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D -5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane 3mm thick . including carriage of materials within all leads and lifts.The rates are inclusive of octroi, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.	153.36	Pe square metre	650.00	Rs.Six hundred fifty only	99684	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018						Total:	99684 ✓
2) The rates shall be including of all types of taxes including GST ectra)							
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021							
Percentage quoted Rate in Figures							
Percentage quoted Rate in Words							
Note: Rates quoted in figures & words are mandatory							
by the contractor otherwise the tender will be rejected.							



 Executive Engineer,
 Una Division, HPWD.,
 Una

63

5


SCHEDULE OF QUANTITY							Estimated Cost	99953/-
Name of work :A/R & M/O residential building at Una (SH: Painting and other repair work in SDM residence in DC colony)(Phase-I)							Earnest Money	2000/-
							Time limit	One month
Sl. No.	Description of work		Unit	RATE In		AMOUNT		
				Figures	Words			
1	Applying one coat of Acrylic washable emulsion spectrum quartz king or equivalent finish for interior painting with brushes plain smooth finish composed of acrylic polymere in emulsion inorganic /special pigment siliceous aggregate anti fungicides anti- rusting and foaming in two coat including necessary putty to give smooth even surface, sand papered smooth complete of Asian/Dulux make complete in all respect including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	373.05	Per Square metre	65.00	Rupees Sixty five only	24248		
2	Painting two coats (excluding priming coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning of all dirt dust and other foreign matter sand papering and stopping with enamel paint other than white.including carriage of material within all leads and lifts and other incidentials. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	34.91	Per square metre	65.00	Rupees Sixty five only	2269		
3	Providing and laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, in skirting, riser of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately).Size of Tile 1200x600 mm including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government	44.69	Per Square metre	1150.00	Rupees one thousand one hundred fifty only	51394		
4	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, holsting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	0.94	Per quantial	9800.00	Rupees Nine thousand eight hundred only	9212		
4	Providing and fixing corner unit 600mm including carriage of materials within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.00	each	290.00	Rupees Two hundred ninety only	580		

5	Providing and fixing sink 15mm mixer for kitchen sink with casted swinging spout tap of make cera or equivalent).including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1	each	3000.00	Rupees Three thousand only	3000
6	Providing and fixing 15mm bib tap with long nose including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	5.00	each	850.00	Rupees Eight hundred fifty only	4250
7	Providing and fixing chromium plated brass bib taps with cap stain heads 15mm dia weight 400gms including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.00	each	800.00	Rupees Eight hundred only	1600
8	Providing and fixing brass angle valve 15mm without nuts and pipes including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.00	each	850.00	Rupees Eight hundred fifty only	3400
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018					Total:	99953
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate in Figures						
Percentage quoted Rate in Words						
Note: Rates quoted In figures & words are mandatory						
by the contractor otherwise the tender will be rejected.						


 Executive Engineer
 Una Division, HPPW
 Una

SCHEDULE OF QUANTITY							Estimated Cost	99954/-
Name of work :A/R & M/O residential building at Una (SH: Laying tiles and aluminium work in							Earnest Money	2000/-
SDM residence in DC colony (Phase-II)							Time limit	One month
Sl. No.	Description of work		Unit	RATE In		AMOUNT		
				Figures	Words			
1	Providing and laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, in skirting, riser of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately). Size of Tile 1200x600 mm including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government	34.56	Per Square metre	1150.00	Rupees one thousand one hundred fifty only	39744		
2	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) for fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron) including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax GST, labour cess or other taxes imposed by the Government.	52.28	Per kilogramme	500.00	Rupees Five hundred only	26140		
3	Providing and fixing 12mm thick pre-laminated water proof particle board(decorative lamination on both sides) grade-I medium density flat pressed, three layer board FPT-1 or graded wood particle board FPT-1 conforming to IS: 3087, bonded with BWP type synthetic resin adhesive as per IS: 848 and pre-laminated conforming to IS: 12823, Grade_I, Type-UU marked including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	6.40	Per square metre	1800.00	Rupees One thousand eight hundred only	11520		

4	Providing and fixing glazing with glass panes of 5.50mm(five point fifty millimetre) thickness(weight not less than 13.75kilogramme square metre in aluminium door, window , ventilator shutters make it Hindcol Co.Jindal Indian aluminium Co. and partition etcetra with PVC/neoprens gasket etcetra complete upto floor all level/height as per the architectural drawings including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax GST,labour cess or other taxes imposed by the Government.	2.88	Per square metre	650.00	Rupees Six hundred fifty only	1872
5	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	2.11	Per quantial	9800.00	Rupees Nine thousand eight hundred only	20678
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				Total:	99954
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate In Figures					
	Percentage quoted Rate In Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					



 Executive Engineer,
 Una Division, HPPWB,
 Una

95
7

SCHEDULE OF QUANTITY							
Name of work :A/R & M/O residential building Una (SH: repair of plaster, painting and other maintenance for type-III qtr. No.14 and 20 DC colony Una					Estimated Cost		99859/-
					Earnest Money		2000/-
					Time limit		One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Applying Birla white wall care putty over plaster/other surface after thoroughly brushing the surface free from mortar drops dirt loose materials and other foreign matter sand papered smooth to give final matter finish to the surface complete including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	50.00	Per square metre	60.00	Rupees Sixty only	3000	
2	Applying one coat of AcrylicWashable emulsion Spectrum quartz king or equivalent finish for interior painting with brushes plain smooth finish composed of acrylic polymere in emulsion inorganic/special pigment siliceous aggregate anti fungicides anti-rusting & foaming in two coat i/c necessary putty to give smooth even surface, sand papered smooth complete including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	608.28	Per square metre	65.00	Rupees Sixty five only	39538	
3	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @ 0.75 ltr /10 sqm including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	133.56	Per square metre	65.00	Rupees Sixty five only	8681	
4	Painting two coat(excluding priming coat)on wood and wood based surfaces with enamel paint to given and even shade including cleaning of all dirt,dust and other foreign matter sand papering and stopping including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	194.49	Per square metre	65.00	Rupees Sixty five only	12642	
5	Providing and fixing stainless steel kitchen sink of approved standard ISI make with drain board and C.P. waste with C.I. or M.S. Brackets painted white including cutting holes and making good the same but excluding fitting.610 x460 mm with bowl depth 200 mm including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.00	Each	3500	Rupees Three thousand five hundred only	3500	

6	Providing and fixing 40mm(forty millimeter) thick 2 nd class deodar wood wire gauge shutters using galvanized MS wire gauge of IS gauge designation 85-G(eighty five) with wire of dia 0.56mm(zero point fifty six millimeter) for doors windows clerestory windows including bright finished /black enameled Iron butt hinges with necessary screws including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.78	Per square metre	2800.00	Rupees Two thousand eight hundred only	7784
7	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows. Including black enamelled iron butt hinges with necessary screws. 40mm thick 2nd class deodar wood including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.78	Per square metre	3800.00	Rupees Three thousand eight hundred only	10564
8	Providing and fixing aluminium handles anodized transparent or dyed to required colour or shade with necessary screws etc. complete including carriage of materials in all leads and lifts. (125mm) including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	10.00	each	80.00	Rupees Euighty only	800
9	Providing and fixing aluminium tower bolts (Barrel type) anodized transparent or dyed to required shade and colour with screws etc.200 x 10mm including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	10.00	each	120.00	Rupees One hundred twenty only	1200
10	Providing and fixing to wall ceiling and floor galvanised mild steel tubes (Medium grade) tube fitting and clamps including making good the wall, ceiling and floor:-15mm nominal bore including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	10.00	Per running metre	325	Rupees Three hundred twenty five only	3250
11	Providing and fixing vitreous China wash down, water closet (European type. W.C. pan) with integral 'P' or 'S' trap including jointing the trap with soil pipe in cement mortar 1:1(1 cement : 1 sand) (Seat and over to be measured and paid for separately including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.00	Each	2200.00	Rupees Two thousand two hundred only	4400

12	Providing and fixing automatic flushing cistern with a pair of C.I. Or M.S. brackets complete with fittings including C.I. Syphonic apparatus, mosquito proof lid, C.P. Brass unions and coupling for connections with inlet, outlet and overflow pipes including cutting holes and making good the same (overflow pipe to be measured and paid for separately) including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.00	Each	1500.00	Rupees One thousand five hundred only	1500
13	Providing and fixing hydraulic door closer duly I.S marked including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	3.00	each	1000.00	Rupees One thousand only	3000
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				Total:	99859
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate In Figures					
	Percentage quoted Rate In Words					
	Note: Rates quoted In figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					



 Executive Engineer,
 Una Divn.HP.P.W.B.,
 Una

95

8

SCHEDULE OF QUANTITY						Estimated Cost	98586/-
Name of work : A/R & M/O Type-III Qtr No.4 & 6 HP.PWD.,at Rakkar Colony Distt. Una H.P(S.H. :- Repair of Wood work, Distemping painting etc.)						Earnest Money	2000/-
						Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Providing wood work in frames of doors, windows,clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately.(Sal wood)including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.093	Per cubic metre	95000.00	Rupees Ninety five thousand only	8835	
2	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, including panelling , all complete as per direction of Engineer-incharge Kiln seasoned and chemically treated sheesham wood 30 mm thick shutters including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	7.10	Per square metre	4000.00	Rupees Four thousand only	28400	
3	Providing and fixing wire gauge shutters using galvanised M.S. wire gauge of I.S. gauge of average width of aperture 1.4mm both side direction with wire of dia 0.63 mm for doors, windows and clerestory windows 1/c bright finished black enamelled iron hinges with necessary screws. Hollock woods 30 mm thick including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.60	Per square metre	3000.00	Rupees Three thousand only	25800	
4	Removing dry or oil bound by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including carriage of material within all leads and lifts.	269.18	Per square metre	7.00	Rupees Seven only	1884	
5	Providing and applying white cement based putty of average thickness 1 mm, of approved brand andmanufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	134.59	Per square metre	60.00	Rupees Sixty only	8075	
6	Distemping with oil bound washable distemper of 13.41.1 New work (two or more coats) over and including water thinnable priming coat with cement primer.including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	269.18	Per square metre	60.00	Rupees Sixty only	16151	
7	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade. Two or more coats on new work.including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	83.71	Per square metre	65.00	Rupees Sixty five only	5441	

8	Providing and fixing PVC low level flushing cistern with controlled device (handle lever) conforming to IS: 7231, with all fittings and fixtures complete 10 ltr. Capacity Including carriage of material within all leads and lifts.	2.00	Per square metre	500.00	Rupees Five hundred only	1000
9	Providing and fixing CP brass angle valve for basin for basin mixer and geyser points of approved quality conforming to IS: 8931 15mm nominal bore .Including carriage of material within all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.00	each	550.00	Rupees Five hundred fifty only	1100
10	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931: 15 mm nominal bore.including carriage of material within all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.00	each	500.00	Rupees Five hundred only	1000
11	Providing and fixing ball valve (brass) of approved quality high or low pressure with plastic floats complete 15mm nominal bore .Including carriage of material within all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.00	each	450.00	Rupees Fourt hundred fifty only	900
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				Total:	98586
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate In Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer
 Una Divn.HP.P.W.S.,
 Una


(92)

(9)

SCHEDULE OF QUANTITY							Estimated Cost	99737/-
Name of work : A/R & M/O LIG Qtr No.90 to 95 Pooled accomodation at Rakkar Colony Distt. Una H.P(Earnest Money	2000/-
S.H. :- Repair of Wood work, Distemping painting etc.)							Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Providing wood work in frames of doors, windows,clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately.(Sal wood)including carriage of material within all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.115	Per cubic metre	95000.00	Rupees Ninety five thousand only	10925		
2	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, including panelling , all complete as per direction of Engineer-incharge Kiln seasoned and chemically treated sheesham wood 30 mm thick shutters including carriage of material within all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	5.90	Per square metre	4000.00	Rupees Four thousand only	23600		
3	P/F wire gauge shutters using galvanised M.S. wire gauge of I.S. gauge of average width of aperture 1.4mm both side direction with wire of dia 0.63 mm for doors, windows and celerestory windows i/c bright finished black enamelled iron hinges with necessary screws. Hollock woods 30 mm thick including carriage of material within all leads and lifts and other incidentals.The rate Includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.50	Per square metre	3000.00	Rupees Three thousand only	13500		
4	Providing and fixing fly proof stainless steel grade 304 wire gauge, to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia. 0.50 mm all complete including carriage of material within all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	13.11	Per square metre	850.00	Rupees Eight hundred fifty only	11144		
5	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade. Two or more coats on new work.Including carriage of material within all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	103.24	Per square metre	65.00	Rupees Sixty five only	6711		
6	Removing dry or oil bound by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including carriage of material within all leads and lifts.	304.20	Per square metre	7.00	Rupees Seven only	2129		
7	Providing and applying white cement based putty of average thickness 1 mm, of approved brand andmanufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of material within all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	91.26	Per square metre	60.00	Rupees Sixty only	5476		

b


8	Distemping with oil bound washable distemper of 13.41.1 New work (two or more coats) over and including water thinnable priming coat with cement primer. Including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	304.20	Per square metre	60.00	Rupees Sixty only	18252
9	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931: 15 mm nominal bore. Including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	8.00	each	500.00	Rupees Five hundred only	4000
10	Providing and fixing brass stop cock of approved quality. 15mm Nominal Bore. including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	4.00	each	550.00	Rupees Five hundred fifty only	2200
11	Providing and fixing ball valve (brass) of approved quality high or low pressure with plastic floats complete 15mm nominal bore .including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	4.00	each	450.00	Rupees Four hundred fifty only	1800
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				Total:	99737
	2) The rates shall be including of all types of taxes including GST etcra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3)1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer
 Una Divn. HP. P.D.
 Una

(93)

10

SCHEDULE OF QUANTITY							Estimated Cost	98293/-
Name of work : A/R & M/O LIG Qtr No.94 to 95 Pooled accomodation at Rakkar Colony Distt. Una H.P(Earnest Money	2000/-
S.H. :- Providing and laying R/wall)							Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 and as per direction of the Engineer- In - Charge Including carriage of materials within all leads and lifts and other incidental.	13.50	Per cubic metre	170.00	Rupees One hundred seventy only	2295		
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 40mm forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.	26.88	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	90048		
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	35.00	Each	170.00	Rupees One hundred seventy only	5950		
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018							Total:	98293
2) The rates shall be including of all types of taxes including GST ectra)								
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021								
Percentage quoted Rate in Figures								
Percentage quoted Rate in Words								
Note: Rates quoted in figures & words are mandatory								
by the contractor otherwise the tender will be rejected.								



 Executive Engineer
 Una Divn.HP.
 Una

(11)

SCHEDULE OF QUANTITY								
						Estimated Cost	99708/-	
Name of work :A/R & M/O residential building at Una (SH: Providing and laying roof treatment and outer repair in District Attorney and ACJM residence)						Earnest Money	2000/-	
						Time limit	One month	
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick induding cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:5 (1 cement: 5 sand)including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	70.56	Per square metre	160.00	Rupees One hundred sixty only	11290		
2	Brick work with common burnt clay F.P.S.(Non modular) bricks of class designation 7.5 in superstructure above plinth level upto all floor level /height in all shapes and size cement mortar 1:6(one cement: six sand) including curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax GST,labour cess or other taxes imposed by the Government.	3.50	Per cubic metre	6300.00	Rupees Six thousand three hundred only	22050		
3	Providing and laying in position cement concrete for plain/reinforced concrete in open foundation for all type structure complete in cement concrete 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.05	Per cubic metre	4600.00	Rupees Four thousand six hundred only	4830		
4	Providing and fixing polycarbonated transparent sheet 1.20mm thick in roofing with galvanised J or L hooks bolts and nuts with GI limpet and bitumen rubber washer complete with all accessories as required as per direction of Engineer-In-charge including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax GST,labour cess or other taxes imposed by the Government.	8.57	Per square metre	1300.00	Rupees One thousand three hundred only	11141		
5	Steel work welded in built up sections,trusses and framed work,including cutting ,hoisting ,fixing in position and applying a priming coat of red lead paint.IN beams joists channels , angles, tee , flats with connecting plates or angle cleats as in main and cross beams , hip and jack rafetrs, purlins connected to common rafters and the like including carriage of materials within all leads ad lifts.The rate includes octroi,royalty,Malkhana Toll tax , goods service tax,labour cess or other taxes imposed by the Governmment	1.03	Per Quantial	9800.00	Rupees Nine thousand eight hundred only	10094		

6

6	Finishing wall with weather proof exterior grade emulsion of approved design(Apex ultima/heritage) or its equivalent on undecorated wall surface(two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt,dust, and other foreign matter etc. including sand paper smooth complete.including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	207.15	Per square metre	65.00	Rupees Sixty five only	13465
7	Providing and laying water proofing treatment in sunken portion of WC,s bath room etc. by applying cement slurry mixed with water proofing cement compound consisting of applying (a) after surface preparation, first layer of slurry of cement @ 0.488 kg/sqm mixed with water proofing cement compound @ 0.253 kg/sqm.This layer will be allowed to air cure for 4 hours (b) second layer oof slurry of cement @ 0.242kg/sqm mixed with water proofing cement compound @ 0.126kg/sqm.This layer will be allowed to air cure for 4 hours followed with water curing for 48 hours including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	89.46	Per square metre	300.00	Rupees Four hundred sixty five only	26838
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				Total:	99708
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate In Figures					
	Percentage quoted Rate In Words					
	Note: Rates quoted In figures & words are mandatory					
	by the contractor, otherwise the tender will be rejected.					


 Executive Engineer,
 Una Division, HPBWD.,
 Una

SCHEDULE OF QUANTITY						Estimated Cost	99922/-
						Earnest Money	2000/-
Name of work :A/R & M/O non-residential building at Una (SH: Painting and toilet repair at police chowki sadar Una at Old Mini Secretariate)						Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT	
				Figures	Words		
1	Demolition RCC/RB work above GL upto floor two level including disposal of unserviceable material and stacking the serviceable material within any leads and lifts and other incidentials. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.27	Per cubic metre	550.00	Rupees Five hundred fifty only	149	
2	Demolition of brick work above GL upto floor two level including disposal of unserviceable material and stacking the serviceable material within any leads and lifts and other incidentials. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.66	Per cubic metre	550.00	Rupees Five hundred fifty only	913	
3	Brick work with common burnt clay F.P.S.(Non modular) bricks of class designation 7.5 in superstructure above plinth level upto all floor level /height in all shapes and size- cement mortar 1:6(one cement: six sand) including curing complete including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax GST,labour cess or other taxes imposed by the Government.	1.84	Per cubic metre	6300.00	Rupees Six thousand three hundred only	11592	
4	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick including cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:5 (1 cement: 5 sand)including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	15.56	Per square metre	160.00	Rupees One hundred sixty only	2490	
5	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops dust loose material and foreign matter sand papered smooth to give final matter finish to the surface complete including carriage of materials within all leads ad lifts.The rate includes octroi,royalty,Malkhana Toll tax , goods service tax,labour cess or other taxes imposed by the Government	15.56	Per square metre	60.00	Rupees Sixty only	934	
6	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats)including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	126.83	Per square metre	60.00	Rupees Sixty only	7610	

7 a)	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) for fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron) including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax GST, labour cess or other taxes imposed by the Government.	26.55	Per kilogramme	500.00	Rupees Five hundred only	13275
b)	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) complete. Powder coated aluminium (minimum thickness of powder coating 50 micron) including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	20.76	Per kilogramme	500.00	Rupees Five hundred only	10380
8	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber/ neoprene gasket etc. complete as per the architectural drawings and the the directions of Engineer-in-charge (cost of aluminium snap beading shall be paid in basic item) with float glass panes of 5mm thickness (weight not less than 12.5kg/sqm) including entire carriage of material within all leads and lifts and other incidentals as per direction by the Engineer-in-charge. The rate includes octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	0.54	Per square metre	1150.00	Rupees One thousand one hundred fifty only	621
9	Providing and fixing 12 mm thick pre-laminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge Pre-laminated particle board with decorative lamination on both sides including entire carriage of material within all leads and lifts and other incidentals as per direction by the Engineer-in-charge. The rate includes octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	2.22	Per square metre	1000.00	Rupees One thousand only	2220
10	Providing and fixing aluminium tower bolts (barrel type) anodized transparent or dyed to required shade and colour with screws etc. complete including carriage of materials with all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. . (a) 200x10mm (two hundred into ten millimetre)	10.00	Each	60.00	Rupees Sixty only	600

6

11	Providing and fixing aluminum handles anodized transparent or dyed to required colour and shade with necessary screws etc complete including carriage of materials with all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. (a) 125mm (one hundred twenty five millimetre)	10.00	Each	65.00	Rupees Sixty five only	650
12	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement : four sand : eight graded crushed / broken stone aggregate 20mm (twenty millimetre) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	1.18	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	3953
13	Providing and laying in position cement concrete for plain/reinforced concrete in open foundation for all type structure complete in cement concrete 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	0.54	Per cubic metre	4600.00	Rupees Four thousand six hundred only	2484
14	Steel reinforcement (Sai/RINL/Shyam steel Tisco, Jindal panther (JSPL) make) for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	10.80	Per Kilogramme	90.00	Rupees Ninety only	972
15	Providing and fixing 10mm (ten millimetre) thick anti skid water proof stain and impact resistant heavy duty vetrified tiles Nitco /Kajaria (600x600x10mm) (six hundred into six hundred into ten millimetre) manufactured of approved shade and colour in flooring treads of steps and landing laid on a bed of 12mm (twelve millimetre) thick cement mortar 1:3 (one cement: three sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment to match the shade of tiles as required complete including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government...	8.28	Per Square Metre	1100.00	Rupees One thousand one hundred only	9108

16	Providing and laying Duro stone vetrified tiles Kajaria,Nitco,Somany quality orient ,Rak by the Engineer-in-charge (600x600mmx8mm)(three hundred into three hundred into eight millimetre) in grey/coloured of required shade in skirting risers of steps and dado on 12mm thick cememnt mortor 1:3(1cement:3sand)laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles complete including carriage of materials within all leads and lifts and other incidentials. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	25.41	Per square metre	1150.00	Rupees One thousand one hundred fifty only	29222
17	Providing and fixing 110mm high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	11.00	Per running metre	250.00	Rupees Two hundred fifty only	2750
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018				Total:	99922
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate In Figures					
	Percentage quoted Rate In Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer
 Una Division, HPP & D.,
 Una

12

SCHEDULE OF QUANTITY						
Name of work :A/R & M/O residential building at Una (SH: Providing and laying outer repair type-III building Qtr No.9 to 20 in D.C. Colony Una)				Estimated Cost		99839/-
				Earnest Money		2000/-
				Time limit		One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick including cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:5 (1 cement: 5 sand)including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	15.48	Per square metre	160.00	Rupees One hundred sixty only	2477
2	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops dust loose material and foreign matter sand papered smooth to give final matter finish to the surface complete including carriage of materials within all leads ad lifts.The rate includes octroi,royalty,Malkhana Toll tax , goods service tax,labour cess or other taxes imposed by the Government	15.48	Per square metre	60.00	Rupees Sixty only	929
3	Providing and fixing glazing with glass panes of 4mm thickness(weight not less than 10kg./sqm.including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax GST,labour cess or other taxes imposed by the Government.	1.04	P/sqm	650.00	Rupees Six hundred fifty only	676
4	Finishing wall with weather proof exterior grade emulsion of approved design(Apex ultima/heritage) or its equivalent on undecorated wall surface(two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt,dust, and other foreign matter etc. including sand paper smooth complete.including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1473.18	Per square metre	65.00	Rupees Sixty five only	95757
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				Total:		99839
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020.dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate In Figures						
Percentage quoted Rate In Words						
Note: Rates quoted in figures & words are mandatory						
by the contractor otherwise the tender will be rejected.						

K. Gupta
Executive Engineer,
Una Divn.HP.PWD. *Una*

(96)


(14)

SCHEDULE OF QUANTITY						Estimated Cost	99944/-
Name of work : A/R & M/O LIG 104 Quarters Pooled accomodation at Rakkar Colony Distt. Una H.P. S.H. :- Repair of Wood work, Distemping painting etc.)						Earnest Money	2000/-
						Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately. (Sal wood) including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	0.038	Per cubic metre	95000.00	Rupees Ninety five thousand only	3610	
2	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, including panelling, all complete as per direction of Engineer-in-charge Kiln seasoned and chemically treated sheesham wood 30 mm thick shutters including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	3.74	Per square metre	4000.00	Rupees Four thousand only	14960	
3	P/F wire gauge shutters using galvanised M.S. wire gauge of I.S. gauge of average width of aperture 1.4mm both side direction with wire of dia 0.63 mm for doors, windows and clerestory windows i/c bright finished black enamelled iron hinges with necessary screws. Hollock woods 30 mm thick including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	1.50	Per square metre	3000.00	Rupees Three thousand only	4500	
4	Providing and fixing fly proof stainless steel grade 304 wire gauge, to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia. 0.50 mm all complete including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	2.42	Per square metre	850.00	Rupees Eight hundred fifty only	2057	
5	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade. Two or more coats on new work including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	34.41	Per square metre	65.00	Rupees Sixty five only	2237	
6	Removing dry or oil bound by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including carriage of material within all leads and lifts.	101.40	Per square metre	7.00	Rupees Seven only	710	
7	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	101.40	Per square metre	60.00	Rupees Sixty only	6084	

6

8	Distempering with oil bound washable distemper of 13.41.1 New work (two or more coats) over and including water thinnable priming coat with cement primer, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	101.40	Per square metre	55.00	Rupees Fifty five only	5577
9	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joints with white cement and matching pigments etc., complete of joints. Size of Tile 600x600 mm, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	23.53	Per square metre	1100.00	Rupees One thousand one hundred only	25883
10	Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades steps and dados over 12 mm thick bed of cement Mortar except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of 1:3 (1 cement: 3 coarse sand) and jointing with grey complete, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	14.16	Per square metre	800.00	Rupees Eight hundred only	11328
11	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm) including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government...	92.55	Per square metre	65.00	Rupees Sixty five only	6016
12	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931: 15 mm nominal bore, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	6.00	each	500.00	Rupees Five hundred only	3000
13	Providing and fixing brass stop cock of approved quality, 15mm Nominal Bore, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	2.00	each	550.00	Rupees Five hundred fifty only	1100
14	Providing and fixing G.I./ PE-AL-PE/ PP-R pipes, 15 mm dia nominal bore, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	6.00	Per running metre	300.00	Rupees Three hundred only	1800
15	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement : 4 fine sand) including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	10.40	Per square metre	160.00	Rupees One hundred sixty only	1664
16	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 450x300 mm with a pair of 15 mm C.P. brass pillar taps, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	1.00	each	2000.00	Rupees Two thousand only	2000

17	Providing and fixing vitreous china wash down, water closet squatting pan (European type WC pan) with integral P or S Trap Vc jointing the trap with soil pipe in cement mortar 1:1 Cera or its equivalent) including Seat cover & fittings, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana ,toll tax, GST, labour cess or other taxes imposed by the Government..	1.00	each	2500.00	Rupees Two thousand five hundred only	2500
18	Providing and fixing kitchen sink with C.I. brackets, C.P. brass chain with rubber plug, 40 mm C.P. brass waste complete, including painting the fittings and brackets, cutting and making good the walls wherever required White glazed fire clay kitchen sink of size 600x450x 250 mm including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana ,toll tax, GST, labour cess or other taxes imposed by the Government..	1.00	each	3000.00	Rupees Three thousand only	3000
19	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana ,toll tax, GST, labour cess or other taxes imposed by the Government..	0.19	Per cubic metre	4600.00	Rupees Four thousand six hundred only	874
20	Demolishing dry brick pitching in floors, drains etc. including stacking of serviceable material and disposal of unserviceable material within 50 metres lead : including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana ,toll tax, GST, labour cess or other taxes imposed by the Government..	0.67	Per cubic metre	550.00	Rupees Five hundred fifty only	369
21	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana ,toll tax, GST, labour cess or other taxes imposed by the Government..	7.50	Per kilogramme	90.00	Rupees Ninety only	675
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				Total:	99944
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer
 Una Divn. HP. PWD.
 Una


126

15

SCHEDULE OF QUANTITY						Estimated Cost	99641/-
Name of work : A/R & M/O LIG 104 & 108 Quarters Pooled accomodation at Rakkar Colony Distt. Una H.P(S.H. :- Repair of tile works etc.)						Earnest Money	2000/-
						Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joints with white cement and matching pigments etc., complete of joints . Size of Tile 600x600 mm.including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	70.52	Per square metre	1100.00	Rupees One thousand one hundred only	77572	
2	Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours,shades steps and dados over 12 mm thick bed of cement Mortar except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of 1:3 (1 cement: 3 coarse sand) and jointing with grey complete.including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	25.20	Per square metre	800.00	Rupees Eight hundred only	20160	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size)including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.188	Per cubic metre	4600.00	Rupees Four thousand six hundred only	865	
4	Demolishing dry brick pitching in floors, drains etc. Including stacking of serviceable material and disposal of unserviceable material within 50 metres lead :including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.67	Per cubic metre	550.00	Rupees Five hundred fifty only	369	

6

5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	7.50	Per kilogramme	90.00	Rupees Ninety only	675
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				Total:	99641
	2) The rates shall be including of all types of taxes including GST etcra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3)1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer
 Una Divn. HP. PW
 Una

118

16

SCHEDULE OF QUANTITY						Estimated Cost	99749/-
						Earnest Money	2000/-
Name of work : Repair & maintenance of HP.PWD., residential building at Jalgran Tehsil & Distt.Una (SH: P/L Interlock pavers along residence)(Part -I)						Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	10.65	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	35678	
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	71.99	Per square metre	890.00	Rupees Eight hundred ninety only	64071	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018						Total:	99749
2) The rates shall be including of all types of taxes including GST ectra)							
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021							
Percentage quoted Rate in Figures							
Percentage quoted Rate In Words							
Note: Rates quoted In figures & words are mandatory							
by the contractor otherwise the tender will be rejected.							

Kuldeep
Executive Engineer,
Una Divn.HP.PWD,Una

117


17

SCHEDULE OF QUANTITY

				Estimated Cost		99382/-
Name of work : Repair & maintenance of HP.PWD., residential building at Jalgran Tehsil & Distt.Una (SH: P/L interlock pavers along residence)(Part -II)				Earnest Money		2000/-
				Time limit		One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	9.94	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	33299
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter lockingpaver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and patternincluding entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	74.25	Per square metre	890.00	Rupees Eight hundred ninety only	66083
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)A(17)2/0212 dated 7.8.2018				Total:		99382
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate In Figures						
Percentage quoted Rate In Words						
Note: Rates quoted in figures & words are mandatory						
by the contractor otherwise the tender will be rejected.						

Kanishk
Executive Engineer
Una Divn.HP.PWD.,Una

SCHEDULE OF QUANTITY						
Name of work : Repair & maintenance of HP.PWD., residential building at Jalgran Tehsil & Distt.Una (SH: P/L interlock pavers along residence)(Part -III)				Estimated Cost		99355/-
				Earnest Money		2000/-
				Time limit		One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	10.70	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	35845
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	71.36	Per square metre	890.00	Rupees Eight hundred ninety only	63510
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				Total:		99355
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bld as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate in Figures						
Percentage quoted Rate in Words						
Note: Rates quoted in figures & words are mandatory						
by the contractor otherwise the tender will be rejected.						


 Executive Engineer,
 Una Divn.HP.PWD., Una

121
19

SCHEDULE OF QUANTITY							
Name of work : Repair & maintenance of HP.PWD., residential building at Jalgran Tehsil & Distt.Una (SH: P/L interlock pavers along residence)(Part -IV)					Estimated Cost		99912/-
					Earnest Money		2000/-
					Time limit		One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	10.76	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	36046	
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	71.76	Per square metre	890.00	Rupees Eight hundred ninety only	63866	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018					Total:		99912
2) The rates shall be including of all types of taxes including GST ectra)							
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021							
Percentage quoted Rate In Figures							
Percentage quoted Rate In Words							
Note: Rates quoted in figures & words are mandatory							
by the contractor otherwise the tender will be rejected.							


 Executive Engineer,

Una Divn.HP.PWD,Una

105

20

SCHEDULE OF QUANTITY							Estimated Cost	99550/-
Name of work : A/R & M/O Type-LIG Qtr. No.91 & 92 pooled accommodation at Rakkar colony Una (SH: Repair of roof with water proofing compound etc)							Earnest Money	2000/-
							Time limit	One month
							AMOUNT	
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick including cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:4 (1 cement : 4 sand)including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .	30.40	Per square metre	160.00	Rupees One hundred sixty only	4864		
2	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes Supreme/finolex/Kitch make conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 110mm (one hundred ten millimetre) nominal size including entire carriage of material within all leads and lifts and other Incidentals as per the direction by the Engineer-in-charge	5.80	Per running metre	250.00	Rupees Two hundred fifty only	1450		
3	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer, 3 mm thickwater proofing membrane, black finished reinforced withglass fibre matt consisting of a coat of bitumen primerfor bitumen membrane @ 0.40 litre/sqm by thesame membrane manufactured of denslty at 25°C, 0.87 -0.89 kg/litre and viscosity 70 - 160 cps. Over the primercoat the layer of membrane shall be laid using butanetorch and sealing all joints etc., and preparing thesurface complete. The vital physical and chemicalparameters of the membrane shall be as under : Jointstrength in longitudinal and transverse direclion at 23°Cas 350/300 N/5 cm. Tear strength in longitudinal andtransverse direction as 80/80N. Softening point ofmembrane not less than 150°C. Cold flexibility shall beupto -2°C when tested in accordance with ASTM, D -5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane 3mm thick . including carriage of materials within all leads and lifts. The rates are Inclusive of octroi, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.	143.44	Pe square metre	650.00	Rs. Six hundred fifty only	93236		
				Total:		99550		
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)A(17)2/0212 dated 7.8.2018								
2) The rates shall be including of all types of taxes including GST ectra)								
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021								
Percentage quoted Rate in Figures								
Percentage quoted Rate in Words								
Note: Rates quoted in figures & words are mandatory								
by the contractor otherwise the tender will be rejected.								

Executive Engineer
Una Divn. HP. PWD

SCHEDULE OF QUANTITY						
					Estimated Cost	99548/-
					Earnest Money	2000/-
					Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick including cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:4 (1 cement :4 sand) including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge.	30.40	Per square metre	160.00	Rupees One hundred sixty only	4864
2	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes Supreme/finolex/Kitch make conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 110mm (one hundred ten millimetre) nominal size including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge	5.79	Per running metre	250.00	Rupees Two hundred fifty only	1448
3	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer, 3 mm thick water proofing membrane, black finished reinforced with glass fibre matt consisting of a coat of bitumen primer for bitumen membrane @ 0.40 litre/sqm by the same membrane manufactured of density at 25°C. 0.87 -0.89 kg/litre and viscosity 70 - 160 cps. Over the primer coat the layer of membrane shall be laid using butane torch and sealing all joints etc., and preparing the surface complete. The vital physical and chemical parameters of the membrane shall be as under : Joint strength in longitudinal and transverse direction at 23°C as 350/300 N/5 cm. Tear strength in longitudinal and transverse direction as 60/80N. Softening point of membrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D -5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane 3mm thick including carriage of materials within all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	143.44	Per square metre	650.00	Rs. Six hundred fifty only	93236
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018					Total:	99548
2) The rates shall be including of all types of taxes including GST etcra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate in Figures						
Percentage quoted Rate in Words						
Note: Rates quoted in figures & words are mandatory						
by the contractor otherwise the tender will be rejected.						

K. Lalwani
Executive Engineer

Una-Divn HP PWD Ind

107

22

SCHEDULE OF QUANTITY

Name of work : A/R & M/O Type-LIG Qtr. No.95 & 96 pooled accommodation at Rakkar colony Una (SH: Repair of roof with water proofing compound etc)						Estimated Cost	99545/-
						Earnest Money	2000/-
						Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick including cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:4 (1 cement :4 sand)including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .	30.40	Per square metre	160.00	Rupees One hundred sixty only	4864	
2	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes Supreme/finolex/Kitch make conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (I) Single socketed pipes 110mm (one hundred ten millimetre) nominal size including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge	5.78	Per running metre	250.00	Rupees Two hundred fifty only	1445	
3	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer, 3 mm thickwater proofing membrane, black finished reinforced withglass fibre matt consisting of a coat of bitumen primerfor bitumen membrane @ 0.40 litre/sqm by thesame membrane manufactured of density at 25°C. 0.87 -0.89 kg/litre and viscosity 70 - 160 cps. Over the primercoat the layer of membrane shall be laid using butanetorch and sealing all joints etc., and preparing thesurface complete. The vital physical and chemicalparameters of the membrane shall be as under : Jointstrength in longitudinal and transverse direction at 23°Cas 350/300 N/5 cm. Tear strength in longitudinal andtransverse direction as 60/80N. Softening point ofmembrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM. D -5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane 3mm thick . including carriage of materials within all leads and lifts.The rates are inclusive of octroi, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.	143.44	Pe square metre	650.00	Rs.Six hundred fifty only	93236	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)A(17)2/0212 dated 7.8.2018						Total:	99545
2) The rates shall be including of all types of taxes including GST etc(tra)							
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021							
Percentage quoted Rate in Figures							
Percentage quoted Rate in Words							
Note: Rates quoted in figures & words are mandatory							
by the contractor otherwise the tender will be rejected.							

K. Gupta
Executive Engineer
Una Divn. HP, PWD Una

(108)

(23)

SCHEDULE OF QUANTITY						
					Estimated Cost	99646/-
Name of work : A/R & M/O Type-LIG Qtr. No.97 & 98 pooled accommodation at Rakkar colony Una (SH: Repair of roof with water proofing compound etc)					Earnest Money	2000/-
					Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick including cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:4 (1 cement :4 sand)including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .	31.00	Per square metre	160.00	Rupees One hundred sixty only	4960
2	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes Supreme/finolex/Kitch make conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 110mm (one hundred ten millimetre) nominal size including entire carriage of material within all leads and lifts and other Incidentals as per the direction by the Engineer-in-charge .	5.80	Per running metre	250.00	Rupees Two hundred fifty only	1450
3	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer, 3 mm thickwater proofing membrane, black finished reinforced withglass fibre matt consisting of a coat of bitumen primerfor bitumen membrane @ 0.40 litre/sqm by thesame membrane manufactured of density at 25°C, 0.87 -0.89 kg/litre and viscosity 70 - 160 cps. Over the primercoat the layer of membrane shall be laid using butanetorch and sealing all joints etc., and preparing thesurface complete. The vital physical and chemicalparameters of the membrane shall be as under : Jointstrength in longitudinal and transverse direction at 23°Cas 350/300 N/5 cm. Tear strength in longitudinal andtransverse direction as 60/80N. Softening point ofmembrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D -5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane 3mm thick . including carriage of materials within all leads and lifts.The rates are inclusive of octroi, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.	143.44	Pe square metre	650.00	Rs.Six hundred fifty only	93236
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018					Total:	99646
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate In Figures						
Percentage quoted Rate In Words						
Note: Rates quoted in figures & words are mandatory						
by the contractor otherwise the tender will be rejected.						

Pravish
Executive Engineer
Una Divn HP PWD

109

24

SCHEDULE OF QUANTITY						Estimated Cost	99644/-
Name of work : A/R & M/O Type-LIG Qtr. No.99 & 100 pooled accommodation at Rakkar colony Una (SH: Repair of roof with water proofing compound etc)						Earnest Money	2000/-
						Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick including cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs. with cement mortar 1:4 (1 cement : 4 sand) including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge.	31.00	Per square metre	160.00	Rupees One hundred sixty only	4960	
2	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes Supreme/finolex/Kitch make conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 110mm (one hundred ten millimetre) nominal size including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge.	5.79	Per running metre	250.00	Rupees Two hundred fifty only	1448	
3	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer, 3 mm thick water proofing membrane, black finished reinforced with glass fibre matt consisting of a coat of bitumen primer for bitumen membrane @ 0.40 litre/sqm by the same membrane manufactured of density at 25°C, 0.87 -0.89 kg/litre and viscosity 70 - 160 cps. Over the primer coat the layer of membrane shall be laid using butane torch and sealing all joints etc., and preparing the surface complete. The vital physical and chemical parameters of the membrane shall be as under : Joint strength in longitudinal and transverse direction at 23°C as 350/300 N/5 cm. Tear strength in longitudinal and transverse direction as 60/80N. Softening point of membrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D -5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane 3mm thick including carriage of materials within all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	143.44	Per square metre	650.00	Rs. Six hundred fifty only	93236	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@ (17)2/0212 dated 7.8.2018						Total:	99644
2) The rates shall be including of all types of taxes including GST etc (ra)							
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021							
Percentage quoted Rate in Figures							
Percentage quoted Rate in Words							
Note: Rates quoted in figures & words are mandatory							
by the contractor otherwise the tender will be rejected.							

K. K. K.
Executive Engineer
Una Divn. HP, PW, P. & S.

110

25

SCHEDULE OF QUANTITY							Estimated Cost	99641/-
Name of work : A/R & M/O Type-LIG Qtr. No.101 & 102 pooled accommodation at Rakkar colony Una (SH: Repair of roof with water proofing compound etc)							Earnest Money	2000/-
							Time limit	One month
							AMOUNT	
S. No.	Description of work	Quantity	Unit	RATE In				
				Figures	Words			
1	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:4 (1 cement :4 sand)Including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .	31.00	Per square metre	160.00	Rupees One hundred sixty only		4960	
2	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes Supreme/finolex/Kitch make conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. (i) Single socketed pipes 110mm (one hundred ten millimetre) nominal size including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge	5.78	Per running metre	250.00	Rupees Two hundred fifty only		1445	
3	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer, 3 mm thickwater proofing membrane, black finished reinforced withglass fibre matt consisting of a coat of bitumen primerfor bitumen membrane @ 0.40 litre/sqm by thesame membrane manufactured of density at 25°C, 0.87 -0.89 kg/litre and viscosity 70 - 160 cps. Over the primercoat the layer of membrane shall be laid using butanetorch and sealing all joints etc., and preparing thesurface complete. The vital physical and chemicalparameters of the membrane shall be as under : Jointstrength in longitudinal and transverse direction at 23°Cas 350/300 N/5 cm. Tear strength in longitudinal andtransverse direction as 60/80N. Softening point ofmembrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D -5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane 3mm thick . including carriage of materials within all leads and lifts.The rates are Inclusive of octroi, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.	143.44	Pe square metre	650.00	Rs.Six hundred fifty only		93236	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018							Total:	99641
2) The rates shall be including of all types of taxes including GST etdra)								
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021								
Percentage quoted Rate in Figures								
Percentage quoted Rate in Words								
Note: Rates quoted in figures & words are mandatory								
by the contractor otherwise the tender will be rejected.								

Executive Engineer
Una Divn.HP PWD Una

(11)

26

SCHEDULE OF QUANTITY							Estimated Cost	99598/-	
Name of work : A/R & M/O Type-LIG Qtr. No.103 & 104 pooled accommodation at Rakkar colony Una (SH: Repair of roof with water proofing compound etc)							Earnest Money	2000/-	
							Time limit		One month
							AMOUNT		
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT			
				Figures	Words				
1	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick including cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:4 (1 cement :4 sand)including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .	30.70	Per square metre	160.00	Rupees One hundred sixty only	4912			
2	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes Supreme/finolex/Kitch make conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 110mm (one hundred ten millimetre) nominal size including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge	5.80	Per running metre	250.00	Rupees Two hundred fifty only	1450			
3	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer, 3 mm thickwater proofing membrane, black finished reinforced withglass fibre matt consisting of a coat of bitumen primerfor bitumen membrane @ 0.40 litre/sqm by thesame membrane manufactured of density at 25°C, 0.87 -0.89 kg/litre and viscosity 70 - 160 cps. Over the primercoat the layer of membrane shall be laid using butanetorch and sealing all joints etc., and preparing thesurface complete. The vital physical and chemicalparameters of the membrane shall be as under : Jointstrength in longitudinal and transverse direction at 23°Cas 350/300 N/5 cm. Tear strength in longitudinal andtransverse direction as 60/80N. Softening point ofmembrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D -5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane 3mm thick . including carriage of materials within all leads and lifts.The rates are inclusive of octroi, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.	143.44	Pe square metre	650.00	Rs.Six hundred fifty only	93236			
						Total:	99598		
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)A(17)2/0212 dated 7.8.2018									
2) The rates shall be including of all types of taxes including GST etdra)									
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021									
Percentage quoted Rate in Figures									
Percentage quoted Rate in Words									
Note: Rates quoted in figures & words are mandatory									
by the contractor otherwise the tender will be rejected.									

K. K. K. K.
Executive Engineer
Una Divn.HP.PWP. Una

117

27

SCHEDULE OF QUANTITY							Estimated Cost	99732/-
Name of work : A/R & M/O Type-LIG Qtr. No.120 & 121 pooled accommodation at Rakkar colony Una (SH: Repair of roof with water proofing compound etc)							Earnest Money	2000/-
							Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick including cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:4 (1 cement :4 sand)including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .	31.60	Per square metre	160.00	Rupees One hundred sixty only	5056		
2	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes Supreme/finolex/Kitch make conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 110mm (one hundred ten millimetre) nominal size including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge	5.76	Per running metre	250.00	Rupees Two hundred fifty only	1440		
3	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer, 3 mm thickwater proofing membrane, black finished reinforced withglass fibre matt consisting of a coat of bitumen primerfor bitumen membrane @ 0.40 litre/sqm: by thesame membrane manufactured of density at 25°C, 0.87 -0.89 kg/litre and viscosity 70 - 160 cps. Over the primercoat the layer of membrane shall be laid using butanetorch and sealing all joints etc., and preparing thesurface complete. The vital physical and chemicalparameters of the membrane shall be as under : Jointstrength in longitudinal and transverse direction at 23°Cas 350/300 N/5 cm. Tear strength in longitudinal andtransverse direction as 60/80N. Softening point ofmembrane not less than 150°C. Cold flexibility shall beupto -2°C when tested in accordance with ASTM, D -5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane 3mm thick , including carriage of materials within all leads and lifts.The rates are inclusive of octroi, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.	143.44	Pe square metre	650.00	Rs.Six hundred fifty only	93236		
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)A(17)2/0212 dated 7.8.2018							Total:	99732
2) The rates shall be including of all types of taxes including GST ectra)								
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021								
Percentage quoted Rate in Figures								
Percentage quoted Rate in Words								
Note: Rates quoted in figures & words are mandatory								
by the contractor otherwise the tender will be rejected.								

K. Singh
Executive Engineer

26

SCHEDULE OF QUANTITY						
Name of work : A/R & M/O Type-LIG Qtr. No.105 & 106 pooled accommodation at Rakkar colony Una				Estimated Cost	99598/-	
(SH: Repair of roof with water proofing compound etc)				Earnest Money	2000/-	
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick including cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:4 (1 cement :4 sand)including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .	30.70	Per square metre	160.00	Rupees One hundred sixty only	4912
2	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes Supreme/finolex/Kitch make conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 110mm (one hundred ten millimetre) nominal size including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge	5.80	Per running metre	250.00	Rupees Two hundred fifty only	1450
3	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer, 3 mm thickwater proofing membrane, black finished reinforced withglass fibre matt consisting of a coat of bitumen primerfor bitumen membrane @ 0.40 litre/sqm by thesame membrane manufactured of density at 25°C, 0.87 -0.89 kg/litre and viscocity 70 - 160 cps. Over the primercoat the layer of membrane shall be laid using butanetorch and sealing all joints etc., and preparing thesurface complete. The vital physical and chemicalparameters of the membrane shall be as under : Jointstrength in longitudinal and transverse direction at 23°Cas 350/300 N/5 cm. Tear strength in longitudinal andtransverse direction as 60/80N. Softening point ofmembrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D -5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane 3mm thick . including carriage of materials within all leads and lifts.The rates are inclusive of octroi, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.	143.44	Per square metre	650.00	Rs.Six hundred fifty only	93236
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2016				Total:		99598
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification Issued by the Principat Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate In Figures						
Percentage quoted Rate In Words						
Note: Rates quoted In figures & words are mandatory						
by the contractor otherwise the tender will be rejected.						

K. K. K.
Executive Engineer
Una Divn HP PWD

113

29

SCHEDULE OF QUANTITY						
Name of work : A/R & M/O Type-LIG Qtr. No.107 & 108 pooled accommodation at Rakkar colony Una (SH: Repair of roof with water proofing compound etc)				Estimated Cost	99593/-	
				Earnest Money	2000/-	
				Time limit	One month	
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick including cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:4 (1 cement :4 sand) including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge.	30.70	Per square metre	160.00	Rupees One hundred sixty only	4912
2	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes Supreme/finolex/Kitch make conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 110mm (one hundred ten millimetre) nominal size including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge	5.78	Per running metre	250.00	Rupees Two hundred fifty only	1445
3	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer, 3 mm thick water proofing membrane, black finished reinforced with glass fibre matt consisting of a coat of bitumen primer for bitumen membrane @ 0.40 litre/sqm by the same membrane manufactured of density at 25°C, 0.87 -0.89 kg/litre and viscosity 70 - 160 cps. Over the primer coat the layer of membrane shall be laid using butane torch and sealing all joints etc., and preparing the surface complete. The vital physical and chemical parameters of the membrane shall be as under : Joint strength in longitudinal and transverse direction at 23°C as 350/300 N/5 cm. Tear strength in longitudinal and transverse direction as 60/80N. Softening point of membrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D -5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane 3mm thick including carriage of materials within all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	143.44	Per square metre	650.00	Rs. Six hundred fifty only	93236
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				Total:		99593
2) The rates shall be including of all types of taxes including GST etcra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)/1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate in Figures						
Percentage quoted Rate in Words						
Note: Rates quoted in figures & words are mandatory						
by the contractor otherwise the tender will be rejected.						

Kishor
Executive Engineer

Una Divn HP-PWR Una

114

30

SCHEDULE OF QUANTITY							Estimated Cost	99742/-
Name of work : A/R & M/O Type-LIG Qtr. No.109 & 110 pooled accommodation at Rakkar colony Una (SH: Repair of roof with water proofing compound etc)							Earnest Money	2000/-
							Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick including cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:4 (1 cement :4 sand)including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .	31.60	Per square metre	160.00	Rupees One hundred sixty only	5056		
2	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes Supreme/finolex/Kitch make conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 110mm (one hundred ten millimetre) nominal size including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge	5.80	Per running metre	250.00	Rupees Two hundred fifty only	1450		
3	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer, 3 mm thickwater proofing membrane, black finished reinforced withglass fibre matt consisting of a coat of bitumen primerfor bitumen membrane @ 0.40 litre/sqm by thesame membrane manufactured of density at 25°C. 0.87 -0.89 kg/litre and viscosity 70 - 160 cps. Over the primercoat the layer of membrane shall be laid using butanetorch and sealing all joints etc., and preparing thesurface complete. The vital physical and chemicalparameters of the membrane shall be as under : Jointstrength in longitudinal and transverse direction at 23°Cas 350/300 N/5 cm. Tear strength in longitudinal andtransverse direction as 60/80N. Softening point ofmembrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D -5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane 3mm thick . including carriage of materials within all leads and lifts.The rates are inclusive of octrol, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.	143.44	Pe square metre	650.00	Rs.Six hundred fifty only	93236		
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018							Total:	99742
2) The rates shall be including of all types of taxes including GST ectra)								
3) The bidder are requested to submit their bid as per notification Issued by the Prindpal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021								
Percentage quoted Rate In Figures								
Percentage quoted Rate In Words								
Note: Rates quoted in figures & words are mandatory								
by the contractor otherwise the tender will be rejected.								

Executive Engineer

Una Divn HP PWA Una

(115)

(31)

SCHEDULE OF QUANTITY						Estimated Cost	99737/-
Name of work : A/R & M/O Type-LIG Qtr. No.116 & 117 pooled accommodation at Rakkar colony Una (SH: Repair of roof with water proofing compound etc)						Earnest Money	2000/-
						Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick induding cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:4 (1 cement :4 sand)including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .	31.60	Per square metre	160.00	Rupees One hundred sixty only	5056	
2	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes Supreme/finolex/Kitch make conforming to IS : 13592 Type A. including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 110mm (one hundred ten millimetre) nominal size including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge	5.78	Per running metre	250.00	Rupees Two hundred fifty only	1445	
3	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer, 3 mm thickwater proofing membrane, black finished reinforced withglass fibre matt consisting of a coat of bitumen primerfor bitumen membrane @ 0.40 litre/sqm by thesame membrane manufactured of density at 25°C, 0.87 -0.89 kg/litre and viscosity 70 - 160 cps. Over the primercoat the layer of membrane shall be laid using butanetorch and sealing all joints etc., and preparing thesurface complete. The vital physical and chemicalparameters of the membrane shall be as under : Jointstrength in longitudinal and transverse direction at 23°Cas 350/300 N/5 cm. Tear strength in longitudinal andtransverse direction as 60/80N. Softening point ofmembrane not less than 150°C. Cold flexibility shall beupto -2°C when tested in accordance with ASTM, D -5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane 3mm thick . including carriage of materials within all leads and lifts.The rates are inclusive of octroi, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.	143.44	Pe square metre	650.00	Rs.Six hundred fifty only	93236	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018						Total:	99737
2) The rates shall be including of all types of taxes including GST elctra)							
3) The bidder are requested to submit their bid as per nollfication issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021							
Percentage quoted Rate in Figures							
Percentage quoted Rate in Words							
Note: Rates quoted in figures & words are mandatory							
by the contractor otherwise the tender will be rejected.							

K. K. K. K.
Executive Engineer

Una Distt HP PW

(116)


(32)

SCHEDULE OF QUANTITY							Estimated Cost	99735/-
Name of work : A/R & M/O Type-LIG Qtr. No.118 & 119 pooled accommodation at Rakkar colony Una (SH: Repair of roof with water proofing compound etc)							Earnest Money	2000/-
							Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick including cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:4 (1 cement :4 sand)including entire cartage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .	31.60	Per square metre	160.00	Rupees One hundred sixty only	5056		
2	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes Supreme/finolex/Kitch make conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 110mm (one hundred ten millimetre) nominal size including entire cartage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .	5.77	Per running metre	250.00	Rupees Two hundred fifty only	1443		
3	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer, 3 mm thickwater proofing membrane, black finished reinforced withglass fibre matt consisting of a coat of bitumen primerfor bitumen membrane @ 0.40 litre/sqm by thesame membrane manufactured of density at 25°C, 0.87 -0.89 kg/litre and viscosity 70 - 150 cps. Over the primercoat the layer of membrane shall be laid using butanetorch and sealing all joints etc., and preparing thesurface complete. The vital physical and chemicalparameters of the membrane shall be as under : Jointstrength in longitudinal and transverse direction at 23°Cas 350/300 N/5 cm. Tear strength in longitudinal andtransverse direction as 60/80N. Softening point ofmembrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D -5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane 3mm thick . including cartage of materials within all leads and lifts.The rates are inclusive of octroi, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.	143.44	Pe square metre	650.00	Rs.Six hundred fifty only	93236		
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)A(17)2/0212 dated 7.8.2018							Total:	99735
2) The rates shall be including of all types of taxes including GST ectra)								
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021								
Percentage quoted Rate in Figures								
Percentage quoted Rate in Words								
Note: Rates quoted in figures & words are mandatory								
by the contractor otherwise the tender will be rejected.								

Executive Engineer

SCHEDULE OF QUANTITY							Estimated Cost	82583/-
Name of work : A/R & M/O Asst. Commr. quarter No.27 Type-III residential building at Rakkar Distt.Una (SH: C/O Car shed size 3.50x3.00 with structural steel and prepainted steel sheet etc)							Earnest Money	2000/-
							Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 and as per direction of the Engineer- In - Charge including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.410	Per cubic metre	170.00	Rupees One hundred seventy only	70		
2	Providing and laying in position cement concrete for plain/reinforced concrete in open foundation for all type structure complete in cement concrete 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.41	Per cubic metre	4800.00	Rupees Four thousand eight hundred only	1968		
3	Steel work welded in built up sections, trusses and framed work including cutting, hoisting, fixing in position and applying a priming coat of red lead paintIn grating, in RS joists , channels angles, tees including carriage of materials within all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	4.560	Per Quintal	10000.00	Rupees Ten thousand only	45600		
4	Providing and fixing 0.60mm thick prepainted steel sheet in roofing over steel members/ trusses ,prepainted steel hot dipped metallic zinc coated sheet with top coat of regular modified polyster (R.N.P.) organic coating of 20(twenty) microns over 5(five) microns primer coating to back coat of polyster of five micron over 5 (five) microns primer coating including fixing with prepainted Iron J or L hooks bolts and nuts 6mm diametre with prepainted limpet and rubber washers complete including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	10.50	Per Square metre	1100.00	Rupees One thousand one hundred only	11550		
5	Providing and laying cement concrete 1:5:10(one cement:five sand: ten graded stone aggregate 40mm(forty millimetre) nominal size and curing complete including the cost of form work in foundation and plinth including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.58	Per cubic metre	3000.00	Rupees Three thousand only	4740		


6	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, maikhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	10.50	Per square metre	890.00	Rupees Eight hundred ninety only	9345
7	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50mm including strengthening with 2mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge made of GI wire of dia 4mm including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty, maikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	14.000	Per square metre	665.00	Rupees Six hundred sixty five only	9310
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)G(17)2/0212 dated 7.8.2018				Total:	82583
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate In Figures					
	Percentage quoted Rate In Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer
 Una Divn. HP. PW
 Una

134

34

SCHEDULE OF QUANTITY						
					Estimated Cost	98402/-
					Earnest Money	2000/-
					Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repair to scratches etc. complete including material within any leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government.	831.15	Per square metre	8.00	Rupees Eight only	6649
2	Applying Biria white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops dust loose material and foreign matter sand papered smooth to give final matter finish to the surface complete including carriage of materials within all leads and lifts. The rate includes octroi, royalty, Malikhana Toll tax, goods service tax, labour cess or other taxes imposed by the Government	277.05	Per square metre	60.00	Rupees Sixty only	16623
3	Finishing walls with apex exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	831.15	Per square metre	85.00	Rupees Eighty five only	70648
4	Painting wood work with deluxe multi surface paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacture including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	68.96	Per square metre	65.00	Rupees Sixty five only	4482
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)6(17)2/0212 dated 7.8.2018						98402
2) The rates shall be including of all types of taxes including GST etcra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate in Figures						
Percentage quoted Rate in Words						
Note: Rates quoted in figures & words are mandatory						
by the contractor otherwise the tender will be rejected.						


 Executive Engineer
 Una Divn. HP. PW
 Una

135


35

SCHEDULE OF QUANTITY						
					Estimated Cost	98886/-
Name of work :A/R & M/O residential building for in DC colony Una (SH: providing painting out side and DC residence (Part-II)					Earnest Money	2000/-
					Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repair to scratches etc. complete including material within any leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	812.67	Per square metre	8.00	Rupees Eight only	6501
2	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops dust loose material and foreign matter sand papered smooth to give final matter finish to the surface complete including carriage of materials within all leads ad lifts.The rate includes octroi,royalty,Malkhana Toll tax , goods service tax,labour cess or other taxes imposed by the Government	270.89	Per square metre	60.00	Rupees Sixty only	16253
3	Finishing walls with apex exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) Including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government .	812.67	Per square metre	85.00	Rupees Eighty five only	69077
4	Painting steel work with deluxe multi surface paint to give an even shade . Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.80 ltr/10 sqm of approved brand and manufacture including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government .	108.54	Per square metre	65.00	Rupees Sixty five only	7055
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018						98886
2) The rates shall be including of all types of taxes including GST etcetra)						
3) The bidder are requested to submit their bid as per notification Issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate In Figures						
Percentage quoted Rate In Words						
Note: Rates quoted in figures & words are mandatory						
by the contractor, otherwise the tender will be rejected.						

Kaushal
Executive Engineer
Una Divn.HP.PWD
Una

136
36

SCHEDULE OF QUANTITY						
					Estimated Cost	96960/-
Name of work :A/R & M/O residential building for in DC colony Una (SH: providing painting out side and DC residence (Part-III))					Earnest Money	2000/-
					Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repair to scratches etc. complete including material within any leads and lifts and other incidentals. The rate Includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	858.06	Per square metre	8.00	Rupees Eight only	6864
2	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops dust loose material and foreign matter sand papered smooth to give final matter finish to the surface complete including carriage of materials within all leads ad lifts.The rate includes octroi,royalty,Malkhana Toll tax , goods service tax,labour cess or other taxes imposed by the Government	286.02	Per square metre	60.00	Rupees Sixty only	17161
3	Finishing walls with apex exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) including entire carriage of material within all leads and lifts and other Incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	858.06	Per square metre	85.00	Rupees Eighty five only	72935
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018						96960
2) The rates shall be including of all types of taxes including GST etc(tra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted Rate In Figures						
Percentage quoted Rate In Words						
Note: Rates quoted in figures & words are mandatory						
by the contractor, otherwise the tender will be rejected.						


 Executive Engineer
 Una Divn.HP.PWD
 Una

(109)

(37)

N/R
✓

Schedule of Quantity							
						Estimated Cost	95020
Name of work: Repair & Maintenance of Non-residential building at Una Distt.Una (SH: Providing services out sources basis of One No.Supervisor/work inspector for Period of five month i.e. 1st January 2026 to May 2026)						Earnest Money	2000/-
						Time limit	Five month
Sl. No.	Description of work	Qty	Unit	RATE In		AMOUN T	
				Figures	Words		
1	Providing Services on temporary basis of Supervisor /work inspector to assist court cases during working hour 10AM to 5 PM or as when required by the officer-in-charge.	151 days	P/day	629.27	Rupees Six hundred twenty nine and paise twenty seven only	95020	
					Total:	95020	
Percentage quoted Rate in Figures							
Percentage quoted Rate in Words							
Note: Rates quoted in figures & words are mandatory							
by the contractor otherwise the tender will be rejected.							

K. K. K.
Executive Engineer,
Una Division, HPPWD.,
Una

(93)


(3)

SCHEDULE OF QUANTITY					Estimated cost	99666/-
					Earnest money	2000/-
					Time limit	One month
Name of Work: Repair & maintenance of office of Assistant Engineer HP.PWD.,Sub-Division No.I Una at DC colony Una (HP)(SH: P/L painting and other repair etc(Part-I))						
S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in Rs.)
				Figures	Words	
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs scratches complete including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	326.03	Per square metre	7.00	Rupees Seven only	2282
2	Repair to plaster in patches of 2.50sqm and under 10 to 15mm thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20mtr. with Cement mortar 1:4 (1cement:4sand)including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	40.00	Per square metre	160.00	Rupees One hundred sixty only	6400
3	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops dust loose material and foreign matter sand papered smooth to give final matter finish to the surface complete including carriage of materials within all leads ad lifts.The rate includes octroi,royalty,Malkhana Toll tax , goods service tax,labour cess or other taxes imposed by the Government	40.00	Per square metre	60.00	Rupees Sixty only	2400
4	Distempering (two coat) with oil bound washable distemper of approved brand and manufacture and of required shade on decorated wall surfaces to give an even shade after thoroughly brushing the surface clean of all grease dirt,loose,pieces of scales and also including preparing the surface even and sand papered smooth including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	171.61	Per square metre	55.00	Rupees Sixty five only	9439
5	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Two or more coats applied on walls @ 1.67 ltr/10 sqm over and including one coat of Special primer applied @2.20 ltr /10 sqm including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	158.30	Per square metre	65.00	Rupees Sixty five only	10290

12

6	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Sal wood, including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	0.052	Per cubic metre	95000	Rupees Ninety five thousand only	4940
7	Providing and fixing 40mm(forty millimeter) thick 2 nd class deodar wood wire gauge shutters using galvanized MS wire gauge of IS gauge designation 85-G(eighty five) with wire of dia 0.56mm(zero point fifty six millimeter) for doors windows clerestory windows including bright finished black enameled iron butt hinges with necessary screws including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	5.88	Per square metre	3000.00	Rupees Three thousand only	17640
8	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows. Including black enameled iron butt hinges with necessary screws. 40mm thick 2nd class deodar wood, including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	5.88	Per square metre	4000.00	Rupees Four thousand only	23520
9	Providing and fixing glazing with glass panes of 5.50mm(five point fifty millimetre) thickness(weight not less than 13.75kilogramme square metre in aluminium door, window, ventilator shutters make it Hindcol Co. Jindal Indian aluminium Co. and partition etcetra with PVC/neoprens gasket etcetra complete upto floor all level/height as per the architectural drawings including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax GST, labour cess or other taxes imposed by the Government.	2.19	Per square metre	650.00	Rupees Six hundred fifty only	1424
10	Providing and fixing aluminium tower bolts (Barrel type) anodized transparent or dyed to required shade and colour with screws etc. 200 x 10mm including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government	20.00	each	70.00	Rupees Seventy only	1400
11	Providing and fixing aluminium handles anodized transparent or dyed to required colour or shade with necessary screws etc. complete including carriage of materials in all leads and lifts. (125mm) including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government	15.00	each	80.00	Rupees Eighty only	1200

12	Painting two coat(excluding priming coat)on wood and wood based surfaces with enamel paint to given and even shade including cleaning of all dirt,dust and other foreign matter sand papering and stopping including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government	82.73	Per square metre	65.00	Rupees Sixty five only	5377
13	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	0.68	Per Quantial	9500.00	Rupees Nine thousand five hundred only	6451
14	Writing letters or figures on any surface with black japan paint(stops, comas, hyphens and the like not to be measured and paid separately) Indian (letters figures) includingthe coat of material including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	3540.00	Per letter per cm. height	1.95	Rupees One point ninety five five	6903
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				G.Total	99666
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted In figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer
 Una Divn.HP.PW
 Una

(20)

(39)

SCHEDULE OF QUANTITY

Estimated cost

82185/-

Earnest money

2000/-


Time limit

One month

Name of Work: A/R & M/O Non-residential building at Una (SH: Repair of CCTV surveillance system of CP PLUS with IP quality at circle office Una (HP)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Providing and fixing IP BULLET CAMERA 4 MP night vision including entire carriage of material within all leads and lifts and other incidentals as per the direction of the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	5.00	each	5800.00	Rupees Five thousand eight hundred only	29000
2	Providing and fixing NVR 16 CHANNEL including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.00	each	38000.00	Rupees Thirty eight thousand only	38000
3	Providing and fixing POE switch including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	2.00	each	4850.00	Rupees Four thousand eight hundred fifty only	9700
4	Providing and fixing RJ 45 connector - including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	10.00	each	175.00	Rupees One hundred seventy five only	1750
5	Providing and fixing 3U Rack including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.00	each	1575.00	Rupees One thousand five hundred seventy five only	1575

6	Providing and fixing WIRE CAT 6 including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are Inclusive octrol, oyalty.malkana,toll tax,sale tax,GST,labour cess or other taxes imposed bythe Government	60.00	Per Running metre	36.00	Rupees Thirty six only	2160
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				G.Total	82185
	2) The rates shall be including of all types of taxes including GST etcra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted In figures & words are mandatory					
	by the contractor otherwise the tender will be rejected					


 Executive Engineer
 Una Division, HPPWD, Una

(94)

(40)

SCHEDULE OF QUANTITY

Estimated cost 99750/-

Earnest money 2000/-

Time limit One month


Name of Work: Repair & maintenance of office of Assistant Engineer HP.PWD.,Sub-Division No.I Una at DC colony Una (HP)(SH: P/L water proofing etc(Part-II))

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer, 3 mm thickwater proofing membrane, black finished reinforced withglass fibre matt consisting of a coat of bitumen primerfor bitumen membrane @ 0.40 litre/sqm by thesame membrane manufactured of density at 25°C, 0.87 -0.89 kg/litre and viscosity 70 - 160 cps. Over the primercoat the layer of membrane shall be laid using butanetorch and sealing all joints etc., and preparing thesurface complete. The vital physical and chemicalparameters of the membrane shall be as under : Jointstrength in longitudinal and transverse direction at 23°Cas 350/300 N/5 cm. Tear strength in longitudinal andtransverse direction as 60/80N. Softening point ofmembrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D -5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane 3mm thick . including carriage of materials within all leads and lifts.The rates are inclusive of octroi, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.	115.4	Pe square metre	650.00	Rs.Six hundred fifty only	75010
2	Second class half brick work using common burnt clay building bricks in superstructure upto all floor level in CM 1:4 (One cement: four sand) including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government	14.00	Per square metre	650.00	Rupees Six hundred fifty only	9100
3	Providing and fixing vitreous China wash down, water closet (European type. W.C. pan) with integral 'P' or 'S' trap including jointing the trap with soll pipe in cement mortar 1:1(1 cement : 1 sand) (Seat and over to be measured and paid for separately including carriage of materials within all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government...	1.00	Each	2200.00	Rupees Two thousand two hundred only	2200
4	Providing and fixing PTMT coloured/white PVC low level duel flushing cistern with a pair of PVC/CI/MS bracket complete with fittings including PVC syphonic apparatus such as lead valve ,less syphon, 15mm(fifteen millimetre) nominal size PVC ball valve with polythene float,PVC handle,union and coupling for connection with inlet,outlet and overflow pipes 40mm(forty millimetre) dia PVC flush bend with cistern and closet over flow pipe to be measured and paid for separately)including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.00	each	1500.00	(Rupees One thousand five hundred only.	1500

5	Providing and fixing vitreous China wash basin with single hole for pillar tap with C.I. or M.S. brackets painted white including cutting holes and making good the same but excluding fittings:- 630mmx450mm including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government	1.00	Each	1,800.00	Rupees One thousand eight hundred only	1800
6	Providing and fixing PVC plastic seat cover as per the direction by the E-in-c including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government	1.00	each	550.00	Rupees Five hundred fifty only	550
7	Providing and fixing PTMT jet spray of approved quality and colour with one metre tube as per direction of the E-in-c including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government	1.00	each	350.00	Rupees Three hundred fifty only	350
8	Chromium plated brass bib taps with cap stain heads. i) 15 mm dia. Weight 400 gms including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government	1.00	Each	800.00	Rupees Eight hundred only	800
9	Providing and fixing 32mm dia lead waste pipes for wash basin or sink including brass check nut including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government	2.00	Each	150.00	Rupees One hundred fifty only	300
10	Providing and fixing CP waste including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government	2.00	Each	150.00	Rupees One hundred fifty only	300
11	Providing and fixing PVC connection for wash basin/sink-including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government	2.00	Each	120.00	Rupees One hundred twenty only	240
12	Providing and fixing CP brass pillar tap 15mm dia including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government	1.00	Each	800.00	Rupees Eight hundred only	800

6

13	Providing and fixing ange valve 15mm dia without nuts and pipes including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government	4.00	each	800.00	Rupees Eight hundred only	3200
14	P/F hydraulic door closer duly I.S marked including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government	2.00	each	1000.00	Rupees One thousand only	2000
15	P/F 450x600mm bevelled edge mirror-including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government	1.00	each	650.00	Rupees Six hundred fifty only	650
16	P/F 750x12mm towel rail-including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government	1.00	each	450.00	Rupees Four hundred fifty only	450
17	P/F CP brass soap dish-including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government	2.00	Each	250.00	Rupees Two hundred fifty only	500
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				G.Total	99750
	2) The rates shall be including of all types of taxes including GST etctra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer,
 Una Divn.HP.P.W.,
 Una

41


SCHEDULE OF QUANTITY								
						Estimated Cost	99608/-	
Name of work : Restoration of rain damage to Path from the house of Dr. Attri etc. to house of Shri Ram Mutri In ward No.1 in village Arniala upper MC Una(SH: Providing and laying interlocking paver blocks km.0/0 to 0/040)(Under VKVNY(MLALAD)						Earnest Money	2000/-	
						Time limit	One month	
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter lockingpaver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 60 mm thick ISI mark C.C. paver block of M-30 grade with approved color design and patternincluding entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	116.00	Per square metre	800.00	Rupees Eight hundred only	92800		
2	Providing and laying in position cement concrete for plain/reinforced concrete in open foundation for all type structure complete in cement concrete 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.48	Per cubic metre	4600.00	Rupees Four thousand six hundred only	6808		
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018					Total:	99608		
2) The rates shall be including of all types of taxes including GST ectra)								
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021								
Percentage quoted Rate In Figures								
Percentage quoted Rate In Words								
Note: Rates quoted in figures & words are mandatory								
by the contractor otherwise the tender will be rejected.								

Kanishk
Executive Engineer
Una Divn.HP.PWD.
Una

42

SCHEDULE OF QUANTITY							Estimated Cost	99935/-
Name of work : C/O Path near the house of Shri Balram etc. in village Lalsingl MC Una Tehsil & Distt.Una (SH: P/L Interlocking paver blocks km.0/027 to 0/054) (Under VKVNY(MLALAD)							Earnest Money	2000/-
							Time limit	One month
							S. No.	
					Figures	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sele tax,GST,labour cess or other taxes imposed by the Government.			8.91	Per cubic metre	170.00	Rupees One hundred seventy only	1515
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed / stone aggregate 40mm (forty Millimeter) nominal size in or under wateror ground complete including pumping or balling out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..			8.91	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	29849
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter lockingpaver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 60 mm thick ISI mark C.C. paver block of M-30 grade with approved color design and patternincluding entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.			81.00	Per square metre	800.00	Rupees Eight hundred fifty only	64800
4	Providing and laying in position cement concrete for plain/reinforced concrete in open foundation for all type structure complete in cement concrete 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..			0.82	Per cubic metre	4600.00	Rupees Four thousand six hundred only	3772


	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				Total:	99935
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate In Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted In figures & words are mandatory					
	by the contractor, otherwise the tender will be rejected.					


 Executive Engineer
 Una Divn.HP.PWD
 Una

43

SCHEDULE OF QUANTITY						
				Estimated Cost	99981/-	
Name of work : C/O Path near the house of Shri Balram etc. in village Lalsingi MC Una Tehsil & Distt.Una (SH: P/L interlocking paver blocks km.0/0 to 0/027) (Under VKVNY(MLALAD)				Earnest Money	2000/-	
				Time limit	One month	
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	8.91	Per cubic metre	170.00	Rupees One hundred seventy only	1515
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed / stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.91	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	29849
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter lockingpaver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 60 mm thick ISI mark C.C. paver block of M-30 grade with approved color design and patternincluding entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	81.00	Per square metre	800.00	Rupees Eight hundred fifty only	64800

4	Providing and laying in position cement concrete for plain/reinforced concrete in open foundation for all type structure complete in cement concrete 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.83	Per cubic metre	4600.00	Rupees Four thousand six hundred only	3818
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)A(17)2/0212 dated 7.8.2018				Total:	99981
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate In Figures					
	Percentage quoted Rate In Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer
 Una Divn.HP.P.W.D.,
 Una

50
44

SCHEDULE OF QUANTITY							
						Estimated Cost	82330/-
						Earnest Money	2000/-
Name of work :Restoration of rain damages on link road Charatgarh to Sasan road near the house of Pooran Chand km.0/0 to 1/200(SH: P/L 80mm thick interlocking paver in RD.0/493.50 to 0/507.20)(Under deposit VKVNY(MLALAD)						Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Demolishing cement concrete manually / by mechanical means including disposal in cement concrete 1:3:6 material within any leads and lifts.including stacking of steel bars and disposal of unserviceable .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	8.22	Per cubic metre	550.00	Rupees Five hundred fifty only	4521	
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.92	Per cubic metre	170.00	Rupees One hundred seventy only	326	
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	9.32	Per cubic metre	3300.00	Rupees Three thousand three hundred only	30756	

4	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	46.58	Per square metre	850.00	Rupees Eight hundred fifty only	39583
5	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.23	Per cubic metre	5800.00	Rupees Five thousand eight hundred only	7134
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				Total:	82330
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer,
 Una Division, HRPWD.,
 Una.

42

45

SCHEDULE OF QUANTITY								
						Estimated Cost	89162/-	
Name of work :Restoration of rain damages on link road Charatgarh to Sasan road near the house of Pooran Chand km.0/0 to 1/200(SH: P/L 80mm thick interlocking paver in RD.0/521.10 to 0/535.92)(Under deposit VKVNY(MLALAD)						Earnest Money	2000/-	
						Time limit	One month	
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Demolishing cement concrete manually / by mechanical means including disposal in cement concrete 1:3:6 material within any leads and lifts.including stacking of steel bars and disposal of unserviceable .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	8.89	Per cubic metre	550.00	Rupees Five hundred fifty only	4890		
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.07	Per cubic metre	170.00	Rupees One hundred seventy only	352		
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	10.08	Per cubic metre	3300.00	Rupees Three thousand three hundred only	33264		

4	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	50.52	Per square metre	850.00	Rupees Eight hundred fifty only	42942
5	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.33	Per cubic metre	5800.00	Rupees Five thousand eight hundred only	7714
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	89162
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer,
 Una Division, HPWD,
 Una.

SCHEDULE OF QUANTITY							Estimated Cost	99393/-
Name of work :Restoration of rain damages on link road to village Bharolian Khurd km.0/0 to2/0 (SH: P/L CC interlocking paver block at RD.0/574 to 0/586)							Earnest Money	2000/-
							Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.62	Per cubic metre	170.00	Rupees One hundred seventy only	275		
2	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by mix in place method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification caluse 402 for grading -I material including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	9.54	Per cubic metre	1100.00	Rupees One thousand one hundred only	10494		
3	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	3.60	Per cubic metre	3900.00	Rupees Three thousand nine hundred only	14040		
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	6.36	Per cubic metre	3300.00	Rupees Three thousand three hundred only	20988		

5	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	60.00	Per square metre	850.00	Rupees Eight hundred fifty only	51000
6	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (One cement :two sand: four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	0.56	Per cubic metre	4600.00	Rupees Four thousand six hundred only	2576
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@ (17)2/0212 dated 7.8.2018				Total:	99373
	2) The rates shall be including of all types of taxes including GST ectra)					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate In Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer,
 Una Division, HPBWD,
 Una.

(131)

47

Estimated cost 99741/-
 Earnest money 2000/-
 Time limit One month

Name of Work: Restoration of damages occurred due to laying of OFC in various roads under Mehatpur Sub-Divn, No. II HP.PWD., Mehatpur (SH: Providing, fixing and art painting of information boards etc) (Rakkar section)						
S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Providing and erecting direction and place identification sign boards with size 1200x900mm(One thousand two hundred into nine hundred millimetre))as per IRC:67 made of 1.5mm thick MS sheeting vide clause 1701.2.3, with area not exceeding 0.9 sqm.supported on mild steel 40mm dia pipe 2(two) Nos firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450mmx450mmx600mm,600mm below ground level as per approved drawing and MORD technical specification clause 1701 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.00	each	6500.00	Rupees Six thousand five hundred only	26000
2	Painting two coats (excluding priming coat) on new steel and other metal surfaces with enamel paint brush to give an even shade including cleaning the surface of all dirt, dust and other foreign matter with enamel paint other than white including carriage of materials within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.64	Per square metre	60.00	Rupees Sixty only	518
3	Writing letters or figures on any surface with black japan paint(stops, comas, hyphens and the like not to be measured and paid separately) Indian (letters figures) includingthe coat of material including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	37550.00	Per letter per cm. height	1.95	Rupees One point ninety five five	73223
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				G.Total	99741
	2) The rates shall be including of all types of taxes including GST etcra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3)1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

Koushik
Executive Engineer,
Una Divn. HP.PWD. Una

132

46

SCHEDULE OF QUANTITY

Estimated cost 99546/-

Earnest money 2000/-

Time limit One month

Name of Work: Restoration of damages occurred due to laying of OFC in various roads under Mehatpur Sub-Divn, No. II HP.PWD., Mehatpur (SH: Providing, fixing and art painting of information boards etc) (Santoshgarh section)

S. No.	Description of work	Quantity	Unit	Rates (In. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Providing and erecting direction and place identification sign boards with size 1200x900mm(One thousand two hundred into nine hundred millimetre) as per IRC:67 made of 1.5mm thick MS sheeting vide clause 1701.2.3, with area not exceeding 0.9 sqm. supported on mild steel 40mm dia pipe 2(two) Nos firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450mmx450mmx600mm, 600mm below ground level as per approved drawing and MORD technical specification clause 1701 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkana, toll tax, GST, labour cess or other taxes imposed by the Government..	4.00	each	6500.00	Rupees Six thousand five hundred only	26000
2	Painting two coats (excluding priming coat) on new steel and other metal surfaces with enamel paint brush to give an even shade including cleaning the surface of all dirt, dust and other foreign matter with enamel paint other than white including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	8.64	Per square metre	60.00	Rupees Sixty only	518
3	Writing letters or figures on any surface with black japan paint(stops, commas, hyphens and the like not to be measured and paid separately) Indian (letters figures) including the coat of material including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government..	37450.00	Per letter per cm. height	1.95	Rupees One point ninety five five	73028
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				G.Total	99546
	2) The rates shall be inclusive of all types of taxes including GST etc (ra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

Executive Engineer,

Una Division, HPPWD., Una

129

49

SCHEDULE OF QUANTITY

Estimated cost 99825/-

Earnest money 2000/-

Time limit One month

Name of Work: Restoration of damages occurred due to laying of OFC in various roads under Mehatpur Sub-Divn, No. II HP.PWD., Mehatpur (SH: Painting and art painting of ordinary km. stones, 200 mtrs. Stones and information sign boards etc) (Mehatpur section)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Removing old paint from steel and other metal surfaces and making the surface even with paint remover of approved brand and manufacture including carriage of material within all leads and lifts	21.60	Per square metre	30.00	Rs. Thirty only	648
2	Applying priming coat over new steel & other metal surfaces after & including preparing the surface by thoroughly cleaning oil grease dirt and other foreign matter and scoured with wire brushes fine steel wool scrapers and sand paper compleyte with readymixed priming paint brushing red lead, red oxide/ zine oxide chrome including carriage of materials within all leads and lifts and other incidentials. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	21.60	Per square metre	45.00	Rupees Forty five only	972
3	Painting two coats (excluding priming coat) on new steel and other metal surfaces with enamel paint brush to give an even shade including cleaning the surface of all dirt, dust and other foreign matter with enamel paint other than white including carriage of materials within all leads and lifts and other incidentials. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	21.60	Per square metre	60.00	Rupees Sixty only	1296
4	Applying priming coat on new concrete/ masonry/ asbestos cement/plastered surfaces after and including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required with :-ready mixed primer including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government. .	25.20	Per Square metre	45.00	Rupees Forty five only	1134
5	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops dust loose material and foreign matter sand papered smooth to give final matter finish to the surface complete including carriage of materials within all leads and lifts. The rate includes octroi, royalty, Malkhana Toll tax, goods service tax, labour cess or other taxes imposed by the Government	25.20	Per square metre	60.00	Rupees Sixty only	1512

6	Painting two coats (excluding priming coat) on new concrete masonry/ plaster surfaces with ready mixed paint brushing for use on floors to give an even shade including clearing the surface of all dirt, dust and other foreign matter and sand papering as required with paint other than white including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	25.20	Per square metre	65.00	Rupees Sixty five only	1638
7	Writing letters or figures on any surface with black japan paint(stops, comas, hyphens and the like not to be measured and paid separately) Indian (letters figures) including the coat of material including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government. .	47500.00	Per letter per cm. height	1.95	Rupees One point ninety five five	92625
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				G.Total	99825
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer,
 Una Division, HPPWD,
 Una

130

50

SCHEDULE OF QUANTITY

Estimated cost	99643/-
Earnest money	2000/-
Time limit	One month

Name of Work: Restoration of damages occurred due to laying of OFC in various roads under Mehatpur Sub-Divn, No. II HP.PWD., Mehatpur (SH: Providing, fixing and art painting of information boards etc) (Mehatpur section)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Providing and erecting direction and place identification sign boards with size 1200x900mm (One thousand two hundred into nine hundred millimetre) as per IRC:67 made of 1.5mm thick MS sheeting vide clause 1701.2.3, with area not exceeding 0.9 sqm. supported on mild steel 40mm dia pipe 2(two) Nos firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450mmx450mmx600mm, 600mm below ground level as per approved drawing and MORD technical specification clause 1701 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkana, toll tax, GST, labour cess or other taxes imposed by the Government.	4.00	each	6500.00	Rupees Six thousand five hundred only	26000
2	Painting two coats (excluding priming coat) on new steel and other metal surfaces with enamel paint brush to give an even shade including cleaning the surface of all dirt, dust and other foreign matter with enamel paint other than white including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	8.64	Per square metre	60.00	Rupees Sixty only	518
3	Writing letters or figures on any surface with black japan paint (stops, commas, hyphens and the like not to be measured and paid separately) Indian (letters figures) including the coat of material including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	37500.00	Per letter per cm. height	1.95	Rupees One point ninety five five	73125
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)C(17)2/0212 dated 7.8.2018				G.Total	99643
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No. PBW(B) A(3)1/2020-1 dated 7.10.2021					
	Percentage quoted Rate In Figures					
	Percentage quoted Rate In Words					
	Note: Rates quoted In figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

K. Singh
Executive Engineer

Una Divn. HP. PWD., Una

219

81

SCHEDULE OF QUANTITY

Estimated cost 99223/-

Earnest money 2000/-

Time limit One month


Name of Work: Restoration of rain damages Bangarh Nangran road to Ghalore Chowk upto Punjab Boundary km.0/0 to 2/500 Tehsil & Distt.Una (HP)
(SH: C/O R/wall at RD.2/450 to 2/455) (Deposit work)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	7.75	Per cubic metre	170.00	Rupees One hundred seventy only	1318
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	27.75	Per cubic metre	3300.00	Rupees Three thousand three hundred only	91575
3	Providing form work with steel plates 3.15mm(three decimal fifteen millimeter) thick welded with angle iron in frame of 30x30x5 mm (thirty into thirty into five millimeter) size so as to give a fair finish including centering shuttering strutting and propping etcetera with wooden battens and ballies for all heights of propping and centering below supporting floor to ceiling and removal of same for in-situ reinforced concrete and plain concrete work in vertical surfaces such as walls(any thickness) partitions and the like including attached pilasters buttresses,plinth and string courses and the like including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	16.00	Per Square metre	300.00	Rupees Three hundred only	4800

[Signature]

[Signature]

4	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	9.00	Each	170.00	Rupees One hundred sixty only	1530
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				G.Total	99223
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer,
 Una Division, HP PWD.,
 Una

220

52

SCHEDULE OF QUANTITY				Estimated cost	99053/-
----------------------	--	--	--	----------------	---------

Earnest money 2000/-


Time limit One month

Name of Work: Restoration of rain damages Bangarh Nangran road to Ghalore Chowk upto Punjab Boundary km.0/0 to 2/500 Tehsil & Distt.Una (HP)
(SH: C/O R/wall at RD.2/455 to 2/460) (Deposit work)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	7.75	Per cubic metre	170.00	Rupees One hundred seventy only	1318
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	27.75	Per cubic metre	3300.00	Rupees Three thousand three hundred only	91575
3	Providing form work with steel plates 3.15mm(three decimal fifteen millimeter) thick welded with angle iron in frame of 30x30x5 mm (thirty into thirty into five millimeter) size so as to give a fair finish including centering shuttering strutting and propping etcetera with wooden battens and ballies for all heights of propping and centering below supporting floor to ceiling and removal of same for in-situ reinforced concrete and plain concrete work in vertical surfaces such as walls(any thickness) partitions and the like including attached pilasters buttresses,plinth and string courses and the like including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	16.00	Per Square metre	300.00	Rupees Three hundred only	4800

h


4	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.00	Each	170.00	Rupees One hundred sixty only	1360
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				G.Total	99053
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer,
 Una Division, HRWD,
 Una

(61) (S3)

SCHEDULE OF QUANTITY								
Name of work :Improvement of Vulnerabope spots on Old Hoshiarpur road km.0/0 to 4/330 (SJH: Providing and recting crash barrier at RD.3/870 to 3/892(LHS)							Estimated Cost	89116/-
							Earnest Money	2000/-
							Time limit	One month
Sl. No.	Description of work		Unit	RATE In			AMOUNT	
				Figures	Words			
1	Demolition above GL upto floor two level including disposal of unserviceable material and stacking the serviceable RCC/RB wrk material within any leads and lifts and other incidentials. The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.45	Per cubic metre	550.00	Rupees Five hundred fifty only		798	
2	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 and as per direction of the Engineer- In - Charge including carriage of materials within all leads and lifts and other incidental .	0.53	Per cubic metre	170.00	Rupees One hundred sixty only		90	
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (One cement :two sand: four graded crushed /broken stone aggregate.20mm. (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.11	Per cubic metre	4800.00	Rupees Four thousand eight hundred only		10128	

4	Providing and erecting a "W" metal beam crash barrier comprising of 3mm thick corrugated sheet metal beam rail, 70cm. above road/ground level, fixed on ISMC series channel vertical post 150x75x5mm spaced 2m centre to centre 1.8m. high 1.1m. below ground/ road level, all steel parts and fittings to be galvansed by hot dip process, all fittings to conform to IS: 1367 and IS: 1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5mm, 330mm long complete as per clause 810 including carriage of material within all leads and lifts and other incidentials. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	22.00	Per Running metre	3550.00	Rupees Three thousand five hundred fifty only	78100
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				Total:	89116
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer
 Una Divn. HP. PWD
 Una


(106)

(54)

SCHEDULE OF QUANTITY									
							Estimated Cost	89138/-	
	Name of work :Improvement of Vulnerable spots on Old Hoshiarpur road km.0/0 to 4/330 (SJH: Providing and recting crash barrier at RD.3/810 to 3/832(RHS)							Earnest Money	2000/-
								Time limit	One month
Sl. No.	Description of work		Unit	RATE In		AMOUNT			
				Figures	Words				
1	Demolition above GL upto floor two level including disposal of unserviceable material and stacking the serviceable RCC/RB wrk material within any leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.45	Per cubic metre	550.00	Rupees Five hundred fifty only	798			
2	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 and as per direction of the Engineer- In - Charge including carriage of materials within all leads and lifts and other incidental .	0.66	Per cubic metre	170.00	Rupees One hundred sixty only	112			
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (One cement :two sand: four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.11	Per cubic metre	4800.00	Rupees Four thousand eight hundred only	10128			

6

4	Providing and erecting a "W" metal beam crash barrier comprising of 3mm thick corrugated sheet metal beam rail, 70cm. above road/ground level, fixed on ISMC series channel vertical post 150x75x5mm spaced 2m centre to centre 1.8m. high 1.1m. below ground/ road level, all steel parts and fittings to be galvanized by hot dip process, all fittings to conform to IS: 1367 and IS: 1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5mm, 330mm long complete as per clause 810 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	22.00	Per Running metre	3550.00	Rupees Three thousand five hundred fifty only	78100
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	89138
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer
 Una Divn. HP. PW
 Una

(127)

(55)

Schedule of Quantity										Estimated cost :	85000
										Earnest Money :	20000/-
										Time Limit :	One Month
Name of Work :		M/T on Link road Village Malukpur to Binewal Govt. Sr. Sec. School in Village Majara Sucha Singh etc. from Punna to Saint Soldger School, Badsehda to Peer Sathan IPH Scheme, Village Sanoli to Mahinder Singh etc., C/o link road Shani Dev Temple to Punjab Border, Widening & strengthening of roads in Village Fatehpur and C/o Link road to house of Bakshi Ram from km-0/00 to km-2/500 under NABARD.(SH: Preparation of Working Estimate and DNIT).									
S. No.	Description of Item	Qty.	Unit	Rate (Rs.)	Rate in words	Amount (Rs.)					
1.0	Preparation of Working Estimate and DNIT for M/T on Link road Village Malukpur to Binewal Govt. Sr. Sec. School in Village Majara Sucha Singh etc. from Punna to Saint Soldger School, Badsehda to Peer Sathan IPH Scheme, Village Sanoli to Mahinder Singh etc., C/o link road Shani Dev Temple to Punjab Border, Widening & strengthening of roads in Village Fatehpur and C/o Link road to house of Bakshi Ram from km-0/00 to km-2/500 under NABARD.	1.0	No.	85000.00	Rs. Eighty Five Thousand only	85000					
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018					Total =	85000					
2) The rates shall be including of all types of taxes including GST ectra)											
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021											
Percentage quoted Rate in Figures											
Percentage quoted Rate in Words											
Note: Rates quoted in figures & words are mandatory											
by the contractor otherwise the tender will be rejected.											


 Executive Engineer
 Una Division
 HPPWD Una

88

56

SCHEDULE OF QUANTITY				Estimated cost	99997/-
				Earnest money	2000/-
				Time limit	One month

Name of Work: Repair & maintenance of Behdala Jankour via Abada Barana road km.0/0 to 4/600 Tehsil & Distt.Una (SH: C/O R/wall along road from RD.0/934.85 to 0/945.50) **Under MDPE Deposit**

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	6.66	Per cubic metre	170.00	Rupees One hundred seventy only	1132
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or balling out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	28.70	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	96145
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax, octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	16.00	Each	170.00	Rupees One hundred seventy only	2720
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				G.Total	99997
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

K. Singh
Executive Engineer
Una Divn.HP.PWD, Una

57

SCHEDULE OF QUANTITY				Estimated cost	99827/-
				Earnest money	2000/-
				Time limit	One month


Name of Work: Repair & maintenance Behdala Jankour via Abada Barana road km.0/0 to 4/600 Tehsil & Distt.Una (SH: C/O R/wall along road from RD.0/945.50 to 0/956.15) Under MDPE Dipat

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	6.66	Per cubic metre	170.00	Rupees One hundred seventy only	1132
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	28.70	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	96145
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax, octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	15.00	Each	170.00	Rupees One hundred seventy only	2550
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				G.Total	99827
	2) The rates shall be including of all types of taxes including GST etcra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate In Figures					
	Percentage quoted Rate In Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

K. M. D. A.
Executive Engineer
Una Divn. HP. PWD. Una

(58)

SCHEDULE OF QUANTITY						
					Estimated Cost	99000/-
					Earnest Money	2000/-
Name of work: Annual repair & Maintenance on Various roads in Basoli Section under Sub-Division No.1 HP.PWD., Una HP.PWD.,(SH: Hiring of excavator Cum Loader clearance of earthen shoulders and road side drains etc					Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Hiring of hydraulic excavator 0.90 cum. fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock(where blasting is prohibited) as per direction of the Engineer-in-charge .The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	90.00	Per Hour	1100.00	Rupees One thousand one hundred only	99000
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	99000
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	4) The bidder should have his own machinery.					
	5) The bidder must have provide machinery immediately as an when required.					
	Percentage quoted Rate In Figures					
	Percentage quoted Rate In Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer-
 Una Divn.HP.PWD.,
 Una

59

SCHEDULE OF QUANTITY						
					Estimated Cost	99000/-
					Earnest Money	2000/-
					Time limit	One month
Name of work: Annual repair & Maintenance on Various roads in Una Section under Sub-Division No.1 HP.PWD.,Una (SH: Hiring of excavator Cum Loader clearance of earthen shoulders and road side drains etc.						
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Hiring of hydraulic excavator 0.90 cum. fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock(where blasting is prohibited) as per direction of the Engineer-in-charge .The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	90.00	Per Hour	1100.00	Rupees One thousand one hundred only	99000
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				Total:	99000
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	4) The bidder should have his own machinery.					
	5) The bidder must have provide machinery immediately as an when required.					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

Kunal
Executive Engineer
Una Divn.HP.PWD,
Una

110

60


SCHEDULE OF QUANTITY				Estimated cost	97681/-
				Earnest money	2000/-
				Time limit	One month

Name of Work: Repair and maintenance of link road to village Galua (SH: Providing and fixing grating on drain at RD.0/0 to 0/013) Under AEC Deposit

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.30	Per cubic metre	170.00	Rupees One hundred seventy only	221
2	Demolition above GL upto floor two level RCC/RB works including disposal of unserviceable material and stacking the serviceable material within any leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	2.93	Per cubic metre	1000.00	Rupees One thousand only	2930
3	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick including cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:5 (1 cement: 5 sand) including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	9.00	Per square metre	170.00	Rupees One hundred seventy only	1530
4	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	3.51	Per cubic metre	4000.00	Rupees Four thousand only	14040
5	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.46	Per cubic metre	6000.00	Rupees Six thousand only	8760

6

6	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	7.02	Per quantial	10000.00	Rupees Ten thousand only	70200
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				G.Total	97681
	2) The rates shall be including of all types of taxes including GST etctra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer
 Una Divn.HP.P.W.D.
 Una

(112)

(61)

	SCHEDULE OF QUANTITY				Estimated cost	97848/-
--	-----------------------------	--	--	--	----------------	---------


Earnest money 2000/-

Time limit One month

Name of Work: Repair and maintenance of link road to village Galua (SH: Providing and fixing grating on drain at RD.0/026 to 0/039) Under F.C Deposit

S. No.	Description of work	Quantity	Unit	Rates (In. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	2.28	Per cubic metre	170.00	Rupees One hundred seventy only	388
2	Demolition above GL upto floor two level RCC/RB works including disposal of unserviceable material and stacking the serviceable material within any leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	2.93	Per cubic metre	1000.00	Rupees One thousand only	2930
3	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:5 (1 cement: 5 sand) including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	9.00	Per square metre	170.00	Rupees One hundred seventy only	1530
4	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	3.51	Per cubic metre	4000.00	Rupees Four thousand only	14040
5	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.46	Per cubic metre	6000.00	Rupees Six thousand only	8760

6	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	7.02	Per quantial	10000.00	Rupees Ten thousand only	70200
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018				G.Total	97848
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate In Figures					
	Percentage quoted Rate In Words					
	Note: Rates quoted In figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					



 Executive Engineer
 Una Divn.HP PWD.,
 Una

(111)

(62)

SCHEDULE OF QUANTITY						Estimated cost	98234/-
						Earnest money	2000/-
						Time limit	One month
Name of Work: Repair and maintenance of link road to village Galua (SH: Providing and fixing grating on drain at RD.0/013 to 0/026) Under OFC Deposit							
S. No.	Description of work	Quantity	Unit	Rates (In. Rs.)		Amount (in. Rs.)	
				Figures	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	4.55	Per cubic metre	170.00	Rupees One hundred seventy only	774	
2	Demolition above GL upto floor two level RCC/RB works including disposal of unserviceable material and stacking the serviceable material within any leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	2.93	Per cubic metre	1000.00	Rupees One thousand only	2930	
3	Repair to plaster in patches of 2.5 Sq.mtr and under and 10 to 15 mm thick including cutting the patch in proper shape and replasting the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20 mtrs with cement mortar 1:5 (1 cement: 5 sand) including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	9.00	Per square metre	170.00	Rupees One hundred seventy only	1530	
4	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	3.51	Per cubic metre	4000.00	Rupees Four thousand only	14040	
5	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.46	Per cubic metre	6000.00	Rupees Six thousand only	8760	


6	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.02	Per quantial	10000.00	Rupees Ten thousand only	70200
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				G.Total	98234
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate In Figures					
	Percentage quoted Rate In Words					
	Note: Rates quoted In figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer
 Una Divn.HP.RWD.,
 Una

(63)

SCHEDULE OF QUANTITY					Estimated Cost	98493/-
Name of work : A/R & M/O link road to village Lower Arniala km.0/0 to 1/0(SH: P/F CC interlocking paver blocks at RD.0/040 to 0/083 (Right side berms)					Earnest Money	2000/-
					Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	14.62	Per cubic metre	170.00	Rupees One hundred seventy only	2485
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed / stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	7.31	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	24489
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter lockingpaver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and patternincluding entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	73.10	Per square metre	850.00	Rupees Eight hundred fifty only	62135


4	Providing and laying in position cement concrete for plain/reinforced concrete in open foundation for all type structure complete in cement concrete 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other Incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.040	Per cubic metre	4600.00	Rupees Four thousand six hundred only	9384
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)A(17)2/0212 dated 7.8.2018				Total:	98493
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification Issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate In Figures					
	Percentage quoted Rate In Words					
	Note: Rates quoted In figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer
 Una Divn.HP.
 Una

126

64


SCHEDULE OF QUANTITY						
					Estimated Cost	93960/-
					Earnest Money	2000/-
	Name of work : A/R & M/O to link road from Jhalera to Una via lower lalsingl km.0/0 to 4/340(SH: Providing and marking of rumble strip lines 100mm at RD.1/605 to 2/415) (Under OFC deposit)				Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing and applying 2.5mm thick road marking strips(retro-reflective) of specified shade/colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour T&P cleaning the road surface of all dirt, seals, oil grease and foreign material etc. complete including carriage of materials within all leads and lifts. The rate includes octroi, royalty, Malkhana Toll tax, goods service tax, labour cess or other taxes imposed by the Government	162.00	Per square metre	580.00	Rupees Five hundred eighty only	93960
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				Total:	93960
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in Figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer
 Una Divn. HP. PW.,
 Una

127

65

SCHEDULE OF QUANTITY						
					Estimated Cost	92800/-
					Earnest Money	2000/-
	Name of work : A/R & M/O to link road from Jhalera to Una via lower lalsingi km.0/0 to 4/340(SH: Providing and marking of rumble strip lines 100mm at RD.0/0 to 0/800) (Under OFC deposit)				Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing and applying 2.5mm thick road marking strips (retro-reflective) of specified shade/colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour T&P cleaning the road surface of all dirt, seals, oil grease and foreign material etc. complete including carriage of materials within all leads and lifts. The rate includes octroi, royalty, Malkhana Toll tax, goods service tax, labour cess or other taxes imposed by the Government	160.00	Per square metre	580.00	Rupees Five hundred eighty only	92800
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)A(17)2/0212 dated 7.8.2018				Total:	92800
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer
 Una Divn. HP. PW
 Una

137

66

SCHEDULE OF QUANTITY						
					Estimated Cost	99876/-
					Earnest Money	2000/-
					Time limit	One month
Name of work : A/R & M/O Santoshgarh Mehatpur road km.0/0 to 7/0(Under road safety) (SH: Providing and marking of edge line, rumble strip lines and zehra crossing at junction & near to school Hsopital etc. at RD.5/500 to 5/965)						
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing and applying 2.5mm thick road marking strips(retro-reflective) of specified shade/colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour T&P cleaning the road surface of all dirt, seals, oil grease and foreign material etc. complete including carriage of materials within all leads and lifts. The rate includes octroi, royalty, Malkhana Toll tax, goods service tax, labour cess or other taxes imposed by the Government	172.20	Per square metre	580.00	Rupees Five hundred eighty only	99876
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				Total:	99876
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate In Figures					
	Percentage quoted Rate In Words					
	Note: Rates quoted In figures & words are mandatory					
	by the contractor, otherwise the tender will be rejected.					

Kailash
 Executive Engineer
 Una Divn. HP. PW
 Una

128

67


SCHEDULE OF QUANTITY						
Name of work : A/R & M/O Santoshgarh Mehatpur road km.0/0 to 7/0(Under road safety) (SH: Providing and marking of edge line, rumble strip lines and zehra crossing at junction & near to school Hsopital etc. at RD.5/975 to 6/410)					Estimated Cost	99737/-
					Earnest Money	2000/-
					Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing and applying 2.5mm thick road marking strips(retro-reflective) of specified shade/colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour T&P cleaning the road surface of all dirt, seals, oil grease and foreign material etc. complete including carriage of materials within all leads and lifts. The rate includes octroi, royalty, Malkhana Toll tax, goods service tax, labour cess or other taxes imposed by the Government	171.96	Per square metre	580.00	Rupees Five hundred eighty only	99737
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B) (17)2/0212 dated 7.8.2018				Total:	99737
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

K. S. D. Singh
 Executive Engineer
 Una Divn. HP. PW
 Una

139

68

SCHEDULE OF QUANTITY							Estimated Cost	99992/-
Name of work : A/R & M/O Santoshgarh Mehatpur road km.0/0 to 7/0(Under road safety) (SH: Providing and marking of edge line, rumble strip llnes and zehra crossing at junction & near to school Hsopital etc. at RD.6/425 to 6/990)							Earnest Money	2000/-
							Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Providing amnd applying 2.5mm thick road marking strips(retroi-reflective) of specified shade/colour using hot thermoplastic material by fully/ semi automatic tyhermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experinenced operator on road surface including cost of material, labour T&P cleaning the road surface of all dirt , seals , oil grease and foreign material etc. complete including carnage of materials within all leads ad lifts.The rate includes octroi,royalty,Malkhana Toll tax , goods service tax,labour cess or other taxes imposed by the Governmmnt	172.40	Per square metre	580.00	Rupees Five hundred eighty only	99992		
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				Total:	99992		
	2) The rates shall be including of all types of taxes Including GST ectra)							
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021							
	Percentage quoted Rate In Figures							
	Percentage quoted Rate In Words							
	Note: Rates quoted in figures & words are mandatory							
	by the contractor, otherwise the tender will be rejected.							


 Executive Engineer
 Una Divn.HP.PWB
 Una


846

19

SCHEDULE OF QUANTITY						
					Estimated Cost	99941/-
Name of work :Repair & maintenance of link road Dehlan Behdala km.0/0 to 2/060 (SH: P/L 80mm thick interlocking paverin RD.1/660 to 1/684.50) Both side shoulders Under MDPE					Earnest Money	2000/-
Deposit					Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Demolishing cement concrete manually / by mechanical means including disposal in cement concrete 1:3:6 material within any leads and lifts.including stacking of steel bars and disposal of unserviceable .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	9.80	Per cubic metre	550.00	Rupees Five hundred fifty only	5390
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	7.35	Per cubic metre	170.00	Rupees One hundred seventy only	1250
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	9.80	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	32830

be

4	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	48.85	Per square metre	890.00	Rupees Eight hundred ninety only	43477
5	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	2.93	Per cubic metre	5800.00	Rupees Five thousand eight hundred only	16994
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				G.Total	99941
	2) The rates shall be including of all types of taxes including GST etcra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3)1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer,
 Una Division, HPFW
 Una


7

(741)

(40)

SCHEDULE OF QUANTITY						Estimated Cost	99932/-
						Earnest Money	2000/-
Name of work Repair & maintenance of link road Dehlan Behdala km.0/0 to 2/060 (SH: P/L 80mm thick Intrerlocking paverin RD.1/684.50 to 1/709) Both side shoulders under MDPE Deposit						Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Demolishing cement concrete manually / by mechanical means including disposal in cement concrete 1:3:6 material within any leads and lifts.including stacking of steel bars and disposal of unserviceable .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	9.80	Per cubic metre	550.00	Rupees Five hundred fifty only	5390	
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	7.35	Per cubic metre	170.00	Rupees One hundred seventy only	1250	
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	9.80	Per cubic metre	3350.00	Rupees Three thousand three hundred fifty only	32830	

4	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	48.84	Per square metre	890.00	Rupees Eight hundred ninety only	43468
5	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	2.93	Per cubic metre	5800.00	Rupees Five thousand eight hundred only	16994
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				G.Total	99932
	2) The rates shall be including of all types of taxes including GST etcra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3)1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					


 Executive Engineer,
 Una Division, HPPWD,
 Una

122

71

SCHEDULE OF QUANTITY						
Name of work : Restoration of rain damage on 120metre span bridge on Una Santoshgarh road at RD.1/760 (SH: Channelization of khad on upstream side of Rampur bridge 1/760 at Middle of the khad)				Estimated Cost		99726/-
				Earnest Money		2000/-
				Time limit		One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Excavation for roadway in marshy soil with hydraulic excavator 0.90cum. bucket capacity including cutting and loading in tippers and disposal within any leads and lifts. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	953.40	Per cubic metre	104.60	Rupees One hundred four and paise sixty only	99726
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				Total:	99726
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate in Figures					
	Percentage quoted Rate in Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

K. Singh
 Executive Engineer
 Una Divn. HP. PW
 Una

123

72

SCHEDULE OF QUANTITY						
				Estimated Cost		99726/-
				Earnest Money		2000/-
				Time limit		One month
Name of work : Restoration of rain damage on 120metre span bridge on Una Santoshgarh road at RD.1/760 (SH: Channelization of Khad on Upstream side of Rampur bridge 1/760 RHS Upstream)						
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Excavation for roadway in marshy soil with hydraulic excavator 0.90cum. bucket capacity including cutting and loading in tippers and disposal within any leads and lifts.The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	945.00	Per cubic metre	104.60	Rupees One hundred four and paise sixty only	98847
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B) (17)2/0212 dated 7.8.2018				Total:	98847
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted Rate In Figures					
	Percentage quoted Rate In Words					
	Note: Rates quoted in figures & words are mandatory					
	by the contractor otherwise the tender will be rejected.					

Kumala
 Executive Engineer
 Una Divn. HP. PW.,
 Una