

OFFICE OF THE EXECUTIVE ENGINEER BANGANA DIVISION HIMACHAL PRADESH PUBLIC WORKS  
DEPARTMENT BANGANA

No:- PW-BGN-CB/T-1/2025-26-  
To

10851-59

Dated:- 12-12-25


The Executive Engineer (IT Cell),  
Nigam Vihar, HP Shimla-2.  
[cc-pwd-hp@nic.in](mailto:cc-pwd-hp@nic.in).

Subject:- Publication of Tender Notice.

Sir,


Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender. As per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16<sup>th</sup> July, 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website.

DA/- Notice Inviting Tender/Scheduled of Quantity  
And "A" Certificate.

  
Executive Engineer  
Bangana Division  
HPPWD Bangana

Copy forwarded with its enclosures for information to:-


1. The Engineer-in-Chief, H.P.P.W.D., Shimla-2.
2. The Chief Engineer (HZ), H.P.P.W.D., Hamirpur.
3. The Superintending Engineer, 15<sup>th</sup> Circle, HPPWD, Una.
4. The Assistant Engineer, Sub Division, HPPWD Bangana and Basal.
5. Drawing Branch in this office.
6. Accounts Branch in this office.
7. Notice Board.

  
Executive Engineer  
Bangana Division  
HPPWD Bangana

**OFFICE OF THE EXECUTIVE ENGINEER BANGANA DIVISION HIMACHAL PRADESH PUBLIC WORKS  
DEPARTMENT BANGANA**

**CERTIFICATE.**

Certified that the works are of urgent in nature and for larger public interest so there is exigencies/emergency in calling these tenders without press vide this office letter No. PW-BGN/CB/T-1/2025-26- 10851-59 dated 12-12-2025

  
Executive Engineer  
Bangana Division  
HPPWD Bangana



**OFFICE OF THE EXECUTIVE ENGINEER BANGANA DIVISION HIMACHAL PRADESH PUBLIC WORKS  
DEPARTMENT BANGANA**

**NOTICE INVITING TENDER.**

Sealed percentage rate tender on form 6 & 8 are hereby invited by the Executive Engineer Bangana Division HPPWD Bangana on behalf of Governor of HP. from the approved eligible contractors enlisted in HPPWD, for the following works; so as to reach this office on **19.12.2025 up to 10:30 AM** and same will be opened on the same day at **11.00 AM** in presence of the interested contractors or their authorized representative. The application will be received in this office on at **16.12.2025 up to 3.00 PM**. The tender form can be had from the office of Executive Engineer Bangana Division HPPWD Bangana on cash payment (Non-refundable) on **18.12.2025** during office Hours **up to 4:00 PM**. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Bangana Division HPPWD Bangana cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The tender document fee shall also be deposited by the applicant/ contractor with at the time of application in the shape of Demand Draft or Cash (Non-Refundable) otherwise tender documents/ Forms shall not be issued. The offer of tender shall be kept upon for 60 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment/renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Work/Job No.	Name of Work	Estimated Cost	Earnest Money	Time Period	Eligible of Class
1	A/R & M/O Office of Executive Engineer HPPWD Division Bangana District Una HP. (Sub Head:- Printing & Supplying of Different Stationery Items)	96536.00	2000.00	One Month	C&D
2	R.R.D on UAM road Km 2/000 to 19/000 (SH: Providing of 1 No's Computer at Teuri Section) under O.F.C Head	97835.00	1900.00	Two Month	C&D
3	R.R.D on UAM road Km 2/000 to 19/000 (SH: Providing of 1 No's Computer at Khurwain Section) under O.F.C Head	99978.00	1900.00	Two Month	C&D
4	Restoration of Rain damages on various roads under HP.PWD Sub-Division DBR-Basal ( SH:- Removal of Slips, Maintenance of Berms and Drains Under Section Khurwain)	99954.00	2000.00	Two Month	C&D
5	Restoration of Rain damages on various roads under HP.PWD Sub-Division DBR-Basal ( SH:- Removal of Slips, Maintenance of Berms and Drains Under Section Teuri)	99636.00	2000.00	Two Month	C&D
6	Restoration of Rain damages on various roads under HP.PWD Sub-Division DBR-Basal ( SH:- Removal of Slips, Maintenance of Berms and Drains Under Section Teuri)	98640.00	2000.00	Two Month	C&D
7	Restoration of Rain damages on various roads under HP.PWD Sub-Division DBR-Basal ( SH:- Removal of Slips, Maintenance of Berms and Drains Under Section Khurwain)	99995.00	2000.00	Two Month	C&D
8	Restoration of Rain damages on various roads under HP.PWD Sub-Division DBR-Basal ( SH:- Removal of Slips, Maintenance of Berms and Drains Under Section Dhamandri)	97835.00	2000.00	Two Month	C&D
9	Restoration of Rain damages on various roads under Chattara Section ( SH:- Maintenance of Berms and Drains)	99978.00	2000.00	Two Month	C&D
10	Stock Storage at HP. PWD Sub-Division DBR-Basal (SH: Supply and Stacking machine made buildings Bricks in Khurwain Section)	99954.00	2000.00	Two Month	C&D
11	Stock Storage at HP. PWD Sub-Division DBR-Basal (SH: Supply and Stacking machine made buildings Bricks in Khurwain Section)	99636.00	2000.00	Two Month	C&D
12	Restoration of Rain damages on various roads under HP.PWD Sub-Division DBR-Basal ( SH:- Hiring of J.C.B. for removal of Slips, Road side drain, Shoulder berms and road surface in section Khurwain)	98640.00	2000.00	Two Month	C&D
13	Restoration of Rain damages on various roads under HP.PWD Sub-Division DBR-Basal ( SH:- Hiring of J.C.B. for removal of Slips, Road side drain, Shoulder berms and road surface in Khurwain Section)	99995.00	2000.00	Two Month	C&D

14	Restoration of Rain damages on various roads under HP.PWD Sub-Division DBR-Basal ( SH:- Hiring of J.C.B. for removal of Slips, Road side drain, Shoulder berms and road surface in Khruwain Section)	97835.00	2000.00	Two Month	C&D
15	Restoration of Rain damages on various roads under HP.PWD Sub-Division DBR-Basal ( SH:- Removal of Slips, Maintenance of berms and Drain in Chattara Section)	99978.00	2000.00	Two Month	C&D
16	C/o link road Surjehra Khuhi to Shiv Mandir & Satsang Ghar (SH: C/o Edge wall in Km 0/009 to 0/025.50 LHS)	99954.00	2000.00	Two Month	C&D
17	R.R.D on Various roads under HP.PWD Sub-Division Bangana (SH: Maintenance of Berms & Drains in various roads under Section Bangana-I)	99636.00	2000.00	Two Month	C&D
18	R.R.D on Various roads under HP.PWD Sub-Division Bangana (SH: Maintenance of Berms & Drains in various roads under Section Bangana-I)	98640.00	2000.00	Two Month	C&D
19	Restoration of Rain damages on U.A.M. road to Harot (SH: Embankment in Damaged road surface in Km 13/000 to 13/220)	99995.00	2000.00	Two Month	C&D
20	A/R & M/O on Type-II Quarter HPPWD Division Bangana Tehsil Bangana District Una HP. (Sub Head:- Providing and Fixing Sanitary Items)	54542.00	1100.00	One Month	C&D

**HIM SUCHANA AVAM JAN SAMPARK.**

*Arul Chinn*  
 Executive Engineer  
 Bangana Division  
 HPPWD Bangana,  
 On behalf of Governor of Himachal Pradesh.



## Percentage BOQ


<b>Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana</b>  <b>Name of Work: R.R.D on UAM road Km 2/000 to 19/000 (SH: Providing of 1 No's Computer at Teuri Section) under O.F.C Head</b>		Estimated Cost Rs	92500.00
		Earnest Money Rs	2000.00
		Time Limit:	Two Month

**Name of Bidder/ Bidding Firm/ Company :-**

### PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Providing & installation, testing and commissioning of HP All-in-one PC 13th Genration Intel Core i-5, 27" FHD 16GB RAM, 1TB SSD, Intel UMA Graphics, 710 white wireless keyboard and Mouse Combo (Window 11 Home, MSO-21, Shell white, 6.72 Kg), minimum three year warranty, as required complete in all respect, as per the entire satisfaction and as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1.00	Each	92500.00	92500.00	Rupees Ninety Two Thousand Five Hundred Only
<b>Total in Figures</b>					<b>92500.00</b>	Rupees Ninety Two Thousand Five Hundred Only
<b>Qouted Rate in Figures</b>		<b>Excess (+)</b>				
		<b>Less (-)</b>				

  
 Executive Engineer  
 Bangana Division  
 HP.PWD.Bangana

## Percentage BOQ

2

<b>Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana</b>	<b>Estimated Cost</b>	92500.00
<b>Name of Work: R.R.D on UAM road Km 2/000 to 19/000 (SH: Providing of 1 No's Computer at Khurwain Section) under O.F.C Head</b>	<b>Earnest Money</b>	2000.00
<b>Name of Bidder/ Bidding Firm/ Company :-</b>	<b>Time Limit:</b>	Two Month

### PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )


Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Providing & installation, testing and commissioning of HP All-in-one PC 13th Genration Intel Core i-5, 27" FHD 16GB RAM, 1TB SSD, Intel UMA Graphics, 710 white wireless keyboard and Mouse Combo (Window 11 Home, MSO-21, Shell white, 6.72 Kg), minime three year warranty, as required complete in all respect, as per the entire satisfaction and as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1.00	Each	92500.00	92500.00	Rupees Ninety Two Thousand Five Hundred Only
<b>Total in Figures</b>					<b>92500.00</b>	Rupees Ninety Two Thousand Five Hundred Only
<b>Qouted Rate in Figures</b>		<b>Excess (+)</b>				
		<b>Less (-)</b>				

  
 Executive Engineer  
 Bangana Division  
 HP.PWD.Bangana



# Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana					Estimated Cost Rs	99785.00
Name of work:- Restoration of Rain damages on various roads under HP.PWD Sub-Division DBR-Basal ( SH:- Removal of Slips, Maintenance of Berms and Drains Under Section Khruwain)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	Two Month
<p align="center"><b>PRICE SCHEDULE</b></p> <p>(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )</p>						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. including carriage of materials with in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	535.00	Per cubic metre	125.00	66875.00	Rupees Sixty Six Thousand Eight Hundred & Seventy Five Only
2.00	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	466.00	Per Square Metre	50.00	23300.00	Rupees Twenty Three Thousand Three Hundred Only
3.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	489.30	Per Square Metre	14.00	6850.00	Rupees Six Thousand Eight Hundred & Fifty Only
4.00	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	120.00	Per Running Metre	23.00	2760.00	Rupees Two Thousand Seven Hundred & Sixty Only
<b>Total in Figures</b>					<b>99785.00</b>	Rupees Ninety Nine Thousand Seven Hundred & Eighty Five Only
<b>Quoted Rate in Figures</b>					Excess (+)	
					Less (-)	

  
 Executive Engineer  
 Bangana Division  
 HP.PWD.Bangana



## Percentage BOQ

**Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana**

**Name of work:- Restoration of Rain damages on various roads under HP.PWD Sub-Division DBR-Basal ( SH:- Removal of Slips, Maintenance of Berms and Drains Under Section Teuri)**

**Name of Bidder/ Bidding Firm/ Company :-**

**Estimated Cost Rs** 99951.00


**Earnest Money Rs** 2000.00

**Time Limit:** Two Month

### PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. including carriage of materials with in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	535.00	Per cubic metre	125.00	66875.00	Rupees Sixty Six Thousand Eight Hundred & Seventy Five Only
2.00	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	466.00	Per Square Metre	50.00	23300.00	Rupees Twenty Three Thousand Three Hundred Only
3.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	489.30	Per Square Metre	14.00	6850.00	Rupees Six Thousand Eight Hundred & Fifty Only
4.00	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	127.20	Per Running Metre	23.00	2926.00	Rupees Two Thousand Nine Hundred & Twenty Six Only
<b>Total in Figures</b>					<b>99951.00</b>	Rupees Ninety Nine Thousand Nine Hundred & Fifty One Only
<b>Qouted Rate in Figures</b>		<b>Excess (+)</b>				
		<b>Less (-)</b>				

  
 Executive Engineer  
 Bangana Division  
 HP.PWD. Bangana



5

**Percentage BOQ**

<b>Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana</b>						Estimated Cost Rs	99987.00
<b>Name of work:- Restoration of Rain damages on various roads under HP.PWD Sub-Division DBR-Basal ( SH:- Removal of Slips, Maintenance of Berms and Drains Under Section Teuri)</b>						Earnest Money Rs	2000.00
<b>Name of Bidder/ Bidding Firm/ Company :-</b>						Time Limit:	Two Month
<b>PRICE SCHEDULE</b>							
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )							
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words	
1.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. including carriage of materials with in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	535.00	Per cubic metre	125.00	66875.00	Rupees Sixty Six Thousand Eight Hundred & Seventy Five Only	
2.00	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	466.00	Per Square Metre	50.00	23300.00	Rupees Twenty Three Thousand Three Hundred Only	
3.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	489.30	Per Square Metre	14.00	6850.00	Rupees Six Thousand Eight Hundred & Fifty Only	
4.00	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	128.80	Per Running Metre	23.00	2962.00	Rupees Two Thousand Nine Hundred & Sixty Two Only	
<b>Total in Figures</b>					<b>99987.00</b>	Rupees Ninety Nine Thousand Nine Hundred & Eighty Seven Only	
<b>Qouted Rate in Figures</b>		Excess (+)					
		Less (-)					

  
 Executive Engineer  
 Bangana Division  
 HP.PWD.Bangana



# Percentage BOQ


Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana					Estimated Cost Rs	98856.00
Name of work:- Restoration of Rain damages on various roads under HP.PWD Sub-Division DBR-Basal ( SH:- Removal of Slips, Maintenance of Berms and Drains Under Section Khruwain)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	Two Month
<p align="center"><b>PRICE SCHEDULE</b></p> <p>(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )</p>						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. including carriage of materials with in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	535.00	Per cubic metre	125.00	66875.00	Rupees Sixty Six Thousand Eight Hundred & Seventy Five Only
2.00	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	466.00	Per Square Metre	50.00	23300.00	Rupees Twenty Three Thousand Three Hundred Only
3.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	489.30	Per Square Metre	14.00	6850.00	Rupees Six Thousand Eight Hundred & Fifty Only
4.00	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	79.60	Per Running Metre	23.00	1831.00	Rupees One Thousand Eight Hundred & Thirty One Only
Total in Figures					98856.00	Rupees Ninety Eight Thousand Eight Hundred & Fifty Six Only
Qouted Rate in Figures					Excess (+)	
					Less (-)	

  
 Executive Engineer  
 Bangana Division  
 HP.PWD.Bangana



**Percentage BOQ**


<b>Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana</b>					Estimated Cost Rs	99003.00
<b>Name of work:- Restoration of Rain damages on various road under Dhamandri Section (SH:- Removal of Slips, Maintenance of Berms and Drains)</b>					Earnest Money Rs	2000.00
<b>Name of Bidder/ Bidding Firm/ Company :-</b>					Time Limit:	Two Month
<b>PRICE SCHEDULE</b>						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. including carriage of materials with in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	535.00	Per cubic metre	125.00	66875.00	Rupees Sixty Six Thousand Eight Hundred & Seventy Five Only
2.00	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	466.00	Per Square Metre	50.00	23300.00	Rupees Twenty Three Thousand Three Hundred Only
3.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	489.30	Per Square Metre	14.00	6850.00	Rupees Six Thousand Eight Hundred & Fifty Only
4.00	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	86.00	Per Running Metre	23.00	1978.00	Rupees One Thousand Nine Hundred & Seventy Eight Only
<b>Total in Figures</b>					<b>99003.00</b>	Rupees Ninety Nine Thousand & Three Only
<b>Qouted Rate in Figures</b>					Excess (+)	
					Less (-)	

  
 Executive Engineer  
 Bangana Division  
 HP.PWD.Bangana



**Percentage BOQ**

<b>Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana</b>					<b>Estimated Cost</b>	<b>99946.00</b>
<b>Name of work:- Restoration of Rain damages on various roads under Chattara Section ( SH:- Maintenance of Berms and Drains)</b>					<b>Earnest Money</b>	<b>2000.00</b>
<b>Name of Bidder/ Bidding Firm/ Company :-</b>					<b>Time Limit:</b>	<b>Two Month</b>
<b>PRICE SCHEDULE</b>						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1480.00	Per Square Metre	50.00	74000.00	Rupees Seventy Four Thousand Only
2.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1480.00	Per Square Metre	14.00	20720.00	Rupees Twenty Thousand Seven Hundred & Twenty Only
3.00	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	227.20	Per Running Metre	23.00	5226.00	Rupees Five Thousand Two Hundred & Twenty Six Only
<b>Total in Figures</b>					<b>99946.00</b>	Rupees Ninety Nine Thousand Nine Hundred & Fourty Six Only
<b>Qouted Rate in Figures</b>					<b>Excess (+)</b>	
					<b>Less (-)</b>	

  
 Executive Engineer  
 Bangana Division  
 HP.PWD.Bangana



9

**Percentage BOQ**

<b>Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana</b>					Estimated Cost Rs	99900.00
<b>Name of Work: Stock Storage at HP. PWD Sub-Division DBR-Basal (SH: Supply and Stacking machine made buildings Bricks in Khurwain Section)</b>					Earnest Money Rs	2000.00
<b>Name of Bidder/ Bidding Firm/ Company :-</b>					Time Limit:	Two Month
<b>PRICE SCHEDULE</b>						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Supply and Stacking at site first class machine made modular bricks for approved brick klin, including loading & unloading and stacking properly at site as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	3700.00	Each	27.00	99900.00	Rupees Ninety Nine Thousand Nine Hundred Only
<b>Total in Figures</b>					<b>99900.00</b>	Rupees Ninety Nine Thousand Nine Hundred Only
<b>Qouted Rate in Figures</b>		<b>Excess (+)</b>				
		<b>Less (-)</b>				

  
**Executive Engineer**  
**Bangana Division**  
**HP.PWD.Bangana**

(10)

## Percentage BOQ

**Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana**

Estimated Cost  
Rs 99954.00

**Name of Work: Stock Storage at HP. PWD Sub-Division DBR-Basal (SH: Supply and Stacking machine made buildings Bricks in Khurwain Section)**

Earnest Money  
Rs 2000.00


Time Limit: Two Month

**Name of Bidder/ Bidding Firm/ Company :-**

### PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Supply and Stacking at site first class machine made modular bricks for approved brick klin, including loading & unloading and stacking properly at site as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	3702.00	Each	27.00	99954.00	Rupees Ninety Nine Thousand Nine Hundred & Fifty Four Only
<b>Total in Figures</b>					<b>99954.00</b>	Rupees Ninety Nine Thousand Nine Hundred & Fifty Four Only
<b>Quoted Rate in Figures</b>		<b>Excess (+)</b>				
		<b>Less (-)</b>				

  
**Executive Engineer**  
**Bangana Division**  
**HP.PWD. Bangana**



## Percentage BOQ

<b>Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana</b>	<b>Estimated Cost</b> Rs	<b>98986.00</b>
<b>Name of Work: Restoration of Rain damages on various roads under HP.PWD Sub-Division DBR-Basal ( SH:- Hiring of J.C.B. for removal of Slips, Road side drain, Shoulder berms and road surface in section Khruwain)</b>	<b>Earnest Money</b> Rs	<b>2000.00</b>
<b>Name of Bidder/ Bidding Firm/ Company :-</b>	<b>Time Limit:</b>	<b>Two Month</b>

### PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Hiring of J.C.B(Excavator-Cum-Loader) including P.O.L. (Petrol Oil Lubricant) charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation if necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berms. Minimum 25 cubic meter of earth work shall be done by machine in one hour, otherwise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	86.00	Per Hours	1151.00	98986.00	Rupees Ninety Eight Thousand Nine Hundred & Eighty Six Only
<b>Total in Figures</b>					<b>98986.00</b>	Rupees Ninety Eight Thousand Nine Hundred & Eighty Six Only
<b>Qouted Rate in Figures</b>		<b>Excess (+)</b>				
		<b>Less (-)</b>				

  
 Executive Engineer  
 Bangana Division  
 HP.PWD. Bangana



## Percentage BOQ


<b>Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana</b>			Estimated Cost Rs	98411.00
<b>Name of Work: Restoration of Rain damages on various roads under HP.PWD Sub-Division DBR-Basal ( SH:- Hiring of J.C.B. for removal of Slips, Road side drain, Shoulder berms and road surface in section Khruwain)</b>			Earnest Money Rs	2000.00
			Time Limit:	Two Month

**Name of Bidder/ Bidding Firm/ Company :-**

### PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Hiring of J.C.B(Excavator-Cum-Loader) including P.O.L. (Petrol Oil Lubricant) charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation if necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berms. Minimum 25 cubic meter of earth work shall be done by machine in one hour, otherwise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	85.50	Per Hours	1151.00	98411.00	Rupees Ninety Eight Thousand Four Hundred & Eleven Only
<b>Total in Figures</b>					<b>98411.00</b>	Rupees Ninety Eight Thousand Four Hundred & Eleven Only
<b>Qouted Rate in Figures</b>		<b>Excess (+)</b>				
		<b>Less (-)</b>				

  
 Executive Engineer  
 Bangana Division  
 HP.PWD. Bangana



## Percentage BOQ

**Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana**

Estimated Cost  
Rs 97835.00

**Name of Work: Restoration of Rain damages on various roads under HP.PWD Sub-Division DBR-Basal ( SH:- Hiring of J.C.B. for removal of Slips, Road side drain, Shoulder berms and road surface in section Khruwain)**

Earnest Money  
Rs 2000.00

Time Limit: Two Month

**Name of Bidder/ Bidding Firm/ Company :-**

### PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Hiring of J.C.B(Excavator-Cum-Loader) including P.O.L. (Petrol Oil Lubricant) charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation if necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berms. Minimum 25 cubic meter of earth work shall be done by machine in one hour, otherwise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	85.00	Per Hours	1151.00	97835.00	Rupees Ninety Seven Thousand Eight Hundred & Thirty Five Only
<b>Total in Figures</b>					<b>97835.00</b>	Rupees Ninety Seven Thousand Eight Hundred & Thirty Five Only
<b>Qouted Rate in Figures</b>		<b>Excess (+)</b>				
		<b>Less (-)</b>				

  
Executive Engineer  
Bangana Division  
HP.PWD.Bangana



## Percentage BOQ

**Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana**

**Name of work:- Restoration of Rain damages on various roads under HP.PWD Sub-Division DBR-Basal ( SH:- Removal of Slips, Maintenance of berms and Drain in Chattara Section)**

Estimated Cost  
Rs. 99978.00

Earnest Money  
Rs. 2000.00

**Name of Bidder/ Bidding Firm/ Company :-**

Time Limit: Two Month

### PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. including carriage of materials with in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	535.00	Per cubic metre	125.00	66875.00	Rupees Sixty Six Thousand Eight Hundred & Seventy Five Only
2.00	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	466.00	Per Square Metre	50.00	23300.00	Rupees Twenty Three Thousand Three Hundred Only
3.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	489.30	Per Square Metre	14.00	6850.00	Rupees Six Thousand Eight Hundred & Fifty Only
4.00	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	128.40	Per Running Metre	23.00	2953.00	Rupees Two Thousand Nine Hundred & Fifty Three Only
<b>Total in Figures</b>					<b>99978.00</b>	Rupees Ninety Nine Thousand Nine Hundred & Seventy Eight Only
<b>Quoted Rate in Figures</b>		Excess (+)				
		Less (-)				

*[Signature]*  
Executive Engineer  
Bangana Division  
HP.PWD.Bangana



# Percentage BOQ

Tender Inviviting Authority:- Excecutive Engineer HPPWD Division Bangana

Name of work:- C/o link road Surjehra Khuhi to Shiv Mandir & Satsang Ghar (SH: C/o Edge wall in Km 0/009 to 0/025.50 LHS)

Estimated Cost Rs 99344.00

Earnest Money Rs 2000.00

Name of Bidder/ Bidding Firm/ Company :-

Time Limit: Two Month

## PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks( where blasting is prohibited ) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	7.43	Per cubic metre	280.00	2080.00	Rupees Two Thousand & Eighty Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty, malkhana ,toll tax, GST, labour cess or other taxes imposed by the Government..	22.28	Per Cubic metre	3923.00	87404.00	Rupees Eighty Seven Thousand Four Hundred & Four Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm ( one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 ( one) vertical : 20 ( twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	34.00	Each	290.00	9860.00	Rupees Nine Thousand Eight Hundred & Sixty Only
Total in Figures					99344.00	Rupees Ninety Nine Thousand Three Hundred & Fourty Four
Qouted Rate in Figures		Excess (+)				
		Less (-)				


Executive Engineer  
Bangana Division  
HP.PWD. Bangana



(16)

**Percentage BOQ**

<b>Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana</b>					<b>Estimated Cost</b> Rs	<b>99636.00</b>
<b>Name of work:- R.R.D on Various roads under HP.PWD Sub-Division Bangana (SH: Maintenance of Berms &amp; Drains in various roads under Section Bangana-I)</b>					<b>Earnest Money</b> Rs	<b>2000.00</b>
<b>Name of Bidder/ Bidding Firm/ Company :-</b>					<b>Time Limit:</b>	<b>Two Month</b>
<b>PRICE SCHEDULE</b>						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	870.00	Per Square Metre	45.00	39150.00	Rupees Thirty Nine Thousand One Hundred & Fifty Only
2.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	870.00	Per Square Metre	17.00	14790.00	Rupees Fourteen Thousand Seven Hundred & Ninety Only
3.00	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	384.00	Per Running Metre	119.00	45696.00	Rupees Fourty Five Thousand Six Hundred & Ninety Six Only
<b>Total in Figures</b>					<b>99636.00</b>	Rupees Ninety Nine Thousand Six Hundred & Thirty Six Only
<b>Qouted Rate in Figures</b>		<b>Excess (+)</b>				
		<b>Less (-)</b>				

  
**Executive Engineer**  
**Bangana Division**  
**HP.PWD.Bangana**



17

## Percentage BOQ

**Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana**

**Name of work:- R.R.D on Various roads under HP.PWD Sub-Division Bangana (SH: Maintenance of Berms & Drains in various roads under Section Bangana-I)**

Estimated Cost Rs **98640.00**

Earnest Money Rs **2000.00**


**Name of Bidder/ Bidding Firm/ Company :-**

Time Limit: **Two Month**

### PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	900.00	Per Square Metre	45.00	40500.00	Rupees Fourty Thousand Five Hundred Only
2.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	900.00	Per Square Metre	17.00	15300.00	Rupees Fifteen Thousand Three Hundred Only
3.00	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	360.00	Per Running Metre	119.00	42840.00	Rupees Fourty Two Thousand Eight Hundred & Fourty Only
<b>Total in Figures</b>					<b>98640.00</b>	Rupees Ninety Eight Thousand Six Hundred & Fourty Only
<b>Quoted Rate in Figures</b>		<b>Excess (+)</b>				
		<b>Less (-)</b>				

  
 Executive Engineer  
 Bangana Division  
 HP.PWD.Bangana

(18)

## Percentage BOQ

<b>Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana</b>	<b>Estimated Cost Rs</b>	<b>99995.00</b>
<b>Name of Work: Restoration of Rain damages on U.A.M. road to Harot (SH: Embankment in Damaged road surface in Km 13/000 to 13/220)</b>	<b>Earnest Money Rs</b>	<b>2000.00</b>
<b>Name of Bidder/ Bidding Firm/ Company :-</b>	<b>Time Limit:</b>	<b>Two Month</b>

### PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Construction of embankment with approved materials deposited at site from roadway cutting and excvation of other road structures or other sources in layers of suitable thickness not exceeding 200mm ( two hundred millimetre) spreading to required slope to lines, grades, level and cross sections as per drawings or directions of the Engineer-in-charge including preparation of foundation for embankment in all kinds and classification of soils including saturated soil and dewatering/ bailing out of water wherever required including hauling of materials for construction of embankment within all leads and lifts. including carriage of material with in all leads and lifts and other incidentals .The rate includes octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1086.90	Per cubic metre	92.00	99995.00	Rupees Ninety Nine Thousand Nine Hundred & Ninety Five Only
<b>Total in Figures</b>					<b>99995.00</b>	Rupees Ninety Nine Thousand Nine Hundred & Ninety Five Only
<b>Qouted Rate in Figures</b>					<b>Excess (+)</b>	
					<b>Less (-)</b>	

  
 Executive Engineer  
 Bangana Division  
 HP.PWD.Bangana



## Percentage BOQ

**Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana**

**Name of work:- A/R & M/O on Type-II Quarter HP.PWD. Division Bangana Tehsil Bangana Distt. Una (HP) (SH: Providing & Fixing Sanitary Items)**

Estimated Cost  
Rs 54542.00

Earnest Money  
Rs 1100.00

**Name of Bidder/ Bidding Firm/ Company :-**

Time Limit: One Month

### PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete upto all floor level including painting of fittings and brackets, cutting and making good the walls and floors wherever required W.C. pan with ISI marked white solid plastic seat and lid of Parryware, Sanitaryware, Neycer, Cera/Hindware, including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	2.00	Each	7334.00	14668.00	Rupees Fourteen Thousand Six Hundred & Sixty Eight Only
2.00	Providing and fixing Stainless Steel towel rail of Jaquar (ACN-CHR-1111SM) complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour 600 mm ( six hundred millimetre) long including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	Each	651.70	652.00	Rupees Six Hundred & Fifty Two Only
3.00	Providing and fixing Wall Hung Wash Basin of 550 x 400 x 190mm size (ARS-WHT-39801 of Jaquar) with 15 mm (fifteen millimetre) diameter single hole Single Lever Basin Mixer without Popup waste with 450mm Long Braided Hoses of Jaquar (OPP-CHR-15053 BPM), 32 mm (thirty two millimetre) C.P. brass waste of standard pattern ( Hindware or Jaquar), including painting of fittings and brackets, cutting and making good the walls wherever required including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	Each	7177.00	7177.00	Rupees Seven Thousand One Hundred & Seventy Seven Only
4.00	Providing and fixing white vitreous china pedestal make of Cera/Hindware, Parryware, Sanitaryware, Neycer for wash basin completely recessed at the back for the reception of pipes and fittings complete upto all floor level as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	1.00	Each	4898.10	4898.00	Rupees Four Thousand Eight Hundred & Ninety Eight Only
5.00	Providing and fixing P.V.C. waste semi rigid pipe for sink or wash basin including P.V.C. waste fittings complete 32mm ( thirty two millimetre) dia of Supreme /Fenolax make including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	Each	240.20	480.00	Rupees Four Hundred & Eighty Only
6.00	Providing and fixing CP soap Dish Holder of Jaquar ( ACN-CHR-1131N ) with concealed fitting arrangements including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	Each	382.00	764.00	Rupees Seven Hundred & Sixty Four Only
7.00	Providing and fixing C.P. brass toilet paper holder complete upto all floor level including carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.00	Each	1150.00	2300.00	Rupees Two Thousand Three Hundred Only



	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
8.00	Providing and fixing pillar tap JAQUAR Continental Prime Series Table Mounted Regular HOT and Cold Basin Mixer/TAP (Chrome)   Twin Side Lever, Brass Body Water Tap/Faucet/Cock for Bathroom/Kitchen Wash Basin   COP-CHR-167BPM including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	Each	4393.00	4393.00	Rupees Four Thousand Three Hundred & Ninety Three Only
9.00	Providing and fixing Single Lever Bib Cock Water Tap for Bathroom with Wall Flange and Teflon Tape/ Tap for Home/Tap for Bathroom including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3.00	Each	620.00	1860.00	Rupees One Thousand Eight Hundred & Sixty Only
10.00	Providing and fixing 15mm (fifteen millimetre) nominal bore size G.I. Pipes complete with G.I. fittings and clamps, including making good the walls etcetera concealed pipe, including painting with anti corrosive bitumastic paint, cutting chases and making good the wall make of Jindal (Hissar)/Tata make including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	5.00	Each	329.45	1647.00	Rupees One Thousand Six Hundred & Forty Seven Only
11.00	Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube upto 1 metre long with S.S. triangular plate to European type W.C. of quality and make of Jal, Jaquar, Kingstone, Gem, Parko, Tecno, ESS, Seiko Make complete upto all floor level as approved by Engineer - in - charge including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.00	Each	601.00	1202.00	Rupees One Thousand Two Hundred & Two Only
12.00	Providing and fixing 15mm (fifteen millimeter) nominal bore C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 make of Kingston, Gem, Prko, Techno, ESS, ESS, Sieko, Jaquar as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	4.00	Each	600.00	2400.00	Rupees Two Thousand Four Hundred Only
13.00	Providing and fixing aluminium die cast body tubular type Universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg (Thirty five kilogramme) and door width upto 700 mm (Seven hundred millimetre), with necessary accessories and screws etcetera complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	Each	1800.70	3601.00	Rupees Three Thousand Six Hundred & One Only
14.00	Providing and fixing 15 liter storage Geyser (having brand logo with ISI make Havells Instanio Prime) including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	Each	8500.00	8500.00	Rupees Eight Thousand Five Hundred Only
<b>Total in Figures</b>					<b>54542.00</b>	Rupees Fifty Four Thousand Five Hundred & Forty Two Only
<b>Quoted Rate in Figures</b>					<b>Excess (+)</b>	
					<b>Less (-)</b>	

*Amal Kumar*  
**Executive Engineer**  
**Bangana Division**  
**HP, PWD, Bangana**