



"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP PWD as per revised enlistment rules so as to reach in the office of under signed on 05.01.2026 up to 11.30 A.M. and will be opened on the same day at (12.00 noon) in the presence of intending contractors. The tender application will be received in this office on 02.01.2026 up to 10.00 A.M. to 12.00 P.M. and tender form can be had from this office on 03.01.2026 from 2.00 P.M. to 5.00 P.m. The earnest money as shown against each in the shape of F D R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Construction of road from NH-154 to village Panjangna km. 0/0 to 1/180. in GP. Har Gunain (SH - Construction of edge wall at km. 0/138 to 0/153 under BASP deposit scheme ID BSP/2024/800).	Rs. 99,964/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two Months
2	Restoration of rain damages on Har Kumharda Bhaora Harizan Basti road km. 0/0 to 2/0 under SCSP (SH - Construction of Breast /Protection wall to house at km. 0/692 to 0/698).	Rs. 96,542/-	RS. 1,900/-	Rs. 350/-	Class "D"	Three Months
3	Restoration of rain damages on Draman- Kun- Tar road km. 0/0 to 7/225 (SH - Removal of Slip at Various RD's).	Rs. 99,244/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two Months
4	Restoration of rain damages on Machhyal Bhararu Bihun road km. 0/00 to 12/0 (SH - Removal of Slip at Various RD's).	Rs. 98,586/-	Rs. 2,000/-	Rs. 350/-	Class "D"	One Months
5	Restoration of rain damages on various roads under Joginder Nagar Sub Division No.II HP PWD Joginder Nagar (Bhararu Section).(SH - Hiring of tipper for Shifting and Carriage of Various types of materials etc.	Rs. 99,000/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Three Months
6	Construction of road from NH-154 to village Panjangna km. 0/0 to 1/180. (SH - Construction of RCC hume pipe culvert at km. 0/073 under BASP deposit scheme ID BSP/2024/800.	Rs. 98,536/-	Rs. 2,000/-	Rs. 350/-	Class "D"	One Months
7	R/O Restoration of rain damages on Kuthera Pipli Dhanotu to Lower Ladwan and Chatarbhuja km. 0/0 to 4/0 (SH - Construction of retaining wall at km. 0/603.50 to 0/607.10) under NDF Deposit SID:NDF/2025/4).	Rs. 74,347	Rs. 1,500/-	Rs. 350/-	Class "D"	Three Months
8	Restoration of rain damages on various road under Joginder Nagar, Sub Division No.II HPPWD Joginder Nagar (Chaurtra Section). (SH - Hiring of Tipper for Shifting and carriage of Various types of materials etc.).	Rs. 99,000	RS. 2,000/-	Rs. 350/-	Class "D"	Three Months
9	R/O Restoration of rain damages on Kuthera Pipli Dhanotu to lower Ladwan and Chatarbhuja km. 0/0 to 4/0 (SH - Construction of retaining wall at km. 0/600 to 0/603.50) under NDF Deposit SID:NDF/2025/4.)	Rs. 75,371/-	Rs. 1,500/-	Rs. 350/-	Class "D"	Three Months
10	Restoration of rain damages on Har Kumharda Bhaora Harizan Basti road km. 0/0 to 2/0 under SCSP (SH - Construction of Breast /Protection wall to house at km. 0/685 to 0/691).	Rs. 96,576/-	RS. 1,900/-	Rs. 350/-	Class "D"	Three Months

Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

1. The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
2. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
3. For on behalf of Governor of Himachal Pradesh the Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
4. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
5. Only two tenders form will be issued to the contractor/firm which may be noted.
6. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
7. The contractor shall be responsible for rectifying defects noticed within six months from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
8. The contractor shall have all required machinery such as Truck/Tipper, Mixture, water tanker Vibrator etc. or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
9. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking he will get complete the works in hand before award of work with in schedule time.
10. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
11. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/permit.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033.

No. PW-JND-B&R-EA-I/NIT/Press/2025-26-

21545-21594

Dated:- 17/12/2025

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Account Branch in this office.
9. Notice Board.
10. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.

E.A.O. - 91

1

159

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Construction of road from NH-154 to village Panjanga km.0/0 to 1/180. in GP .Har Gunain
 (Sh:-Construction of edge wall at Km.0/138 to 0/153 under BASP deposit scheme ID BSP/2024/800

Estimate Cost:
 Earnest Money:
 Time Limit :

99,964.00
 2,000.00
 Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time including GST.	4.86	Per cubic metre	609.90	Rupees Six Hundred Nine And Paise Ninety Only	2,964.00
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time including GST.	16.20	Per cubic metre	5,987.65	Rupees Five Thousand Nine Hundred Eighty Seven And Paise Sixty Five Only	97,000.00
Total						99,964.00

Total

159

Draft schedule of quantity approved
 for ₹ 99,964/- (Ninety nine thousand nine hundred sixty four)

Executive Engineer

B & R Division HP.PWD,

Jalandhar Nagar

422

E No - 315

DNIT/ DRAFT SCHEDULE OF QUANTITY

Name of Work :- Restoration of rain damages on Har Kumharda Bhaora Harizan Basti road km.0/0 to 2/0 Under SCSP (SH):-Construction of breast /protection wall to house at RD 0/692 to 0/698)

Sr. No.	Description of work	No. or Qty.	Unit	Estimate Cost:		Three Months	
				Figures	Words	Amount	P
						Rs.	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time including GST.	8.67	Per cubic metre	198.40	Rupees One Hundred Ninety Eight And Paise Forty Only	1,720.00	
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time including GST.	3.06	Per cubic metre	609.90	Rupees Six Hundred Nine And Paise Ninety Only	1,866.00	
3	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time including GST..	14.10	Per cubic metre	6,452.90	Rupees Six Thousand Four Hundred Fifty Two And Paise Ninety Only	90,986.00	

422

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time including GST.	6.00	Each	328.25	Rupees Three Hundred Twenty Eight And Paise Twenty Five Only	1,970.00
	Total					96,542.00

Draft schedule of quantity approved for 96,542/- (Ninty six thousand five hundred forty two) only

Executive Engineer

B & R Division HP.PWD,

Joginder Nagar

3


(434)

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on Draman-Kun-Tar road km.0/0 to 7/225 (SH:- Removal of slip at various RD.s)				Estimate Cost: Earnest Money: Time Limit :		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material as per technical specification clause 302.3.5 and 1611. including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge . The rate is inclusive all taxes levy by the government time to time including GST.	531.00	Per cubic metre	186.90	Rupees One Hundred Eighty Six And Paise Ninety Only	99,244.00
Total				Total		99,244.00

(434)

Draft Schedule of Quantity approved for (99,244) / -
(Ninety Nine Thousand and two Hundred forty four only) / -


Executive Engineer
E & R Division HP.PWD,
Joginder Nagar


433

E.No - 318 (4)
DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on Machhyal Bhararu Bihun road km.0/0 to 12/0 (SH:- Removal of slip at various RD.s)				Estimate Cost: Earnest Money: Time Limit :		98,586.00 2,000.00 Two Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material as per technical specification clause 302.3.5 and 1611. including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge . The rate is inclusive all taxes levy by the government time to time including GST.	527.48	Per cubic metre	186.90	Rupees One Hundred Eighty Six And Paise Ninety Only	98,586.00	
Total					Total	98,586.00	

Draft Schedule of Quantity for approved box 98,586/-
(Ninety Eight Thousand and Five Hundred Eight Six only) -

433


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Draft Schedule of Quantity

Estimated Cost:- 99000.00
 Earnest Money:- 2000.00
 Time:- One month

Name of work:- Restoration of Rain damages on various roads under Joginder Nagar Sub Division No.II HP,PWD Joginder Nagar (Bhararu Section).
 Sub Head:- Hiring of Tipper for shifting and carriage of various types of materials etc.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hire charges of tipper for carriage/shifting of soling stone earth, moorum, premix material, seal coat etc. having capacity of 5.50 (five point five zero) cubic metre per trip and covering 70 (seventy) kilometers per day (9AM to 5PM), the contractor/owner of tipper shall bear the expensive of POL charges, repair of machineries including driver and helper wages. Any accident and other damages to private and Govt property occur during the working hours in the work shall be the responsibility of the contractor and disposal of excavated material/ slips debris with in all leads and lifts as per the direction of Engineer-in-Charge. The rates are inclusive of all taxes including GST levy by the Govt. time to time.	22.00	4500.00	Rupees Four thousand five hundred and paise nil only	Per day	99000.00
					Total:-	99000.00

Assistant Engineer,
 B&R Sub Division No.II,
 HP.PWD, Joginder Nagar

Draft schedule of quantity approved for Rs 99,000/- (Ninty nine thousand) only

Executive Engineer
 B&R Division, HPPWD
 Joginder Nagar (H.P.)

E.No-90

6

158

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Construction of road from NH-154 to village Panjanga km.0/0 to 1/180.in GP .Har Gunain (Sh:- Construction of RCC hume pipe culvert at Km.0/073 under BASP deposit scheme ID BSP/2024/800				Estimate Cost: Earnest Money: Time Limit : Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate	AMOUNT Rs. P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time including GST.	21.40	Per cubic metre	Figures 609.90 Words Rupees Six Hundred Nine And Paise Ninety Only	13,052.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentials. The rate is inclusive all taxes levy by the government time to time including GST.	9.73	Per cubic metre	7,452.30 Rupees Seven Thousand Four Hundred Fifty Two And Paise Thirty Only	72,511.00
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentials.The rate is inclusive all taxes levy by the government time to time including GST.	1.99	Per cubic metre	6,519.00 Rupees Six Thousand Five Hundred Nineteen Only	12,973.00
Total					98,536.00

158

Draft schedule of quantity approved for
 ₹ 98,536/- (Ninety eight thousand five hundred
 thirty six) only

~~Executive Engineer~~
 B&R Division, HPPWD
 Joginder Nagar (H.P.)

7

441

Name of Work : R/O Restoration of rain damages on Kuthera Pipli Dhanotu to Lower Ladwan and SID: NDF/2025/4 Sr. No.									
DNIT/DRAFT SCHEDULE OF QUANTITY Construction of retaining wall at km 0/603.50 to 0/607.10 under NDF Deposit									
Description of work									
Sr. No.	No. or Qty.	Unit	Figures	Rate		Estimate Cost: Earnest Money: Time Limit :	AMOUNT		
				Words	P		Rs.	P	
1	4.87	Per cubic metre	609.90	Rupees Six Hundred Nine And Paise Ninety Only			2,970.00		
2	11.06	Per cubic metre	6,135.20	Rupees Six Thousand One Hundred Thirty Five And Paise Twenty Only			67,855.00		
3	2.00	Per cubic metre	1,104.30	Rupees One Thousand One Hundred Four And Paise Thirty Only			2,209.00		

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time including GST.	4.00	Each	328.25	Rupees Three Hundred Twenty Eight And Paise Twenty Five Only	1,313.00
	Total					74,347.00

*Draft schedule of quantity approved for
#74347/- (E Seventy four thousand three
hundred forty seven) only*

Executive Engineer

B & R Division HP.PWD,

Joginder Nagar

Draft Schedule of Quantity

Name of work:- Restoration of Rain damages on various roads under Joginder Nagar Sub Division No.II HP.PWD Joginder Nagar (Chautra Section).
Sub Head:- Hiring of Tipper for shifting and carriage of various types of materials etc.

Estimated Cost:- 99000.00
Earnest Money:- 2000.00
Time:- One month

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hire charges of tipper for carriage/shifting of soling stone earth, moorum, premix material, seal coat etc. having capacity of 5.50 (five point five zero) cubic metre per trip and covering 70 (seventy) kilometers per day (9AM to 5PM), the contractor/owner of tipper shall bear the expensive of POL charges, repair of machineries including driver and helper wages. Any accident and other damages to private and Govt property occur during the working hours in the work shall be the responsibility of the contractor and disposal of excavated material/ slips debris with in all leads and lifts as per the direction of Engineer-in-Charge. The rates are inclusive of all taxes including GST levy by the Govt. time to time.	22.00	4500.00	Rupees Four thousand five hundred and paise nil only	Per day	99000.00
					Total:-	99000.00

Assistant Engineer,
B&R Sub Division No.II,
HP.PWD, Joginder Nagar

Draft schedule of quantity approved for
99,000/- (Ninty nine thousand) only

Executive Engineer
B&R Division, HPPWD
Joginder Nagar (H.P.)

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : R/O Restoration of rain damages on Kuthera Pipli Dhanotu to Lower Ladwan and Chaturbhujia km.0/0 to 4/0 (Sh:- Construction of retaining wall at km 0/600 to 0/603.50) under NDF Deposit SID: NDF/2025/4

Estimate Cost: 75,371.00
Earnest Money: 1,500.00
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time including GST.	4.83	Per cubic metre	609.90	Rupees Six Hundred Nine And Paise Ninety Only	2,946.00
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time including GST.	11.22	Per cubic metre	6,135.20	Rupees Six Thousand One Hundred Thirty Five And Paise Twenty Only	68,837.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time including GST.	2.06	Per cubic metre	1,104.30	Rupees One Thousand One Hundred Four And Paise Thirty Only	2,275.00

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time including GST.	4.00	Each	328.25	Rupees Three Hundred Twenty Eight And Paise Twenty Five Only	1,313.00
	Total					75,371.00

*Draft schedule of quantity approved for Rs 75371/-
(75 Seventy five thousand three hundred and seventy one) only*

[Signature]
Executive Engineer

B & R Division HP.PWD,

Joginder Nagar

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time including GST.	5.00	Each	328.25	Rupees Three Hundred Twenty Eight And Paise Twenty Five Only	1,641.00
	Total					96,576.00

*Draft schedule of quantity approved for ₹ 96,576/- only
(₹ Ninety six thousand five hundred seventy six) only*

Executive Engineer

B & R Division HP.PWD,

Joginder Nagar