

**Office of the Executive Engineer Bangana Division Himachal Pradesh
Public Works Department Bangana.**

Phone No. 01975- 262283

E-mail:- ee-ban-hp@nic.in

No:- PW-BGN-CB/T-1/2025-26-
To

— 12504-12

Dated:- 29/01/2026

The Executive Engineer (IT Cell),
Nigam Vihar, HP Shimla-2.
cc-pwd-hp@nic.in.

Subject:- Publication of Tender Notice.

Sir,

Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender. As per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website.

**DA/- Notice Inviting Tender/Scheduled of Quantity
And "A" Certificate.**

A. K. G. G. G.
Executive Engineer
Bangana Division
HPPWD Bangana.

Copy forwarded with its enclosures for information to:-

1. The Engineer-in-Chief, H.P.P.W.D., Shimla-2.
2. The Chief Engineer (HZ), H.P.P.W.D., Hamirpur.
3. The Superintending Engineer, 15th Circle, HPPWD, Una.
4. The Assistant Engineer, Sub Division, HPPWD Bangana and Basal.
5. Drawing Branch in this office.
6. Accounts Branch in this office.
7. Notice Board.

↗
Executive Engineer
Bangana Division
HPPWD Bangana.

**Office of the Executive Engineer Bangana Division Himachal Pradesh
Public Works Department Bangana.**



Phone No. 01975- 262283

E-mail:- ee-ban-hp@nic.in

CERTIFICATE.

Certified that the works are of urgent in nature and for larger public interest so there is exigencies/emergency in calling these tenders without press vide this office letter No. PW-BGN/CB/T-1/2025-26- 1204-12 dated

29/01
2026

Ashwini Kumar
Executive Engineer
Bangana Division
HPPWD Bangana

Office of the Executive Engineer Bangana Division Himachal Pradesh
Public Works Department Bangana.

Phone No. 01975- 262283

E-mail:- ee-ban-hp@nic.in

NOTICE INVITING TENDER.

Scaled percentage rate tender on form 6 & 8 are hereby invited by the Executive Engineer Bangana Division HPPWD Bangana on behalf of Governor of HP from the approved eligible contractors enlisted in HPPWD, for the following works, so as to reach this office on **05.02.2026 up to 10:30 AM** and same will be opened on the same day at **11.00 AM** in presence of the interested contractors or their authorized representative. The application will be received in this office on at **02.02.2026 up to 3.00 PM**. The tender form can be had from the office of Executive Engineer Bangana Division HPPWD Bangana on cash payment (Non-refundable) on **04.02.2026** during office Hours **up to 4:00 PM**. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Bangana Division HPPWD Bangana cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The tender document fee shall also be deposited by the applicant/ contractor with at the time of application in the shape of Demand Draft or Cash (Non-Refundable) otherwise tender documents/ Forms shall not be issued. The offer of tender shall be kept upon for 60 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment/renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid copy of Registration as required, Copy of PAN Card, EPF filing which no tender form will be issued to him.**


Work/Job No.	Name of Work	Estimated Cost	Earnest Money	Time Period	Eligible of Class
1	Restoration of Rain Damages on Various Road Under DBR-Basal Sub Division. (Sub Head:- Maintenance of Berms, Drains & Removal of Slips in Khurwain Section)	Rs. 99826.00	Rs. 2000.00	One Month	C&D
2	Restoration of Rain Damages on UAM Road. (Sub Head:- Maintenance of Berms, Drain & Removal of Slips in Khurwain Section)	Rs. 99626.00	Rs. 2000.00	One Month	C&D
3	Restoration of Rain Damages on Various Roads Under DBR- Basal Sub Division (Sub Head:- Hiring of JCB for Removal of Slips, Road Side Drain, Shoulder Berms & Road Surface in Khurwain Section)	Rs. 89775.00	Rs. 1800.00	One Month	C&D
4	Restoration of Rain Damages on Piploo Sukrial Road Km. 0/000 to 7/240. (Sub Head:- Removal of Slips Km. 3/450 to 5/015)	Rs. 99975.00	Rs. 2000.00	One Month	C&D
5	Restoration of Rain Damages on Piploo Sukrial Road Km. 0/000 to 7/240. (Sub Head:- Removal of Slips Km. 3/150)	Rs. 99875.00	Rs. 2000.00	One Month	C&D
6	Restoration of Rain Damages on Piploo Sukrial Road Km. 0/000 to 7/240. (Sub Head:- Removal of Slips in Km. 5/030 to 6/915)	Rs. 99835.00	Rs. 2000.00	One Month	C&D
7	Restoration of Rain Damages on Handola Jaghatkhana Km. 0/000 to 3/390. (Sub Head:-Hiring of Poelain (Heavy Duty Excavator) From Km. 1/200 to 1/700 in Bihru Section)	Rs. 99495.00	Rs. 2000.00	One Month	C&D
8	Restoration of Rain Damages on Handola Jaghatkhana Km. 0/000 to 3/390. (Sub Head:- Hiring of Poelain (Heavy Duty Excavator) from Km. 1/700 to 3/200 in Bihru Section)	Rs. 99830.00	Rs. 2000.00	One Month	C&D
9	Restoration of Rain Damages on Link Road to Harizan Basti Padyola Km. 0/000 to 2/000. (Sub Head:- Hiring of JCB in Lathiani Section)	Rs. 99960.00	Rs. 2000.00	One Month	C&D
10	Restoration of Rain Damages on Kodra Jole Road Km. 0/000 to 2/000 (Sub Head:- Hiring of JCB in Lathiani Section)	Rs. 99750.00	Rs. 2000.00	One Month	C&D
11	Stock Storage in HPPWD Sub Division DBR-Basal. (Sub Head:- Supply & Stacking 900MM Dia Hume Pipe in Dhamandri Section)	Rs. 92000.00	Rs. 1900.00	One Month	C&D
12	Restoration of Rain Damages on Hatli Beri Road Km. 0/000 to 1/105. (Sub Head:- Construction of R/Wall from RD. 0/300 to 0/315)	Rs. 76404.00	Rs. 1600.00	One Month	C&D
13	Restoration of Rain Damages on Link Road Village Dharet to Kodra Km. 0/000 to 3/000. (Sub Head:- Construction of R/Wall from RD. 0/440 to 0/445.80)	Rs. 95772.00	Rs. 2000.00	One Month	C&D
14	Restoration of Rain Damages on Link Road Village Dharet to Kodra Km.0/000 to 3/000. (Sub Head:- Construction of R/Wall from 0/446 to 0/451.80)	Rs. 95843.00	Rs. 2000.00	One Month	C&D
15	Repair & Maintenance of HPPWD Rest House at Bangana District Una HP. (Sub Head:- Repair of VIP Toilet, Joinery Work etc).	Rs. 99628.00	Rs. 2000.00	One Month	C&D
16	Restoration of Rain Damages on Handola to Jaghatkhana Km. 0/000 to 3/390 (Sub Head:- Hiring of Tipper Under Section Bihru)	Rs. 99125.00	Rs. 2000.00	One Month	C&D

HIM SUCHANA AVAM JAN SAMPARK.

Ashish Chandra
Executive Engineer
Bangana Division
HPPWD Bangana
On behalf of Governor of Himachal Pradesh.


Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana						Estimated Cost Rs	99826.00
Name of work:- Restoration of Rain Damages on Various road under DBR-Basal Sub-Division (SH: Maintenance of berms, Drain and Removal of Slips in Khurwain Section)						Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-						Time Limit:	One Month
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words	
1.00	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	600.00	Per Square Metre	50.00	30000.00	Rupees Thirty Thousand Only	
2.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	600.00	Per Square Metre	14.00	8400.00	Rupees Eight Thousand Four Hundred Only	
3.00	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	200.00	Per Running Metre	23.00	4600.00	Rupees Four Thousand Six Hundred Only	
4.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. including carriage of materials with in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Government	451.00	Per cubic metre	126.00	56826.00	Rupees Fifty Six Thousand Eight Hundred & Twenty Six Only	
Total in Figures					99826.00	Rupees Ninety Nine Thousand Eight Hundred & Twenty Six Only	
Qouted Rate in Figures					Excess (+)		
					Less (-)		


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana					Estimated Cost Rs	99626.00
Name of work:- Restoration of Rain Damages on UAM road (SH: Maintenance of berms, Drain and Removal of Slips in Khurwain Section)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	One Month
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	400.00	Per Square Metre	50.00	20000.00	Rupees Twenty Thousand Only
2.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	400.00	Per Square Metre	14.00	5600.00	Rupees Five Thousand Six Hundred Only
3.00	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	200.00	Per Running Metre	23.00	4600.00	Rupees Four Thousand Six Hundred Only
4.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. including carriage of materials with in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	551.00	Per cubic metre	126.00	69426.00	Rupees Sixty Nine Thousand Four Hundred & Twenty Six Only
Total in Figures					99626.00	Rupees Ninety Nine Thousand Six Hundred & Twenty Six Only
Qouted Rate in Figures					Excess (+)	
					Less (-)	


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

3

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on Various road under DBR-Basal Sub-Division (SH: Hiring of J.C.B for removal of Slips, road side drain, Shoulder berms and road surface in Khurwain Section)

Estimated Cost Rs 89775.00

Earnest Money Rs 1800.00

Name of Bidder/ Bidding Firm/ Company :-

Time Limit: One Month

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Hiring of J.C.B(Excavator-Cum-Loader) including P.O.L. (Petrol Oil Lubricant) charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation if necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berms. Minimum 25 cubic meter of earth work shall be done by machine in one hour, otherwise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	85.50	Per Hours	1050.00	89775.00	Rupees Eighty Nine Thousand Seven Hundred & Seventy Five Only
Total in Figures					89775.00	Rupees Eighty Nine Thousand Seven
Quoted Rate in Figures		Excess (+)				
		Less (-)				

A. M. Chaur
Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana	Estimated Cost Rs	99975.00
Name of work:- R.R.D. on Piploo Sukrial road Km 0/000 to 7/240 (SH: Removal of Slips Km 3/450 to 5/015)	Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-	Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. including carriage of materials with in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	799.80	Per cubic metre	125.00	99975.00	Rupees Ninety Nine Thousand Nine Hundred & Seventy Five Only
Total in Figures		+			99975.00	Rupees Ninety Nine Thousand Nine
Qouted Rate in Figures		Excess (+)				
		Less (-)				

Amel Chauhan
Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- R.R.D. on Piploo Sukrial road Km 0/000 to 7/240 (SH: Removal of Slips Km 0/000 to 3/150)

Name of Bidder/ Bidding Firm/ Company :-

Estimated Cost Rs	99875.00
Earnest Money Rs	2000.00
Time Limit:	One Month

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. including carriage of materials with in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	799.00	Per cubic metre	125.00	99875.00	Rupees Ninety Nine Thousand Eight Hundred & Seventy Five Only
Total in Figures					99875.00	Rupees Ninety Nine Thousand Eight
Quoted Rate in Figures		Excess (+)				
		Less (-)				


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana					Estimated Cost Rs	99835.00
Name of work:- R.R.D. on Piploo Sukrial road Km 0/000 to 7/240 (SH: Removal of Slips Km 5/030 to 6/915)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	One Month
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. including carriage of materials with in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	798.68	Per cubic metre	125.00	99835.00	Rupees Ninety Nine Thousand Eight Hundred & Thirty Five Only
Total in Figures					99835.00	Rupees Ninety Nine Thousand Eight
Quoted Rate in Figures		Excess (+)				
		Less (-)				


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

Percentage BOQ

7

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana					Estimated Cost Rs	99495.00
Name of work:- Restoration of Rain Damages on Handola Jaghatkhana Km 0/000 to 3/390 (SH:- Hiring of Poclain (Heavy duty Excavator) from Km 1/200 to 1/700 in Bihru Section)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Hiring of Heavy duty Excavator (POCK LANE/L&T) with 90 H.P Engine and lifting capacity of minimum 5000 Kms including P.O.L charges, shifting charges and other anciliary equipments as required at site of work for cutting in earth work in all heights in all kinds of soil such as Kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including chieselling/wedging out of rocks etc. where blasting is prohibited including saturated soils including filling in embankments where including consolidating with sheep foot rollers and disposal of this unserviceable materials in all leads and lifts including mechanical transportation if necessary. The disposal of this unserviceable materials has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place the contractor is liable for it. All salvaged materials such as quarried stone shall belong to the department and maximum useful quantity of stones from cutting work shall have to be neatly stacked along the road side on road burms. The work involves widening from existing width to IRC single lane standard width formation width 5 meters in straight and 7 meter in curves as per their radius. Minimum 40 cum of earth work shall be done by the Machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.) With rock breaker. The rate includes octori, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	29.70	Per Hours	3350.00	99495.00	Rupees Ninety Nine Thousand Four Hundred & Ninety Five Only
Total in Figures					99495.00	Rupees Ninety Nine Thousand Four
Qouted Rate in Figures					Excess (+)	
					Less (-)	

Executive Engineer
 Bangana Division
 HP.PWD, Bangana

Percentage BOQ

#8

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on Handola Jaghatkhana Km 0/000 to 3/390 (SH:- Hiring of Poclain (Heavy duty Excavator) from Km 1/700 to 3/200 in Bihru Section)

Name of Bidder/ Bidding Firm/ Company :-

Estimated Cost Rs 99830.00


Earnest Money Rs 2000.00

Time Limit: One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Hiring of Heavy duty Excavator (POCK LANE/L&T) with 90 H.P Engine and lifting capacity of minimum 5000 Kmts including P.O.L charges, shifting charges and other anciliary equipments as required at site of work for cutting in earth work in all heights in all kinds of soil such as Kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including chieselling/wedging out of rocks etc. where blasting is prohibited including saturated soils including filling in embankments where including consolidating with sheep foot rollers and disposal of this unserviceable materials in all leads and lifts including mechanical transportation if necessary. The disposal of this unserviceable materials has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place the contractor is liable for it. All salvaged materials such as quarried stone shall belong to the department and maximum useful quantity of stones from cutting work shall have to be neatly stacked along the road side on road burms. The work involves widening from existing width to IRC single lane standard width formation width 5 meters in straight and 7 meter in curves as per their radius. Minimum 40 cum of earth work shall be done by the Machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.) With rock breaker. The rate includes octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	29.80	Per Hours	3350.00	99830.00	Rupees Ninety Nine Thousand Eight Hundred & Thirty Only
Total in Figures					99830.00	Rupees Ninety Nine Thousand Eight
Qouted Rate in Figures		Excess (+)				
		Less (-)				


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

9


Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana					Estimated Cost Rs	99960.00
Name of work:- Restoration of Rain Damages on Link road to Harizan Basti Padyola Km 0/000 to 2/000 (SH: Hiring of JCB in Lathiani Section)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	One Month
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Hiring of J.C.B(Excavator-Cum-Loader) including P.O.L. (Petrol Oil Lubricant) charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation if necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berms. Minimum 25 cubic meter of earth work shall be done by machine in one hour, otherwise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.	95.20	Per Hours	1050.00	99960.00	Rupees Ninety Nine Thousand Nine Hundred & Sixty Only
Total in Figures					99960.00	Rupees Ninety Nine Thousand Nine
Qouted Rate in Figures				Excess (+)		
				Less (-)		


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

Percentage BOQ

(10)

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana						Estimated Cost Rs	99750.00
Name of work:- Restoration of Rain Damages on Kodra Jole road Km 0/000 to 2/000 (SH: Hiring of JCB in Lathiani Section)						Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-						Time Limit:	One Month
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words	
1.00	Hiring of J.C.B(Excavator-Cum-Loader) including P.O.L. (Petrol Oil Lubricant) charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation if necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berms. Minimum 25 cubic meter of earth work shall be done by machine in one hour, otherwise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	95.00	Per Hours	1050.00	99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only	
Total in Figures					99750.00	Rupees Ninety Nine Thousand Seven	
Qouted Rate in Figures		Excess (+)					
		Less (-)					


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana				Estimated Cost Rs	92000.00	
Name of work:- Stock Storage at HP.PWD Sub-Division DBR-Basal (SH: Supply and stacking 900mm dia Hume Pipe in Dhamandri- Section)				Earnest Money Rs	1900.00	
Name of Bidder/ Bidding Firm/ Company :-				Time Limit:	One Month	
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Supply and Stacking RCC 900mm dia Hume pipes NP-2 (2.50 mtr length each pipe) i/c collar approved brand/ISI marked including loading & unloading and stacking properly at site, including carriage of materials within all leads and lifts and including all incidentals and as per drawings and technical specification as per the direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	10.00	Each	9200.00	92000.00	Rupees Ninety Two Thousand Only
Total in Figures					92000.00	Rupees Ninety Two Thousand Only
Qouted Rate in Figures		Excess (+)				
		Less (-)				


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- R.R.D. on Hatli Beri Road Km 0/000 to 1/105 (SH: C/o R/wall from Rd 0/300 to 0/315)

Estimated Cost Rs 76404.00

Earnest Money Rs 1600.00

Name of Bidder/ Bidding Firm/ Company :-

Time Limit: One Month

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

PRICE SCHEDULE

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks (where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	7.20	Per cubic metre	300.00	2160.00	Rupees Two Thousand One Hundred & Sixty Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	16.35	Per Cubic metre	4000.00	65400.00	Rupees Sixty Five Thousand Four Hundred Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	14.00	Each	246.00	3444.00	Rupees Three Thousand Four Hundred & Fourty Four Only
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	6.75	Per Cubic metre	800.00	5400.00	Rupees Five Thousand Four Hundred Only
Total in Figures					76404.00	Rupees Seventy Six Thousand Four Hundred & Four Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				

Executive Engineer
Bangana Division
HP.PWD.Bangana

14/13

Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana					Estimated Cost Rs	95772.00
Name of work:- R.R.D. onLink road Village Dharet to Kodra Km 0/000 to 3/000 (SH: C/o R/wall from Rd 0/440 to 0/445.80)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	One Month
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender.Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	10.08	Per cubic metre	300.00	3024.00	Rupees Three Thousand &Twenty Four Only
2.00	Providing and laying cement concrete 1:5:10(one cement five sand: ten graded stone aggregate 40mm(forty millimeter)nominal size and curing complete including cost of form work with MS plates plain concrete on ground or under water and curing complete including pumping bailing out water dewatering removal of slush or required at site which may arise at the time of laying under water complete for all heights and depths in retaining wall /breast wall as per drawing and HP.PWD., technical specification direction of Engineer-in-charge including carriage of materials within all leads and lifts . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	24.21	Per Cubic metre	3550.00	85946.00	Rupees Eighty Five Thousand Nine Hundred & Forty Six Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	10.00	Each	246.00	2460.00	Rupees Two Thousand Four Hundred & Sixty Only
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	6.68	Per Cubic metre	650.00	4342.00	Rupees Four Thousand Three Hundred & Forty Two Only
Total in Figures					95772.00	Rupees Ninety Five Thousand Seven Hundred & Seventy Two Only
Qouted Rate in Figures					Excess (+)	
					Less (-)	


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

(15) (14)

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- R.R.D. on Link road Village Dharet to Kodra Km 0/000 to 3/000 (SH: C/o R/wall from Rd 0/446 to 0/451.80)

Estimated Cost
Rs 95843.00

Earnest Money
Rs 2000.00

Name of Bidder/ Bidding Firm/ Company :-

Time Limit: One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	10.08	Per cubic metre	300.00	3024.00	Rupees Three Thousand & Twenty Four Only
2.00	Providing and laying cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm (forty millimeter) nominal size and curing complete including cost of form work with MS plates plain concrete on ground or under water and curing complete including pumping bailing out water dewatering removal of slush or required at site which may arise at the time of laying under water complete for all heights and depths in retaining wall /breast wall as per drawing and HP PWD, technical specification direction of Engineer-in-charge including carriage of materials within all leads and lifts. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	24.23	Per Cubic metre	3550.00	86017.00	Rupees Eighty Six Thousand & Seventeen Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical 20 (twenty horizontal) toward drawing face complete as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	10.00	Each	246.00	2460.00	Rupees Two Thousand Four Hundred & Sixty Only
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	6.68	Per Cubic metre	650.00	4342.00	Rupees Four Thousand Three Hundred & Forty Two Only
Total in Figures					95843.00	Rupees Ninety Five Thousand Eight Hundred & Forty Three Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

#6 15

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana	Estimated Cost Rs	99628.00
Name of work:- Repair & Maintenance of HPPWD Rest House at Bangana Distt. Una HP. (SH: Reapir of VIP Toilet, Joinery Work etc.)	Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-	Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make Hindalco, Jindal, Indian Aluminium Company conforming to IS 733 and IS 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete for shutters of doors, windows and ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber neoprene gasket required (Fittings shall be paid for separately Polyester powder coated aluminium (minimum thickness of polyester powder coating 50 micron) complete upto all floor level as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) including carriage of materials with in all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	51.10	Per Kilogramme	736.00	37610.00	Rupees Thirty Seven Thousand Six Hundred & Ten Only
2.00	Providing and fixing 12 mm thick Pre-laminated particle board with decorative lamination on both sides flat pressed three layer or graded wood particle board conforming to IS 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.06	Per Square meter	1732.00	10496.00	Rupees Ten Thousand Four Hundred & Ninety Six Only
3.00	Providing and fixing Float glass panes of nominal thickness 5 mm (five millimetre) make of Modi Float, Saint Govind, Aashai (weight not less than 12.5kg/sqm (twelve point five kilogram per square metre) of renewing glass panes with putty and nails wherever necessary including racking out the old putty including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	0.39	Per Square meter	1483.00	578.00	Rupees Five Hundred & Seventy Eight Only
4.00	Providing & fixing fly proof Stainless steel (grade 304(three hundred four)) wire gauze of 0.5 mm(zero point five millimetre) dia wire and 1.4 mm (one point four millimetre) aperture on both sides complete to windows, clerestory windows & doors with aluminium snap beading and nuts & bolts complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.43	Per Square meter	1480.00	3596.00	Rupees Three Thousand Five Hundred & Ninety Six Only
5.00	Providing and fixing 18 mm (Eighteen millimetre) thick HDHMR (High density High moisture Resistance board of (Action Tesa/Kitply/Century ply make) in shelves/box for cup board with butt joints and fixing with nails and screws etcetera complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.31	Per Square meter	1950.00	16205.00	Rupees Sixteen Thousand Two Hundred & Five Only
6.00	Providing and fixing Cup Board Shutters with 18 mm (Eighteen millimetre) thick HDHMR (High density High moisture Resistance board of Action TESA / Green Ply/ Kit Ply/ Century Ply make with necessary screws and bright finished stainless steel piano hinges, complete upto all floor level including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.60	Per Square meter	2210.00	3536.00	Rupees Three Thousand Five Hundred & Thirty Six Only
7.00	Providing and fixing 0.7 mm/ (Zero point seven millimetre) to 0.8 mm (Zero point eight millimetre) thick coloured or plain lamination sheet of Greenlam/ century ply / kit ply or its equivalent make on boards/ply wood sheets with approved adhesive and nails etc complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	5.12	Per Square meter	1091.00	5586.00	Rupees Five Thousand Five Hundred & Eighty Six Only
8.00	Providing and fixing bright /matt finished Stainless steel handles (size 165mm), ISI marked, with necessary screws etcetera complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.00	Per Square meter	440.00	3520.00	Rupees Three Thousand Five Hundred & Twenty Only

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
9.00	Providing and fixing Triple strip vertical type magnetic catcher of approved quality (Hettich/Godrej) in cupboard / ward robe shutters, including fixing with necessary screws etcetera complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	8.00	Per Square meter	93.00	744.00	Rupees Seven Hundred & Forty Four Only
10.00	Providing and fixing powder coated telescopic drawer channels 300 mm long with necessary screws etc. in cupboard / ward robe drawer, including fixing with necessary screws etcetera complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.00	Per Square meter	361.00	1444.00	Rupees One Thousand Four Hundred & Forty Four Only
11.00	Providing and fixing aluminium sliding door bolts 250x16mm, ISI marked Powder coated aluminium (minimum thickness of powder coating 50 micron) , transparent or dyed to required colour or shade, with nuts and screws etcetera complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	2.00	Each	289.00	578.00	Rupees Five Hundred & Seventy Eight Only
12.00	Providing and fixing aluminium tower bolts 200x10mm, ISI marked Powder coated aluminium (minimum thickness of powder coating 50 micron) transparent or dyed to required colour or shade, with necessary screws etcetera complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	6.00	Each	105.00	630.00	Rupees Six Hundred & Thirty Only
13.00	Providing and fixing aluminium tower bolts 150x10mm, ISI marked Powder coated aluminium (minimum thickness of powder coating 50 micron) transparent or dyed to required colour or shade, with necessary screws etcetera complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	4.00	Each	90.00	360.00	Rupees Three Hundred & Sixty Only
14.00	Providing and fixing aluminium handles 200mm, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etcetera complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	9.00	Each	92.00	828.00	Rupees Eight Hundred & Twenty Eight Only
15.00	Providing and fixing P.V.C. waste semi rigid pipe for sink or wash basin including P.V.C. waste fittings complete 32mm (thirty two millimetre) dia of Supreme /Fenolax make including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	Each	143.00	143.00	Rupees One Hundred & Forty Three Only
16.00	Providing and fixing Stainless Steel Hanger complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	Each	551.00	1102.00	Rupees One Thousand One Hundred & Two Only
17.00	Providing and fixing Stainless Steel towel ring complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	Each	1907.00	1907.00	Rupees One Thousand Nine Hundred & Seven Only
18.00	Providing and fixing glass shelf with edges round off 600x120 mm, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm long screws, rawl plugs etc., complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	Each	2403.00	2403.00	Rupees Two Thousand Four Hundred & Three Only
19.00	Providing and fixing corner glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm long screws, rawl plugs etc., complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	Each	1621.00	1621.00	Rupees One Thousand Six Hundred & Twenty One Only
20.00	Providing and fixing Chromium Plated soap Dish with CP Brass bracket fixed to wooden cleat with C p brass Screw complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	Each	1100.00	2200.00	Rupees Two Thousand Two Hundred Only
21.00	Providing and fixing Chromium Plated liquid soap dispenser with CP Brass bracket fixed to wooden cleat with C p brass Screw complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	Each	659.00	659.00	Rupees Six Hundred & Fifty Nine Only
22.00	Providing and fixing Chromium Plated Tumble Holder with CP Brass bracket fixed to wooden cleat with C p brass Screw complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.00	Each	731.00	2924.00	Rupees Two Thousand Nine Hundred & Twenty Four Only
23.00	Providing and fixing uplasticised PVC connection pipe with brass unions 45 cm length 15 mm nominal bore including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	5.00	Each	110.00	550.00	Rupees Five Hundred & Fifty Only

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
24.00	Providing and fixing Chromium Plated grating of approved quality and colour including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	Each	154.00	308.00	Rupees Three Hundred & Eight Only
25.00	Providing and fixing Chromium Plated waste coupling for wash basin and sink, of approved quality and colour including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	Each	100.00	100.00	Rupees One Hundred Only
Total in Figures					99628.00	Rupees Ninety Nine Thousand Six Hundred & Twenty Eight Only
Quoted Rate in Figures					Excess (+)	
					Less (-)	


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

(7) (16)

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana					Estimated Cost Rs	99125.00
Name of work:- Restoration of Rain Damages on Handola to Jaghatkhana Km 0/000 to 3/390 (SH:- Hiring of Tipper under Section Bihru)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	One Month
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Hiring of Tipper 5.5 cum capacity having lift system for carriage of meterial to different site of work eith in all leads and lifts to the entire satisfaction of the Engineer In-charge. The tipper should work minimum 8.00(Eight hours) from 9.00 A.M. to 5.00P.M. dally. Any loss to public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel of the tipper, driver and repair work shall have to be bome by the contractor /owner. The daily log book wiil be maintained at site which should be duly verified by the Engineer-in charge.. The rate includes octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	32.50	Per Day	3050.00	99125.00	Rupees Ninety Nine Thousand One Hundred & Twenty Five Only
Total in Figures					99125.00	Rupees Ninety Nine Thousand One
Qouted Rate in Figures		Excess (+)				
		Less (-)				


Executive Engineer
Bangana Division
HP.PWD.Bangana