HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

E-Mail id-ee-bil2-hp@nic.in
Phone No.01978-222550

SHORT TERM TENDER NOTICE

Sealed items rates tender for the following works are hereby invited by the Executive Engineer, Bilaspur Division No.II, HP. PWD., Bilaspur (H.P) from the eligible contractors of the appropriates class registered in HP.PWD., as per revised enlistment rules so as to reach in the office undersigned on 16.01.2026 upto 10.30AM and will be opened on the same day at 11.00AM in the presence of intending contractors. The tender application will be received in this office alongwith cash payment on account of cost of tender form and the tender form can be had from this office on dated 15.01.2026 upto 12.30 PM. and will be sale on the same day at 4.00P.M.The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued to contractor on production of proof of enlistment, GST and Pan No.etc. Conditional tender and tender received without earnest money will be rejected straightway. The offer of the tender shall be kept open for 45 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT, other specifications and conditions of the tender can be seen by the contractors in the office of the undersigned on any working day during the office hours.

S. No.	Name of work	Estimated of cost	Earnest Money	Cost of form	Time limit
1	Restoration of Rain Damages on Sh.Naina Devi Ji Bhakra road Km.0/00 to 37/300(SH:- Construction of B/Wall at RD.1/731.25 to 1/735).	Rs.95,172/-	Rs.2,000/-	Rs.350/-	Three Months
2	Restoration of Rain Damages on Sh.Naina Devi Ji Bhakra road Km.0/00 to 37/300(SH:- Construction of B/Wall at RD.1/738.75 to 12/742.50).	Rs.95,159/-	Rs.2,000/-	Rs.350/-	Three Months
3	Restoration of Rain Damages on link road from Swahan to Village Dolra Km.0/00 to 1/200(SH:-Construction of Hume pipe culvert at RD.0/165).	Rs.96,027/-	Rs.2,000/-	Rs.350/-	Three Months
4.	Restoration of Rain Damages on Sh.Naina Devi Ji Bhakra road Km.0/00 to 37/300(SH:- Construction of Catchpit wall of hume pipe culvert at RD.1/743.75)).	Rs.94,347/-	Rs.1,900/-	Rs.350/-	Three Months
5	Restoration of Rain djamages on link road Beherera Dabat Km.0/00 to 4/500 (SH:- Hiring of Excavator cum loader/JCB & Tractor with trolley for removal of slips, dressing of berms/clearance of drains in Km.0/00 to 4/500)for the year 2025-26 Job No.28	Rs.98,994/-	Rs.2,000/-	Rs.350/-	One Month
6	Restoration of Rain damages on link road Makri Bariwala road Km.0/00 to 4/500 (SH:- Hiring of Excavator cum loader/JCB & Tractor with trolley for removal of slips, at RD.0/000 to 2/000)for the year 2025-26 Job No.27	Rs.98,994/-	Rs.2,000/-	Rs.350/-	One Month
7	A/R & M/O Ghawandal to Sh.Naina Devi Ji Temple road Km.0/00 to 3/855(SH:-Maintenance of Earthen Shoulder and Construction of unlined surface drain in Km.2/030 to 2/750)	Rs.99,330/-	Rs.2,000/-	Rs.350/-	One Month
8	Restoration of Rain djamages on link road Khal Tibba road Km.0/00 to 7/00 (SH:- Hiring of Excavator cum loader/JCB & Tractor with trolley for removal of slips, at RD.0/000 to 2/000)for the year 2025-26 Job No.29	Rs.99,849/-	Rs.2,000/-	Rs.350/-	One Month
9	A/R & M/O Ghawandal to Sh.Naina Devi Ji Temple road Km.0/00 to 3/855(SH:-Maintenance of Earthen Shoulder and Construction of unlined surface drain in Km.2/850 to 3/500)	Rs.99,840/-	Rs.2,000/-	Rs.350/-	One Month
10	A/R & M/O Ghawandal to Sh.Naina Devi Ji Temple road Km.0/00 to 3/855(SH:-Maintenance of Earthen Shoulder and Construction of unlined surface drain in Km.1/060 to 2/000)	Rs.99,555/-	Rs.2,000/-	Rs.350/-	One Month
11	Restoration of Rain Damages on various roads under Kothipura Section & Chharol Section under Bilaspur Sub-Division No.III,HP.PWD.,Bilaspur(SH:-Hiring of Excavator cum loader/JCB & Tipper for removal of slips at various RDs) for the year 2025-26 Job No.4	Rs.99,473/-	Rs.2,000/-	Rs.350/-	One Month
12	Restoration of Rain Damages on various roads under Bilaspur Sub-Division No.III(Deoth Section)(SH:-Supplying of mixed material bitumenious concrete at HMP).	Rs.99,425/-	Rs.2,000/-	Rs.350/-	One Month
13	A/R & M/O various roads under Bilaspur Sub-Division No.III(SH:-Supplying and stacking at site of work crushed stone aggregate, 10mm to 12.5mm, 40mm nominal size and sand)	Rs.99,984/-	Rs.2,000/-	Rs.350/-	Three Months
14	Repair & Maintenance on various road under Bilaspur Sub-Division No.III(SH:-Supplying of mixed material bitumenious concrete at HMP)	Rs.99,910/-	Rs.2,000/-	Rs.350/-	One Month

Certified that tenders are being called for due to exigencies of works in the public interest.

Terms and Conditions:-

1. The Contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason.
3. The Contractor/firm must have his registration and GST No. The copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No.II, HP.PWD, Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be rejected straight way.
5. The contractor/ Firms are requested to insert the rate of each item both in words and in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.

No.PW/NBT/CB/Tender-State/EA-1/2025- 12466-74 Dated:- 09/01/2026

Copy forwarded to the following for information and necessary action to:-

1. The Engineer-in-Chief, HP.PWD, Nirman Bhawan Nigam Vihar Shimla-2.
2. The Superintending Engineers,10th Circle, HP. PWD., Bilaspur.
3. The Executive Engineers (IT) O/o Engineer-in-Chief, HP.PWD., Shimla through email-ceict-pwd-shi@hp.gov.in & cc-pwd-hp@nic.in for uploading the same on HP.PWD web portal.
4. The Assistant Engineer,HP.PWD., Sub-Division Swarghat/ Sh.Naina Devi /No.III Bilaspur.
5. Drawing Branch in this office/ Notice Board.

Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.

	SCHEDULE OF QUANTITY.	Estimated cost:- Rs.95,172/-Only.					
		Earnest Money :- Rs.2,000/- Only.					
		Time:- Three Months.					
NAME OF WORK:- Restoration of Rain Damages on Sh. Naina Devi ji Bhakra road km 0/00 to 37/300 (SH:- Construction of B/wall at Rd 1/731.25 to 1/735)							
Sr No	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.16	cubic metre			Per cubic metre	
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary roacks including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.15	cubic metre			Per cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : Six graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.61	Cubic metre			Per Cubic metre	
4	Providing weepholes in brick masonry/stone masonary/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204. 3.7.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.00	Nos.			Each	
	Total:-						

Executive Engineer,
Bilaspur Division No. 2
HP. PWD., Bilaspur

	SCHEDULE OF QUANTITY.	Estimated cost:- Rs.95,159/-Only.					
		Earnest Money :- Rs.2,000/- Only.					
		Time:- Three Months.					
NAME OF WORK:- Restoration of Rain Damages on Sh. Naina Devi ji Bhakra road km 0/00 to 37/300 (SH:- Construction of B/wall at Rd 1/738.75 to 1/742.50)							
Sr No	Description of items.	Quantity		Rates in Figure.	Rates in Words.	Unit	Amount
1	2	3		4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.16	cubic metre			Per cubic metre	
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary roacks including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.11	cubic metre			Per cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : Six graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.61	Cubic metre			Per Cubic metre	
4	Providing weepholes in brick masonry/stone masonary/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204. 3.7.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.00	Nos.			Each	
	Total:-						

Executive Engineer,
Bilaspur Division No. I
HP. PWD., Bilaspur(H.P.)

	SCHEDULE OF QUANTITY.	Estimated cost:- Rs.96,027/-Only.
		Earnest Money :- Rs.2,000/- Only.
		Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages on link road from Swahan to village Dolra km 0/00 to 1/200 (SH:- Construction of Hume pipe culvert at RD 0/165)

Sr No	Description of items.	Quantity		Rates in Figure.	Rates in Words.	Unit	Amou
1	2	3		4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary roacks including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.14	cubic metre			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : Six graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.26	Cubic metre			Per Cubic metre	
3	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement :Two fine sand) including testing of joints etc. complete 450 mm (Four Hundred Fifty Millimeter) dia. R.C.C. pipe including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.00	Running Meter			Per Running Meter	
	Total:-						

Executive Engineer,
Bilaspur Division No
HP. PWD., Bilaspur

	SCHEDULE OF QUANTITY.	Estimated cost:- Rs.94,347/-Only.
		Earnest Money :- Rs.1,900/- Only.
		Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages on Sh. Naina Devi ji Bhakra road km 0/00 to 37/300 (SH:- Construction of Catchpit wall of hume pipe culvert at RD 1/743.75)

Sr No	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary roacks including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.13	cubic metre			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : Six graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.30	Cubic metre			Per Cubic metre	
3	Providing weepholes in brick masonry/stone masonary/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204. 3.7.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.00	Nos.			Each	
	Total:-						

Executive Engineer,
Bilaspur Division No.
HP. PWD., Bilaspur (H

	SCHEDULE OF QUANTITY.		Estimated Cost:- Rs.=98,994 /-Only.
			Earnest Money:- Rs.= 2,000/-Only.
			Time:- One Month.

Name of work :- Restoration of Rain damages on link road Beherera-Dabat km 0/00 to 4/500 (SH:- Hiring of Excavator cum loader/JCB & Tractor with trolley for removal of slips, dressing of berms/ clearance of drains in km 0/00 to 4/500) For the Year 2025-26 Job No.-28

Sr No.	Description of items.	Quantity		Rate In		Unit	Amount
				In Figure	In words.		
1	2	3	4	5	6	7	8
1	Providing one number Exacavator cum loader/JCB in good condition on hire bases at site of work for removal of slip.The rate includes octori, malkhana, toll tax, Goods-Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	62.00	Hours			Per Hours	
2	Providing one number Tractor with trolley in good condition. on hire basis having capacity of 3 to 5 tonne per trip for carriage of material i.e aggregate , soil , mud , boulders etc with in all leads and lifts as per direction of Engineer-In-Charge .The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	40.00	Hours			Per Hours	
	Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Exacavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
i)	The One Number Tractor with trolley will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fullly responsible for any loss/damages to any private /Govt. Property during the execution of work						
	Total						

Executive Engineer,
Bilaspur Division No. 2
HP. PWD., Bilaspur (H.P.)

	SCHEDULE OF QUANTITY.		Estimated Cost:- Rs.=99,849 /-Only.
			Earnest Money:- Rs.= 2,000/-Only.
			Time:- One Month.

Name of work :- Restoration of Rain damages on link road Makri Bariwala road km 0/00 to4/500 (SH:- Hiring of Excavator cum loader/JCB & Tractor with trolley for removal of slips at Rd 0/000 to 2/000) For the Year 2025-26 Job No.-27

Sr No.	Description of items.	Quantity		Rate In		Unit	Amoun
				In Figure	In words.		
1	2	3	4	5	6	7	8
1	Providing one number Exacavator cum loader/JCB in good condition on hire bases at site of work for removal of slip.The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output.by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	67.00	Hours			Per Hours	
2	Providing one number Tractor with trolley in good condition. on hire basis having capacity of 3 to 5 tonne per trip for carriage of material i.e aggregate , soil , mud , boulders etc with in all leads and lifts as per direction of Engineer-In-Charge .The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	32.00	Hours			Per Hours	
	Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Exacavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
i)	The One Number Tractor with trolley will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fullly responsible for any loss/damages to any private /Govt. Property during the execution of work						
	Total						

Executive Enginee
Bilaspur Division N
HP. PWD., Bilaspu

	SCHEDULE OF QUANTITY.	Estimated cost:- Rs.99,330/-Only.					
		Earnest Money :- Rs.2,000/- Only.					
		Time:- One Month.					

NAME OF WORK:- A/R & M/O Ghawandal to Sh. Naina Devi Ji Temple road km 0/00 to 3/855 (SH:- Maintenance of Earthen Shoulder and Construction of unlined surface drain in km 2/030 to 2/750)

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification clause 1903 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge.The rate includes octori, malkhana, toll tax, Goods and Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1100.00	Cubic Meter			Per Cubic Meter	
2	Construction of unlined surface drains of average cross-sectional area 0.20 sqm in soil to specified lines, grades, level and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50m (average lead 25m) as per Technical Specification Clause 307 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge.The rate includes octori, malkhana, toll tax, Goods and Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	330.00	Cubic Meter			Per Cubic Meter	
	Total						

Executive Engineer,
Bilaspur Division No. 2
HP. PWD., Bilaspur (HP)

	SCHEDULE OF QUANTITY.		Estimated Cost:- Rs.=99,849 /-Only.
			Earnest Money:- Rs.= 2,000/-Only.
			Time:- One Month.

Name of work :- Restoration of Rain damages on link road Khal Tibba road km 0/00 to 7/00 (SH:- Hiring of Excavator cum loader/JCB & Tractor with trolley for removal of slips at 0/000 to 2/000) For the Year 2025-26 Job No.-29

Sr No.	Description of items.	Quantity		Rate In		Unit	Amou
				In Figure	In words.		
1	2	3	4	5	6	7	8
1	Providing one number Exacavator cum loader/JCB in good condition on hire bases at site of work for removal of slip.The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	67.00	Hours			Per Hours	
2	Providing one number Tractor with trolley in good condition. on hire basis having capacity of 3 to 5 tonne per trip for carriage of material i.e aggregate , soil , mud , boulders etc with in all leads and lifts as per direction of Engineer-In-Charge .The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	32.00	Hours			Per Hours	
	Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Exacavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
i)	The One Number Tractor with trolley will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fullly responsible for any loss/damages to any private /Govt. Property during the execution of work						
	Total						

Executive Engineer,
Bilaspur Division No.
HP. PWD., Bilaspur (H

	SCHEDULE OF QUANTITY.	Estimated cost:- Rs.99,840/-Only.
		Earnest Money :- Rs.2,000/- Only.
		Time:- One Month.

NAME OF WORK:- A/R & M/O Ghawandal to Sh. Naina Devi Ji Temple road km 0/00 to 3/855 (SH:- Maintenance of Earthen Shoulder and Construction of unlined surface drain in km 2/850 to 3/500)

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification clause 1903 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge.The rate includes octori, malkhana, toll tax, Goods and Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1200.00	Cubic Meter			Per Cubic Meter	
2	Construction of unlined surface drains of average cross-sectional area 0.20 sqm in soil to specified lines, grades, level and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50m (average lead 25m) as per Technical Specification Clause 307 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge.The rate includes octori, malkhana, toll tax, Goods and Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	240.00	Cubic Meter			Per Cubic Meter	
	Total						

Executive Engineer,
Bilaspur Division No.
HP. PWD., Bilaspur(H)

	SCHEDULE OF QUANTITY.	Estimated cost:- Rs.99,555/-Only.
		Earnest Money :- Rs.2,000/- Only.
		Time:- One Month.

NAME OF WORK:- A/R & M/O Ghawandal to Sh. Naina Devi Ji Temple road km 0/00 to 3/855 (SH:- Maintenance of Earthen Shoulder and Construction of unlined surface drain in km 1/060 to 2/000)

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification clause 1903 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge.The rate includes octori, malkhana, toll tax, Goods and Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1165.00	Cubic Meter			Per Cubic Meter	
2	Construction of unlined surface drains of average cross-sectional area 0.20 sqm in soil to specified lines, grades, level and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50m (average lead 25m) as per Technical Specification Clause 307 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge.The rate includes octori, malkhana, toll tax, Goods and Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	270.00	Cubic Meter			Per Cubic Meter	
	Total						

Executive Engineer,
Bilaspur Division No.
HP PWD, Bilaspur

	SCHEDULE OF QUANTITY.		Estimated Cost:- Rs.=99,473 /-Only.
			Earnest Money:- Rs.= 2,000/-Only.
			Time:- One Month.

Name of work :- Restoration of Rain Damages on various roads under Kothipura Section& Chharol Section under Bilaspur Sub-Division No.-III HPPWD Bilaspur (SH:- Hiring of Excavator cum loader/JCB & Tipper for removal of slips at Various RDs) For the Year 2025-26 Job No.-4

Sr No.	Description of items.	Quantity		Rate In		Unit	Amount
				In Figure	In words.		
1	2	3	4	5	6	7	8
1	Providing one number Exacavator cum loader/JCB in good condition on hire bases at site of work for removal of slip.The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	75.00	Hours			Per Hours	
2	Providing one number Tipper in good condition. on hire basis having capacity of 5.5 cum or 10 tonne per trip for carriage of material i.e aggregate , soil , mud , boulders etc with in all leads and lifts as per direction of Engineer-In-Charge.The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.00	Hours			Per Hours	
	Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Exacavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
i)	The One Number Tipper will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fullly responsible for any loss/damages to any private /Govt. Property during the execution of work						
	Total						

Executive Enginee
Bilaspur Division N
HP. PWD., Bilaspur

	SCHEDULE OF QUANTITY.		Estimated Cost:- Rs.=99,425/-Only.
			Earnest Money:- Rs. =2,000/- only
			Time:- One Month.

Name of work :- Restoration of Rain damages on various roads under Bilaspur Sub-Division No.-III (Deoth Section) (SH:- Supplying of mixed material bitumenious concrete at HMP)

Sr.No	Sub-head and item of work.	Quantity	Rate		Unit	Amoun
			Figure	words.		
1	Providing Mixed material for bitumenious concrete with 100-120 TPH batch type nearest **Hot Mix plant** producing an average output of 75 Tonnes per hour using crushed aggregates of specified grading ,premixed with bitumenious binder@ 5.4 to 5.6 percent of mix as per Morth specication clause No.503 complete in all respects The bitumenious, aggregate,sand and filler will be arranged by the supplier in all leads and lifts including loading of mixed material at **Hot Mix plant .** The mixed material will be carried by departmental tipper and work will be executed as per direction and entire satisfaction of Engineer in charge.	10.25			per cubic metre	
				Total Rs.		

Executive Engineer,
Bilaspur Division No
HP. PWD., Bilaspur

	SCHEDULE OF QUANTITY.	Estimated cost:- Rs.99,984/- Only.
		Earnest Money :- Rs.2,000/- Only
		Time:- Three Months.

NAME OF WORK:- A/R & M/O various roads under Bilaspur Sub-Division No.-III (SH:-Supplying and Stacking at site of work crushed stone aggregate,10mm to 12.5mm,40 mm nominal size and sand)

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Supplying and stacking at site broken/ crushed stone aggregate of hard stone of following nominal size free from disintegrated, dataterious and orginic materials, stacking along road side uniform stacked including carriage of materials, with in all leads and lift as per direction by the Engineer in charge. The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.						
I)	10 mm (Ten millimeter) to 12.5 mm (Twelve point Five Millimeter) nominal size	22.00	Cubic Metre	1463.00	Rs.One thousand Four Hundred Sixty Three only	Per Cubic Metre	32186.0
ii)	40 mm (forty millimeter) nominal size	37.50	Cubic Metre	1505.00	Rs. One Thousand Five Hundred Five only.	Per cubic metre	56438.0
2	Supplying and stacking at site coarsed sand of approved quality (conforming to HPPWD specification 1990 Vol.-1) clean and freee from in jurcous soft and floty persion in proper stacks including carriage of materials, with in all leads and lift and as per direction by the Engineer in charge. The rates includes octroi,royality ,Malkana toll tax goods and serivice tax ,building and other construction work, welfare cess, royality of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00	Cubic Metre	1420.00	Rs. One thousand Four hundred Twenty only.	Per cubic metre	11360.0
	Total:-						**99984.0**

Executive Engineer,
Bilaspur Division No.
HP PWD., Bilaspur

	SCHEDULE OF QUANTITY.		Estimated Cost:- Rs.=99,910/-Only.
			Earnest Money:- Rs. =2,000/- only
			Time:- One Month.

Name of work :- Repair and Maintenance on various road under Bilaspur Sub- Division No.-III (SH:- Supplying of mixed material bitumenious concrete at HMP).

Sr.No	Sub-head and item of work.	Quantity	Rate		Unit	Amour
			Figure	words.		
1	Providing Mixed material for bitumenious concrete with 100-120 TPH batch type nearest **Hot Mix plant** producing an average output of 75 Tonnes per hour using crushed aggregates of specified grading ,premixed with bitumenious binder@ 5.4 to 5.6 percent of mix as per Morth specication clause No.503 complete in all respects The bitumenious, aggregate,sand and filler will be arranged by the supplier in all leads and lifts including loading of mixed material at **Hot Mix plant .** The mixed material will be carried by departmental tipper and work will be executed as per direction and entire satisfaction of Engineer in charge.	10.30			per cubic metre	
				Total Rs.		

Executive Engineer,
Bilaspur Division No
HP. PWD., Bilaspur