HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

"NOTICE INVITING TENDERS"

Sealed item/ percentage rate tender on form NO. 6&8 are hereby invited by the Executive Engineer, Bilaspur Division No. I, HP.PWD., Bilaspur on behalf of Governor of Himachal Pradesh from the approved and eligible contractors enlisted in PWD Department so as to reach in this office on or before **_15/01/2026** up to 10.30 A.M. and will be opened on the same day at **11.00 A.M.** in the presence of the intending contractors or their authorized representatives who may like to be present. If it happens to be holiday on that day tenders will be opened on next working day. The application for obtaining the tender forms will be received up to **12/01/2026** up to 5.00 PM and the tender form can be had from this office on **13/01/2026** during the office hours.

The Earnest money in the shape of National Saving Certificate Time deposit Accounts/FDR of any Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, Division No. I., HP.PWD., Bilaspur must be accompanied with each application for obtaining the tenders. The tender application received without earnest money /cost of tender forms will similarly be rejected. The undersigned reserves the right to reject the tenders without assigning any reason.

Sr. No	Name of work	Estimated cost (In Rs.)	Earnest Money (In Rs.)	Cost of form (In Rs.)	Time limit
1	Repair and restoration of rain damages on NH-21 to Lower Lakhanpur road Distt. Bilaspur. (SH: Construction of edging wall at RD 0/170 to 0/189.75)	99,957/-	2000/-	350	One month
2	Repair and restoration of rain damages on NH-21 to Lower Lakhanpur road Distt. Bilaspur. (SH: Construction of edging wall at RD 0/189.75 to 0/209.50)	99,957/-	2000/-	350	One month
3	C/O link road Khandui Dangu road KM 0/0 to 2/500. (SH: P/L soling and wearing at RD 1/500 to 1/530).	49,759/-	1000/-	350	One month
4.	Supply and installation of UPS and Printer (Under Deposit work) Job No.1.	99,660/-	2000/-`	350	One month
5	Supply and installation of UPS and Printer (Under Deposit work) Job No.2.	99,660/-	2000/-	350	One month
6	Repair and restoration of rain damages on link road from Kandrour Bamta to Viilage Behal Kandela road KM 0/0 to 0/400. (SH: C/O B/Wall at RD 0/100 to 0/119.50).	99,917/-	2000/-	350	One month
7	Restoration of rain damages on link road Harizan Basti Seri Balohi KM 0/0 to 1/0 (SH: C/O B/Wall at RD 0/250 to 0/258).	99,258/-	2000/-	350	One month
8	Repair and maintenance of PWD Gang Hutt at Harnora. (S: P/F structural steel work and pre-painted roofing in varandah.)	95,690/-	2000/-	350	One month
9	C/o link road from Chabra to House of Sh. Babu Ram GP Nichli Bhater Tehsil Sadar Distt. BilaspurKM 0/0 to 0/500. (SH: P/L soling and interlocking paver block 80 mm thick at RD 0/171.20 to 0/181.20)	56,963/-	1200/-	350	One month
10	Restoration of rain damages on various roads under Kuthera Sub Division (SH: Hiring of tipper for removal of slips at various RDs)	99,000/-	2000/-	350	One month

11	C/O link road Dali to Jungle Jhaleda KM 0/0 to 1/750. (SH: Removal of formation deficiency KM 1/390 to 1/480.	99,856/-	2000/-	350	One month
12.	Restoration of rain damages on various roads under Kuthera Sub Division (SH: C/O unlined drain at various roads.)	99,977/-	2000/-	350	One month
13.	A/R & M/O Circuit House Bilaspur. (SH: Repair of furniture sofa and emulsion interior side suit No. 11,12,12 and Hall.)	99,659/-	2000/-	350	One month
14.	Restoration of rain damages on various roads under Kuthera Sub Division (SH: Hiring of Excavator-cum-loader/ Hydraulic Excavator.)	99,000/-	2000/-	350	One month
15	Restoration of rain damages on various roads under Kuthera Sub Division (SH: Hiring of Excavator-cum-loader/ Hydraulic Excavator.)	99,000/-	2000/-	350	One month
16.	Restoration of rain damages on various roads under Bilaspur Sub Division No. II (SH: C/O unlined drain at various roads.)	99,945/-	2000/-	350	One month
17	Restoration of rain damages on Patta Morsinghi road KM 0/0 to 11/070. (SH: C/O B/Wall at RD 3/900 to 3/907.40)	98,491/-	2000/-	350	One month
18	Restoration of rain damages on Harlog Hawan Trifalghat road KM 0/0 to 13/500. (SH: C/O V-shape drain at RD 6/565 to 6/615)	98,284/-	2000/-	350	One month

1. **Certified that the tenders for above said works are being called of emergent nature in exigency of public interest.**

TERMS & CONDITIONS: -

1. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
2. The contractor will not have more than two works in hand at the time of tender and only up to completion of work satisfactorily including adherence to quality future work will be awarded to him. All undertaking that he is not having more than two works in hand must be recorded in the application, failing which application of such contractor shall be rejected without any notice to him.
3. Earnest money should be accompanied with application. Application without earnest money will not be entertained.
4. The photo copy of Pan Number/GST/EPF/Registration should be attached with the application otherwise tender form will not be issued.

Executive Engineer,
Bilaspur, Division No.I
HP.PWD, Bilaspur.
Dated :- 07/01/2026

NO.PW-BLP-I-CB-EA-I-Tender/ 2025- 16923-40

Copy forwarded to the following for information please.

1. The Engineer-in-Chief, HP.PWD; Shimla-I.
2. The Chief Engineer (HZ) HP.PWD, Hamirpur.
3. The Superintending Engineer, 10th Circle, HP.PWD, Bilaspur .
4. The Executive Engineer (IT) O/o the Engineer-in-Chief, HP.PWD, Shimla through email:- cc-pwd-hp@nic.in alongwith copies of Schedule of quantities for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. All the contractors as per record of this office.
7. Accounts Branch/ Drawing Branch/Supdt. in this office.
8. Notice Board.

Executive Engineer,
Bilaspur, Division No.I,
HP.PWD, Bilaspur.

	SCHEDULE OF QUANTITY.	Estimated cost Rs. = 99,957/-only Earnest Money Rs. = 2,000/- only. Time Limit. = One Month

Name of Work:- Repair and Restoration of rain damages on NH-21 to Lower Lakhanpur road Distt. Bilaspur. (SH:- Construction of edging wall at RD. 0/170 to 0/189.75).

Sr No	Description of items.	Qty.		Rates		Amount
				In Figure	In words	
1	2	3	4	5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m,(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.38	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated plain/reinforced concrete 1:3:6 (One cement : three sand :six graded crushed stone aggregate 40 mm (forty milimetre) in open foundations complete as per drawings and technical specifications clause 802,803,1202 & 1203 . plain cement concrete grade M-10 (M-ten) Nominal mix including cost of form work and curing complete and including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	14.81	Per Cubic metre			
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	11.26	Per Cubic metre			
		TOTAL				

Executive Engineer
Bilaspur Division No.1
HP.PWD, Bilaspur

(2)

	DRAFT SCHEDULE OF QUANTITY.	Estimated cost Rs. = 99,957/-only Earnest Money Rs. = 2,000/- only. Time Limit. = One Month

Name of Work:- Repair and Restoration of rain damages on NH-21 to Lower Lakhanpur road Distt. Bilaspur. (SH:- Construction of edging wall at RD. 0/189.75 to 0/209.50).

Sr No	Description of items.	Qty.		Rates		Amount
				In Figure	In words	
1	2	3	4	5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m,(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.38	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated plain/reinforced concrete 1:3:6 (One cement : three sand :six graded crushed stone aggregate 40 mm (forty milimetre) in open foundations complete as per drawings and technical specifications clause 802,803,1202 & 1203 . plain cement concrete grade M-10 (M-ten) Nominal mix including cost of form work and curing complete and including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	14.81	Per Cubic metre			
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	11.26	Per Cubic metre			
		TOTAL				

Executive Engineer
Bilaspur Division No.1
HP.PWD, Bilaspur

Schedule of Quantity

Estimated cost Rs.= 49,759/-only	
Earnest Money Rs. = 1,000/- only.	
Time Limit. = One month.	

Name of work:- Construction of link road Khandui Dhangu road Km. 0/00 to 2/500. (SH:- P/L Solling and wearing at RD. 1/500 to 1/530).

Sr No.	Description of items.	Qty.	Unit	Rate		Amount
				In Figure	In words	
1	2	3	4	5	6	8
1	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne (Eight to twelve tonne) capacity after excavating earth to an average of 22.5 cm (Twenty two point five centimetre) depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earthwith lead upto 50 m (Fifty metres). including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	100.50	Per Square Metre			
2	Supplying and stacking at site. 90 mm to 45 mm (Ninety to forty five milimetre) size stone aggregate. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.05	Per Cubic metre			
3	Supplying and stacking at site. 63 mm to 45 mm (Sixty three to forty five milimetre) size stone aggregate. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.86	Per Cubic metre			
4	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road/vibratory roller 8-10 tonne (Eight to ten tonne) capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density as per technical specification clause 405.. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.91	Per Cubic metre			
	TOTAL					

Executive Engineer
Bilaspur Division No.1
HP.PWD, Bilaspur

(4)

Schedule of Quantity	Estimated cost Rs. = 99,660/- only. Earnest Money Rs. = 2000/- only. Time Limit. = One month

Name of work:- Supplying and installation of UPS and Printer). (Under Deposit work) Job No. 1

Sr. No.	Description of items.	Quantity		Rate		Unit	Amount
				In Figure	In words		
1	2	3		4	5	6	7
1	**Printer:- HP Laser MFP M1188FNW** with printer, Scan & copy and fax A4 size paper, Printing, Printing speed 20 PPM, Resolution 1200 dpi Memory 128 MB, Scan resolution 1200dpi memory ADF, wireless connectivity, USB 2.0, paper tray capacity 150 pages with one year warranty. (Expect consumable & breakage & burnt items). as per the provisions of the manufacturing company. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00				Each	
2	**600VA Offline UPS** (Numberic or equivalent) with SMF batteries to provide 10 min. backup:- with 3 years carry in warranty. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00				Each	
	TOTAL					**Total**	

Executive Engineer
Bilaspur Division No.1
HP.PWD, Bilaspur

(5)

Schedule of Quantity	Estimated cost Rs. = 99,660/- only. Earnest Money Rs. = 2000/- only. Time Limit. = One month

Name of work:- Supplying and installation of UPS and Printer). (Under Deposit work) Job No. 11

Sr. No.	Description of items.	Quantity		Rate		Unit	Amount
				In Figure	In words		
1	2	3		4	5	6	7
1	**Printer:- HP Laser MFP M1188FNW** with printer, Scan & copy and fax A4 size paper, Printing, Printing speed 20 PPM, Resolution 1200 dpi Memory 128 MB, Scan resolution 1200dpi memory ADF, wireless connectivity, USB 2.0, paper tray capacity 150 pages with one year warranty. (Expect consumable & breakage & burnt items). as per the provisions of the manufacturing company. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00				Each	
2	**600VA Offline UPS** (Numberic or equivalent) with SMF batteries to provide 10 min. backup:- with 3 years carry in warranty. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00				Each	
	TOTAL					**Total**	

Executive Engineer
Bilaspur Division No.1
HP,PWD, Bilaspur

(6)

	SCHEDULE OF QUANTITY.	Estimated cost Rs. = 99,917/-only Earnest Money Rs. = 2000/- only. Time Limit. = One Month

Name of Work:- Restoration of rain damages on link road from Kandrour Bamta to village Behal Kandela road Km. 0/00 to 0/400. (SH:- C/O B/Wall at RD. 0/100 to 0/119.50).

Sr No	Description of items.	Qty.		Rates		Amount
				In Figure	In words	
1	2	3	4	5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m,(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.25	Per Cubic metre			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty milimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.50	Per Cubic metre			
3	Providng weepholes in brick masonary/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.00	Each			
		TOTAL				

Executive Engineer
Bilaspur Division No.1
HP.PWD, Bilaspur

(7)

	SCHEDULE OF QUANTITY.	Estimated cost Rs. = 99,258/-only Earnest Money Rs. = 2000/- only. Time Limit. = One Month

Name of Work:- Restoration of rain damages on link road Harizan Basti Seri Balohi Km. 0/00 to 1/00. (SH:- C/O B/Wall at RD. 0/250 to 0/258).

Sr No	Description of items.	Qty.		Rates		Amount
				In Figure	In words	
1	2	3	4	5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m,(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.40	Per Cubic metre			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty milimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.80	Per Cubic metre			
3	Providng weepholes in brick masonary/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.00	Each			
		TOTAL				

Executive Engineer
Bilaspur Division No.1
HP.PWD, Bilaspur

(9)

Schedule of Quantity

Estimated cost Rs.= 56,963/-only	
Earnest Money Rs. = 1200/- only.	
Time Limit. = One month.	

Name of work :- Construction of link road from Chabra to Houose of Sh. Babu Ram G.P Nichali Bhater Tehsil Sadar Distt. Bilaspur Km. 0/00 to 0/500. (SH:- P/L Soling and interlocking paver block 80mm thick at Rd. 0/171.20 to 0/181.20).

Sr No.	Description of items.	Qty.	Unit	Rate		Amount
				In Figure	In words	
1	2	3	4	5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m,(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre). including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.65	Per Cubic metre			
2	Stone soling properly hand packed filling intersties with kharnja stone and cnsolidation to the required level including spreadly bining material `moorum or earth etc. complete as per HP.PWD specification. 100mm (One hundred Millimeter) spread thickness, including carriage of materials, within all leads and lifts as per dirction of Engineer-in - Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.33	Cubic Meter			
3	Providing and laying mechanically mixed and vibrated plain/reinforced concrete 1:3:6 (One cement : three sand :six graded crushed stone aggregate 40 mm (forty milimetre) in open foundations complete as per drawings and technical specifications clause 802,803,1202 & 1203 . plain cement concrete grade M-10 (M-ten) Nominal mix including cost of form work and curing complete and including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.48	Per Cubic metre			
4	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and weeping extra sand. complete all as per direction of Engineer-in Charge 80 mm thick C.C. paver block of M-50 grade with approved color design and pattern. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.06	Per Square Metre			
	TOTAL					

Executive Engineer
Bilaspur Division No.1
HP.PWD, Bilaspur

10

Schedule of Quantity

Estimated cost Rs. = 99,900/- only.
Earnest Money Rs. = 2000/- only.
Time Limit. = One Month

Name of work :- Resoration of rain damages on various roads under Kuthera Sub Division. (SH:- Hiring of tipper for removal of slips at various roads).

Sr No.	Description of items.	Qty.	Unit	Rate		Amount
				In Figure	In words	
1	Hiring of tipper 5.5 cum capacity having lift system for carriage of material to different site of work with in all leads and lifts to the entire satisfaction of the Engineer-in-Charge. Minimum working hours will be 8 hours per day, if working hours will be less than 8 hours in a day then the rate will be paid proportionately as per actual. The dumping site of material be arranged by the contractor at his own level and no dumping will be allowed along road side or in forest land failing which the contractor will be responsible for any kind of panel action as per rule of Hon'ble court.	22.00	per day			

Executive Engineer
Bilaspur Division No.1
HP.PWD, Bilaspur

(11)

	SCHEDULE OF QUANTITY.	Estimated cost Rs. = 99,856/-only Earnest Money Rs. = 2,000/ only. Time Limit. = One Month

Name of Work:- Construction of link road dfrom Dali to Jangal Jhaleda road Km. 0/00 to 1/750. (SH:-Removal of formation deficiency KM 1/390 to 18480

Sr No	Description of items.	Qty.		Rates		Amount
				In Figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centemere) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (TenPer Square Metre) on plan) including getting out and disposal of excavated earth lead upto 50 m (Fifty metre) and lift upto 1.5 m, (One point five metre) as directed by Engineer-in-charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	605.19	Per Cubic Metre			
	TOTAL					

Executive Engineer
Bilaspur Division No.1
HP.PWD, Bilaspur

(12)

Draft Schedule of Quantity	Estimated cost Rs.= 99,977/-only
	Earnest Money Rs. = 2,000/- only.
	Time Limit. = One month.

Name of work:- Restoration of rain damages on various road under Kuthera Sub Division. (SH:- Construction of unlined drain at various roads).

Sr No.	Description of items.	Qty.	Unit	Rate		Amount
				In Figure	In words	
1	2	3	4	5	6	8
1	Construction of unlined surface drains of average cross-sectional area 0.20 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1544.05	Per Runing Meter			
	TOTAL					

Executive Engineer
Bilaspur Division No.1
HP.PWD, Bilaspur

13

Schedule of Quantity

Estimated cost Rs. = 99,659/- only
Earnest Money Rs. = 2000/- only
Time Limit. = One month

Name of Work:- A/R & M/O PWD Circuit House Bilaspur. (SH:- Repair of furniture sofa and emulsion interior side suit No. 11, 12, 13 & Hall).

Sr No	Description	Qty.	Rates		Unit	Amount
			In Figure	In words		
1	2	3	5	6	7	8
1	Repair of sofas in cushion setting and back with foams and well finished including warnish as per direction of Engineer-in-charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
1.1	Three seater	1.00			Each	
1.2	Single seater	6.00			Each	
2	Removing dry oil bound distemper, water proofing cement paint and like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	433.97			Per Square Metre	
3	Applying Birla white putty wall care putty over plaster surfaces after thoroughly brushing the surface fre mortar drops,duist,loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	303.78			Per Square Meter	
4	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. Two coats. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	433.97			Per Square Meter	

5	Painting one coat(excluding priming coat)on previously painted wood and wood based surfaces with enamel paint brushing to given and even shade including cleaning of all dirt,dust and other foreign matter sand papering and stopping including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	42.27			Per Square Metre	
		TOTAL				

Executive Engineer
Bilaspur Division No.1
HP.PWD, Bilaspur

Draft Schedule of Quantity						Estimated cost Rs. = 99,000/-only. Earnest Money Rs. = 2000/- only. Time Limit. = One Month
Name of work :- Resoration of rain damages on various road under Kuthera Sub Division. (SH:- Hiring of Excavator-cum-loader/Hydraulic Excavator).						
Sr No.	Description of items.	Qty.	Unit	Rate		Amount
				In Figure	In words	
1	Providing one number Excavator cum loader/JCB in good condition on hire bases site of work for removal of slip with in all leades and lifts as per direction of Engineer-in-Charge. The dumping site of material be arranged by the contractor at his own level and no dumping will be allowed along road side or in forest land failing which the contractor will be responsible for any kind of panel action as per rule of Hon'ble court.	90.00	Hours			

Executive Engineer
Bilaspur Division No.1
HP.PWD, Bilaspur

15

Draft Schedule of Quantity	Estimated cost Rs. = 99,000/-only.
	Earnest Money Rs. = 2000/- only.
	Time Limit. = One Month

Name of work :- Resoration of rain damages on various road under Kuthera Sub Division. (SH:- Hiring of Excavator-cum-loader/Hydraulic Excavator).

Sr No.	Description of items.	Qty.	Unit	Rate		Amount
				In Figure	In words	
1	Providing one number Excavator cum loader/JCB in good condition on hire bases site of work for removal of slip with in all leades and lifts as per direction of Engineer-in-Charge. The dumping site of material be arranged by the contractor at his own level and no dumping will be allowed along road side or in forest land failing which the contractor will be responsible for any kind of panel action as per rule of Hon'ble court.	90.00	Hours			

Executive Engineer
Bilaspur Division No.1
HP,PWD, Bilaspur

16

Schedule of Quantity	Estimated cost Rs.= 99,945/-only
	Earnest Money Rs. = 2,000/- only.
	Time Limit. = One month.

Name of work:- Restoration of rain damages on various road under Bilaspur Sub Division No. II. (SH:- Construction of unlined drain at various roads).

Sr No.	Description of items.	Qty.	Unit	Rate		Amount
				In Figure	In words	
1	2	3	4	5	6	8
1	Construction of unlined surface drains of average cross-sectional area 0.20 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1543.55	Per Runing Meter			
	TOTAL					

Executive Engineer
Bilaspur Division No.1
HP.PWD, Bilaspur

(17)

SCHEDULE OF QUANTITY

Estimated Cost =Rs 98491.00
Earnest Money=Rs. 2000-00
Time = one months

NAME OF WORK :- Restoration of Rain Damages on Patta Morsinghi road km 0/0 to 11/070.(Sh:-C/O Breast wall at RD 3/900 To 3/907.40)

Sr No	Description of items.	Quantity		Rates In figure	In words	Unit	Amount
1	2	3		4	5	6	7
1	Earth work in excavation for all type of road Structures as per drawing and technical specificatios clause 305.1 including setting out, construction of shoring and barcing, removal of stumps and other deleterious material and disposal of unservicable material all leads and lift including dressing of sides and bottom and backfilling in trenches with excavated suitable material. up to all depth including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge..	**2.45**	Cubic Metre			Per Cubic Metre	
2	Providing concrete for plain / reinforced concrete clause 802, 803,1202 & 1203. MORD specification 800 & 1200 . curing complete including cost of centring and shuttering in foundation and plinth including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.	**0.00**	Cubic Metre			Per Cubic Metre	
3	Providing and laying cement concrete 1:5:10 (One cement : Five sand : 10 graded stone aggregate) with 15 % plums and curing complete including the cost of form work for plain / reinforced concrete in retaining walls, breast walls, the size of plum should be 150 to 300 mm as per drawing & HP, PWD, technicai specifications . including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge.	**18.64**	Cubic Metre			Per Cubic Metre	
4	Providing weepholes in brick masonery / stone masonary plain reinforced concrete, abutment, wing wall, return wall with 100 mm dia PVC pipe extending, through the full width of the structures with slopes of 1 (V):20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge.	**15.80**	Nos.			Each	

Executive Engineer
Bilaspur Division No.1
HP.PWD, Bilaspur

(18)

Schedule of quantity

Estimated cost Rs.	98284
Earnest Money Rs.	2000.00
Time Limit. = one month	

Name of work:- R/R damages on Harlog,Hawan,Trifalghat road km 0/0 to 13/500.(SH:- Construcation of V-shape drain at Rds.6/565 to 6/615)

Sr No	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In Word		
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten Per Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m,(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.00			Per Cubic Metre	
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 (PCC M-10 Grade 1:3:6) including shuttering and carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge.-	16.50			Per Cubic Metre	

Executive Engineer
Bilaspur Division No.1
HP,PWD, Bilaspur