

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Offline

No. PWD-Da/TA/Tender /2025-26 7595-97
To

Dated: -03-01-2026


The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2

Subject: - Publishing of Tender Notice.

Dear Sir,


Enclosed please find herewith the tender Notice of work as given in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.


Copy forwarded to the Superintending Engineer, 7th Circle,
HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive
Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie


Certificate

Certified that the tenders called vide this office letter No. PWD-
/TA/Tender /2025-26:- 7595-97 dated 03.01.2026 is emergent nature and in Public
interest.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

Certificate

Certified that the tenders called vide this office letter No. PWD-
/TA/Tender /2025-26:- 7595-97 dated 03.01.2026 is emergent nature and in Public
interest.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Offline

"NOTICE INVITING TENDERS"

Sealed Item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Dalhousie Division, HPPWD, Dalhousie on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

1. Date of receipt of application for the tender Form a /w requisite documents:- 09.01.2026 onward (between 2:00 p.m.to 4:30.p.m.)

2. Date of issue/sale of tender form against Cash payment (non refundable). 09.01.2026


The tender shall be received up to 3:00 PM on 12.01.2026 and will be opened on the same day at 3:30 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender will be salad by this office against cash payment as shown below (Non refundable) during the working hours on 09.01.2026

The Earnest Money in the shape of National Saving Certificate/FDR of any Bank in HP duly pledged in favour of Executive Engineer, Dalhousie Division, HPPWD, Dalhousie a must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1.	Restoration of Rain damage on link road to village Bhariyatta km. 0/0 to 2/00 (Village road) (SH:-Construction of PCC Retaining wall at RD 0/150 to 0/165 & 0/350 to 0/370) (Under PDNA-2023)	284912.00	6000.00	350.00	Two months	D & C
2.	Restoration of Rain Damage on various road under HPPWD Division Dalhousie (SH:- Supplying and stacking of Calcium Chloride for spraying on Snow Bounded roads).	120000.00	2500.00	350.00	Two Months	D&C
3.	Restoration of rain Damage due to Digging of road by Jal Shakti Vibhag on Pukhri to Dharamshala road Km. 0/0 to 1/750 (SH:- Construction of Retaining wall at RD 0/670 to 0/676).	85857.00	2000.00	350.00	Two Months	D&C
4.	Restoration of Rain Damage on Link road JK Clark to Village Ruliyani Km. 0/0 to 0/390 (SH:- Construction of Retaining wall at RD. 0/120 to 0/123.90).	97766.00	2000.00	350.00	Two Months	D&C
5	Restoration of Rain damage on Dalhousie Cantt to Bathri road km. 0/0 to 4/700(Village road) (SH:-Construction of PCC Retaining wall at RD 3/150 to 3/180) (Under PDNA-2023)	214785.00	4500.00	350.00	Two months	D & C
6.	Restoration of Rain Damage on Various roads Under Banikhet Sub Division HPPWD Banikhet (SH:- Removal of Slips in various roads).	485000.00	10000.00	350.00	One Month	D&C
7.	Restoration of Rain Damage on Link road to Village Lohali Km. 0/0 to 0/615 (SH:- Repair of road side work with CC 0:2:4 at various RD's)	99756.00	2000.00	350.00	Two Months	D&C

8.	Restoration of Rain Damage on Link road JK Clark to Village Ruliyani Km. 0/0 to 0/390 (SH:- Construction of Retaining wall at RD. 0/123.90 to 0/127.80).	97766.00	2000.00	350.00	Two Months	D&C
----	--	----------	---------	--------	------------	-----

1. The tender forms will not be issued to those Contractors whose performance is not found satisfactory. .
2. GST No. Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.
3. Application without all documents will not be entertained.
4. Proxy application will not be entertained.



Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

No. PWD/TA/Tender /2025-26 7598-7648

Dated:- 03-01-2026

Copy forwarded to the following for information and necessary action please:-

- 1 Engineer-in-Chief, HPPWD, Shimla.
- 2 All the Chief Engineer in HPPWD.
- 3 All SEs/EE in HPPWD.
- 4 All AEs/Contractor under this Division.
- 5 Deputy Commissioner, Chamba
- 6 BDO Bhattiyat.
- 7 Sub Divisional Magistrate/Tehsildar Dalhousie.
- 8 Notice Board of this office.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie

Schedule of Qty.

Job No. 01 TS 138


Estimated Cost :- Rs. 284912.00

Earnest Money :- Rs. 6000.00

Time Limit :- Two Months

Name of work: -Restoration of rain damage on Link road to village Bhariyatta Km. 0/0 to 2/00 (Village road) (SH: -Construction of PCC Retaining wall at RD 0/150 to 0/165 & 0/350 to 0/370). (Under PDNA-2023)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax, GST or other taxes imposed by the Government.	18.55			Per Cubic Metre	
2	Providing and Laying plain cement concrete 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (forty millimetre) nominal size mechanically mixed and vibrated in foundation for all type structure complete for all hights / depth including curing and cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, Toll tax, sales tax, GST or any other taxes imposed by the Government.	52.20			Per Cubic Metre	
3	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia Metres, PVC pipe Finolex/Vigor/Ashirvad/Astral etc exetnding through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and tencical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, Toll tax, sale tax GST or other taxes imposed by the Government.	24.00			Each	
4	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	17.55			Per Cubic Metre	
					Total: -	


 Executive Engineer
 Dalhousie Division,
 HPPWD, Dalhousie

Schedule of qty.

Job No. 02 TS No. 141

Estimated Cost: - Rs. 120000.00

Earnest Money :- Rs. 2500.00

Time Limit :- Two Month

Name of work: - Restoration of rain damage on various roads under HPPWD Division Dalhousie (SI:- Supplying and stacking of Calcium Chloride for spraying on Snow Bounded roads).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Supplying and stacking for Calcium Chloride in form of Powder/slacked for spraying on frozen snow bounded roads in 50kg (fifty kiligrame) bag and asper the direction of the Engineer-In-Charge. The material shall confirm to the MORD specification. including carriage of materials within all leads and lift and other incidental. The rate quoted by the contractor shall be inclusive of all taxes such as municipal, octroi, Malkana royalty toll tax, GST and other local taxes imposed by the Government.	4000.00			Per Kilograme	
					Total	


Executive Engineer
Dalhousie Division,
HPPWD, Dalhousie

Schedule of qty.

Job No. 03 TS 139

Estimated Cost :- Rs. 85857.00

Earnest Money :- Rs. 2000.00

Time Limit :- Two Months

Name of work: -Restoration of rain damage due to Digging of road by Jal Shakti Vibhag on Pukhri to Dharamshala road Km. 0/0 to 1/750 (SII: -Construction of Retaining wall at RD 0/670 to 0/676).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax, GST or other taxes imposed by the Government.	6.51			Per Cubic Metre	
2	Providing and Laying plain cement concrete 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (forty millimetre) nominal size mechanically mixed and vibrated in foundation for all type structure complete for all hights / depth including curing and cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, Toll tax, sales tax, GST or any other taxes imposed by the Government.	15.66			Per Cubic Metre	
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	4.77			Per Cubic Metre	
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia Metres, PVC pipe Finolex/Vigor/Ashirvad/Astral etc exetnding through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, Toll tax, sale tax GST or other taxes imposed by the Government.	7.00			Each	
					Total: -	

Executive Engineer
Dalhousie Division,
HPPWD, Dalhousie

Schedule of qty.

Job No. 04 TS 142

Estimated Cost: - Rs. 97766.00

Earnest Money :- Rs. 2000.00

Time Limit :- Two Months

Name of work: -Restoration of rain damage on Link road JK Clark to village Ruliyani Km. 0/0 to 0/390 (SII: -Construction of Retaining wall at RD. 0/120 to 0/123.90).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax, GST or other taxes imposed by the Government.	7.10			Per Cubic Metre	
2	Providing and Laying plain cement concrete 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (forty millimetre) nominal size mechanically mixed and vibrated in foundation for all type structure complete for all highs / depth including curing and cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, Toll tax, sales tax, GST or any other taxes imposed by the Government.	18.17			Per Cubic Metre	
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	4.97			Per Cubic Metre	
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia Metres, PVC pipe Finolex/Vigor/Ashirvad/Astral etc exetnding through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and tecnical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, Toll tax, sale tax GST or other taxes imposed by the Government.	7.00			Each	
					Total: -	

Executive Engineer
Dalhousie Division,
HPPWD, Dalhousie

Schedule of qty.

Job No. 05 TS 137


Estimated Cost: - Rs. 214785.00

Earnest Money :- Rs. 4500.00

Time Limit :- Two Months

Name of work: -Restoration of rain damage on Dalhousie Cantt to Bathri road Km. 0/0 to 4/700 (Village road) (SII: -Construction of PCC Retaining wall at RD 3/150 to 3/180). (Under PDNA-2023)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax, GST or other taxes imposed by the Government.	16.80	594.00		Per Cubic Metre	
2	Providing and Laying plain cement concrete 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (forty millimetre) nominal size mechanically mixed and vibrated in foundation for all type structure complete for all hights / depth including curing and cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, Toll tax, sales tax, GST or any other taxes imposed by the Government.	39.15	4862.80		Per Cubic Metre	
3	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia Metres, PVC pipe Finolex/Vigor/Ashirvad/Astral etc extnding through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and tecdical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, Toll tax, sale tax GST or other taxes imposed by the Government.	18.00	261.95		Each	
4	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	12.38	784.50		Per Cubic Metre	
					Total: -	


 Executive Engineer
 Dalhousie Division,
 HPPWD, Dalhousie

Schedule of qty.

Job No. 06 TS 145


Estimated Cost: - Rs. 485000.00

Earnest Money :- Rs. 10000.00

Time Limit :- One Month

Name of work: -Restoration of rain damage on Various roads under Banikhet Sub Division HP PWD Banikhet (SII: - Removal of Slips in various roads).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in Charge. The rate including the octroi, royalty , Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	3883.73			Per Cubic Metre	
					Total	


Executive Engineer
Dahousie Division,
HPPWD, Dahousie

Schedule of qty.


Estimated Cost: - Rs. 99756.00

Earnest Money :- Rs. 2000.00

Time Limit :- Two Month

Name of work :- Restoration of Rain damage on link road to village Lohali Km. 0/0 to 0/615 (SI:- Repair of road side work with CC 1:2:4 at various RD's)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Providing and laying mechanically mixed plain cement concrete nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate 20 mm (Twenty milimeter) nominal size) and curing complete work in foundation, footing bases and the alike and mass concrete as required at site including the cost of form work as per drawing and MORD technical specification sections 802,803,1202 & 1203 including carriage of material within all leads and lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government.	16.39			Per Cubic Metre	
					Total	


 Executive Engineer
 Dalhousie Division,
 HPPWD, Dalhousie

Schedule of qty.

Estimated Cost :- Rs. 97766.00

Earnest Money :- Rs. 2000.00

Time Limit :- Two Months

Name of work: -Restoration of rain damage on Link road JK Clark to village Ruliyani Km. 0/0 to 0/390 (SII: -Construction of Retaining wall at RD. 0/123.90 to 0/127.80).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax, GST or other taxes imposed by the Government.	7.10	594.00		Per Cubic Metre	
2	Providing and Laying plain cement concrete 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (forty millimetre) nominal size mechanically mixed and vibrated in foundation for all type structure complete for all hights / depth including curing and cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, Toll tax, sales tax, GST or any other taxes imposed by the Government.	18.17	4833.10		Per Cubic Metre	
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	4.97	784.50		Per Cubic Metre	
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia Metres. PVC pipe Finolex/Vigor/Ashirvad/Astral etc exetnding through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and tecnical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, Toll tax, sale tax GST or other taxes imposed by the Government.	7.00	261.92		Each	
					Total: -	

Executive Engineer
Dalhousie Division,
HPPWD Dalhousie