HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW-SRDD-CB-CTR-NIT-2025-26- 1749-83 Dated:- 05-01-2026

To

The Executive Engineer (IT Cell),
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- **Notice Inviting Tender for uploading the same on departmental website.**

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office for uploading the same on departmental website as per notification Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B)A(3)1/2024 dated Shimla-2 the 03-01-2024 and PWD-B-A0(3)/8/2025-300858 dated 09-10-2025 as the works mentioned in the tender Notice are urgent in nature and in public interest.

Encl:-Copy of NIT

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhami
Ph. 0177-2790534

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-
3. The Superintending Engineer, 4th Circle, HPPWD., Shimla-3.
4. All the Superintending Engineer, in HPPWD. (SZ)
5. The Deputy Commissioner Shimla Distt. Shimla.
6. The Sub Divisional Magistrate Shimla.
7. All the Executive Engineers in HPPWD, (SZ).
8. All the Assistant Engineer, working under this division.
9. All the heads of the branches in this office.
10. Notice Board.

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhami
Ph. 0177-2790534

Scanned with OKEN Scanner

HIMACHAL PRADESH

PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Shimla Rural Division H.P.P.W.D. Dhami on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Services Tax Act, 2017 so as to reach in this office on before **16.01.2026 up to 11:30 AM** and the same shall be opened on the same day at **12:00 P.M.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **15.01.2026 up to 5.00 PM** and the application for issue of tender form shall be received on **15.01.2026 up to 3:00 PM.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Shimla Rural Division HPPWD Dhami must be accompanied with the application for tender documents. Please not any exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be dept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No.	Name of Work	Estimated Cost (In Rs.)	EMD	Time	Cost of Form
1	R/R damages on Galog Nehra Okhroo road Km. 0/00 to 11/135 (SH: C/O R/Wall at Rd. 6/409 to 6/411 and 6/417 to 6/419).	98273/-	2000/-	One Month	Rs.350/-
2	A/R & M/O Tutikandi Sheelgaon via Kiari road Km. 0/00 to 3/870 (SH: C/O R/Wall at Rd. 2/549 to 2/554.50).	99600/-	2000/-	One month	Rs.350/-
3	Preparation forest diversion case under F.C.A. 1980 for (i) Construction of link road from Shoghi Anandpur to Mohri Gehar Km. 0/00 to 1/100).	65000/-	2000/-	One Month	Rs.350/-
4	A/R & M/O Chanawag Dawaroo road Km. 0/00 to 1/700 (SH: C/O B/Wall at Rd. 0/587.50 to 0/595).	94939/-	2000/-	One Month	Rs.350/-
5	R/R damages on Hiranagar Sharog road Km. 0/00 to 5/00 (SH: C/O R/Wall at Rd. 0/870 to 0/872.55).	98324 /-	2000/-	One Month	Rs.350/-
6	R/R damages on Kadrain Nalawan road Km. 0/00 to 3/00 (SH: C/O B/Wall at Rd. 2/945 to 2/955).	96440 /-	2000/-	One Month	Rs.350/-
7	R/R damages on link road to village Dishti Km. 0/00 to 3/00 (SH: C/O R/Wall at Rd. 2/650 to 2/653).	99906 /-	2000/-	One Month	Rs.350/-
8	A/R & M/O various roads under Sub Division Jutogh (SH: Providing & Fixing of typical informatory boards and village board). Badhari section).	98000 /-	2000/-	One Month	Rs.350/-

Scanned with OKEN Scanner

9	A/R & M/O various roads under Sub Division Jutogh (SH: Providing & Fixing of typical informatory boards and village board).	99400 /-	2000/-	One Month	Rs.350/-
10	A/R & M/O rest house at Taradevi Distt. Shimla H.P.(SH: Providing & fixing MS BP sheet, steel work and cup board shutter old rest htereof).	99929 /-	2000/-	One Month	Rs.350/-
11	A/R & M/O rest house at Taradevi Distt. Shimla H.P.(SH: Providing & fixing Panelling old rest house thereof) Set No.4.	97795 /-	2000/-	One Month	Rs.350/-
12	A/R & M/O Shoghi Mehli road Km. 0/00 to 12/375 (SH: Maintenance of berms/shoulder, maintenance of drains & minor slips in Km. 8/00 to 12/375).	99730 /-	2000/-	One Month	Rs.350/-
13	A/R & M/O Shoghi Mehli road Km. 0/00 to 12/375 (SH: Maintenance of drain/ white washing etc. in Km. 0/00 to 6/500)	96192 /-	2000/-	One Month	Rs.350/-
14	A/R & M/O Type three Quarter Set No.8 in HPPWD. Sub division Totu (SH: Painting and Distempering etc.).	48629 /-	1000/-	One Month	Rs.350/-
15	C/O link road from Poabo Chora to village Sujana, Distt. Shimla (HP) Km. 0/00 to 1/220 (SH: Preparation of FRA case in all respect).	70000 /-	1400/-	One Month	Rs.350/-
16	A/R & M/O Jalog to Kothi road Km. 0/00 to 5/180 (SH: C/O unlined surface drain, Maintenance of earthen shoulder, Maintenance of Hume pipe culvert at various Rds. between Km. 2/500 to 5/180).	99387 /-	2000/-	One Month	Rs.350/-
17	A/R & M/O Shara Nallah to Nadoth road Km. 0/00 to 2/700 (SH: C/O unlined surface drain, Maintenance of earthen shoulder, Maintenance of Hume pipe culvert at various Rds. between Km. 0/00 to 2/700).	99242 /-	2000/-	One Month	Rs.350/-
18	R/R damages on Pakki Bawari Shakrah Sedan road Km. 0/00 to 5/700 (SH: C/O R-wall at Rd. 4/213.50 to 4/217).	99530 /-	2000/-	One Month	Rs.350/-
19	Special repair to Director Residence at Judicial academy ghandal (SH: P/F Jaffari on back side, Almunium work, interlocking tiles and painting etc.) Job No.3	83354 /-	2000/-	One Month	Rs.350/-
20	Special repair to Director Residence at Judicial academy ghandal (SH: P/F Jaffari on back side, Almunium work, interlocking tiles and painting etc.) Job No.4	31101 /-	1000/-	One Month	Rs.350/-
21	A/R & M/O Bangora Kalihatti Bastigunana road Km. 0/00 to 11/675 (SH: C/O R-Wall at Rds. 10/300 to 10/304.30).	98427 /-	2000/-	One Month	Rs.350/-
22	A/R & M/O Bangora Kalihatti Bastigunana road Km. 0/00 to 11/675 (SH: C/O R-Wall at Rds. 10/790 to 10/794.30).	98376 /-	2000/-	One Month	Rs.350/-
23	R/R damages on link road Hiranagar to Upperli Fatechi road Km. 0/00 to 0/780 (SH: C/O R-Wall at Rds. 0/493 to 0/496.30).	99603 /-	2000/-	One Month	Rs.350/-
24	C/O link road from Anandpur to Kahala Lohala road Km. 0/00 to 1/500(SH: C/O R-Wall at Rds. 0/000 to 0/005.50). MMGSY	94604 /-	2000/-	One Month	Rs.350/-
25	A/R & M/O Sangti Neri road Km. 0/00 to 6/645 (SH: C/O V-shape drain in Km. 0/000 to 0/200).	95619 /-	2000/-	One Month	Rs.350/-
26	A/R & M/O Hanuman Mandir to Trari road Km. 0/00 to 2/395 (SH: Providing correction with WBM G-III).	99968 /-	2000/-	One Month	Rs.350/-
27	R/R damages on Chauri ki ghatti to Yan via Bhad road Km. 0/000 to 9/960 (SH: C/O Edge wall at Rd. 9/160 to 9/180).	97561 /-	2000/-	One Month	Rs.350/-
28	R/R damages on Anandpur to Tara Mata Mandir road Km. 0/00 to 2/200 (SH: C/O R-Wall at Rds. 2/105 to 2/110.50).	93584 /-	2000/-	One Month	Rs.350/-

Scanned with OKEN Scanner

29	C/O link road from Kufridhar to Shanol Km. 0/00 to 2/120 (SH: Formation Cutting in earth work in Km. 0/570 to 0/630).	90555 /-	2000/-	One Month	Rs.350/-
30	C/O link road from Kufridhar to Shanol Km. 0/00 to 2/120 (SH: Formation Cutting in earth work in Km. 1/615 to 1/720).	97678 /-	2000/-	One Month	Rs.350/-
31	S/R to Judicial Academy to Ghandal Distt. Shimla (SH: Painting in Admn. Block internal side).	99956 /-	2000/-	One Month	Rs.350/-
32	S/R to Judicial Academy to Ghandal Distt. Shimla (SH: P/F polycarbonate sheet & painting in Hostel).	88246 /-	2000/-	One Month	Rs.350/-
33	S/R to Judicial Academy to Ghandal Distt. Shimla (SH: Painting & repair work in Admn. Block & Hostel etc.).	99725 /-	2000/-	One Month	Rs.350/-
34	R/R damages on Kadrain Nalawan road Km. 0/00 to 3/000 (SH: C/O PCC B/Wall at Rds. 1/710 to 1/718.80).	99829 /-	2000/-	One Month	Rs.350/-
35	R/R damages on Kadrain Nalawan road Km. 0/00 to 3/000 (SH: C/O PCC R/Wall at Rds. 2/090 to 2/094.30).	98774 /-	2000/-	One Month	Rs.350/-
36	R/R damages on Hiranagar Petrol Pump to Jablog road Km. 0/00 to 0/700 (SH: C/O R/Wall at Rds. 0/640 to 0/643.50).	98944 /-	2000/-	One Month	Rs.350/-
37	R/R damages in Govt. Sr. Sec. School Rampuri Keonthal (SH: C/O R/Wall back side of school Job No.II) Deposit Work.	97938 /-	2000/-	One Month	Rs.350/-
38	R/R damages in Govt. Sr. Sec. School Rampuri Keonthal (SH: C/O R/Wall back side of school Job No.III) Deposit Work.	97938 /-	2000/-	One Month	Rs.350/-
39	R/R damages on Dargi Machryana Judloo road Km. 0/00 to 11/900 (SH: Removal of slips at various Rds.).	99640 /-	2000/-	One Month	Rs.350/-
40	R/R damages on Simloh Dargi via Nagar road Km. 0/00 to 2/825 (SH: Removal of slips at various Rds.).	98870 /-	2000/-	One Month	Rs.350/-
41	R/R damages on Baggipul Thachi Sharog road Km. 0/00 to 6/00 (SH: Removal of slips at various Rds.).	99835 /-	2000/-	One Month	Rs.350/-
42	R/R damages on Banuti Pahal road Km. 0/00 to 16/150 (SH: C/O R/Wall at Rds. 0/210 to 0/217).	91430 /-	2000/-	One Month	Rs.350/-

Followings documents should be attached with the application for tenders:-

(i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.

(ii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.

Executive Engineer
Shimla Rural Division
H.P.P.W.D. Dhami

Certificate

Certified that the tenders called vide this notice inviting tender for 42 (Forty two) jobs are due to exigencies/emergency of works in the larger public interest.

Executive Engineer
Shimla Rural Division
H.P.P.W.D. Dhami.

Scanned with OKEN Scanner

Schedule Of Quantity

Name of Work :- Restoration of Rain Damages on Galog Nehra Okhroo Road km. 0/00 to 11/135 (SH:- Constuction of Retaining wall at Rd. 6/409 to 6/411 and 6/417 to 6/419)

Estimated Cost:- 98,273.00
Earnest Money:- 2000.00
Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shallbe carried,out true tolines,grades,side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	3.46	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	808
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	6.94	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2474
3	Providing and laying lean cement concrete 1:4:8 (one cement :four sand :eight graded stone aggregate 20mm nominal size)(Twenty milimetre) and curing complete excluding cost of form work with pidilite or Dr.fixit water proofing treatment as per the direction of the Engineer-in-Charge but including carriage of materials up to all leads and lifts.	19.54	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per Cubic metre	89884
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pie extending through the full with of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 Including carriage of material within all leads and lifts.	16.08	Rmt	170.00	Rupees One Hundred Seventy Only	Per running metre	2734
5	Back filling filling behind abutment wing wall and retaning wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I.Including carriage of material within all leads and lifts.	2.82	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2374
	Total Rs						**98273**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Name Of Work :- A/R & M/O TutiKandi Sheelgon via kiari road km. 0/00 to 3/870 (SH:- Construction of Retaining wall at Rd. 2/549 to 2/554.50)

Estimated Cost:- 99,600.00
Earnest Money:- 2,000.00
Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
1	2			In figures	In words		
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shallbe carried,out true tolines,grades,side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	3.96	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	924
2	Earth work in excavation for structures as per drawing and technical specification clauses 305 1 including setting out. construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	8.47	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	3020
3	Providing and laying lean cement concrete 1:4:8 (one cement :four sand :eight graded stone aggregate 20mm nominal size)(Forty milimetre) and curing complete excluding cost of form work with pidilite or Dr.fixit water proofing treatment as per the direction of the Engineer-in-Charge but including carriage of materials up to all leads and lifts.	18.92	Cum	4700.00	Rupees Four Thousand Seven Hundred Only	Per cubic metre	88924
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pie extending through the full with of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 Including carriage of material within all leads and lifts	13.50	Rmt.	190.00	Rupees One Hundred Ninety Only	Per running Metre	2565
5	Back filling filling behind abutment wing wall and retaning wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP PWD., specifications of 1990 volume-I.Including carriage of material within all leads and lifts.	4.95	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	4167
	Total Rs.						**99600**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Scanned with OKEN Scanner

Schedule Of Quantity

Name Of Work :- Preparation of Forest Diversion case under F.C.A 1980 for (i) Construction of link road from Shoghi Anandpur to Mohri Gehar km. 0/00 to 1/100)

Estimated Cost:- 65,000.00
Earnest Money:- 2,000.00
Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Preparation of Forest Deversion case Under Forest Conservation Act-1980 including preparation of revenue papers of land falling on the road alignment and collection of other field date. All relevant documents/formats mandatory required would be attached with the case as per latest requirement of Ministry of Environment and forest conservation Govt. of India after getting the joint inspection/ site including computer typing in 6 copies, binding complete and getting it through from **HP, PWD Sub Division Shoghi HP, PWD Division Dhami office of range Officer Mashobra, office of DFO Shimla Conservator of Forest Department Shimla** including attending all the observations, if raise, at many time by any office and to prepare the same by neatly and accurately filling in all the formats/Documents complete in all respect as per direction and complete satisfaction of HP, PWD and Forest Department.	1.00	Per Case	65000.00	Rupees Sixty Five Thousand Only	Per Case	65000
	Total Rs.						**65000**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Scanned with OKEN Scanner

Name of Work:- Annual Repair & Maintenance of Chanawag Dawaroo Road Km. 0/00 to 1/700 (Sh: Construction of Breast Wall in Between Km. 0/587.50 to 0/595)

SCHEDULE OF QUANTITY

Estimated Cost - Rs 94939 /- only
Earnest Money - Rs 2000 /-only
Time :- One Month

S. No.	Sub head and items of work	Qty.		Rate figures	Rate	Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	7.50	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1751.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	5.25	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1872.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.43	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	89378.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	11.40	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1938.00
0						**Total:**	**94939.00**

Amount Quoted by the Contractor in Percentage **Rs.**

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Hiranagar Sharog Road Km. 0/00 to 5/00 (Sh: C/o R-wall at Rd. 0/870 to 0/872.55)

Estimated Cost: - Rs 98324 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	3.26	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	761.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	4.98	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1775.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.29	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	93334.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	7.60	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1292.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	1.38	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	1162.00
0						**Total:**	**98324.00**

Amount Quoted by the Contractor in Percentage	**Rs.**	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Scanned with OKEN Scanner

Name of Work:- Restoration of rain damages on Kadrain Nalawan Road Km. 0/00 to 3/00 (Sh: Construction of Breast wall at Rd. 2/945 to 2/955)

SCHEDULE OF QUANTITY

Estimated Cost - Rs 96440 /- only
Earnest Money - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	3.30	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	770.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	5.10	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1818.00
3	Providing and Laying cement concrete for plain / reinforced conc In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.90	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	91540.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	13.60	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	2312.00
0						Total:	96440.00

Amount Quoted by the Contractor in Percentage **Rs.**

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Scanned with OKEN Scanner

Name of Work:- Restoration of rain damages on Link Road to village Dishti Road Km. 0/00 to 3/00 (Sh: Construction of R-Wall at Rd. 2/650 to 2/653)

SCHEDULE OF QUANTITY

Estimated Cost - Rs 99906 /- only
Earnest Money - Rs 2000 /-only
Time - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1 5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603 1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	3.70	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	864.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	4.23	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1508.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.47	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	94162.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	2.41	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2029.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	7.90	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1343.00
0						**Total:**	**99906.00**

Amount Quoted by the Contractor in Percentage	**Rs.**	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Name of Work :- A/R & M/O various roads under Sub Division Jutogh (SH:- Providing and fixing of typical informatory boards and village board) (Badhari Section)

Estimated Cost:- 98,000.00
Earnest Money:- 2000.00
Time:- One Months.

S No	Description of Work	No of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Providing and fixing of retro-reflectorized cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Çause 1701.2.3 fixed over M S sheeting, 1.5 mm thick supported on a mild steel angle iron post 75x40 Le firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm X 450mm X 600mm below ground level as per drawings and Technical Specification Clause 801 i) Direction and place in nidification sign with size 1200x900 (informatory sign board)	14.00	No	7000.00	Rupees Seven Thousand Only	Each	98000
	Total Rs.						**98000**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Scanned with OKEN Scanner

Schedule Of Quantity

Name of Work :- A/R & M/O various roads under Sub Division Jutogh (SH:- Providing and fixing of typical informatory boards and village board)

Estimated Cost:- 99,400.00
Earnest Money:- 2000.00
Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Providing and fixing of retro-reflectorized cautionary, mandatory and informatory sign as per IRC.67 made of encapsulated lens type reflective sheeting vide Çause 1701.2.3 fixed over M S sheeting, 1.5 mm thick supported on a mild steel angle iron post 75x40 Le firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm X 450mm X 600mm below ground level as per drawings and Technical Specification Clause 801. i) Direction and place in nidification sign with size 1200x900 (informatory sign board)	10.00	No	7000.00	Rupees Seven Thousand Only	Each	70000
2	Providing and fixing of retro-reflectorized cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide clause 1701.2.3 fixed over aluminum sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm X 6mm firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm X 450mm X 600mm below ground level as per drawings and Technical Specification Clause 1801(900/600 direcation and place edification)	6.00	No	4900.00	Rupees Four Thousand Nine Hundred Only	Each	29400
	Total Rs.						**99400**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Scanned with OKEN Scanner

Schedule Of Quantity

Name of Work :- Annual Repair & Maintenance to Rest House at Tara Devi (SH:- Providing and Fixing MS BP sheet, Steel work, Wood work, and Cup board shutter

Estimated Cost:- 99,929.00
Earnest Money:- 2000.00
Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Structural steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including carriage of material in all leads and lifts as per direction of the Engineer in charge.	281.60	Kg.	93.00	Rupees Ninety Three Only	Per Kilogram	26189
2	Providing and fixing MS BP sheet 2.00 mm thick in eves board /facia/ soffits/ ceiling including cutting fixing and welding to steel roof members and applying a coat of red lead primer. including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	9.18	Sqm	1750.00	Rupees One Thousand Seven Hundred Fifty Only	Per Square metre	16065
3	Providing and fixing 19mm thick Commercial Board water proof shutters with 6mm thick hard wood edging for cup boards i/c fixing with nickel plated piano hinges with screws etc complete as per specification and as per the directions of Engineer-in Charge including carriage of materials with in all leads, lifts and other incidentals .	2.32	Sqm	1684.50	Rupees One Thousand Six Hundred Eighty Four and Paise Fifty Only	Per Square metre	3908
4	Providing wood work in frames of doors , window , clearstory windows and other frames wrought framed and fixed inposition with hold fast lugs or with dash fasterners of required dia & lenght (hold fast lugs or dash fasterner shall be oaid for separately) saal wood including carriage of material in all leads and lifts as per direction of the Engineer in Charge	0.0975	Cum	120690.00	Rupees One Lakh Twenty Thousand Six Hundred Ninety Only	Per Cubic metre	11767
5	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows.including black enamelled iron butt hinges with necessary screws. including carriage of material in all leads and lifts as per direction of the Engineer in Charge	2.64	Sqm	3550.00	Rupees Three Thousand Five Hundred Fifty Only	Per Square metre	9372
6	Providing and fixing wire gauge shutters using galvanised M.S. wire gauge of I.S. gauge designation 85 G, with wire of dia 0.63 mm for doors windows and clerestorey windows including bright finished black enamelled iron hinges with necessary screws. 35 mm thick in 2nd class deodar wood including carriage of materials within all leads and lifts and as per the direction of Engineer-in-Charge.	2.64	Sqm	3485.00	Rupees Three Thousand Four Hundred Eighty Five Only	Per Square metre	9200
7	Providing and 3mm thick ACP Sheet in panelling fixed in aluminium doors window shutter andportion frames with CP brass /stainless stell screws etc.	17.1	Sqm	1370.00	Rupees One Thousand Three	Per Square metre	23427
	Total Rs						**99929**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Name of Work :- Annual Repair & Maintenance to Rest House at Tara Devi (SH:- Providing and Fixing Panelling Old Rest house thereof) Set No. 4.

Estimated Cost:- 97,795.00
Earnest Money:- 2000.00
Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Providing and fixing 40mm thick plain framed panelling with necessary screws , priming coat on unexposed surface etc complete 2nd class Devdar wood complete.	27.18	Sqm	3598.05	Rupees Three Thousand Five Hundred Ninety Eight and Paise Four Only	Per Square metre	97795
	Total Rs						**97795**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Scanned with OKEN Scanner

Schedule Of Quantity

Name of Work :- A/R & M/O on Shoghi Mehli road km. 0/00 to 12/375 (SH:- Maintenance of Berms/ shoulder, Maintenance of Drain,& minor slips in km. 8/00 to 12/375)

Estimated Cost:- 99.730.00
Earnest Money:- 2,000.00
Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	11100.00	Sqm	4.50	Rupees Four and Paise Fifty Only	Per Square metre	49950
2	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907. including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	3300.00	Rmt.	4.50	Rupees Four and Paise Fifty Only	Per Running Metre	14850
3	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611. The rate including octroi, royality, Malkana toll tax, GST or any other taxes inputfor or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	252.00	Cum	90.00	Rupees Ninety Only	Per cubic metre	22680
4	Maintenance of Hume pipe Culvert by way of Clearing, Cleaning, Erosion repair, repairs to cracks, parapet wall and protection work as per drawing and technical specification Clause 1908 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	7.00	No.	1750.00	Rupees One Thousand Seven Hundred Fifty Only	Each	12250
	Total Rs.						**99730**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Name of Work :- A/R & M/O Shoghi Mehli road km. 0/00 to 12/375 (SH:- Maintenance of drain / white washing etc. in km. 0/00 to 6/500)

Estimated Cost:- 96,192.00
Earnest Money:- 2000.00
Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	White washing two coats on parapet walls and tree trunks including preparation of surface by cleaning scraping etc. as per technical specifications Clause 1915 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge.	3006.00	Sqm	32.00	Rupees Thirty Two Only	Per Square metre	96192
	Total Rs.						**96192**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Scanned with OKEN Scanner

Name Of Work :- Annual Reapair & Maintenance of Type three Quarter Set No. 8 in HPPWD Sub Division Totu (Sh: Painting and Distempeing etc.)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 48629 /- only
Earnest Money : - Rs. 1000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate	Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Distempering (two coats) with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surfaces to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth. Priming coat with distemper primer including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	219.64	Sqm	120.00	Rupees One Hundred Twenty Only	Per Square Metre	26357.00
2	Painting two coats(excluding prime coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering & stoping With enamel paint other than white including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	34.94	Sqm	130.00	Rupees One Hundred Thirty Only	Per Square Meter	4542.00
3	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	53.49	Sqm	146.00	Rupees One Hundred Forty Six Only	Per Square Metre	7810.00
4	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	81.94	Sqm	75.00	Rupees Seventy Five Only	Per Square Metre	6146.00
5	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with 5.0 mm thick glass including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	4.45	Sqm	848.00	Rupees Eight Hundred Forty Eight Only	Per Square Metre	3774.00
0						**Total:**	**48629.00**

Amount Quoted by the Contractor in Percentage	**Rs.**	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Scanned with OKEN Scanner

Jule Of Quantity

Name Of Work :- C/o Link Road from Poabo Chora to village Sujana , Distt Shimla (HP) km. 0/00 to 1/220 (SH:- Preperation of FRA Case in all respect)

Estimated Cost
Earnest Money
Time:- One Months

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Preparation of Geo refrence digital map and Collecting the data from proposed site including fild visits Preparation of Kml file. Geo coordinates along with making of Habitations to be benefited by construction of project and dumping area of proposed site. Making The allignment in soft copy and submission in hard copy. Preperation of Forest case(FRA) proposed road in Jutog Sub Division. Preperation of Folders complete in all respect and submmit to the department as per the direction of Engineer- in- charge.	1.00	Job	70000.00	Rupees Seventy Thousand Only	Per Job	70000
	Total Rs.						70000
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Scanned with OKEN Scanner

Schedule of Quantity

Name of Work :- A/R & M/O Jalog to Kothi road Km 0/00 to 5/180 (SH: C/O unlined surface drain, Maintenance of Earthen Shoulder, Maintenance of Hume Pipe Culvert at various Rds between Km 2/500 to 5/180)

Estimated Cost:- 99387.00 Only.
Earnest Money: 2000.00 Only.
Time: - One month

S. No	Description of Work	Nos of Qty		Rate		Unit	Amount
				In Figure	In word		
1	2	3	4	5	6	7	8
1	Construction of unlined surface drain of average cross sectional area 0.4 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and technical specification clause 307. Excavated material to be used in embankment at site.	1041.00	Rmt	75.00	Seventy Five Rupees	Rmt	78075.00
2	Maintenance of Earthen Shoulder (filling with fresh soil) Making up loss of material / irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per tonne including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	1032.00	Sqm	16.00	Sixteen Rupees	Sqm	16512.00
3	Maintenance of Hume pipe Culvert by way of Clearing, Cleaning, Erosion repar repairs to cracks parapet wail and protection work as per drawing and technical specification Clause 1908 carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	3.00	Nos.	1600.00	One Thousand and Six Hundred Rupees	Nos.	4800.00
					Total		**99387.00**
	Amount procured by the contractor in percentage	**Rs.**					
	Conditions:- All the Machineries/materials will be procurred by the contractor himself and bills will be submitted						

Executive Engineer
Shimla Rural Division
HPPWD Dhami

Scanned with OKEN Scanner

Schedule of Quantity

Name of Work :- A/R & M/O Shara Nallah to Nadoth Km 0/00 to 2/700 (SH: C/O unlined surface drain, Maintenance of Earthen Shoulder, Maintenance of Hume Pipe Culvert at various Rds between Km 0/00 to 2/700)

Estimated Cost:- 99242.00 Only.
Earnest Money: 2000.00 Only.
Time: - One month

S. No	Description of Work	Nos of Qty		Rate		Unit	Amount
				In Figure	In word		
1	*2*	*3*	*4*	*5*	*6*	*7*	*8*
1	Construction of unlined surface drain of average cross sectional area 0.4 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and technical specification clause 307. Excavated material to be used in embankment at site.	990.00	Rmt	75.00	Seventy Five Rupees	Rmt	74250.00
2	Maintenance of Earthen Shoulder (filling with fresh soil) Making up loss of material / irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per tonne including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	1062.00	Sqm	16.00	Sixteen Rupees	Sqm	16992.00
3	Maintenance of Hume pipe Culvert by way of Clearing, Cleaning, Erosion repar repairs to cracks parapet wail and protection work as per drawing and technical specification Clause 1908 carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	5.00	Nos.	1600.00	One Thousand and Six Hundred Rupees	Nos.	8000.00
					Total		**99242.00**
	Amount procured by the contractor in percentage	**Rs.**					
	Conditions:- All the Machineries/materials will be procurred by the contractor himself and bills will be submitted						

Executive Engineer
Shimla Rural Division
HPPWD Dham

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Pakki Bawari Shakrah Sedan Road Km. 0/00 to 5/700 (Sh: Construction of R-wall at Rd. 4/213.50 to 4/217)

Estimated Cost :- Rs 99530 /- only
Earnest Money :- Rs. 2000 /-only
Time :- One Month

S. No.	Sub head and items of work	Qty.		Rate	Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	3.15	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	735.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	7.95	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2834.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.85	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	91310.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	3.99	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	3359.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	7.60	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1292.00
0						**Total:**	**99530.00**

Amount Quoted by the Contractor in Percentage	**Rs.**	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Special Repair to Director Residence at Judicial Academy Ghandal (Sh: Providing & fixing Jaffari on back Side, Aluminium Work, Interlocking tiles and painting etc.) Job No. 3

Estimated Cost: - Rs 83354 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
1	2	3		4	5	6	7
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	2.13	Cum	5846.00	Rupees Five Thousand Eight Hundred Forty Six Only	Per Cubic Metre	12452.00
2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	746.34	Kg.	95.00	Rupees Ninety Five Only	Per Kilogramme	70902.00
0						**Total:**	**83354.00**

Amount Quoted by the Contractor in Percentage	**Rs.**	

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Special Repair to Director Residence at Judicial Academy Ghandal (Sh: Providing & fixing Jaffari on back Side, Aluminium Work, Interlocking tiles and painting etc.) Job No. 4

Estimated Cost: - Rs 31101 /- only
Earnest Money : - Rs. 1000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
1	2	3		4	5	6	7
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	0.38	Cum	5846.00	Rupees Five Thousand Eight Hundred Forty Six Only	Per Cubic Metre	2221.00
2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	248.78	Kg.	95.00	Rupees Ninety Five Only	Per Kilogramme	23634.00
3	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	45.62	Sqm.	115.00	Rupees One Hundred Fifteen Only	Per Square Meter	5246.00
0						**Total:**	**31101.00**

Amount Quoted by the Contractor in Percentage	**Rs.**	

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Annual Repair & Maintenance on Bangora Kalihatti Bastigunana Road Km. 0/00 to 11/675 (Sh: Construction of R-wall at Rd. 10/300 to 10/304.30)

Estimated Cost - Rs 98427 /- only
Earnest Money - Rs. 2000 /-only
Time :- One Month

S. No.	Sub head and items of work	Qty.		Rate	Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	7.35	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1715.00
2	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement 4 sand 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.08	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	92368.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	10.20	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1734.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	3.10	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty	Per cubic metre	2610.00
0						**Total:**	**98427.00**

Amount Quoted by the Contractor in Percentage **Rs.**

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Annual Repair & Maintenance on Bangora Kalihatti Bastigunana Road Km. 0/00 to 11/675 (Sh: Construction of R-wall at Rd. 10/790 to 10/794.30)

Estimated Cost :- Rs 98376 /- only
Earnest Money :- Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate	Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	7.35	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1715.00
2	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.08	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	92368.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge	3.10	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2610.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	9.90	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1683.00
0						**Total:**	**98376.00**

Amount Quoted by the Contractor in Percentage	**Rs.**	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain Damages Link Road Hiranagar to Upperli Fatechi Road Km. 0/00 to 0/780 (Sh: Construction of Retaining wall at Rd. 0/493 to 0/496.30)

Estimated Cost - Rs 99603 /- only
Earnest Money - Rs 2000 /-only
Time - One Month

S. No.	Sub head and items of work	Qty.		Rate	Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	4.75	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1109.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	5.54	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1975.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement 4 sand 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	20.05	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	92230.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	7.60	Rmt	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1292.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	3.56	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2997.00
0						Total:	99603.00

Amount Quoted by the Contractor in Percentage	Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Name Of Work :- C/O Link road from Anandpur to Kahala, Lohala road km 0/00 to 1/500 (SH:- C/O R/wall at Rd 0/00 to 0/005.50) Under MMGSY

Estimated Cost:- 94,604.00
Earnest Money:- 2,000.00
Time:- One Month.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	3.52	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic metre	822
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge	5.72	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	2039
3	Providing and Laying cement concrete for plain / reinforced concrete In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 14:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	17.77	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per Cubic metre	85296
4	Back filling behind abutment wing wall and retaning wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I Including carriage of material within all leads and lifts.	4.95	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per Cubic metre	4167
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge	12.00	Nos	190.00	Rupees One Hundred Ninety Only	Each	2280
	Total Rs.						**94604**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Annual Repair & Maintenance of Sangti Neri Road Km. 0/00 to 6/645 (Sh: Construction of V-Shape drain in Km. 0/00 to 0/200)

Estimated Cost - Rs 95619 /- only
Earnest Money - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate	Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	20.25	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	7219.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203, P.C.C grade M 10, (i) C.C. 1:3:6 20 mm nominal mix (Twenty Milimetre size) concrete mix , including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	17.00	Cum	5200.00	Rupees Five Thousand Two Hundred Only	Per cubic metre	88400.00
0						**Total:**	**95619.00**

Amount Quoted by the Contractor in Percentage	Rs.	

Note : **(i) All the material will procured by the contractor him self.**

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Name of work:- A/R & M/O Hanuman Mandir to Trari road Km 0/00 to 2/395. (SH: Providing correction with WBM G-III)

Estimated Cost:-99968.00
Earnest Money:- 2,000.00
Time:- One Month.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading III as per Technical Specification Clause 405. By Mechanical means.	44.43	Cum	2250.00	Rupees two thousand two hundred and fifty only	Per cubic metre	99968.00
	Amount Quoted by the Conctrator in percentage	**Rs.**				**Total:-**	**99968.00**
	Conditions:-(i) All the materials will be procured by the contractor himself and bills will be submitted.						

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami.

Scanned with OKEN Scanner

Schedule of Quantity

Name of work: R/R Damages on Chauri ki Ghatti to yan via bhad road km 0/000 to 9/960. (SH : C/O Edge wall at RD 9/160 to 9/180).

Estimated Cost: 97,561/- only

Earnest Money: 2000/-only.

Time: - One month

S. No	Description of Work	Nos of Qty		Rate		Unit	Amount
				In Figure	In word		
1	2	3	4	5	6	7	8
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 metre and a lead upto 20mtr as per drawing and technical specification clause 1603.1 and other deleterious material and disposal upto all leads and lifts as per MORD Specification directed by Engineer –in- Charge .	10.80	Cum	233.40	Two hundred thirty three rupee forty Paisa only	Per Cubic metre	2521.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803,1202 & 1203 in cement concrete 1:4:8 (1 Cement 4 Sand 8 graded stone aggregate 20 mm nominal mix) including carriage of material up to all leads and lifts as per the direction –in- Charge.	19.80	Cum	4800.00	Forty eight Hundred rupees only	Per Cubic metre	95040.00
					Total		**97561.00**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division
HP,PWD, Dhami.

Scanned with OKEN Scanner

Schedule of Quantity

Name of work: R/R Damages on Ananadpur to Tara Mata Mandir km 0/000 to 2/200. (SH : C/O R/wall at RD 2/105 to 2/110.50).

Estimated Cost: 93,584/- only
Earnest Money: 2000/-only.
Time: - One month

S. No	Description of Work	Nos of Qty		Rate		Unit	Amount
				In Figure	In word		
1	2	3	4	5	6	7	8
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 metre and a lead upto 20mtr as per drawing and technical specification clause 1603.1 and other deleterious material and disposal upto all leads and lifts as per MORD Specification directed by Engineer –in- Charge .	3.52	Per Cum	233.40	Two hundred thirty three rupee forty Paisa only	Per Cum	822.00
2	Earth work in excavation for structures as per drawing and technical specifications clause No. 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious material and disposal upto all lead and lifts dressiong of side and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer –in- Charge.	5.72	Per Cum	356.50	Three hundred fifty six rupees fifty paisa only	Per Cum	2039.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803,1202 & 1203 in cement concrete 1:4:8 (1 Cement 4 Sand 8 graded stone aggregate 20 mm nominal mix) including carriage of material up to all leads and lifts as per the direction –in- Charge.	17.77	Per Cum	4800.00	Forty eight Hundred rupees only	Per Cum	85296.00
4	Back filling behind Abutment , wing wall and return wall complete as per drawings and technical specification clause 1204.3.8.	4.95	Per Cum	841.80	Eight hundred forty one rupees eighty paisa only	Per Cum	4167.00
5	Providing and laying 100 mm dia meter pipe for weep holes complete of approved quality including carries of material within all leads and lift.	7.00	No	180.00	One hundred eighty rupees only	Each	1260.00
	Amount Quoted by the Contractor in Percentage				**Total**		**93584.00**
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Divisio
HP,PWD, Dhami.

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work: - Construction of Link Road from Kufridhar to Shanol Km. 0/00 to 2/120 (Sh: Formation Cutting in earth work in Km. 0/570 to 0/630)

Estimated Cost: - Rs 90555 /- only

Earnest Money : - Rs. 2000 /-only

Time- One Month

S.No.	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Cutting in earth work in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP.PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 and sorting out useful/un-useful materials and stacking the same in all leads and lifts and transportation of the unuseful materials for filling in road ways, embankments for grades improvements and leveling to the required grades and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load , animal load or mechanical means along with its leveling fine dressing and all lobour , machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and labour (if any required). the cost of useful materials such as stones,shingles,aggregates and slates shall be sorted out and stacked along road side,which shall not be less than one tenth of JW,one sixth of SR and one third of HR.= 19.40 Cum Qty. which shall be proportionately increase/decrease as the qty. of earth work increase/ decreas in all cases recovered from the contracto @ 300/- (Three Hundred only) per cubic metre shall be efacted any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	387.98	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	90555.00
						Total:	**90555.00**
	Amount Quoted by the Contractor in Percentage						

Executive Engineer,
Shimla Rural Division,
HPPWD Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work: - Construction of Link Road from Kufridhar to Shanol Km. 0/00 to 2/120 (Sh: Formation Cutting in earth work in Km. 1/615 to 1/720)

Estimated Cost: - Rs 97678 /- only
Earnest Money : - Rs. 2000 /-only
Time- One Month

S.No.		Sub head and items of work	Qty.		Rate		Unit	Amount
1		2	3		In figure	In words	6	7
1		Cutting in earth work in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP.PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 and sorting out useful/un-useful materials and stacking the same in all leads and lifts and transportation of the unuseful materials for filling in road ways, embankments for grades improvements and leveling to the required grades and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load , animal load or mechanical means along with its leveling fine dressing and all lobour , machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and labour (if any required). the cost of useful materials such as stones,shingles,aggregates and slates shall be sorted out and stacked along road side,which shall not be less than one tenth of JW,one sixth of SR and one third of HR.= 20.93 Cum Qty. which shall be proportionately increase/decrease as the qty. of earth work increase/ decreas in all cases recovered from the contracto @ 300/- (Three Hundred only) per cubic metre shall be efacted any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	418.50	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	97678.00
							Total:	**97678.00**
		Amount Quoted by the Contractor in Percentage						

Executive Engineer,
Shimla Rural Division,
HPPWD Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Special Repair to Judicial Academy to Ghanal District Shimla (Sh: Painting in Admin Block internal Side)

Estimated Cost. - Rs 99956 /- only
Earnest Money - Rs 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
1	2	3	4	5		6	7
1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq meters and under,including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in- Charge	72.93	Sqm	264.35	Rupees Two Hundred Sixty Four and Paise Thirty Five Only	Per Square Metre	19279.00
2	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc complete.	668.08	Sqm	11.15	Rupees Eleven and Paise Fifteen Only	Per Square Metre	7449.00
3	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	400.85	Sqm.	85.10	Rupees Eighty Five and Paise Ten Only	Per Square Meter	34112.00
4	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: One or more coats on old work including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	668.08	Sqm.	58.55	Rupees Fifty Eight and Paise Fifty Five Only	Per Square Meter	39116.00
0						**Total:**	**99956.00**

Amount Quoted by the Contractor in Percentage **Rs.**

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Special Repair to Judicial Academy to Ghanal District Shimla (Sh: Providing fixing polycarbonate sheet & painting in hostel)

Estimated Cost - Rs 88246 /- only
Earnest Money - Rs. 2000 /-only
Time :- One Month

S. No.	Sub head and items of work	Qty.			Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq meters and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in- Charge	36.72	Sqm	264.35	Rupees Two Hundred Sixty Four and Paise Thirty Five Only	Per Square Metre	9707.00
2	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	332.33	Sqm	11.15	Rupees Eleven and Paise Fifteen Only	Per Square Metre	3705.00
3	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	332.33	Sqm.	85.10	Rupees Eighty Five and Paise Ten Only	Per Square Meter	28281.00
4	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade. One or more coats on old work including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	332.33	Sqm.	58.55	Rupees Fifty Eight and Paise Fifty Five Only	Per Square Meter	19458.00
5	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge	208.05	Kg.	105.00	Rupees One Hundred Five Only	Per Kilogramme	21845.00
6	Fixing of Polycarbonated Sheet 3 mm Thick including vertical / curved surface fixed with nuts complete (labour rate only) as per the direction of Engineer in Charge.	35.00	Sqm.	150.00	Rupees One Hundred Fifty Only	Per Square Meter	5250.00
0						**Total:**	**88246.00**

Amount Quoted by the Contractor in Percentage	**Rs.**	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Special Repair to Judicial Academy to Ghanal District Shimla (Sh: Painting & repair work in Administration Block & Hostel etc.)

Estimated Cost. - Rs 99725 /- only
Earnest Money - Rs 2000 /-only
Time :- One Month

S. No.	Sub head and items of work	Qty.			Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq meters and under,including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in- Charge	2.70	Sqm	264.35	Rupees Two Hundred Sixty Four and Paise Thirty Five Only	Per Square Metre	714.00
2	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	639.60	Sqm	11.15	Rupees Eleven and Paise Fifteen Only	Per Square Metre	7132.00
3	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	639.60	Sqm.	85.10	Rupees Eighty Five and Paise Ten Only	Per Square Meter	54430.00
4	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: One or more coats on old work including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	639.60	Sqm.	58.55	Rupees Fifty Eight and Paise Fifty Five Only	Per Square Meter	37449.00
0						Total:	99725.00

Amount Quoted by the Contractor in Percentage Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Scanned with OKEN Scanner

Name of Work:- Restoration of rain damages on Kadrain Nalawan Road Km. 0/00 to 3/00 (Sh: Construction of PCC B-Wall at Rd. 1/710 to 1/718.80)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 99829 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate	Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	6.60	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1540.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	3.43	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1223.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.68	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	95128.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	11.40	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1938.00
0							
						Total:	99829.00

Amount Quoted by the Contractor in Percentage **Rs.**

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Kadrain Nalawan Road Km. 0/00 to 3/00 (Sh: Construction of PCC R-Wall at Rd. 2/090 to 2/094.30)

Estimated Cost - Rs 98774 /- only
Earnest Money - Rs. 2000 /-only
Time: - One Month

S No.	Sub head and items of work	Qty.		Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	2.88	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	672.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge	4.47	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1594.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.08	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	92368.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge	3.10	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2610.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	9.00	Rmt	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1530.00
0						**Total:**	**98774.00**

Amount Quoted by the Contractor in Percentage	Rs.	

Note : **(i) All the material will procured by the contractor him self.**

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damages on Hiranagar Petrol Pump to Jablog Road Km. 0/00 to 0/700 (Sh: Construction of Retaining 0/640 to 0/643.50)

Estimated Cost - Rs 98944 /- only
Earnest Money - Rs. 2000 /-only
Time - One Month

Sub head and items of work	Qty.		Rate figures		Unit	Amount
2	3		4	5	6	7
Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	5.67	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1323.00
Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge	6.79	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2421.00
Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.85	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	91310.00
Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge	2.42	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2037.00
Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	10.90	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1853.00
					Total:	**98944.00**

Amount Quoted by the Contractor in Percentage **Rs.**

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damages in Govt. Senior Secondary School Rapuri Keonthal (Sh: Construction of Retaining wall back side of school Job No. -II) Deposit Work

Estimated Cost: - Rs 97938 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	6.39	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1491.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	6.67	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2378.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	18.78	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	86388.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	7.67	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	6457.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	7.20	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1224.00
0						**Total:**	**97938.00**

Amount Quoted by the Contractor in Percentage	**Rs.**	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damages in Govt. Senior Secondary School Rapuri Keonthal (Sh: Construction of Retaining wall back side of school Job No. -III) Deposit Work

Estimated Cost: - Rs 97938 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate	Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	6.39	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1491.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	6.67	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2378.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	18.78	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	86388.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	7.67	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	6457.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	7.20	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1224.00
0						**Total:**	**97938.00**

Amount Quoted by the Contractor in Percentage	**Rs.**	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Dargi Macharyana Judloo Road Km. 0/00 to 11/900 (Sh: Removal of Slips at various Rds.)

Estimated Cost: - Rs 99640 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate	Rate figures	Unit	Amount
1	2	3	4	5	6	7
1	Removal of land slides in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto all leads and lifts as technical specifications 302.3.5 and 1611 as per the directions of Enigneer-in-Charge.	1048.84 Cum	95.00	Rupees Ninety Five Only	Per cubic metre	99640.00
0					**Total:**	**99640.00**

Amount Quoted by the Contractor in Percentage	**Rs.**	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Simloh Dargi via Nagar Road Km. 0/00 to 2/825 (Sh: Removal of Slips at various Rds.)

Estimated Cost. - Rs 98870 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
1	2	3	4	5	6	7
1	Removal of land slides in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto all leads and lifts as technical specifications 302.3.5 and 1611 as per the directions of Enigneer-in-Charge.	1040.74 Cum	95.00	Rupees Ninety Five Only	Per cubic metre	98870.00
0					**Total:**	**98870.00**

Amount Quoted by the Contractor in Percentage	**Rs.**	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Baggipul Thachi Sharog Road km. 0/00 to 6/000 (Sh: Removal of Slips at various Rds.)

Estimated Cost: - Rs 99835 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
1	2	3		4	5	6	7
1	Removal of land slides in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto all leads and lifts as technical specifications 302.3.5 and 1611 as per the directions of Enigneer-in-Charge.	1050.89	Cum	95.00	Rupees Ninety Five Only	Per cubic metre	99835.00
0						**Total:**	**99835.00**

Amount Quoted by the Contractor in Percentage **Rs.**

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damages on Banuti Pahal Road Km. 0/00 to 16/150 (Sh: Construction of Retaining wall 0/210 to 0/217)

Estimated Cost - Rs 91430 /- only
Earnest Money - Rs. 2000 /-only
Time - One Month

S. No.	Sub head and items of work	Qty.		Rate	Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	3.78	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	882.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	5.67	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2021.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	18.20	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	83720.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	3.57	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	3005.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	10.60	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1802.00
0						**Total:**	**91430.00**

Amount Quoted by the Contractor in Percentage	**Rs.**	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner