



OFFICE OF  
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh  
Works Department Jaisinghpur 176095 Phone No. 01894-228030

"CERTIFICATE"

Certified that the tenders are being called in exigency of works of public interest vide this office letter No. PWD/JSD/TA/NIT/ 2025-26- 9010-19 dated 27-01-2026.

Executive Engineer  
Jaisinghpur Division  
HP.PWD, Jaisinghpur.



**OFFICE OF**

Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh Works Department  
Jaisinghpur 176095, Telephone No. 01894-228030, Email [ee-jaipwd-hp@gov.in](mailto:ee-jaipwd-hp@gov.in)

**"NOTICE INVITING TENDERS"**

Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **02.02.2026 up to 11:00 A.M.** and the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **31.01.2026 up to 4:00 PM** and the application for issue of tender form shall be received on **31.01.2026 up to 11:00 AM**. The applications for issue of tender forms should be accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates / Saving Account of the Post Office / Time Deposit account / FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD., Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for **75 days**:-


Sr. No.	Name of Work	Estimated Cost (Rs.)	EMD	Time limit	Cost of tender form
1	C/O Com. Of Link road along with protection wall from Dhabi to Kuthan (SH:-C/O Breast wall at from 0/360 to 0/370.) Deposit SDP/2023/158)	199061.00	4000.00	Two Month	350/-
2	Improvement & widening of link road Bhambher to Khajurnoo via Jogi Basti G.P. Bhuana (SH:-Formation cutting between 0/045 to 0/205) Deposit VKV/2023/503)	248452.00	5000.00	Two Month	350/-
3	C/O Protection of land of Sh. Lekh Raj on Dharamshala dadh Chadhiar road (SH:-C/O R/wall from RD 55/050 to 55/059) Deposit VKV/2024/1227)	94788.00	2000.00	Two Month	350/-
4	Repair of Basketball poll in GSS Jalag GP Jalag (SH:-Repair of Basketball poll ) Deposit VKV/2024/2238)	50000.00	1000.00	Two Month	350/-
5	Restoration of rain Damages to Alampur Harsipattan road Km 0/00 to 24/250 (SH:P/L paver Block in shoulder for widening of road Km 19/308 to 19/350)	99198.00	2000.00	Two Month	350/-
6	Restoration of rain Damages on various road under HP.PWD Sub Division Panchrukhi (SH:-Hiring of J.C.B.)	99000.00	2000.00	Two Month	350/-
7	Restoration of rain Damages on Link road to Sandroan Karnghat Km 0/00 to 7/500 (SH:-C/O unlined drains between Km 0/00 to 7/500)	98784.00	2000.00	Two Month	350/-
8	C/O Tin Shed and Installation of floor tiles in the court yard of community Bhawan at Kaluhi at Solbanehr (SH:-C/O Tin shed and tile work) Deposit VKV/2024/1219)	240025.00	4800.00	Two Month	350/-
9	R/O Concrete work from Sanghole Bridge to Shamshan Ghat (SH:-P/L CC pavement Km 0/200 to 0/230, 0/295 to 0/305 and Edge wall at Rd 0/298 to 0/350) Deposit SDF/2024/1973)	98992.00	2000.00	Two Month	350/-
10	Restoration of rain Damages on Tinbar to Jaisinghpur Road Km 0/00 to 18/300 (SH:-C/O unlined drains between Km 0/00 to 8/000)	98784.00	2000.00	Two Month	350/-
11	Restoration of rain Damages on Tikker to Riddkal road Km 0/00 to 4/00 (SH:-C/O wire crate R/wall at RD 1/800 to 1/805.40) (Under PDNA)	493078.00	9900.00	Two Month	350/-

-----Continued page- 2----



**Terms & Conditions:-**

1. The contractors will have to produce a copy of enlistment / renewal of valid class at time of application / tender form.
2. The contractors will have to produce a copy of GST, EPF and PAN.
3. The contractors are directed to insert the rate / percentage both in figures and words.
4. The tenders forms will not be issued to those contractors who have not completed their previous works / commitments or whose performance is not found satisfactory.
5. The Executive Engineer reserves the right to reject / cancel any or all the tenders without assigning any reason.




Executive Engineer  
Jaisinghpur Division  
HP.PWD., Jaisinghpur.  
On behalf of Governor of (Himachal Pradesh)

No.PWD/JSPR/CB/Tenders/2025-26- 9010-19

Dated: 27-01-2026

**Copy to the following for information and necessary action:-**

1. The Chief Engineer (K.Z.) HP.PWD., Dharamshala.
2. The Superintending Engineer, 5<sup>th</sup> Circle. HPPWD, Palampur.
3. The Executive Engineer (IT) O/O E-in-C, HP.PWD., Shimla.
- 4-6. All the Assistant Engineer under this Division.
- 7-8. The Drawings / Accounts Branch in this office.
9. N.I.T. Register.
10. Notice Board.



Executive Engineer  
Jaisinghpur Division  
HP.PWD., Jaisinghpur.


1

**SCHEDULE OF QUANTITY**

Name of work :-C/O/ Com. Of Link road along with protection wall from Dhabi to Kuthan (SH:-C/O Breast wall at from 0/360 to 0/370.) Deposit SDP/2023/158)


		Estimated cost Rs.		199061.00		
		Earnest Money Rs.		4000.00		
		Time Limits		Two Month		
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	17.25	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	3881.00
2	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size ) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	44.16	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per Cubic Metre	187680.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	30.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	7500.00
<b>Total</b>						<b>199061.00</b>
Quoted Rate (in Figures) Percentage		Excess (+)		%		
		Less (-)		%		
<b>G.Total in Figures</b>						
<b>G.Total in Words</b>						

  
 Executive Engineer,  
 Jaisinghpur Division,  
 HP/PWD Jaisinghpur




SCHEDULE OF QUANTITY						
Name of work :-Improvement & widening of link road Bhambher to Khajurnoo via Jogi Basti G.P. Bhuana (SH:-Formation cutting between 0/045 to 0/205 ) Deposit VKV/2023/503)					Estimated cost Rs.	248452.00
					Earnest Money Rs.	5000.00
					Time Limits	Two Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock,soft rocks, hard rocks, chiseling/ wedging out rock ( where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for useful stone of 44.05 (forty four decimal zero five ) cubic metre at the rate of Rs. 300/- (Rupees Three Hundred) per cubic metre shall be effected from the contractors running bill on pro-rata basis as per actual quantity executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	880.10	282.30	Rupees Two Hundred Eighty Two And Paise Thirty Only	Per cubic metre	248452.00
<b>Total</b>						<b>248452.00</b>
Quoted Rate (in Figures) Percentage					Excess (+)	%
					Less (-)	%
<b>G.Total in Figures</b>						
<b>G.Total in Words</b>						

  
 Executive Engineer  
 Jaisinghpur Division  
 HPPWD Jaisinghpur

**SCHEDULE OF QUANTITY**


Name of work :-C/O Protection of land of Sh. Lekh Raj on Dharamshala dadh Chadhiar road (SH:-C/O R/wall from RD 55/050 to 55/059 ) Deposit VKV/2024/1227)		Estimated cost Rs.		94788.00		
		Earnest Money Rs.		2000.00		
		Time Limits		Two Month		
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	8.91	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	2005.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size ) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	23.58	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per cubic Metre	90783.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	8.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	2000.00
<b>Total</b>						<b>94788.00</b>
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
<b>G.Total in Figures</b>						
<b>G.Total in Words</b>						

  
 Executive Engineer,  
 Jaisinghpur Division,  
 HP/PWD Jaisinghpur



SCHEDULE OF QUANTITY							
Name of work :-Repair of Basketball poll in GSS Jalag GP Jalag (SH:-Repair of Basketball poll ) Deposit						Estimated cost Rs.	50000.00
VKV/2024/2238						Earnest Money Rs.	1000.00
						Time Limits	Two Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Providing and fixing Acrylic basketball Back board with ring and Net including all fitting complete as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.00	25000.00	Rupees Twenty Five Thousand Only	Each	50000.00	
<b>Total</b>							<b>50000.00</b>
Quoted Rate (in Figures) Percentage		Excess (+)			%		
		Less (-)			%		
<b>G.Total in Figures</b>							
<b>G.Total in Words</b>							


  
 Executive Engineer,  
 Jaisinghpur Division,  
 HP.PWD Jaisinghpur

**SCHEDULE OF QUANTITY**

Name of work :-Restoration of rain Damages to Alampur Harsipattan road Km 0/00 to 24/250 (SH:P/L paver Block in shoulder for widening of road Km 19/308 to 19/350)		Estimated cost Rs.		99198.00		
		Earnest Money Rs.		2000.00		
		Time Limits		Two Month		
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation for road work in soil with hydraulic of 0.90 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slops, in accordance with requirements of lines, grades and cross-sections, and transporting to the embankment location with a lift upto 1.50m and lead upto 1000 metre as per Technical specification Clause302.3. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	9.45	61.00	Rupees Sixty One Only	Per Cubic Metre	576.00
2	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size ) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	6.3	4200.00	Rupees Four Thousand Two Hundred Only	Per Cubic Metre	26460.00
3	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishig and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty milimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1.08	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per Cubic Metre	6642.00




4	Providing and laying 80 mm thick Interlocking M-40 grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness 80mm (eighty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	50.40	1300.00	Rupees One Thousand Three Hundred Only	Per square metre	65520.00
<b>Total</b>						<b>99198.00</b>
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
<b>G.Total in Figures</b>						
<b>G.Total in Words</b>						

  
 Executive Engineer,  
 Jaisinghpur Division,  
 HP-PWD Jaisinghpur

**SCHEDULE OF QUANTITY**


Name of work :-Restoration of rain Damages on various road under HP.PWD Sub-Division Panchrukhi (SH:-Hiring of J.C.B.)		Estimated cost Rs.		99000.00		
		Earnest Money Rs.		2000.00		
		Time Limits		Two Month		
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.Note:- The hire charges of plant machinery on per hour basis	90.00	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99000.00
	<b>Total</b>					<b>99000.00</b>
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	<b>G.Total in Figures</b>					
	<b>G.Total in Words</b>					

  
 Executive Engineer,  
 Jaisinghpur Division,  
 HP.PWD Jaisinghpur



**SCHEDULE OF QUANTITY**

Name of work :-Restoration of rain Damages on Link road to Sandroan Karnghat Km 0/00 to 7/500 (SH:- C/O unlined drains between Km 0/00 to 7/500)		Estimated cost Rs.	98784.00			
		Earnest Money Rs.	2000.00			
		Time Limits	Two Month			
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Const. of unlined surface drains of average cross sanctioned area 0.40 SQm in soil to specified lines grades level and dimensions, Excavated material to be used in embankment within all leads and lifts as per technical specification clause 307 and as per direction by the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	2400.00	41.16	Rupees Forty One And Paise Sixteen Only	Per running metre	98784.00
<b>Total</b>						<b>98784.00</b>
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						


  
 Executive Engineer,  
 Jaisinghpur Division,  
 HP PWD Jaisinghpur

3	Supplying & Filling in plinth with sand under floor including watering, ramming, consolidating and dressing complete as per PWD specification. The rate is inclusive of cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	2.50	600.00	Rupees Six Hundred Only	Per Cubic Metre	1500.00
4	Providing and laying 60 mm thick Interlocking M-40 grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness 60mm (sixty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shell be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	100.00	1250.00	Rupees One Thousand Two Hundred Fifty Only	Per square metre	125000.00
5	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishig and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty milimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	2.50	6250.00	Rupees Six Thousand Two Hundred Fifty Only	Per Cubic Metre	15625.00
6	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. The Rate is inclusive of toll tax, GST and any other taxes imposed by the Government.	300.00	116.00	Rupees One Hundred Sixteen Only	Per Kilogram	34800.00



3	Supplying & Filling in plinth with sand under floor including watering, ramming, consolidating and dressing complete as per PWD specification. The rate is inclusive of cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	2.50	600.00	Rupees Six Hundred Only	Per Cubic Metre	1500.00
4	Providing and laying <b>60 mm thick</b> Interlocking M-40 grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness <b>60mm (sixty millimetre)</b> as per drawings and Technical Specification Clause 1504 ( <b>The execution of interlocking paver block shall be allowed after duly testing from the authorized labs</b> ) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	100.00	1250.00	Rupees One Thousand Two Hundred Fifty Only	Per square metre	125000.00
5	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishig and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty milimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	2.50	6250.00	Rupees Six Thousand Two Hundred Fifty Only	Per Cubic Metre	15625.00
6	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. The Rate is inclusive of toll tax, GST and any other taxes imposed by the Government.	300.00	116.00	Rupees One Hundred Sixteen Only	Per Kilogram	34800.00

7	Providing and fixing 0.60mm thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge. including carriage of material with in all leads and lifts and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	9.00	1400.00	Rupees One Thousand Four Hundred Only	Per Square Metre	12600.00
<b>Total</b>						<b>240025.00</b>
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
<b>G.Total in Figures</b>						
<b>G.Total in Words</b>						

  
 Executive Engineer,  
 Jaisinghpur Division,  
 H.P. PWD Jaisinghpur

9

**SCHEDULE OF QUANTITY**


Name of work :-R/O Concrete work from Sanghole Bridge to Shamshan Ghat (SH:-P/L CC pavement Km 0/200 to 0/230, 0/295 to 0/305 and Edge wall at Rd 0/298 to 0/350) Deposit SDF/2024/1973)

Estimated cost Rs.	98992.00
Earnest Money Rs.	2000.00
Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	2.63	1200.00	Rupees One Thousand Two Hundred Only	Per Cubic Metre	3156.00
2	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishing and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty milimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	12.47	6200.00	Rupees Six Thousand Two Hundred Only	Per Cubic Metre	77314.00




3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 ( M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	3.78	4900.00	Rupees Four Thousand Nine Hundred Only	Per cubic metre	18522.00
	<b>Total</b>					<b>98992.00</b>
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	<b>G.Total in Figures</b>					
	<b>G.Total in Words</b>					

  
 Executive Engineer,  
 Jaisinghpur Division,  
 HP.PWD Jaisinghpur

(15)

<b>SCHEDULE OF QUANTITY</b>							
Name of work :-Restoration of rain Damages on Tinbar to Jaisinghpur Road Km 0/00 to 18/300 (SH:-C/O unlined drains between Km 0/00 to 8/000)						Estimated cost Rs.	98784.00
						Earnest Money Rs.	2000.00
						Time Limits	Two Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Const. of unlined surface drains of average cross sanctioned area 0.40 SQm in soil to specified lines grades level and diamensions, Excavated material to be used in embankment within all leads and lifts as per technical specification clause 307 and as per direction by the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	2400.00	41.16	Rupees Forty One And Paise Sixteen Only	Per running metre	98784.00	
<b>Total</b>							<b>98784.00</b>
Quoted Rate (in Figures) Percentage		Excess (+)			%		
		Less (-)			%		
<b>G.Total in Figures</b>							
<b>G.Total in Words</b>							

  
 Executive Engineer,  
 Jaisinghpur Division,  
 H.P.W.D Jaisinghpur

**SCHEDULE OF QUANTITY**

Name of work :-Restoration of rain Damages on Tikker to Riddkal road Km 0/00 to 4/00 (SH:-C/O wire crate R/wall at RD 1/800 to 1/805.40) (Under PDNA)

Estimated cost Rs. 493078.00


Earnest Money Rs. 9900.00

Time Limits Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	35.37	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	7958.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size ) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	24.08	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic Metre	90300.00



3	Providing and laying boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm (hundred millimeters into hundred millimeters ) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 40 kg ( forty kilogram) each in toe walls as per drawing and MORTH technical specifications Clause 2503 and as per direction of the Engineer- In -Charge including carriage of materials within all leads and lifts and other incidental.The rate includes octroi, royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	109.62	3000.00	Rupees Three Thousand Only	Per cubic metre	328860.00
4	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200,1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax,GST or any other taxes imposed by the Government.	58.86	950.00	Rupees Nine Hundred Fifty Only	Per cubic Metre	55917.00
5	Construction of embankment with approved materials obtained from borrow pits any lift transporting to site to spreading, grading to required slope and compacting to meet the requirement of table 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidentals . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	40.99	245.00	Rupees Two Hundred Forty Five Only	Per cubic Metre	10043.00
<b>Total</b>						<b>493078.00</b>
Quoted Rate (in Figures) Percentage		Excess (+)		%		
		Less (-)		%		
<b>G.Total in Figures</b>						
<b>G.Total in Words</b>						

  
 Executive Engineer,  
 Jaisinghpur Division,  
 H.P.WD Jaisinghpur