OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh Works Department
Jaisinghpur 176095, Telephone No. 01894-228030, Email ee-jaipwd-hp@gov.in

"NOTICE INVITING TENDERS"

Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **08.01.2026 up to 11:00 A.M.** and the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **07.01.2026** up to **4:00 PM** and the application for issue of tender from shall be received on **07.01.2026** up to **11.30 AM**. The applications for issue of tender forms should accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates / Saving Account of the Post Office / Time Deposit account / FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD., Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for **75** days:-

Sr. No.	Name of Work	Estimated Cost (Rs.)	EMD	Time limit	Cost of tender form
1	Restoration of rain Damages on Alampur to Harsipattan road Km 0/00 to 25/00 (SH:-P/L earth filling Bye pass road from Jaisinghpur Bazzar between Km 0/00 to 0/450) **(Under PDNA)**	464083.00	9300.00	Two Month	350/-
2	Restoration of rain Damages on Alampur to Harsipattan road Km 0/00 to 25/00 (SH:-C/O R/wall at RD 22/055 to 22/065 to protect the road and existing rain shelter) **(Under PDNA)**	474188.00	9500.00	Two Month	350/-
3	Restoration of rain Damages on Mungal to Rananagar road Km 0/00 to 5/500 (SH:-P/L C/O 900 mm dia RCC Hume pipe culvert at RD 4/600) **(Under PDNA)**	198232.00	4000.00	Two Month	350/-
4	Restoration of rain Damages on Dharamshala Dadh Holta Chadhiar Sandhole Road Km 40/500 to 56/000 (SH:-C/O R/wall from RD 45/030 to 45/040) **(Under PDNA)**	188463.00	3800.00	Two Month	350/-
5	Restoration of rain Damages on Dharamshala Dadh Holta Chadhiar Sandhole Road Km 40/500 to 56/000 (SH:-C/O Hume pipe culvert at RD 49/260, 49/465,49/720 and 50/315) **(Under PDNA)**	277719.00	5600.00	Two Month	350/-
6	Restoration of rain Damages on Alampur to Harsipattan road Km 0/00 to 25/00 (SH:-P/L Wire create B/wall Bye pass road from Jaisinghpur Bazzar at RD 0/075 to 0/103) **(Under PDNA)**	487746.00	9800.00	Two Month	350/-
7	Restoration of rain Damages on Alampur to Harsipattan road Km 0/00 to 25/00 (SH:-C/O wire crate R/wall at RD 22/030 to 22/055) **(Under PDNA)**	274388.00	5500.00	Two Month	350/-

--------Contd. P-2--------

Terms & Conditions:-

1. The contractors will have to produce a copy of enlistment / renewal of valid class at time of application / tender form.
2. The contractors will have to produce a copy of GST, EPF and PAN.
3. The contractors are directed to insert the rate / percentage both in figures and words.
4. The tenders forms will not be issued to those contractors who have not completed their previous works / committments or whose performance is not found satisfactory.
5. The Executive Engineer reserves the right to reject / cancel any or all the tenders without assigning any reason.

Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur
On behalf of Governor of Himachal Pradesh)

No.PWD/JSPR/CB/Tenders/2025-26- 8244-53 **Dated:** 1-1-26

Copy to the following for information and necessary action:-

1. The Chief Engineer (K.Z.) HP.PWD., Dharamshala.
2. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
3. The Executive Engineer (IT) O/O E-in-C, HP.PWD., Shimla.
4-6. All the Assistant Engineer under this Division.
7-8. The Drawings / Accounts Branch in this office.
9. N.I.T. Register.
10. Notice Board.

Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.

OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh Works Department
Jaisinghpur 176095 Phone No. 01894-228030
Email ee-jaipwd-hp@gov.in

"CERTIFICATE"

Certified that the tenders are being called in exigency of works of public interest vide this office letter No. PWD/JSD/TA/NIT/ 2025-26- 8244-53 dated 01-01-2026

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Alampur to Harsipattan road Km 0/00 to 25/00 (SH:-P/L earth filling Bye pass road from Jaisinghpur Bazzar between Km 0/00 to 0/450) **(Under PDNA)**

Estimated cost Rs.	**464083.00**
Earnest Money Rs.	**9300.00**
Time Limits	**Two month**

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Construction of embankment with approved materials obtained from borrow pits any lift transporting to site to spreading, grading to required slope and compacting to meet the requirement of table 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidentals . The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	1856.33	250.00	Rupees Two Hundred Fifty Only	Per cubic Metre	464083.00
	Total					**464083.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Alampur to Harsipattan road Km 0/00 to 25/00 (SH:-C/O R/wall at RD 22/055 to 22/065 to protect the road and existing rain shelter) **(Under PDNA)**

Estimated cost Rs.	**474188.00**
Earnest Money Rs.	**9500.00**
Time Limits	**Two month**

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	31.50	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	7088.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, toll tax, GST and all type of other taxes imposed by the Government.	120.00	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic Metre	450000.00

3	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section1200,1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax,GST or any other taxes imposed by the Government.	18.00	950.00	Rupees Nine Hundred Fifty Only	Per cubic Metre	17100.00
	Total					**474188.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP,PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Mungal to Rananagar road Km 0/00 to 5/500 (SH:-P/L C/O 900 mm dia RCC Hume pipe culvert at RD 4/600) **(Under PDNA)**

Estimated cost Rs.	**198232.00**
Earnest Money Rs.	**4000.00**
Time Limits	**Two month**

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	42.73	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	9614.00

2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etctera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	1.29	4850.00	Rupees Four Thousand Eight Hundred Fifty Only	Per cubic metre	6257.00
3	Providing and laying mechanically mixed and vibrated concrete for plain/ cement concrete in sub structure for all type of structure complete using plain cement concrete grade M-15 (M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilograme) per cubic metre in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying under water complete for all heights/ depths including the cost of form work in abutments as per drawings and M.O.R.D. technical specification section 800, 900 and 1200, and as per the direction of Engineer-in-Charge including carriage of material within all leads , lifts and other incidentals .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	11.12	5250.00	Rupees Five Thousand Two Hundred Fifty Only	Per cubic metre	58380.00

4	Providing and laying (to level or slope) 900mm dia (nine hundred millimeter) diameter reinforced cement concrete pipes IS Class NP-2 for culverts in single row including fixing collar with cement mortar 1:2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, bedding concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications clause 1101 and as per direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate including of octroi,royality,Malkana, toll tax , or other taxes imposed by the Government.	7.50	3200.00	Rupees Three Thousand Two Hundred Only	Per Running metres	24000.00
5	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, toll tax, GST and all type of other taxes imposed by the Government.	25.06	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per Cubic Metre	96481.00
6	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	14.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	3500.00
	Total					**198232.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer
Jaisingh... Division
HPPWD ...singhpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Dharamshala Dadh Holta Chadhiar sandhole Road Km 40/500 to 56/000 (SH:-C/O R/wall from Rd 45/030 to 45/040) **(Under PDNA)**

Estimated cost Rs.	**188463.00**
Earnest Money Rs.	**3800.00**
Time Limits	**Two month**

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	16.30	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	3668.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, toll tax, GST and all type of other taxes imposed by the Government.	46.70	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per Cubic Metre	179795.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	20.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	5000.00
	Total					**188463.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Dharamshala Dadh Holta Chadhiar sandhole Road Km 40/500 to 56/000 (SH:-C/O Hume pipe culvert at Rd 49/260, 49/465,49/720 and 50/315) **(Under PDNA)**

Estimated cost Rs.	**277719.00**
Earnest Money Rs.	**5600.00**
Time Limits	**Two month**

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	12.07	250.00	Rupees Two Hundred Fifty Only	Per cubic Metre	3018.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etctera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	48.08	4850.00	Rupees Four Thousand Eight Hundred Fifty Only	Per cubic metre	233188.00

3	Providing and laying (to level or slope) 900mm dia (nine hundred millimeter) diameter reinforced cement concrete pipes IS Class NP-2 for culverts in single row including fixing collar with cement mortar 1:2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, bedding concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications clause 1101 and as per direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate including of octroi,royality,Malkana, toll tax , or other taxes imposed by the Government.	12.50	3000.00	Rupees Three Thousand Only	Per Running metres	37500.00
4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	16.05	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	4013.00
	Total					**277719.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Alampur to Harsipattan road Km 0/00 to 25/00 (SH:-P/L Wire create B/wall Bye pass road from Jaisinghpur Bazzar at Rd 0/075 to 0/103) **(Under PDNA)**

Estimated cost Rs.	**487746.00**
Earnest Money Rs.	**9800.00**
Time Limits	**Two month**

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	35.28	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	7938.00
2	Providing and laying boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm (hundred millimeters into hundred millimeters) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 40 kg (forty kilogram) each in toe walls as per drawing and MORTH technical specifications Clause 2503 and as per direction of the Engineer- In –Charge including carriage of materials within all leads and lifts and other incidental.The rate includes octroi, royality,Malkana,Tol tax, GST or any other taxes imposed by the Government.	161.28	2975.00	Rupees Two Thousand Nine Hundred Seventy Five Only	Per cubic metre	479808.00
	Total					**487746.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Alampur to Harsipattan road Km 0/00 to 25/00 (SH:-C/O wire crate R/wall at Rd 22/030 to 22/055) **(Under PDNA)**

Estimated cost Rs.	**274388.00**
Earnest Money Rs.	**5500.00**
Time Limits	**Two month**

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	85.50	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	19238.00
2	Providing and laying boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm (hundred millimeters into hundred millimeters) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 40 kg (forty kilogram) each in toe walls as per drawing and MORTH technical specifications Clause 2503 and as per direction of the Engineer- In –Charge including carriage of materials within all leads and lifts and other incidental.The rate includes octroi, royality,Malkana,Tol tax, GST or any other taxes imposed by the Government.	81.00	3150.00	Rupees Three Thousand One Hundred Fifty Only	Per cubic metre	255150.00
	Total					**274388.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur