





OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh Works Department
Jaisinghpur 176095 Phone No. 01894-228030
Email ee-jaipwd-hp@gov.in

"CERTIFICATE"

Certified that the tenders are being called in exigency of works of public interest vide this office letter No. PWD/JSD/TA/NIT/ 2025-26- 8259-68 dated 02-01-2026.


**Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur**




OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh Works Department
Jaisinghpur 176095, Telephone No. 01894-228030, Email ee-jaipwd-hp@gov.in

"NOTICE INVITING TENDERS"


Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **12.01.2026 up to 11:00 A.M.** and the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **09.01.2026 up to 4:00 PM** and the application for issue of tender form shall be received on **08.01.2026 up to 11.30 AM.** The applications for issue of tender forms should be accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates / Saving Account of the Post Office / Time Deposit account / FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD., Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for **75 days:-**

Sr. No.	Name of Work	Estimated Cost (Rs.)	EMD	Time limit	Cost of tender form
1	Restoration of rain Damages on Gander Siyara Kudana road Km 0/00 to 9/780 (SH:- C/O B/wall in wire crate between RD 0/320 to 0/343 and 0/950 to 0/955) Under PDNA	491380.00	9900.00	Two Month	350/-
2	Restoration of rain Damages on Various roads under Balakrupi Sub Division (SH:- Hiring of Hydraulic Excavator (JCB) for removal of slips and boulder of various roads under Gander section)	99110.00	2000.00	Two Month	350/-
3	A/R & M/O various road in Balakrupi Section under Balakrupi Sub-Division HP.PWD Jaisinghpur (SH:- Providing and Supplying Delineators)	99000.00	2000.00	Two Month	350/-
4	Restoration of rain Damages on link road from Biara to Batthan Km 0/00 to 3/500 (SH:- P/L CC Pavement from Km 1/00 to 1/055 to 1/085)	99450.00	2000.00	Two month	350/-
5	Restoration of rain Damages on Dharamshala Dadh Holta Chadhiar sandhole Road Km 40/500 to 56/000 (SH:-C/O R/wall from RD 53/570 to 53/585 and 53/790 to 53/805) PDNA	464432.00	9300.00	Two Month	350/-
6	A/R & M/O various road in Gander Section under Balakrupi Sub-Division HP.PWD Balakrupi (SH:- Providing and Supplying Delineators)	99750.00	2000.00	Two Month	350/-

Terms & Conditions:-

1. The contractors will have to produce a copy of enlistment / renewal of valid class at time of application / tender form.
2. The contractors will have to produce a copy of GST, EPF and PAN.
3. The contractors are directed to insert the rate / percentage both in figures and words.
4. The tenders forms will not be issued to those contractors who have not completed their previous works / commitments or whose performance is not found satisfactory.
5. The Executive Engineer reserves the right to reject / cancel any or all the tenders without assigning any reason.


Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.
On behalf of Governor of Himachal Pradesh)


No.PWD/JSPR/CB/Tenders/2025-26-

8259-68

Dated: 02-01-26

Copy to the following for information and necessary action:-

1. The Chief Engineer (K.Z.) HP.PWD., Dharamshala.
2. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
3. The Executive Engineer (IT) O/O E-in-C, HP.PWD., Shimla.
- 4-6. All the Assistant Engineer under this Division.
- 7-8. The Drawings / Accounts Branch in this office.
9. N.I.T. Register.
10. Notice Board.



Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur,


SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Gander siyara Kudana road Km 0/00 to 9/780 (SH:- C/O B/wall in wire crate between RD 0/320 to 0/343 and 0/950 to 0/955) Under PDNA

		Estimated cost Rs.		491380.00	
		Earnest Money Rs.		9900.00	
		Time Limits		Two month	
S. N.	Description of Item	Quantity	Rate		Unit
			In Figures	In Word	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	20.00	230.00	Rupees Two Hundred Thirty Only	Per cubic Metre
2	Providing and laying boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm (hundred millimeters into hundred millimeters) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 40 kg (forty kilogram) each in toe walls as per drawing and MORTH technical specifications Clause 2503 and as per direction of the Engineer- In -Charge including carriage of materials within all leads and lifts and other incidental.The rate includes octroi, royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	146.40	3325.00	Rupees Three Thousand Three Hundred Twenty Five Only	Per cubic metre
	Total				491380.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%
		Less (-)			%
	G.Total in Figures				
	G.Total in Words				

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur

SCHEDULE OF QUANTITY						
Name of work :-Restoration of rain Damages on Various roads under balakrupi Sub Division (SH:- Hiring of Hydraulic Excavator (JCB) for removal of slips and boulder of various roads under Gander section)				Estimated cost Rs.		99110.00
				Earnest Money Rs.		2000.00
				Time Limits		One month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. Note:- The hire charges of plant machinery on per hour basis	90.10	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99110.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	99110.00
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					



 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :A/R & M/O various road in Balakrupi section under Balakrupi Sub-Division HP.PWD
Jaisinghpur (SH:- Providing and Supplying Delineators)

Estimated cost Rs.	99000.00
Earnest Money Rs.	2000.00
Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and supplying delineators made of ABC round body fitted with 2 Nos 100 mm (one hundred millimetre) high reflective reflectors and mounted on MS pipe of 65 mm (Sixty five millimetre) dia and 750 mm (seven hundred fifty millimetre) height duly powder coated anti rust and antitheft steel tube installed as per entire satisfaction and ps as per direction of Engineer-In-Charge.The rate includes octroi,royalty,Malkana,Tol tax, GST imposed by the Government.	132.00	750.00	Rupees Seven Hundred Fifty Only	Each	99000.00
	Total					99000.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

4

SCHEDULE OF QUANTITY						
Name of work :-Restoration of rain Damages on link road from Biara to Batthan Km 0/00 to 3/500 (SH:- P/L CC Pavement from Km 1/00 to 1/055 to 1/085)				Estimated cost Rs.		99450.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishig and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty milimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	15.30	6500.00	Rupees Six Thousand Five Hundred Only	Per Cubic Metre	99450.00
	Total					99450.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Dharamshala Dadh Holta Chadhiar sandhole Road Km 40/500 to 56/000 (SH:-C/O R/wall from RD 53/570 to 53/585 and 53/790 to 53/805) Under PDNA

Estimated cost Rs.		464432.00	
Earnest Money Rs.		9300.00	
Time Limits		Two month	
Rate		Unit	Amount
	In Word		
0	Rupees Two Hundred Twenty Five Only	Per cubic Metre	8336.00
	Rupees Four Thousand Two Hundred Fifty Only	Per Cubic Metre	165750.00
	Rupees Nine Hundred Fifty Only	Per cubic metre	10403.00


4	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	70.05	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per Cubic Metre	269693.00
5	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	41.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	10250.00
	Total					464432.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

6

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
Name of work :A/R & M/O various road in Gander section under Balakrupi Sub-Division HP.PWD Jaisinghpur (SH:- Providing and Supplying Delineators)				Estimated cost Rs.		99750.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and supplying delineators made of ABC round body fitted with 2 Nos 100 mm (one hundred millimetre) high reflective reflectors and mounted on MS pipe of 65 mm (Sixty five millimetre) dia and 750 mm (seven hundred fifty millimetre) height duly powder coated anti rust and antitheft steel tube installed as per entire satisfaction and ps as per direction of Engineer-In-Charge.The rate includes octroi,royalty,Malkana,Tol tax, GST imposed by the Government.	133.00	750.00	Rupees Seven Hundred Fifty Only	Each	99750.00
	Total					99750.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur