



OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095 Phone No. 01894-228030

"CERTIFICATE"

Certified that the tenders are being called in exigency of works of public interest vide this office letter No. PWD/JSD/TA/NIT/ 2025-26- 8812-21 dated 22/01/2026.

Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.



"NOTICE INVITING TENDERS"

Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **31.01.2026 up to 11:00 A.M.** and the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **30.01.2026 up to 4:00 PM** and the application for issue of tender form shall be received on **29.01.2026 up to 04.00 PM**. The applications for issue of tender forms should accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates / Saving Account of the Post Office / Time Deposit account / FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD., Division Jaisinghpur.


The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for **75 days**:-

Sr. No.	Name of Work	Estimated Cost (Rs.)	EMD	Time limit	Cost of tender form
1	C/O Jeepable road in Jakh Baba Ward No.2 (SH:-Improvement, P/L CC Pavement in extension at RD 0/00 to 0/020, 0/070 to 0/090, 0/170 to 0/190, 0/200 to 0/220, U-shape drain at Km 0/070 to 0/090, 0/190 to 0/220, R/wall at RD 1/760 to 1/766 and toe wall of damaged hume pipe at RD 1/766) Deposit	481497.00	9700.00	Two Month	350/-
2	Restoration of rain Damages on Alampur to Harsipattan road Km 0/00 to 25/00 (SH:-P/L GSB Bye pass road from Jaisinghpur Bazaar Km 0/00 to 0/450) PDNA	488070.00	9800.00	Two Month	350/-
3	Restoration of rain Damages under 92.50 Mtr. Span PSC Box Girder Single lane Bridge over Negual Khad on Paprola Alampur road at RD 2/770 (SH:-Removal of slips along excavated Paprola side Abutment) NDRF/PDNA	498960.00	10000.00	Two Month	350/-
4	C/O Utility Stadium at Jaisinghpur Distt. Kangra (HP) (SH:- C/O Boundary wall from SBI ChowK from 0/068 to 0/098) (Deposit)	499798.00	10000.00	Three Month	350/-
5	C/O 1st floor Community Hall at Village Balu Ward No.1 G.P. Gadiara (SH:-C/O Truss alongwith prepainted sheet roofing) Deposit MPLAD 2023/316)	499972.00	10000.00	Two Month	350/-
6	Restoration of rain Damages on Alampur to Harsipattan road Km 0/00 to 25/00 (SH:-P/L Slab over existing sub structure at RD 0/080 and steel Mesh Over Existing drain at Km 0/00 ot 0/020 By pass road from Jaisinghpur Bazaar Km 0/00 to 0/450) PDNA	493224.00	9900.00	Two Month	350/-

-Contd-P-2-

Terms & Conditions:-

1. The contractors will have to produce a copy of enlistment / renewal of valid class at time of application / tender form.
2. The contractors will have to produce a copy of GST, EPF and PAN.
3. The contractors are directed to insert the rate / percentage both in figures and words.
4. The tenders forms will not be issued to those contractors who have not completed their previous works / commitments or whose performance is not found satisfactory.
5. The Executive Engineer reserves the right to reject / cancel any or all the tenders without assigning any reason.




Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur
On behalf of Governor of Himachal Pradesh)

No.PWD/JSPR/CB/Tenders/2025-26- 8812-21

Dated: 22/01/2026

Copy to the following for information and necessary action:-

1. The Chief Engineer (K.Z.) HP.PWD., Dharamshala.
2. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
3. The Executive Engineer (IT) O/O E-in-C, HP.PWD., Shimla.
- 4-6. All the Assistant Engineer under this Division.
- 7-8. The Drawings / Accounts Branch in this office.
9. N.I.T. Register.
10. Notice Board.



Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur


SCHEDULE OF QUANTITY

Name of work :-C/O Jeepable road in Jakh Baba Ward No.2 (SH:-Improvement, P/L CC Pavement in extension at RD 0/00 to 0/020, 0/070 to 0/090, 0/170 to 0/190, 0/200 to 0/220, U-shape drain at Km 0/070 to 0/090, 0/190 to 0/220, R/wall at Rd 1/760 to 1/766 and toe wall of damaged hurne pipe at RD 1/760) Deposit		Estimated cost Rs.				
		Earnest Money Rs.	481497.00			
		Time Limits	Two Month			
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	8.78	2050.00	Rupees Two Thousand Fifty Only	Per Cubic Metre	17999.00
2	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishing and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty millimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	14.25	6250.00	Rupees Six Thousand Two Hundred Fifty Only	Per Cubic Metre	89063.00

3	<p>Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.</p>	1.80	225.00	Rupees Two Hundred Twenty Five Only	Per cubic metre	405,00
4	<p>Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.</p>	12.75	4850.00	Rupees Four Thousand Eight Hundred Fifty Only	Per cubic metre	61838.00

5	<p>Excavation in hilly area in all heights and depths and in all kind of soil by all manual/mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for useful stone of 16.65 (sixteen decimal six five) cubic metre at the rate of Rs. 300/- (Rupees Three Hundred) per cubic metre shall be effected from the contractors running bill on pro-rata basis as per actual quantity executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.</p>	332.85	243.75	Rupees Two Hundred Forty Three And Paise Seventy Five Only	Per cubic metre	81132.00
6	<p>Providing and laying cement concrete 1.5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.</p>	40.32	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per cubic Metre	155232.00

7	Providing and laying mechanically mixed and vibrated concrete for plain/ cement concrete in sub structure for all type of structure complete using plain cement concrete grade M-15 (M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilogram) per cubic metre in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in abutments as per drawings and M.O.R.D. technical specification section 800, 900 and 1200, and as per the direction of Engineer-in-Charge including carriage of material within all leads , lifts and other incidentals .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	11.49	5400.00	Ruppes Five Thousand Four Hundred Only	Per cubic metre	62046.00
8	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	15.00	250.00	Ruppes Two Hundred Fifty Only	Per Running Metre	3750.00
9	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200,1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	10.56	950.00	Ruppes Nine Hundred Fifty Only	Per cubic metre	10032.00
Total						481497.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						


 Executive Engineer
 Jaisinghpur Division
 H.P.P.W.D. Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain Damages on Alampur to Harsipattan road Km 0/00 to 25/00 (SH:-P/L)
 GSB Bye pass road from Jaisinghpur Bazaar Km 0/00 to 0/450) PDNA

Estimated cost Rs. **488070.00**
 Earnest Money Rs. **9800.00**
 Time Limits **Two Month**

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Preparation of sub grade by dressing to camber (Earth work for the cutting involved for Sub grade to be paid for separately depending upon the classification of soil completed as per HPPWD specifications including hauling of materials in all leads, lifts and other incidentals and as per the entire satisfaction and directions of Engineer-in-charge. The rate including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2475.00	1.20	Rupees One And Paise Twenty Only	Per square metre	2970.00
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub-grade completed as per HP.PWD specifications. The rate including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2475.00	1.00	Rupee One Only	Per square metre	2475.00
3	Construction of granular sub-base by providing well graded material, spreading in uniform layers with Tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. for grading-1 material and as per direction by the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	371.25	1300.00	Rupees One Thousand Three Hundred Only	Per cubic metre	482625.00
Total						488070.00
		Quoted Rate (in Figures) Percentage	Excess (+)		%	
			Less (-)		%	
		G.Total in Figures				
		G.Total in Words				

Om
 Executive Engineer
 Jaisinghpur Division
 HPPWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain Damages under 92.50Mtr. Span PSC Box Girder Single lane Bridge over Negual Khad on Paprola alampur road at Rd 2/770 (SH:-Removal of slips along excavated Paprola side Abutment) NDRF/PDNA

S. N.	Description of Item	Quantity	Rate		Unit	Amount	Estimated cost Rs.	
			In Figures	In Word			Earnest Money Rs.	Time Limits
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5m and lead upto 1000 metre as per technical specification 302.3.5 and 1611 (One hours hiring will be justified after removal of 25 cubic metre quantity of disposed material) as per drawing as per the direction of Engineer-in-Charge within all lifts and other incidents. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	5544.00	90.00	Rupees Ninety Only	Per cubic metre.	498960.00	10000.00	Two Month
	Total					498960.00		
	Quoted Rate (in Figures) Percentage	Excess (+) Less (-)			% %			
	G.Total in Figures							
	G.Total in Words							


Amrind
 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- C/O Utility Stadium at Jaisinghpur Distt. Kangra (HP) (SH:- C/O Boundary wall from SBI Chowk from 0/068 to 0/098) (Deposit)

S. N.	Description of Item	Quantity	Rate		Unit	Amount									
			In Figures	In Word											
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains etc. (not exceeding 1.5 m (One decimal five millimetre) in width or 10sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One decimal five millimetre), including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m (Fifty metre). All kind of soil/ordinary soil including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	9.00	250.00	Rupess Two Hundred Fifty Only	Per cubic metre	2250.00									
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	1.80	3750.00	Rupess Three Thousand Seven Hundred Fifty Only	Per cubic Metre	6750.00									
<table border="1"> <thead> <tr> <th colspan="2">Estimated cost Rs.</th> <th>499798.00</th> </tr> <tr> <th colspan="2">Earnest Money Rs.</th> <th>10000.00</th> </tr> <tr> <th colspan="2">Time Limits</th> <th>Two month</th> </tr> </thead> </table>							Estimated cost Rs.		499798.00	Earnest Money Rs.		10000.00	Time Limits		Two month
Estimated cost Rs.		499798.00													
Earnest Money Rs.		10000.00													
Time Limits		Two month													

3	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	7.50	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per Cubic Metre	31875.00
4	Courseed rubble masonry (first sort) with hard stone in foundation and plinth with Cement mortar 1:6 (one cement : six coarse sand) including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and as per the direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	6.08	5600.00	Rupees Five Thousand Six Hundred Only	Per Cubic Metre	34048.00
5	Steel work welded in built up sections Anarkali type cast iron jali/Railing work including cutting hoisting and fixing in position and applying a paint in gratings framed guard bars ladders railings and similar work etcetera complete including carriage of materials within all leads lifts and other incidentals and as per direction of the Engineer-in-charge. The rate is inclusive of octroi, royalty, malkana and all type of taxes imposed by the Government. .	2451.53	160.00	Rupees One Hundred Sixty Only	Per Kilogram	392245.00
6	Steel work riveted in built up sections, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint in grating-framed guards, bars, ladders railings, brackets and similar worksas per drawing and design and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	296.64	110.00	Rupees One Hundred Ten Only	Per Kilogram	32630.00
Total						499798.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						


 Executive Engineer
 Jaisinghpur Division
 HPPWD Jaisinghpur

35

SCHEDULE OF QUANTITY

Name of work :-C/O 1st floor Community Hall at Village Balu Ward No.1 G.P. Gadiara (SH:-C/O Truss alongwith pre-painted sheet roofing) Deposit MPLAD 2023/316

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing form work with mild steel plates 3.15 mm (three point one five millimetre) thick welded with angle iron in frames 30x30x5mm (Thirty into thirty into five millimetre) so as to give a fair finish including centring, shuttering, strutting and propping etcetra with wooden battens and ballies for all heights / depths of propping and centring below supporting floor to ceiling and removal of the same for insitu-reinforced concrete and plain concrete work in Beams, cantilever, girders and lintels Sides and soffits of beams,beam haunchings, cantilevers, girders, bressumers and lintels upto any height/depth upto all floor level including entire carriage of materials with in all leads, lifts and other incidental as per drawings, technical specifications and as per the direction of Engineer-in-Charge.The rate is inclusive of octroi, royalty, malkhana, toll tax, GST any other taxes imposed by the Government.	70.25	350.00	Rupees Three Hundred Fifty Only	Per Square metre	24588.00
2	Providing and laying cement concrete work in suspended floor ,roofs , having slope up to 15,landings , balconies,shelves , Chajjas,lintels, bands, plain window sills, stair case and sprial stair case above plinth level upto fall floor level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 Cement :1.50 sand :3 graded stone aggregate 20 mm nominal size) as per specifications, approved drawing , design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	4.08	7000.00	Rupees Seven Thousand Only	Per cubic Metre	28560.00

Estimated cost Rs.

499972.00

Earnest Money Rs.

10000.00


Time Limits

Two month

6	<p>Providing and fixing pre-painted steel sheet roofing of Tata Dura shine/Reliance/ Jindal/ Steel 0.60 mm thickness (ISI marked Z-120) pre-painted steel sheet wise hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (twenty) micron over 5 (Five) micron and back coating of polyester 5 (five) micron over 5 (five) micron primer coating including fixing with pre-painted iron J or L hooks, bolts, nuts 6 mm (six millimeter) dia with pre-painted limpat and rubber washers complete with all accessories required. The material supplied will be accompanied with test certificate and 20 (twenty) years warranty from the company against corrosion, fading of colour and manufacture defects and further as per specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.</p>	95.32	1450.00	Rupees One Thousand Four Hundred Fifty Only	Per Square metre	138214.00
7	<p>Providing and fixing pre-painted sheet ridge or hips 60cm (sixty centimetre) over all of Kotar metal skin trapezoidal profiled sheeting 0.60mm cover with over all width 1126mm (one thousand one hundred twenty six) 28mm (twenty eight) crest depth at 353mm (three hundred fifty three) 2mm (two millimetre) C/C crest distance. There will be two ribs at the centre for stiffening heaving crest depth of 2.5mm (two decimal five millimetre) the main crest with at top zinc waiting top coat with regular modified polyester coating of approved shade and balancing reverse coat 5.5mm (five decimal five millimetre) dia and 550mm (five hundred fifty millimetre) length with DPDM seal complete in all respect as per approved drawing design The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.</p>	23.70	800.00	Rupees Eight Hundred Only	Per Running Metre	18960.00

6	<p>Providing and fixing prepainted steel sheet roofing of Tata Dura shine/Reliance/ Jindal/ Steel 0.60 mm thickness (ISI marked Z-120) prepainted steel sheet wise hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (twenty) micron over 5 (five) micron and back coating of polyester 5 (five) micron over 5 (five) micron primer coating including fixing with prepainted iron J or L hooks, bolts , nuts 6 mm (six millimeter) dia with prepainted limpat and rubber washers complete with all accessories required. The material supplied will be accompanied with test certificate and 20 (twenty) years warranty from the company against corrosion, fading of colour and manufacture defects and further as per specifications, approved drawing , design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.</p>	95.32	1450.00	Rupees One Thousand Four Hundred Fifty Only	Per Square metre	138214.00
7	<p>Providing and fixing pre-painted sheet ridge or hips 60cm (sixty centimetre) over all of kotar metal skin trapezoidal profiled sheeting 0.60mm cover with over all width 1126mm (one thousand one hundred twenty six) 28mm (twenty eight) crest depth at 353mm (three hundred fifty three) 2mm (two millimetre) C/C crest distance. There will be two ribs at the centre for stiffening heaving crest depth of 2.5mm (two decimal five millimetre) the main crest with at top zinc waiting top coat with regular modified polyester coating of approved shade and balancing reverse coat 5.5mm (five decimal five millimetre) dia and 550mm (five hundred fifty millimetre) length with DPPDM seal complete in all respect as per approved drawing design The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.</p>	23.70	800.00	Rupees Eight Hundred Only	Per Running Metre	18960.00

8	Providing and fixing M.S. B.P. sheet 2 mm (two millimetre) thick of TATA/SAIL / Reliance / Jindal for eaves board/Facia/Soffit/Ceiling including cutting, fixing and jointing with gas/electric welding with steel roof member and applying a coat of red lead primer complete as per PWD specification, approved drawing and design (frame work is to be measured and paid for separately) including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. The Rate is inclusive of toll tax, GST and any other taxes imposed by the Government.	7.16	1550.00	Rupees One Thousand Five Hundred Fifty Only	Per Square Metre	11098.00
9	15 mm (Fifteen millimetre) cement plaster in single coat on rough side of brick/ stone masonry for interior plastering upto floor two level with CM 1:6 (One cement : Six Sand) including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	79.52	220.00	Rupees Two Hundred Twenty Only	Per Square Metre	17494.00
10	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 lit/ 10 sqm) over and including priming coat of exterior primer applied 2.20Kg/10Sqm) and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	79.52	90.00	Rupees Ninety Only	Per Square Metre	7157.00
Total						499972.00
		Excess (+)			%	
		Less (-)			%	
		G.Total in Figures				
		G.Total in Words				


 Executive Engineer,
 Jaisinghpur Division,
 HP PWD Jaisinghpur

3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in Sub Structure using grade M-20 (M-twenty) design mix with cement contents not less than 330 kg (three hundred thirty kilogram) per cubic metre with 40mm (forty millimetre) nominal size graded crushed stone aggregate as per drawing and M.O.R.D. technical specification section 800,900,1200 including the cost of form work and curing complete in aboutment etcetera and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.76	6200.00	Rupees Six Thousand Two Hundred Only	Per cubic Metre	23312.00
4	Supplying fitting and placing HYSDB bar reinforcement in sub-structure complete as per drawing and MORTH technical specifications section 1600 and 2200 including cutting, bending, binding, straightening and placing in position complete in all respect including cost of binding wire upto all height and depth as directed by the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	0.090	95000.00	Rupees Ninety Five Thousand Only	Per Metric Tonne	8550.00
5	Supplying fitting and placing HYSDB bar reinforcement in super structure complete as per drawing and MORTH technical specifications section 1600 and 2300 including cutting, bending, binding, straightening and placing in position complete in all respect including cost of binding wire upto all height and depth as directed by the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1.04	97000.00	Rupees Ninety Seven Thousand Only	Per Metric Tonne	100880.00
6	Steel work riveted in built up sections, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint in grating, framed guards, bars, ledgers railings, brackets and similar works as per drawing and design and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1936.18	110.00	Rupees One Hundred Ten Only	Per Kilogram	212980.00

3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in Sub Structure using grade M-20 (M-twenty) design mix with cement contents not less than 330 kg (three hundred thirty kilogram) per cubic metre with 40mm (forty millimetre) nominal size graded crushed stone aggregate as per drawing and M.O.R.D. technical specification section 800,900,1200 including the cost of form work and curing complete in aboutment etcetera and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.76	6200.00	Rupees Six Thousand Two Hundred Only	Per cubic Metre	23312.00
4	Supplying fitting and placing HYSD bar reinforcement in sub-structure complete as per drawing and MORTH technical specifications section 1600 and 2200 including cutting, bending, binding, straightening and placing in position complete in all respect including cost of binding wire upto all height and depth as directed by the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	0.090	95000.00	Rupees Ninety Five Thousand Only	Per Metric Tonne	8550.00
5	Supplying fitting and placing HYSD bar reinforcement in super structure complete as per drawing and MORTH technical specifications section 1600 and 2300 including cutting, bending, binding, straightening and placing in position complete in all respect including cost of binding wire upto all height and depth as directed by the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1.04	97000.00	Rupees Ninety Seven Thousand Only	Per Metric Tonne	100880.00
6	Steel work riveted in built up sections, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint in grating, framed guards, bars, ladders railings, brackets and similar works as per drawing and design and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1936.18	110.00	Rupees One Hundred Ten Only	Per Kilogram	212980.00

