

REGISTERED

Office of the Executive Engineer, B&R Division, HP PWD Kalpa District Kinnaur (HP)

Web:- www.hppwd.gov.in E mail:- hp-kin@nic.in

Phone No:- 01786-226027 Fax:- 01786-226027.

No:- PW/KNR-E-Tender/2026-
To

10853-55

Dated:- 28/11/2026


The Executive Engineer (IT Cell),
HP.PWD. Shimla-2.

Subject:-

Publication of Tender Notice (OFFLINE)

Enclosed please find herewith the Tender of works costing above 1.00 Lakh and upto 5.00 Lakh as given in the Notice Inviting Tender for uploading on the departmental website as per notification vide Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B) 1/2020 dated 16-07-2021 and even file No. 1/2024 dated 03-01-2024, 03-01-2025 and 1/2024-241828 dated 17-07-2025 and PWD-B-A0(3)/ 8/2025-300858 dated 13-11-2025. The works mentioned in the tender notice are urgent in nature and public interest.

Encl:- NIT, Schedule of Quantity
& Certificate.


Executive Engineer,
Kalpa Division,
HP.PWD, Kalpa.

Copy forwarded for information to:-

1. The Superintending Engineer, 11th Circle, HP.PWD. Rampur Bushahr.
2. Copy to Drawing Branch in this office.


Executive Engineer,
Kalpa Division,
HP. PWD, Kalpa

HP.P.W.D. TENDER NOTICE (offline)

Sealed item rate offline tender on form PWD-6 & 8 are hereby invited on behalf of Governor of Himachal Pradesh by the Executive Engineer, Kalpa Division, HP,PWD; Kalpa for the following works from the approved and eligible contractors enlisted in HP.PWD; so as to reach in the office of the Executive Engineer Kalpa Division HP.PWD. Kalpa on or before **07-02-2026 up to 10.30 A.M.** and shall be opened on the same day at **11:00 AM** in presence of intending contractors or their authorized representatives. The tender form documents can be had from this office (Kalpa Division, HPPWD Kalpa) against cash payment (Non-refundable) on **06-02-2026 upto 4:00 P.M.** No application for issue of tender forms will be received on **06-02-2026 after 4:00 PM.** If the office happens to be closed on the above mentioned dates, the tenders will be sold/opened on the next working day at the same time and venue. The Earnest Money in the shape of National Saving Certificate, F.D.R,s any Post office/Bank in H.P. duly pledged in the name of Executive Engineer, Kalpa Division, HP.PWD. Kalpa must accompany with each tenders. Conditional tenders and application (For purchase of tender forms) received without Earnest Money summarily be rejected. The officer of the tenders shall be kept open for 120 days. The Executive Engineer Reserves (Right to accept or to reject any) or all the tenders without assigning any reasons.

Sr. No	Name of work	Estimated cost	Earnest Money	Time allowed	Cost of form	Eligible class of contractor
1	C/O Link road from Labrang Bus stand to Labrang Gompa Km 0/00 to 1/500 (SH:- C/O R/Wall in Gl. wire carte at RD 0/00 to 0/028)	4,76,574/-	10,000/-	One Month	350/-	"C" & "D" Class
2	C/O Link road from Labrang Bus stand to Labrang Gompa Km 0/00 to 1/500 (SH: C/O R/Wall in G.L. wire carte at RD 0/030 to 0/058)	4,77,890/-	10,000/-	One Month	350/-	"C" & "D" Class
3	Restoration of rain damages (PDNA) on Peo Kalpa C.P. road Km. 0/00 to 6/765 (SH:- C/O R/Wall in G.L. wire crate at RD 4/485 to 4/497.5 and 4/600 to 4/710)	4,89,966/-	10,000/-	One Month	350/-	"C" & "D" Class
4	Restoration of rain damages (PDNA) on Peo Kalpa C.P. road Km. 0/00 to 6/765 (SH:- C/O R/Wall in G.I. wire crate at RD 0/310 to 0/335 and 0/600 to 0/612.5)	4,82,715/-	10,000/-	One Month	350/-	"C" & "D" Class
5	Restoration of rain damages (PDNA) on Peo Kalpa C.P. road Km. 0/00 to 6/765 (SH:- C/O R/Wall in G.I. wire crate at RD 0/510 to 0/547.50)	4,84,281/-	10,000/-	One Month	350/-	"C" & "D" Class
6	Restoration of rain damages (PDNA) on link road from NH-22 to Thangi Km 0/00 to 9/370 (SH-C/O R/Wall in G.L. wire crate at RD 1/110 to 1/120)	3,43,856/-	7, 000/-	One Month	350/-	"C" & "D" Class
7	Restoration of rain damages (PDNA) on link road from NH-22 to Thangi Km 0/00 to 9/370 (SH:- C/O R/Wall in G.I. wire crate at RD 1/815 to 1/827.50)	2,77,232/-	6,000/-	One Month	350/-	"C" & "D" Class

8	Restoration of rain damages (PDNA) on link road from NH-22 to Thangi Km 0/00 to 9/370 (SH:- C/O R/Wall in G.I. wire crate at RD 2/160 to 2/170)	4,98,623/-	10,000/-	One Month	350/	"C" & "D" Class
9	Restoration of rain damages (PDNA) on NH-22 to Taitty valley road Km. 0/00 to 4/545 (SH:-C/O R/Wall in G.L. wire crate at RD 1/650 to 1/665)	4,60,346/-	9,500/-	One Month	350/	"C" & "D" Class
10	Restoration of rain damages (PDNA) on NH-22 to Taitty valley road Km. 0/00 to 4/545 (SH:-C/O R/Wall in G.I wire crate at RD 1/705 to 1/720)	4,75,293/-	10,000/-	One Month	350/	"C" & "D" Class
11	Restoration of rain damages (PDNA) on NH-22 to Taitty valley road Km. 0/00 to 4/545 (SH:-C/O R/Wall in G.I wire crate at RD 1/735 to 1/762.50).	4,66,340/-	9,500/-	One Month	350/	"C" & "D" Class
12	Restoration of rain damages (PDNA) on NH-22 to Taitty valley road Km. 0/00 to 4/545 (SH:-C/O R/Wall in GL wire crate at RD 1/945 to 1/972.5)	4,68,063/-	9,500/-	One Month	350/	"C" & "D" Class
13	Restoration of rain damages (PDNA) on Peo Kalpa C.P. road Km. 0/00 to 6/765 (SH:- C/O R/Wall in RR Masonry at RD 6/705 to 6/729)	4,87,810/-	10,000/-	One Month	350/	"C" & "D" Class
14	Restoration of rain damages (PDNA) on Peo Kalpa CP. road Km. 0/00 to 6/765 (SH:-C/O R/Wall in PCC at RD 5/455 to 5/475).	4,77,823/-	10,000/-	One Month	350/	"C" & "D" Class
15	Restoration of rain damages (PDNA) on Peo Kalpa C.P. road Km. 0/00 to 6/765 (SH:- C/O R/Wall in G.L. wire carte at RD 1/750 to 1/775)	4,25,121/-	9,000/-	One Month	350/	"C" & "D" Class
16	Restoration of rain damages on link road from NH-22 to Ropa Khas Km. 0/00 to 15/850 (SH:-C/O R/Wall in G.I. wire carte at RD 6/215 to 6/248.60)	4,33,778/-	9,000/-	One Month	350/	"C" & "D" Class
17	Restoration of rain damages (PFDNA) on link road to village Pooh Km. 0/00 to 4/270 (SH:-C/O B/Wall in G.L wire crate at RD 0/015 to 0/035 and 0/060 to 0/095)	4,80,359/-	10,000/-	One Month	350/	"C" & "D" Class
18	Restoration of rain damages (PDNA) on link road to village Pooh Km. 0/00 to 4/270 (SH:- C/O R/Wall in GL wire crate at RD 0/235 to 0/250, 0/525 to 0/550 and 0/805 to 0/820)	4,72,880/-	9,500/-	One Month	350/	"C" & "D" Class
19	Restoration of rain damages (PDNA) on link road to village Pooh Km. 0/00 to 4/270 (SH:- C/O R/Wall in G.I wire crate at RD 0/980 to 1/015 and 1/510 to 1/540)	4,76,208/-	10,000/-	One Month	350/	"C" & "D" Class
20	Restoration of rain damages (PDNA) on link road to village Pooh Km. 0/00 to 4/270 (SH:- C/O B/Wall in G.I. wire crate at RD 1/510 to 1/550 and 2/005 to 2/020)	4,79,497/-	10,000/-	One Month	350/	"C" & "D" Class
21	Restoration of rain damages (PDNA) on link road to village Pooh Km. 0/00 to 4/270 (SH:- C/O R/Wall in G.L wire crate at RD 1/560 to 1/615)	4,78,401/-	10,000/-	One Month	350/	"C" & "D" Class

22	Restoration of rain damages (PDNA) on link road to Village Pooh Km. 0/00 to 4/270 (SH:- C/O R/Wall in G.L wire crate at RD 1/775 to 1/805 and 1/815 to 1/840)	4,74,407/-	10,000/-	One Month	350/	“C” & “D” Class
23	Restoration of rain damages (PDNA) on link road to Village Pooh Km. 0/00 to 4/270 (SH:- C/O R/Wall in GL wire crate at RD 4/070 to 4/107.5)	4,84,869/-	10,000/-	One Month	350/	“C” & “D” Class
24	Restoration of rain damages (PDNA) on link road to Village Pooh Km. 0/00 to 4/270 (SH:- C/O B/Wall in RR Masonry at RD 2/720 to 2/732)	4,95,142/-	10,000/-	One Month	350/	“C” & “D” Class
25	Restoration of rain damages (PDNA) on Rarang Ribba road Km. 2/415 to 4/830 (SH:- C/O R/Wall in G.L. wire crate at RD 3/825 to 3/839.4)	4,91,098/-	10,000/-	One Month	350/	“C” & “D” Class
26	Restoration of rain damages (PDNA) on Rarang Ribba road Km. 2/415 to 4/830 (SH:- C/O R/Wall in G.L. wire crate at RD 3/725 to 3/735 and 4/030 to 4/050)	2,98,094/-	6,000/-	One Month	350/	“C” & “D” Class
27	Restoration of rain damages (PDNA) on Peo Karchham Shilti road Km 0/00 to 11/635 (SH:-C/O R/Wall at RD 1/097 to 1/118 and 1/235 to 1/248)	4,95,907/-	10,000/-	One Month	350/	“C” & “D” Class
28	Restoration of rain damages (PDNA) on Peo Karchham Shilti road Km 0/00 to 11/635 (SH:-C/O R/Wall in RR Masonry at RD 1/270 to 1/283)	4,87,487/-	10,000/-	One Month	350/	“C” & “D” Class
29	Restoration of rain/snow damages on various roads in Jangi & Lippa Section under Kalpa Sub Division (SH:- Hiring of JCB for removal of snow/landslides)	4,95,000/-	10,000/-	Three Month	350/	“C” & “D” Class
30	Restoration of rain/snow damages on various roads in Nesang Section under Moorang Sub Division (SH:- Hiring of JCB for removal of snow/landslides)	4,95,000/-	10,000/-	Three Month	350/	“C” & “D” Class
31	Restoration of rain/snow damages on various roads in Moorang Section under Moorang Sub Division (SH:- Hiring of JCB for removal of snow/landslides)	4,95,000/-	10,000/-	Three Month	350/	“C” & “D” Class
32	Restoration of rain/snow damages on various roads in Chango and Yangthang Section under Pooh Sub Division. (SH:- Hiring of JCB for removal of snow/landslides)	4,95,000/-	10,000/-	Three Month	350/	“C” & “D” Class
33	Restoration of rain/snow damages on various roads in Sunnam and Spillow Section under Pooh Sub Division. (SH:- Hiring of JCB for removal of snow/landslides)	4,95,000/-	10,000/-	Three Month	350/	“C” & “D” Class
34	Restoration of rain/snow damages on various roads in Kalpa and Pangi Section under Kalpa Sub Division. (SH:- Hiring of JCB for removal of snow/landslides)	2,64,000/-	5,5,00/-	Three Month	350/	“C” & “D” Class

Terms and conditions:-

Following documents should accompany the application for tenders:-

1. Copy of valid enlistment/renewal order.
2. Copy of GST Registration No.
3. Proof of Valid E.P.F accounts Number allotted by the Provident Fund Commissioner Shimla and copy of PAN Number.
4. Ambiguous/Telegraphic/conditional tenders or tenders by fax/E-Mail shall not be entertained/considered in any case.
5. The contractors should quote the rates of each items in words as well as figures in the Schedule of quantity.
6. The earnest money must also accompany with the application for the tender documents.
7. The tender shall be issued to those contractors who have not more than two works in Hand.

Condition for Job No. 29 to 34 :-The Tender documents shall be issued to those Contractors who possessed Excavator-Cum-Loader (JCB) in good condition alongwith required accessories/attachments for removal of snow/debris during snow fall in the area and undertaking should be submitted by participating Contractors along with Copy of valid Registration of machine.


Executive Engineer,
Kalpa Division,
HP. PWD Kalpa.
Dated:- 28/1/26

No.:- PW/KNR-E-Tender/NIT/2026- 10856-10900


Copy forwarded for information to:-

1. The Engineer-in-Chief, HP.PWD. Shimla-2.
2. The Deputy Commissioner, Kinnaur District at Reckong Peo.
3. The Sub Divisional Officer (Civil) Kalpa at Reckong Peo.
4. The Superintending Engineer, 11th Circle, HP.PWD. Rampur Bushahr.
5. The Block Development Officer, Kalpa at Reckong Peo.
6. The Chairman, Zila Parishad, Kinnaur District at Reckong Peo.
7. The Chairman, Panchayat Samiti Kalpa at Reckong Peo.
8. Drawing Branch in this office.
9. All the Contractors under this Division.
10. Notice Board.


Executive Engineer,
Kalpa Division,
HP. PWD. Kalpa.

CERTIFICATE

Certified that the Tender for work called vide this office Letter No. PW/KNR/E-Tender/2026- 10856-10900 dated 28-01-2026 and 34 (Thirty Four) number of works are of urgent nature and essential for public safety or restoration of infrastructure.


**Executive Engineer,
Kalpa Division,
HP.PWD. Kalpa.**


SCHEDULE OF QUANTITY

Name of work:- C/O Link road from Labrang Bus stand to Labrang Gompa Km 0/00 to 1/500		Estimated Cost :- 4,76,574/-				
(SH:- C/O R/Wall in G.I. wire carte at RD 0/00 to 0/028).		Earnest Money :- 10,000/-				
		Time :- One Month				
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	30.24	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 7,894.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty filve kilograme each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	161.28	₹ 2,906.00	Rupees Two Thousand Nine Hundred Six Only	Per Cubic meter	₹ 468,680.00
Total in figures:-						₹ 476,574.00
Total in Words:-		Rupees Four Lakh SeventySix Thousand Five Hundred SeventyFour Only				
Quoted Percentage rate upto three Digits :-		(+)/(-)				


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- C/O Link road from Labrang Bus stand to Labrang Gompa Km 0/00 to 1/500						Estimated Cost :-	4,77,890/-
(SH:- C/O R/Wall in G.I. wire carte at RD 0/030 to 0/058).						Earnest Money :-	10,000/-
						Time :-	One Month
Sr. No.	Description of items	Qty.	Rate		Unit	Amount	
			In Fig.	In Words			
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	35.28	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 9,210.00	
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty filve kilogram each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	161.28	₹ 2,906.00	Rupees Two Thousand Nine Hundred Six Only	Per Cubic meter	₹ 468,680.00	
Total in figures:-							₹ 477,890.00
Total in Words:-						Rupees Four Lakh SeventySeven Thousand Eight Hundred Ninety Only	
Quoted Percentage rate upto three Digits :-						(+)/(-)	


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.

3

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on Peo Kalpa C.P. road Km. 0/00 to 6/765					Estimated Cost :-	4,89,966/-
(SH:- C/O R/Wall in G.I. wire crate at RD 4/485 to 4/497.5 and 4/680 to 4/710).					Earnest Money :-	10,000/-
					Time	One Month
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	33.45	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 8,732.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty filve kilograme each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	165.60	₹ 2,906.00	Rupees Two Thousand Nine Hundred Six Only	Per Cubic meter	₹ 481,234.00
Total in figures:-						₹ 489,966.00
Total in Words:-					Rupees Four Lakh EightyNine Thousand Nine Hundred SixtySix Only	
Quoted Percentage rate upto three Digits :-					(+)/(-)	


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

4


Executive Engineer,
Kalpa Division (B&R),
HP.PWD; Kalpa.

Executive Engineer,
Kalpa Division (B&R),
HP.PWD; Kalpa.

Name of work:-		Restoration of rain damages (PDNA) on Peo Kalpa C.P. road Km. 0/00 to 6/765 (SH:- C/O R/Wall in G.I. wire crate at RD 0/510 to 0/547.5)		Estimated Cost :-	4,84,281/-	
				Earnest Money :-	10,000/-	
				Time :-	One Month	
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royaltytiy, malkana, toll tax, GST or other taxes imposed by the Government.	51.75	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 13,509.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty filve kilograme each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royaltytiy, malkana, toll tax, GST or other taxes imposed by the Government.	162.00	₹ 2,906.00	Rupees Two Thousand Nine Hundred Six Only	Per Cubic meter	₹ 470,772.00
						₹ 484,281.00
Total in figures:-				Rupees Four Lakh EightyFour Thousand Two Hundred EightyOne Only		
Total in Words:-						
Quoted Percentage rate upto three Digits :-						

Executive Engineer,
Kalpa Division (B&R),
HP.PWD, Kalpa.

Name of work:-		Restoration of rain damages (PDNA) on link road from NH-22 to Thangi Km 0/00 to 9/370		Estimated Cost	:-	3,43,856/-
		(SH:- C/O R/Wall in G.I. wire crate at RD 1/110 to 1/120).		Earnest Money	:-	7,000/-
				Time	:-	One Month
				Unit	Amount	
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	34.80	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 9,085.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogram each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	115.20	₹ 2,906.00	Rupees Two Thousand Nine Hundred Six Only	Per Cubic meter	₹ 334,771.00
Total in figures:-						₹ 343,856.00
Total in Words:-		Rupees Three Lakh FourtyThree Thousand Eight Hundred FiftySix Only				
Quoted Percentage rate upto three Digits :-		(+) / (-)				

**Executive Engineer,
Kalpa Division (B&R),
HP.PWD; Kalpa.**

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on link road from NH-22 to Thangi Km 0/00 to 9/370 (SH:- C/O R/Wall in G.I. wire crate at RD 1/815 to 1/827.5).		Estimated Cost :- 2,77,232/-				
		Earnest Money :- 6,000/-				
		Time :- One Month				
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	17.00	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 4,438.00
2	Providing concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203. P.C.C grade M10 Nominal mix 1:3:6 (one Cement : three coarse sand) : six graded stone aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	19.13	₹ 6,057.00	Rupees Six Thousand FiftySeven Only	Per Cubic meter	₹ 115,870.00
3	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty filve kilograme each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	54.00	₹ 2,906.00	Rupees Two Thousand Nine Hundred Six Only	Per Cubic meter	₹ 156,924.00
Total in figures:-						₹ 277,232.00
Total in Words:-		Rupees Two Lakh SeventySeven Thousand Two Hundred ThirtyTwo Only				
Quoted Percentage rate upto three Digits :-		(+)/(-)				


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on link road from NH-22 to Thangi Km 0/00 to 9/370						
(SH:- C/O R/Wall in G.I. wire crate at RD 2/160 to 2/170).						
Estimated Cost :- 4,98,623/-						
Earnest Money :- 10,000/-						
Time :- One Month						
Amount						
Sr. No.	Description of items	Qty.	Rate		Unit	
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	36.00	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 9,398.00
2	Providing concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203. P.C.C grade M10 Nominal mix 1:3:6 (one Cement : three coarse sand) : six graded stone aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	25.50	₹ 6,057.00	Rupees Six Thousand FiftySeven Only	Per Cubic meter	₹ 154,454.00
3	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty filve kilogramme each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	115.20	₹ 2,906.00	Rupees Two Thousand Nine Hundred Six Only	Per Cubic meter	₹ 334,771.00
Total in figures:-						₹ 498,623.00
Total in Words:-		Rupees Four Lakh NinetyEight Thousand Six Hundred TwentyThree Only				
Quoted Percentage rate upto three Digits :-		(+)/(-)				


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on NH-22 to Taity valley road Km. 0/00 to 4/545		Estimated Cost :- 4,60,346/-				
(SH:- C/O R/Wall in G.I. wire crate at RD 1/650 to 1/665).		Earnest Money :- 9,500/-				
		Time :- One Month				
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	28.69	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 7,490.00
2	Providing concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification -Clause 802,803,1202 & 1203. P.C.C grade M10 Nominal mix 1:3:6 (one Cement : three coarse sand) : six graded stone aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	22.95	₹ 6,057.00	Rupees Six Thousand FiftySeven Only	Per Cubic meter	₹ 139,008.00
3	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty filve kilogram each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	108.00	₹ 2,906.00	Rupees Two Thousand Nine Hundred Six Only	Per Cubic meter	₹ 313,848.00
Total in figures:-						₹ 460,346.00
Total in Words:-		Rupees Four Lakh Sixty Thousand Three Hundred FourtySix Only				
Quoted Percentage rate upto three Digits :-		(+)/(-)				


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on NH-22 to Taity valley road Km. 0/00 to 4/545							Estimated Cost :- 4,75,293/-
(SH:- C/O R/Wall in G.I. wire crate at RD 1/705 to 1/720).							Earnest Money :- 10,000/-
							Time :- One Month
Sr. No.	Description of items	Qty.	Rate		Unit	Amount	
			In Fig.	In Words			
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	26.78	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 6,991.00	
2	Providing concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203. P.C.C grade M10 Nominal mix 1:3:6 (one Cement : three coarse sand) : six graded stone aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	25.50	₹ 6,057.00	Rupees Six Thousand FiftySeven Only	Per Cubic meter	₹ 154,454.00	
3	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty flve kilograme each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	108.00	₹ 2,906.00	Rupees Two Thousand Nine Hundred Six Only	Per Cubic meter	₹ 313,848.00	
Total in figures:-						₹ 475,293.00	
Total in Words:-						Rupees Four Lakh SeventyFive Thousand Two Hundred NinetyThree Only	
Quoted Percentage rate upto three Digits :-						(+)/(-)	


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on NH-22 to Taity valley road Km. 0/00 to 4/545 (SH:- C/O R/Wall in G.I. wire crate at RD 1/735 to 1/762.5)						Estimated Cost :-	4,66,340/-
						Earnest Money :-	9,500/-
						Time :-	One Month
Description of items						Qty.	Rate
Sr. No.						In Fig.	In Words
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.					23.10	₹ 261.05 Rupees Two Hundred SixtyOne Paise Five Only
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty filve kilograme each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.					158.40	₹ 2,906.00 Rupees Two Thousand Nine Hundred Six Only
							₹ 460,310.00
Total in figures:-							₹ 466,340.00
Total in Words:-							
Quoted Percentage rate upto three Digits :-							
						Rupees Four Lakh SixtySix Thousand Three Hundred Fourty Only	
						(+)/(-)	


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on NH-22 to Taity valley road Km. 0/00 to 4/545 (SH:- C/O R/Wall in G.I. wire crate at RD 1/945 to 1/972.5).		Estimated Cost :- 4,68,063/-				
		Earnest Money :- 9,500/-				
		Time :- One Month				
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	29.70	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 7,753.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty filve kilograme each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	158.40	₹ 2,906.00	Rupees Two Thousand Nine Hundred Six Only	Per Cubic meter	₹ 460,310.00
Total in figures:-						₹ 468,063.00
Total in Words:-			Rupees Four Lakh SixtyEight Thousand SixtyThree Only			
Quoted Percentage rate upto three Digits :-		(+)/(-)				


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on Peo Kalpa C.P. road Km. 0/00 to 6/795						
(SH:- C/O R/Wall in RR Masonry at RD 6/705 to 6/729).						
Estimated Cost :-		4,87,810/-				
Earnest Money :-		10,000/-				
Time :-		One Month				
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	63.60	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 16,603.00
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. PCC 1:6:12(one Cement : six coarse sand) : twelve graded stone aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	6.24	4041.70	Rupees Four Thousand FourtyOne Paise Seventy Only	Per Cubic meter	₹ 25,220.00
3	Random rubble masonry with hard stone in superstructure above plinth level and upto floor five level, including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) at window sills, ceiling level and the like. Cement mortar 1:6 (1 cement : 6 coarse sand), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	84.72	5040.05	Rupees Five Thousand Fourty Paise Five Only	Per Cubic meter	₹ 426,993.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification clause 1204.3.8. Granular material (For R/wall), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	11.52	₹ 573.80	Rupees Five Hundred SeventyThree Paise Eighty Only	Per Cubic meter	₹ 6,610.00

(14)

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on Peo Kalpa C.P. road Km. 0/00 to 6/795 (SH:- C/O R/Wall in PCC at RD 5/455 to 5/475).					Estimated Cost :-	4,77,823/-
					Earnest Money :-	10,000/-
					Time :-	One Month
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	53.00	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 13,836.00
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. PCC 1:6:12 (one Cement : six coarse sand) : twelve graded stone aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.20	₹ 4,041.70	Rupees Four Thousand FourtyOne Paise Seventy Only	Per Cubic meter	₹ 21,017.00
3	Providing concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203. P.C.C grade M10 Nominal mix 1:3:6 (one Cement : three coarse sand) : six graded stone aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	70.60	₹ 6,057.00	Rupees Six Thousand FiftySeven Only	Per Cubic meter	₹ 427,624.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification clause 1204.3.8. Granular material (For R/wall), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.00	₹ 573.80	Rupees Five Hundred SeventyThree Paise Eighty Only	Per Cubic meter	₹ 5,164.00

5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia (One hundred millimeter diameter) PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 , including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	37.00	₹ 275.20	Rupees Two Hundred SeventyFive Paise Twenty Only	Each	₹ 10,182.00
	Total in figures:-					₹ 477,823.00
	Total in Words:-	Rupees Four Lakh SeventySeven Thousand Eight Hundred TwentyThree Only				
	Quoted Percentage rate upto three Digits :-	(+)/(-)				


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

Name of work:- Restoration of rain damages (PDNA) on Peo Kalpa C.P. road Km. 0/00 to 6/765 (SH:- C/O R/Wall in G.I. wire carte at RD 1/750 to 1/775).									
Estimated Cost :- 4,25,121/- Earnest Money :- 9,000/- Time :- One Month									
Sr. No.	Description of items	Qty.	Rate		Unit	Amount			
			In Fig.	In Words					
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	25.50	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 6,657.00			
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty filve kilogramme each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	144.00	₹ 2,906.00	Rupees Two Thousand Nine Hundred Six Only	Per Cubic meter	₹ 418,464.00			
Total in figures:-						₹ 425,121.00			
Total in Words:-		Rupees Four Lakh TwentyFive Thousand One Hundred TwentyOne Only							
Quoted Percentage rate upto three Digits :-		(+)/(-)							

HP.PWD, Кара.

16


Executive Engineer,
Kalpa Division (B&R),
HP.PWD-Kalpa.

Executive Engineer,
Kalpa Division (B&R),
HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on link road to village Pooh Km. 0/00 to 4/270 (SH:- C/O B/Wall in G.I. wire crate at RD 0/015 to 0/035 and 0/060 to 0/095).		Estimated Cost :- 4,80,359/-				
		Earnest Money :- 10,000/-				
		Time :- One Month				
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	76.80	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 20,049.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogramme each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	158.40	₹ 2,906.00	Rupees Two Thousand Nine Hundred Six Only	Per Cubic meter	₹ 460,310.00
Total in figures:-						₹ 480,359.00
Total in Words:-						
Quoted Percentage rate upto three Digits :-						
		Rupees Four Lakh Eighty Thousand Three Hundred FiftyNine Only				
		(+)/(-)				


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on link road to village Pooh Km. 0/00 to 4/270					Estimated Cost :-	4,72,880/-
(SH:- C/O R/Wall in G.I. wire crate at RD 0/235 to 0/250, 0/525 to 0/550 and 0/805 to 0/820).					Earnest Money :-	9,500/-
					Time :-	One Month
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	48.15	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 12,570.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogram) each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	158.40	₹ 2,906.00	Rupees Two Thousand Nine Hundred Six Only	Per Cubic meter	₹ 460,310.00
Total in figures:-						₹ 472,880.00
Total in Words:-						
Quoted Percentage rate upto three Digits :-						
			Rupees Four Lakh SeventyTwo Thousand Eight Hundred Eighty Only			
			(+)/(-)			


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.

SCHEDULE OF QUANTITIES		
Name of work:-	Restoration of rain damages (PDNA) on link road to village Pooh Km. 0/00 to 4/270 (SH:- C/O R/Wall in G.I. wire crate at RD 0/980 to 1/015 and 1/510 to 1/540).	
		Estimated Cost :- 4,76,208/-
		Earnest Money :- 10,000/-
		Time :- One Month

SCHEDULE OF QUANTITIES						
Name of work:-		Restoration of rain damages (PDNA) on link road to village Pooch Km. 0/00 to 4/270			Estimated Cost :-	4,76,208/-
		(SH:- C/O R/Wall in G.I. wire crate at RD 0/980 to 1/015 and 1/510 to 1/540).			Earnest Money :-	10,000/-
					Time :-	One Month
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	60.90	₹ 261.05	Rupees Two Hundred SixtyOne Paise Only	Per Cubic meter	₹ 15,898.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogramme each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	158.40	₹ 2,906.00	Rupees Two Thousand Nine Hundred Six Only	Per Cubic meter	₹ 460,310.00
Total in figures:-						₹ 476,208.00
Total in Words:-		Rupees Four Lakh SeventySix Thousand Two Hundred Eight Only				
Quoted Percentage rate upto three Digits :-		(+)/(-)				

**Executive Engineer,
Kalpa Division (B&R),
HP.PWD, Kalpa.**

Name of work:-		Restoration of rain damages (PDNA) on link road to village Pooth Km. 0/00 to 4/270 (SH:- C/O B/Wall in G.I. wire crate at RD 1/510 to 1/550 and 2/005 to 2/020).				Estimated Cost	:- 4,79,497/-
						Earnest Money	:- 10,000/-
						Time	:- One Month
Sr. No.	Description of items	Qty.	Rate		Unit	Amount	
			In Fig.	In Words			
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	73.50	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 19,187.00	
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogram each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	158.40	₹ 2,906.00	Rupees Two Thousand Nine Hundred Six Only	Per Cubic meter	₹ 460,310.00	
Total in figures:-						₹ 479,497.00	
Total in Words:-		Rupees Four Lakh SeventyNine Thousand Four Hundred NinetySeven Only					
Quoted Percentage rate upto three Digits :-		(+)/(-)					

Executive Engineer,
Kalpa Division (B&R),
HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on link road to village Pooch Km. 0/00 to 4/270 (SH:- C/O R/Wall in G.I. wire crate at RD 1/560 to 1/615).		Estimated Cost :-		4,78,401/-		
		Earnest Money :-		10,000/-		
		Time :-		One Month		
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	69.30	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 18,091.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty filve kilogramme each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	158.40	₹ 2,906.00	Rupees Two Thousand Nine Hundred Six Only	Per Cubic meter	₹ 460,310.00
Total in figures:-						₹ 478,401.00
Total in Words:-		Rupees Four Lakh SeventyEight Thousand Four Hundred One Only				
Quoted Percentage rate upto three Digits :-		(+)/(-)				


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on link road to village Pooh Km. 0/00 to 4/270		Estimated Cost :- 4,74,407/-	
(SH:- C/O R/Wall in G.I. wire crate at RD 1/775 to 1/805 and 1/815 to 1/840).		Earnest Money :- 10,000/-	
		Time :- One Month	
		Unit :-	
		Amount :-	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	
		Per Cubic meter	


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on link road to village Pooch Km. 0/00 to 4/270
(SH:- C/O R/Wall in G.I. wire crate at RD 4/070 to 4/107.5).

SCHEDULE OF QUANTITIES						
Name of work:-		Restoration of rain damages (PDNA) on link road to village Pooth Km. 0/00 to 4/270				
(SH:- C/O R/Wall in G.I. wire crate at RD 4/070 to 4/107.5).						
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	54.00	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 14,097.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty filve kilogramme each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	162.00	₹ 2,906.00	Rupees Two Thousand Nine Hundred Six Only	Per Cubic meter	₹ 470,772.00
Total in figures:-						₹ 484,869.00
Total in Words:-						
Quoted Percentage rate upto three Digits :-						
			Rupees Four Lakh EightyFour Thousand Eight Hundred SixtyNine Only			
		(+)/(-)				


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on link road to village Pooh Km. 0/00 to 4/270 (SH:- C/O B/Wall in RR Masonry at RD 2/720 to 2/732).						
		Estimated Cost :-		4,95,142/-		
		Earnest Money :-		10,000/-		
		Time :-		One Month		
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	30.20	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 7,884.00
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. PCC 1:6:12(one Cement : six coarse sand) : twelve graded stone aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	4.12	₹ 4,041.70	Rupees Four Thousand FourtyOne Paise Seventy Only	Per Cubic meter	₹ 16,652.00
3	Random rubble masonry with hard stone in superstructure above plinth level and upto floor five level, including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) at window sills, ceiling level and the like. Cement mortar 1:6 (1 cement : 6 coarse sand), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	91.08	₹ 5,040.05	Rupees Five Thousand Fourty Paise Five Only	Per Cubic meter	₹ 459,048.00

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on Rarang Ribba road Km. 2/415 to 4/830 (SH:- C/O R/Wall in G.I. wire crate at RD 3/825 to 3/839.4).				Estimated Cost :-	4,91,098/-	
				Earnest Money :-	10,000/-	
				Time :-	One Month	
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	34.56	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 9,022.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty filve kilogram each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	165.89	₹ 2,906.00	Rupees Two Thousand Nine Hundred Six Only	Per Cubic meter	₹ 482,076.00
Total in figures:-						₹ 491,098.00
Total in Words:-			Rupees Four Lakh NinetyOne Thousand NinetyEight Only			
Quoted Percentage rate upto three Digits :-			(+)/(-)			


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on Rarang Ribba road Km. 2/415 to 4/830 (SH:- C/O R/Wall in G.I. wire crate at RD 3/725 to 3/735 and 4/030 to 4/050).						
		Estimated Cost :- 4,98,094/-				
		Earnest Money :- 6,000/-				
		Time :- One Month				
SCHEDULE OF QUANTITY						
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	19.80	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 5,169.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty filve kilogram each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	100.80	₹ 2,906.00	Rupees Two Thousand Nine Hundred Six Only	Per Cubic meter	₹ 292,925.00
Total in figures:-						
Total in Words:-						
Quoted Percentage rate upto three Digits :-						
		(+)/(-)	Rupees Two Lakh NinetyEight Thousand NinetyFour Only			
			₹ 298,094.00			


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on Peo Karchham Shilti road Km 0/00 to 11/635 (SH- C/O R/Wall at RD 1/097 to 1/118 and 1/235 to 1/248).									
				Estimated Cost	:-		4,95,907/-		
				Earnest Money	:-		10,000/-		
				Time	:-		One Month		
Sr. No.	Description of items	Qty.	Rate		Unit	Amount			
			In Fig.	In Words					
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.56	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 1,190.00			
2	Excavation in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material as per Clause 1603.2, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	30.52	₹ 341.00	Rupees Three Hundred FourtyOne Only	Per Cubic meter	₹ 10,407.00			
3	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. PCC 1:6:12(one Cement : six coarse sand) : twelve graded stone aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1.89	4041.70	Rupees Four Thousand FourtyOne Paise Seventy Only	Per Cubic meter	₹ 7,639.00			
4	Random rubble masonry with hard stone in superstructure above plinth level and upto floor five level, including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) at window sills, ceiling level and the like. Cement mortar 1:6 (1 cement : 6 coarse sand), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	23.31	5040.05	Rupees Five Thousand Fourty Paise Five Only	Per Cubic meter	₹ 117,484.00			

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on Peo Karchham Shiliti road Km 0/00 to 11/635 (SH:- C/O R/Wall in RR Masonry at RD 1/270 to 1/283).							Estimated Cost :- 4,87,784/-
							Earnest Money :- 10,000/-
							Time :- One Month
Sr. No.	Description of items	Qty.	Rate		Unit	Amount	
			In Fig.	In Words			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	10.40	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 2,715.00	
2	Excavation in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material as per Clause 1603.2, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	37.05	₹ 341.00	Rupees Three Hundred FourtyOne Only	Per Cubic meter	₹ 12,634.00	
3	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. PCC 1:6:12(one Cement : six coarse sand) : twelve graded stone aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	7.15	4041.70	Rupees Four Thousand FourtyOne Paise Seventy Only	Per Cubic meter	₹ 28,898.00	
4	Random rubble masonry with hard stone in superstructure above plinth level and upto floor five level, including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) at window sills, ceiling level and the like. Cement mortar 1:6 (1 cement : 6 coarse sand), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	84.37	5040.05	Rupees Five Thousand Fourty Paise Five Only	Per Cubic meter	₹ 425,229.00	

[illegible]

Executive Engineer,
Kalpa Division (B&R),
HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Name of work:-		Restoration of rain/snow damages on various roads in Jangi & Lippa section under Kalpa Sub-Division (SH:- Hiring of JCB for removal of snow/landslides).		Estimated Cost :-	4,95,000/-
				Earnest Money :-	10,000/-
				Time :-	Three Months
Sr. No.	Description of items	Qty.	Rate		Amount
			In Fig.	In Words	
1	Hiring of One No. JCB in good condition, back Howe and front loader on hire charges basis at the site of work for removal of Snow/slips in all classification of soils dressing of berms, filling of depression and filling behind retaining wall etc. including P.O.L. and establishment charges or running staff wages for minimum six hours per day, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	375.00	₹ 1,320.00	Rupees Thousand Hundred Only One Three Twenty	₹ 495,000.00
Total in figures:-					
Total in Words:-				Rupees Four Lakh NinetyFive Thousand Only	₹ 495,000.00
Quoted Percentage rate upto three Digits :-		(+)/(-)			


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain/snow damages on various roads in Nessang section under Moorang Sub-Division		Estimated Cost :- 4,95,000/-			
(SH:- HIRING OF JCB for removal of snow/landslides).		Earnest Money :- 10,000/-			
		Time :- Three Months			
Sr. No.	Description of items	Qty.	Rate	Unit	Amount
			In Fig.		
1	Hiring of One No. JCB in good condition, back Howe and front loader on hire charges basis at the site of work for removal of Snow/slips in all classification of soils dressing of berms, filling of depression and filling behind retaining wall etc. including P.O.L. and establishment charges or running staff wages for minimum six hours per day, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	375.00	₹ 1,320.00 Rupees Thousand Hundred Only One Three Twenty	Per Hours	₹ 495,000.00
	Total in figures:-				₹ 495,000.00
	Total in Words:-		Rupees Four Lakh NinetyFive Thousand Only		
	Quoted Percentage rate upto three Digits :-	(+)/(-)			


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Executive Engineer,
Kalpa Division (B&R),
HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain/snow damages on various roads in Chango and Yangthang section under Pooch Sub-Division (SH:- HIRring of JCB for removal of snow/landslides).		Estimated Cost :- 4,95,000/-							
		Earnest Money :- 10,000/-							
		Time :- Three Months							
Sr. No.	Description of items	Qty.	<table><tr><th colspan="2">Rate</th></tr><tr><th>In Fig.</th><th>In Words</th></tr></table>	Rate		In Fig.	In Words	Unit	Amount
Rate									
In Fig.	In Words								
1	Hiring of One No. JCB in good condition, back Howe and front loader on hire charges basis at the site of work for removal of Snow/slips in all classification of soils dressing of berms, filling of depression and filling behind retaining wall etc. including P.O.L. and establishment charges or running staff wages for minimum six hours per day, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	375.00	₹ 1,320.00 Rupees Thousand Hundred Only One Three Twenty	Per Hours	₹ 495,000.00				
	Total in figures:-				₹ 495,000.00				
	Total in Words:-	Rupees Four Lakh NinetyFive Thousand Only							
	Quoted Percentage rate upto three Digits :-	(+)/(-)							


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain/snow damages on various roads in Sunam and Spillover section under Pooh Sub-Division						Estimated Cost :- 4,95,000/-
(SH:- HIRING OF JCB FOR REMOVAL OF SNOW/LANDSLIDES).						Earnest Money :- 10,000/-
						Time :- Three Months
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Hiring of One No. JCB in good condition, back Howe and front loader on hire charges basis at the site of work for removal of Snow/slips in all classification of soils dressing of berms, filling of depression and filling behind retaining wall etc. including P.O.L. and establishment charges or running staff wages for minimum six hours per day, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	375.00	₹ 1,320.00	Rupees Thousand Hundred Only	One Three Twenty Per Hours	₹ 495,000.00
	Total in figures:-					₹ 495,000.00
	Total in Words:-	Rupees Four Lakh NinetyFive Thousand Only				
	Quoted Percentage rate upto three Digits :-	(+)/(-)				


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain/snow damages on various roads in Kalpa and Pangri section under Pooch Sub-Division (SH:- Hurring of JCB for removal of snow/landslides).							Estimated Cost :- 2,64,000/-
							Earnest Money :- 5,500/-
							Time :- Three Months
Sr. No.	Description of items	Qty.	Rate		Unit	Amount	
			In Fig.	In Words			
1	Hiring of One No. JCB in good condition, back Howe and front loader on hire charges basis at the site of work for removal of Snow/slips in all classification of soils dressing of berms, filling of depression and filling behind retaining wall etc. including P.O.L. and establishment charges or running staff wages for minimum six hours per day, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	200.00	₹ 1,320.00	Rupees Thousand Hundred Only	One Three Twenty Per Hours	₹ 264,000.00	
	Total in figures:-					₹ 264,000.00	
	Total in Words:-			Rupees Two Lakh SixtyFour Thousand Only			
	Quoted Percentage rate upto three Digits :-	(+)/(-)					


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.