OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG
PH: 01907-222229 Fax: 222229 , e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2024- 12215 Dated:- 24/01/26

To

The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2.

Subject :- Regarding publication of Tender on departmental site.

With reference to the notification issued by the Secretary(PW) to the Government of Himachal Pradesh No. P BW(B)A(3)1/2024 dated 03.01.2024 and PBW-B-F0(2)/3/2024-284016 dated 18.07.2025, enclosed please find herewith the copy of Notice Inviting Tender for the loading on departmental web-site as

Certified that the works mentioned in the Tender Notice are urgent in nature and in coordination with the Disaster Management Act, 2005 Section 24 (i).

Encl:- As above.

Executive Engineer,
B&R Division,
HP PWD Karsog

OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG
PH: 01907-222229 Fax: 222229 , E-mail : ee-kar-hp@nic.in

Notice inviting tender

Sealed item rates tender on form **6 & 8** are hereby invited by the Executive Engineer, B&R Division HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **03.02.2026 upto 11.00** AM and shall be opened on the same day at **12.00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 02.02.2026** for which the application should reach in this office **upto 1.00 PM 02.02.2026.**

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening o f tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	R/O Residence of Hon'ble Judge at Karsog Tehsil Karsog Distt. Mandi (HP) (SH:- Plasting painting and Tiles works in Residence at Karsog) Job No. 1	84,275/-	1,700/-	One Month	350/-
2	R/O Residence of Hon'ble Judge at Karsog Tehsil Karsog Distt. Mandi (HP) (SH:- Water Proofing treatment and repair of toilet in Bed room No. 2 Etc.) Job No. 3	99,724/-	2,000/-	One Month	350/-
3	NDF/2025/117(Repair of) Restoration of Rain Damages on Sanarli Karsog road km 0/00 to 3/300 (SH:- Removal of Slips, Maintenance of berms & C/O Unlined drain in km 0/00 to 3/300)	99,345/-	2,000/-	One Month	350/-
4	R/R damages on link road from Rasog Deom road to Khaneoli road km 0/00 to 1/00 (SH:- Removal of land slide slips & Maintenance of earthen shoulders at various Rds in km 0/00 to 1/00)	99,362/-	2,000/-	One Month	350/-
5	R/R Damages on Shakelar to Tuman road km 0/00 to 2/700 (SH:- Removal of slips in km 0/00 to 2/700) Job No. 2	99,570/-	2,000/-	Two Months	350/-
6	R/R Damages on Kelodhar to Dogra road km 0/00 to 2/700 (SH:-Removal of land slide slips at Various Rds between km 1/290 to 1/500) VKV/2024/2512.	99,954/-	2,000	One month	350/-

7	R/R Damages on Samsothi to Dogra road km 0/00 to 2/700 (SH:- Removal of land slide slips at various RDs between km 0/320 to 0/530) VKV/2021/2008.	99,108/-	2,000/-	One month	350/-
8	R/R Damages on Karsog Kunhu road Km. 0/00 to 10/00 (Sh:- Removal of slips in km. 0/00 to 10/00).	98,824/-	2000/-	One month	350/-
9	R/R Damages on Link road Kot to Chindi via Jaban Km.0/00 to 3/00 (Sh:- Remvoal of slips in Km.0/00 to 3/00).	99,256/-	2,000/-	One month	350/-
10	R/R Damages on Shimla Mandi Road via Tattapani Km. 90/00 to 115/00 (Sh:- C/O Unlined Surface drain in Km 96/00 to 98/00, 106/00 to 109 /00 & dressing of berms etc. in km 96/00 to 97/00 & 106/00 to 107/00)	99,983/-	2,000/-	One month	350/-
11	R/R Damages on Thakurthana Pokhi road km 0/00 to 5/00 (SH:-Removal of land slide slips & Maintenance of earthen shoulders at various RDs in km 0/00 to 2/00)	99,867/-	2,000/-	One month	350/-
12	R/R Damages on Thakurthana Pokhi road km 0/00 to 5/00 (SH:-Removal of land slide slips & Maintenance of earthen shoulders at various RDs in km 2/500 to 5/00)	99,415/-	2,000/-	One month	350/-
13	R/R Damages on Mamail to Mehandi road km 0/00 to 19/00 (SH:- C/O R/Wall at Rd 11/757 to 11/764)	97,542/-	2,000/-,	Two Months	350/-
14	R/R Damages on Pangna Majhangan road km 0/00 to 8/00 (SH:- C/O Parapets at Km 0/135 to 0/250)	99,478/-	2,000/-	Two Months	350/-
15	R/R Damages on Latheri to Khadkan road km 0/00 to 2/00 (SH:- Removal of slips & maintenance of berm in km 0/00 to 2/00)	99,172/-	2,000/-	One Month	350/-
16	R/R Damages on Bhanthal Punni road km 0/00 to 3/00 (SH:- Removal of slips & maintenance of berm in km 0/00 to 3/00)	99,616/-	2,000/-	One Month	350/-
17	R/R Damages on Punni to Harnalla road km 0/00 to 1/500 (SH:- C/O Unlined drain & maintenance of berm in km 0/00 to 1/500)	99,195/-	2,000/-	One Month	350/-
18	R/R damages on Katanda Pokhi road Km. 0/00 to 10/00 (SH:- Removal of slips in various RD Km. 0/00 to 10/00) under PDNA	4,92,857/-	9,900/-	One Month	350/-
19	R/R damages on Dawaru to Talehan road Km. 0/00 to 5/00 (SH:- C/o Canalization of Nallah wire crate & removal of slips in various RDs between Km. 2/140 to 2/220) under PDNA 2023	4,97,907/-	10,000/-	Two months	350/-
20	R/R damages on Dawaru to Talehan road Km. 0/00 to 5/00 (SH:- C/o Canalization of Nallah wire crate & removal of slips in various RDs between Km. 2/00 to 2/080) under PDNA 2023	4,97,907/-	10,000/-	Two months	350/-
21	R/R damages on Dawaru to Talehan road Km. 0/00 to 5/00 (SH:- C/o Canalization of Nallah wire crate & removal of slips in various RDs between Km. 2/080 to to 2/140) under PDNA 2023	4,71,979/-	10,000/-	Two months	350/-
22	R/R damages on link road to village Dachhain Km. 0/00 to 2/500 (SH:- Protection work for abutment of slab culvert at RD 1/435) Job No. 4	99,105/-	2,000/-	One Month	350/-
23	R/R damages on Chouridhar Kotlu road Km. 0/00 to 8/00 (SH:- ROFD at various stretches in Km. 5/675 to 7/00) under PDNA	4,98,088/-	10,000/-	Two months	350/-

24	R/R damages on Chouridhar Kotlu road Km. 0/00 to 8/00 (SH:- ROFD at various stretches in Km. 4/500 to 5/700) under PDNA	4,95,248/-	10,000/-	Two months	350/-
25	R/R damages on Karsog Kunhoo road Km. 0/00 to 10/00 (SH:- C/o PCC edging at RD 0/765 to 0/790)	91,375/-	1,900/-	One Month	350/-

TERMS & CONDITIONS:-

1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act.
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
9. As per Govt. Notification **PW/CTR/32-20Genl Inst-CPWD/2020-37996-3809+5 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.**

Executive Engineer
B&R Division
HPPWD Karsog

No. PW-E-Tender-NIT/2025-26- 12216-21 Dated:- 24.01.25

1. All the Assistant Engineers, working under this Division.
2. Copy to Drawing & Account Branch.
3. Notice board of this office.

Executive Engineer,
B&R Division,
HP PWD Karsog

Percentage Schedule of Quantity

Estimated Cost 84275
Earnest Money 1700
Time One Month

Name of Work:- R/O Residence of Hon'ble Judge at Karsog Tehsil Karsog Distt. Mandi (H.P) (Sh:- Plastering painting and tiles works in Residence at Karsog) Job No. 1

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	15 mm (fifteen millimeter) cement plaster on rough side of single or half brick wall of mix 1:6 (one cement: six coarse sand) and as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	39.92	Per Square Meter	301.00	12016.00	Rupees Twelve Thousand Sixteen and Paise Zero Only
2	Finishing walls with 100% (one hundred percent) Premium acrylic emulsion paint having VOC less than 50 gm/litre (fifty gram per litre) and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. New work (Two or more coats applied @ 1.43 litre/ 10 sqm (one point four three litre per ten square meter). Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm (zero point nine zero litre per ten square meter) as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	76.50	Per Square Meter	148.75	11379.00	Rupees Eleven Thousand Three Hundred Seventy Nine and Paise Zero Only
3	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	175.16	Per Square Meter	112.65	19732.00	Rupees Nineteen Thousand Seven Hundred Thirty Two and Paise Zero
4	Wall painting two coats with water proof acrylic emulsion paint of apex of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre (fifty grams per litre) of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	227.39	Per Square Meter	118.40	26923.00	Rupees Twenty Six Thousand Nine Hundred Twenty Three and Paise Zero Only
5	Providing and laying full body vitrified floor tiles (premium quality) in different sizes(thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero point zero eight percent) and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20 mm (twenty millimeter) thick cement mortar 1:4 (one cement : four coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (three point three kilogram per square meter) including grouting the joints with white cement and matching pigments etc., complete size 600x600 mm of Asian tiles/ Johnson/ Kajaria/ Orient Bell/ Simpolo/ Nitco or its equivalent as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	4.24	Per Square Meter	2226.40	9440.00	Rupees Nine Thousand Four Hundred Forty and Paise Zero Only
6	Providing and Fixing Angular stop cock with wall flange of opel prime no. OPP-15053PM jaquar or equavalent complete in all respect as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	5.00	Each	956.90	4785.00	Rupees Four Thousand Seven Hundred Eighty Five and Paise Zero Only
Total in Figures					84275.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99724
Earnest Money 2000
Time One Month

Name of Work:- R/O Residence of Hon'ble Judge at Karsog Tehsil Karsog Distt. Mandi (HP) (SH:- Water proofing treatment and repair of toilet in Bed room No. 2 Etc.) Job No. 3

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Providing and fixing wash basin with C.I. brackets, 15 mm (fifteen millimeter) C.P. brass pillar taps OPP-CHR-15011BPM , 32 mm (twenty two millimeter) C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Flat back wash basin standard cat. no.10001 of Hindware , Cera,Jaquar, or its equivalent with single 15 mm (fifteen millimeter) C.P. brass pillar tap of opel series of Jaquar or its equivalent and as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1.00	Each	7066.00	7066.00	Rupees Seven Thousand Sixty Six and Paise Zero Only
2	Providing and fixing 110 mm X 90 mm (one hundred ten millimeter into ninety millimeter) PVC floor trap of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etc. complete and as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1.00	Each	1096.45	1096.00	Rupees One Thousand Ninety Six and Paise Zero Only
3	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete and as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1.00	Each	417.05	417.00	Rupees Four Hundred Seventeen and Paise Zero Only
4	Providing and fixing 15 mm (fifteen millimeter) nominal bore G.I. Pipes complete with G.I. fittings and clamps, i/c making good the walls etc. concealed pipe, including painting with anti corrosive bitumastic paint, cutting chases and making good the wall and as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	18.00	Per Running Meter	350.35	6306.00	Rupees Six Thousand Three Hundred Six and Paise Zero Only
5	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1.00	Each	237.80	238.00	Rupees Two Hundred Thirty Eight and Paise Zero Only
6	Providing and fixing C.P. brass shower rose with 15 or 20 mm (fifteen or twenty millimeter) inlet as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1.00	Each	1475.60	1476.00	Rupees One Thousand Four Hundred Seventy Six
7	Providing and Fixing single lever basin mixer single control cat. No. OPP-15011 BPM of Jaquar or equivalent complete as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1.00	Each	5704.90	5705.00	Rupees Five Thousand Seven Hundred Five and Paise Zero Only
8	Providing and fixing chromiumplated brass 50 mm (fifty millimeter) cupboard or wardrobe knobs with nuts complete as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	7.00	Each	65.60	459.00	Rupees Four Hundred Fifty Nine and Paise Zero Only
9	Providing and fixing 100 mm (one hundred millimeter) chromiumplated brass handles with necessary screws etc. complete as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	10.00	Each	118.45	1185.00	Rupees One Thousand One Hundred Eighty Five and Paise Zero Only
10	roviding and laying integral cement based treatment for Providing and laying water proofing treatment on roofs of slabs by applying cement slurry mixed with water proofing cement compound consisting of applying: (a) after surface preparation, first layer of slurry of cement @ 0.488 kg/sqm (zero point four eight eight kilogram per square meter) mixed with water proofing cement Compound @ 0.253 kg/sqm (zero point two five three kilogram per square meter) (b) laying second layer of Fibre glass cloth when the first layer is still green. Overlaps of joints of fibre cloth should not be less than 10 cm (ten centimeter) (c) third layer of 1.5 mm (one point five millimeter) thickness - consisting of slurry of cement @ 1.289 kg/sqm (one point two eight nine kilogram per square meter) mixed with water proofing cement compound @ 0.670 kg/sqm (zero point six seven zero kilogram per square meter) and coarse sand @ 1.289 kg/sqm (one point two eight nine kilogram per square meter). This will be allowed to air cure for 4 hrs. (four hours) followed by water curing for 48 hrs. (forty eight hours) The entire treatment will be taken upto 30 cm (thirty centimeter) on parapet wall and tucked into groove in parapet all around. (d) fourth and final layer of brick tiling with cement mortar (which will be paid for separately. (For the purpose of measurement the entire treated surface will be measured.) and as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	129.02	Per Square Meter	471.50	60833.00	Rupees Sixty Thousand Eight Hundred Thirty Three and Paise Zero Only

11	Providing and fixing European type water closet, white shade, of Cera cat no 51013209SN of Cera/Jaquar or equavalent with PVC cistern SLEEK FRESH DUAL FLUSH (white) of Hindware with 100 mm sand cast Iron P or S trap, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required and as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1.00	Each	14943.05	14943.00	Rupees Fourteen Thousand Nine Hundred Forty Three and Paise Zero Only
Total in Figures					99724.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99345
Earnest Money 2000
Time One month

Name of Work:- NDF/2025/117 (Repair of) Restoration of Rain Damages on Sanarali Karsog road Km 0/00 to 3/300(SH:- Removal of slips, Maintenance of berms & C/O Unlined drain in KM 0/00 to 3/300).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Construction of unlined surface drain of average cross-section area 0.20 sqm(zero point twenty square metre) in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	1200.00	Per Running Meter	23.80	28560.00	Rupees Twenty Eight Thousand Five Hundred Sixty and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	3217.50	Per Square Meter	22.00	70785.00	Rupees Seventy Thousand Seven Hundred Eighty Five and Paise Zero Only
Total in Figures						
Quoted Rate in Figures					99345.00	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 99362
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on link Road from Rasog Deom Road to Khaneoli road Km. 0/00 to 1/00 (SH:- Removal of Land Slide Slips & Maintenance of Earthen Shoulders at various RD in km 0/00 to 1/00).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with	Toatal Amount with all taxes including GST In
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	710.42	Per Cubic Metre	120.00	85250.00	Rupees Eighty Five Thousand Two Hundred Fifty and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	672.00	Per Square Metre	21.00	14112.00	Rupees Fourteen Thousand One Hundred Twelve and Paise Zero Only
Total in Figures					**99362.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 99570
Earnest Money 2000
Time Two Months

Name of Work:- R/R Damages on Shakelar to Tuman Road Km. 0/00 to 2/700 (SH:- Removal of slips in Km. 0/00 to 2/700). Job No.2

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes	Toatal Amount with all taxes including GST In
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	345.75	Per Cubic Metre	120.00	41490.00	Rupees Forty One Thousand Four Hundred Ninety and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	2640.00	Per Square Metre	22.00	58080.00	Rupees Fifty Eight Thousand Eighty and Paise Zero Only
Total in Figures					**99570.00**	
Quoted Rate in Figures					0	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99954
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Kelodhar to Dogra road Km. 0/00 to 2/700(SH:- Removal of land slide slips at various RD's between Km. 1/290 to 1/500)VKV/2024/2512.

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Removal of land slide slip clearance Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lift upto 1.5 m (one point five metre) and lead upto 1000m (one thousand metre) as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	832.95	Per Cubic Meter	120.00	99954.00	Rupees Ninety Nine Thousand Nine Hundred Fifty Four and Paise Zero Only
Total in Figures					**99954.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99108
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Samsothi to Dogra road Km. 0/00 to 2/700(SH:- Removal of land slide slips at various RD's between Km. 0/320 to 0/530)VKV/2021/2008.

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Removal of land slide slip clearance Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lift upto 1.5 m (one point five metre) and lead upto 1000m (one thousand metre) as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	825.90	Per Cubic Meter	120.00	99108.00	Rupees Ninety Nine Thousand One Hundred Eight and Paise Zero Only
Total in Figures						
Quoted Rate in Figures					**99108.00**	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98824
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Karsog Kunhu road Km. 0/00 to 10/00(SH:- Removal of slips in Km. 0/00 to 10/00)

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Removal of land slide slip clearance Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lift upto 1.5 m (one point five metre) and lead upto 1000m (one thousand metre) as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	823.53	Per Cubic Meter	120.00	98824.00	Rupees Ninety Eight Thousand Eight Hundred Twenty Four and Paise Zero Only
Total in Figures					**98824.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	99256
Earnest Money	2000
Time	One Month

Name of Work:- R/R Damages on Link road Kot to Chindi via Jaban Km. 0/00 to 03/00(SH:- Removal of slips in Km. 0/00 to 03/00)

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Removal of land slide slip clearance Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lift upto 1.5 m (one point five metre) and lead upto 1000m (one thousand metre) as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	827.13	Per Cubic - Meter	120.00	99256.00	Rupees Ninety Nine Thousand Two Hundred Fifty Six and Paise Zero Only
Total in Figures					99256.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 99983
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Shimla Mandi Road via Tattapani Km. 90/00 to 115/00 (SH:- C/O unlined surface drain in Km 96/00 to 98/00, 106/00 to 109/00 & dressing of berms etc in km 96/00 to 97/00 & 106/00 to 107/00).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Toatal Amount	Toatal Amount with all taxes including GST In
1	Construction of unlined surface drain of average cross-section area 0.20 sqm in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	4014.00	Per Running Metre	21.80	87505.00	Rupees Eighty Seven Thousand Five Hundred Five and Paise Zero Only
3	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	575.00	Per Square Metre	21.70	12478.00	Rupees Twelve Thousand Four Hundred Seventy Eight and Paise Zero Only
Total in Figures					**99983.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99867
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Thakurthana Pokhi road Km. 0/00 to 5/00(SH:- Removal of land slide slips & Maintenance of Earthen Shoulders at various RD's in Km 0/00 to 2/00).

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	669.99	Per Cubic Meter	120.00	80399.00	Rupees Eighty Thousand Three Hundred Ninety Nine and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto 1000m (one thousand metre) as per technical specification clause 1903 as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	891.00	Per Square Meter	21.85	19468.00	Rupees Nineteen Thousand Four Hundred Sixty Eight and Paise Zero Only
Total in Figures					**99867.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 99415
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Thakurthana Pokhi Road Km 0/00 to 5/00 (SH:- Removal of land Slide Slips & Maintenance of Earthen Shoulders at various RD's in Km 2/500 to 5/00) .

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Toatal Amount	Toatal Amount with all taxes including GST In
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	828.46	Per Cubic Metre	120.00	99415.00	Rupees Ninety Nine Thousand Four Hundred Fifteen and Paise Zero Only
Total in Figures					**99415.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 97542
Earnest Money 2000
Time ~~Four~~ Two Months

Name of Work:- R/R Damages on Mamail Mehandi road Km 0/00 to 19/00 (SH:- C/o R/wall at RD 11/757 to 11/764).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes	Toatal Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	9.66	Per Cubic Metre	390.20	3769.00	Rupees Three Thousand Seven Hundred Sixty Nine and Paise Zero Only
2	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	15.75	Per Cubic Metre	5500.00	86625.00	Rupees Eighty Six Thousand Six Hundred Twenty Five and Paise Zero Only
3	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimetre) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals.	3.36	Per Cubic Metre	1460.95	4909.00	Rupees Four Thousand Nine Hundred Nine and Paise Zero Only
4	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall,return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drewing face complete as per drawing and technical specification clause 614,709,1204.3.7 As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	6.00	Each	373.15	2239.00	Rupees Two Thousand Two Hundred Thirty Nine and Paise Zero Only
Total in Figures					**97542.00**	
Quoted Rate in Figures					**0.00**	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99478
Earnest Money 2000
Time Two Months

Name of Work:- R/R Damages on Pangna Majhangan road Km 0/00 to 8/00 (SH:- C/O Parapets at Km 0/135 to 0/250).

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth and as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	3.10	Per Cubic Meter	390.20	1210.00	Rupees One Thousand Two Hundred Ten and Paise Zero Only
2	Providing and laying concrete for plain/rainforcement concrete 1:3:6 (one cement : three sand : six graded stone aggregae) in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	17.24	Per Cubic Meter	5700.00	98268.00	Rupees Ninety Eight Thousand Two Hundred Sixty Eight and Paise Zero Only
Total in Figures					99478.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 99172
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Latheri to Khadkan Road Km. 0/00 to 2/00 (SH:- Removal of slips & maintenance of berm in km 0/00 to 2/00).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes	Toatal Amount with all taxes including GST In
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	367.18	Per Cubic Metre	120.00	44062.00	Rupees Forty Four Thousand Sixty Two and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	2505.00	Per Square Metre	22.00	55110.00	Rupees Fifty Five Thousand One Hundred Ten and Paise Zero Only
Total in Figures					**99172.00**	
Quoted Rate in Figures					0	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 99616
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Bhanthal Punni Road Km. 0/00 to 3/00 (SH:- Removal of slips & maintenance of berm in km 0/00 to 3/00).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes	Toatal Amount with all taxes including GST In
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	739.38	Per Cubic Metre	120.00	88726.00	Rupees Eighty Eight Thousand Seven Hundred Twenty Six and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	495.00	Per Square Metre	22.00	10890.00	Rupees Ten Thousand Eight Hundred Ninety and Paise Zero Only
Total in Figures					**99616.00**	
Quoted Rate in Figures					0	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99195
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Punni to Harnalla road Km. 0/00 to 1/500(SH:- C/O Unlined drain & Maintenance of berm in Km 0/00 to 1/500).

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Construction of unlined surface drain of average cross-section area 0.20 sqm(zero point twenty square metre) in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	750.00	Per Running Meter	23.80	17850.00	Rupees Seventeen Thousand Eight Hundred Fifty and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto 1000m (one thousand metre) as per technical specification clause 1903 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals	3697.50	Per Square Meter	22.00	81345.00	Rupees Eighty One Thousand Three Hundred Forty Five and Paise Zero Only
					99195.00	
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 492857
Earnest Money 9900
Time One Month

Name of Work:- R/R Damages on Katanda Pokhi Road Km. 0/00 to 10/00 (SH:- Removal of slips in various RD km 0/00 to 10/00) Under PDNA.

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with	Toatal Amount with all taxes including GST In
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	4107.14	Per Cubic Metre	120.00	492857.00	Rupees Four Lakhs Ninety Two Thousand Eight Hundred Fifty Seven and Paise Zero Only
Total in Figures					**492857.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 497907.00
Earnest Money 10000
Time Two Months

Name of Work:- R/R Damages on Dawaru to Talehan road Km. 0/00 to 5/00 (SH:- C/O Channelisation of Nallah, wire crats & Removal of slips in various RD's between RD 2/140 to 2/220).Under PDNA 2023.

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of **45.50** cubic metre @ Rs. 300/- per cubic metre amounting to Rs.**13650/-** only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	350.00	Per Cubic Meter	315.78-	110523.00	Rupees One Lakh Ten Thousand Five Hundred Twenty Three and Paise Zero Only
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (hundred x hundred milimeter) (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogram) each as per drawing and technical specifications Clause 1301 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	125.00	Per Cubic Meter	3013.00	376625.00	Rupees Three Lakhs Seventy Six Thousand Six Hundred Twenty Five and Paise Zero Only
3	Removal of land slide slip clearance Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lift upto 1.5 m (one point five metre) and lead upto 1000m (one thousand metre) as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals	85.12	Per Cubic Meter	126.40	10759.00	Rupees Ten Thousand Seven Hundred Fifty Nine and Paise Zero Only
Total in Figures					**497907.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 497907.00
Earnest Money 10000
Time Two Months

Name of Work:- R/R Damages on Dawaru to Talehan road Km. 0/00 to 5/00 (SH:- C/O Channelisation of Nallah, wire crats & Removal fo slips in various RD's between RD 2/00 to 2/080).Under PDNA 2023.

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of **45.50** cubic metre @ Rs. 300/- per cubic metre amounting to Rs.**13650/-** only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	350.00	Per Cubic Meter	315.78	110523.00	Rupees One Lakh Ten Thousand Five Hundred Twenty Three and Paise Zero Only
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four milimetre) dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (hundred x hundred milimeter) (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogram) each as per drawing and technical specifications Clause 1301 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	125.00	Per Cubic Meter	3013.00	376625.00	Rupees Three Lakhs Seventy Six Thousand Six Hundred Twenty Five and Paise Zero Only
3	Removal of land slide slip clearance Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lift upto 1.5 m (one point five metre) and lead upto 1000m (one thousand metre) as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	85.12	Per Cubic Meter	126.40	10759.00	Rupees Ten Thousand Seven Hundred Fifty Nine and Paise Zero Only
Total in Figures					**497907.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost	471979.00
Earnest Money	10000
Time	Two Months

Name of Work:- R/R Damages on Dawaru to Talehan road Km. 0/00 to 5/00 (SH:- C/O Channelisation of Nallah, wire crats & Removal of slips in various RD's between RD 2/080 to 2/140).Under PDNA 2023.

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Excavation in earth work in hilly area by mechanical means-all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of **34.12** cubic metre @ Rs. 300/- per cubic metre amounting to Rs.**10236/-** only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	262.50	Per Cubic Meter	315.78	82892.00	Rupees Eighty Two Thousand Eight Hundred Ninety Two and Paise Zero Only
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four milimetre) dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (hundred x hundred milimeter) (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogram) each as per drawing and technical specifications Clause 1301 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	93.75	Per Cubic Meter	3013.00	282469.00	Rupees Two Lakhs Eighty Two Thousand Four Hundred Sixty Nine and Paise Zero Only
3	Removal of land slide slip clearance Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lift upto 1.5 m (one point five metre) and lead upto 1000m (one thousand metre) as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	843.50	Per Cubic Meter	126.40	106618.00	Rupees One Lakh Six Thousand Six Hundred Eighteen and Paise Zero Only
Total in Figures					**471979.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99105
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Link road to Village Dachhain Km. 0/00 to 2/500 (SH:- Protection work for abutment of slab culvert at RD 1/435) Job No.4

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Providing concrete for plain/reinforced concrete M-10 grade 1:3:6 (one cement : three course sand : six graded crushed stone aggregate) 40 mm (forty millimeter) nominal size for mechanically mixed and vibrated in open foundation and plinths or similar work complete as per drawing and technical specifications MORD Clause 802, 803,1202 & 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	5.25	Per Cubic Meter.	6368.32	33434.00	Rupees Thirty Three Thousand Four Hundred Thirty Four and Paise Zero Only
2	Providing and laying concrete for plain/rainforcement concrete 1:2:4 (one cement : two sand : four graded stone aggregae) in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	6.84	Per Cubic Meter	7036.00	48126.00	Rupees Forty Eight Thousand One Hundred Twenty Six and Paise Zero Only
3	Supplying and placing HYSD bars reinforcement(Fe 415) in substructure complete as per drawing and specification clasue 1002, 1005, 1010 & 1202 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	184.68	Per Kilo Gram	95.00	17545.00	Rupees Seventeen Thousand Five Hundred Forty Five and Paise Zero Only
Total in Figures					99105.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 498088
Earnest Money 10000
Time Two months

Name of Work:- R/R Damages on Chauridhar Kotlu Road km 0/00 to 8/00 (SH:- ROFD at various Stretches in Km 5/675 to 7/00) Under PDNA.

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with	Toatal Amount with all taxes including GST In
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of **63.150** cubic metre @ Rs. 300/- per cubic metre amounting to Rs.**18945/-** only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	2105.10	Per Cubic Metre	236.61	498088.00	Rupees Four Lakhs Ninety Eight Thousand Eighty Eight and Paise Zero Only
Total in Figures					**498088.00**	
Quoted Rate in Figures					**0.00**	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	495248
Earnest Money	10000
Time	Two months

Name of Work:- R/R Damages on Chauridhar Kotlu Road km 0/00 to 8/00 (SH:- ROFD at various Stretches in Km 4/500 to 5/700) Under PDNA.

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Toatal Amount with all taxes including	Toatal Amount with all taxes including GST in Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of **62.790** cubic metre @ Rs. 300/- per cubic metre amounting to Rs.**18837/-** only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	2093.10	Per Cubic Metre	236.61	495248.00	Rupees Four Lakhs Ninety Five Thousand Two Hundred Forty Eight and Paise Zero Only
Total in Figures					**495248.00**	
Quoted Rate in Figures					**0.00**	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 91375
Earnest Money 1900
Time One Month

Name of Work:- R/R Damages on Karsog Kunhoo road Km. 0/00 to 10/00 (SH:- C/O PCC Edging at RD 0/765 to 0/790).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes	Toatal Amount with all taxes including GST In
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stemps and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	27.50	Per Cubic Meter	350.00	9625.00	Rupees Nine Thousand Six Hundred Twenty Five and Paise Zero Only
2	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	15.00	Per Cubic Meter	5450.00	81750.00	Rupees Eighty One Thousand Seven Hundred Fifty and Paise Zero Only
Total in Figures					**91375.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.