OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG
PH: 01907-222229 Fax: 222229 , e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2024- 12553 Dated:- 30-1-2026

To

The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2.

Subject :- Regarding publication of Tender on departmental site.

With reference to the notification issued by the Secretary(PW) to the Government of Himachal Pradesh No. P BW(B)A(3)1/2024 dated 03.01.2024 and PBW-B-F0(2)/3/2024-284016 dated 18.07.2025, enclosed please find herewith the copy of Notice Inviting Tender for the loading on departmental web-site as

Certified that the works mentioned in the Tender Notice are urgent in nature and in coordination with the Disaster Management Act, 2005 Section 24 (i).

Encl:- As above.

Executive Engineer,
B&R Division,
HP PWD Karsog

OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG
PH: 01907-222229 Fax: 222229 , E-mail : ee-kar-hp@nic.in

Notice inviting tender

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **09.02.2026 upto 11.00** AM and shall be opened on the same day at **12.00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 07.02.2026** for which the application should reach in this office **upto 1.00 PM 07.02.2026.**

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening o f tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	R/R damages on Kelodhar Sainj road Km. 0/00 to 19/00 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)	98,900/-	2,000/-	One Month	350/-
2	R/R damages on Seri Mahawan road Km. 0/00 to 8/00 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips between Km. 4/00 to 8/00)	98,900/-	2,000/-	One Month	350/-
3	R/R damages on various roads under Chnidi Section under HPPWD Pangna Sub-Division (SH:- Hiring of JCB/Excavator cum loader for removal of slips at various RDs)	98,900/-	2,000/-	One Month	350/-
4	R/R damages on Katanda Pokhi road Km. 0/00 to 10/00 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)	98,900/-	2.000/-	One Month	350/-
5	R/R damages on Shakelar Mahog via Navidhar road Km. 0/00 to 9/00 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)	98,900/-	2.000/-	One Month	350/-
6	R/R damages on Rangan Ghaini Shandal road Km. 0/00 to 5/500 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips between Km. 0/00 to 3/500)	98,900/-	2.000/-	One month	350/-

7	R/R damages on Mahunag to Sartyola road Km. 0/00 to 7/105 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips between Km. 0/00 to 3/500)	98,900/-	2.000/-	One month	350/-
8	R/R damages on Shimla Mandi via Tattapani road Km. 90/00 to 115/00(SH:- Hiring of JCB/Excavator cum loader for snow clearance/removal of slips between RD 90/00 to 103/00)	98,900/-	2,000/-	One month	350/-
9	R/R damages on Shimla Mandi via Tattapani road Km. 90/00 to 115/00 (SH:- Hiring of JCB/Excavator cum loader for snow/clearance/removal of slips between RD 103/00 to 115/00)	98,900/-	2,000/-	One month	350/-
10	R/R damages on Kelodhar Chhatri road Km. 0/00 to 19/00 (SH:- removal of land slide & maintenance of earthen shoulders at various RDs in Km. 16/500 to 19/00)	98,671/-	2,000/-	One Month	350/-
11	R/R damages on link road from Gannu to Dateha via Jhunjhuru Km. 0/00 to 5/00 (SH:- Removal of land slide slips and maintenance of earthen shoulders at various RDs in KM. 0/00 to 2/00)	99,917/-	2,000/-	One Month	350/-
12	R/R damages on Kumru to Khadain Km. 0/00 to 5/00 and Bagshar to Seri road 0/00 to 8/00 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis Removal of snow/slips)	98,900/-	2,000/-	One Month	350/-
13	R/R damages on Kelodhar Chhatri Km. 0/00 to 19/00 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis Removal of snow/slips between Km. 0/00 to 10/00)	98,900/-	2,000/-	One Month	350/-
14	R/R damages on Kelodhar Chhatri Km. 0/00 to 19/00 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis Removal of snow/slips between Km. 10/00 to 19/00)	98,900/-	2,000/-	One Month	350/-
15	R/R damages on Bakhrot Sanarli Kelodhar Luhri road Km. 0/00 to 41/800 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis Removal of snow/slips between Km. 13/00 to 27/00)	98,900/-	2,000/-	One Month	350/-
16	R/R damages on Pargagali Reshtadhar road Km. 0/00 to 5/500 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis removal of snow/slips between Km. 0/00 to 3/00)	98,900/-	2,000/-	One Month	350/-
17	R/R damages on Kheel Kufri Mahunag road Km. 0/010 to 11/450 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis removal of snow/slips)	98,900/-	2,000/-	One Month	350/-
18	R/R damages on Chauridhar Kotlu road Km. 0/00 to 8/00 (SH:- ROFD at various stretches in Km. 5/750 to 6/00) under PDNA 2023.	4,99,198/-	10,000/-	Two months	350/-
19	R/R damages on Chauridhar Kotlu road Km. 0/00 to 8/00 (SH:- C/o B/wall at RD 5/750 to 5/765) under PDNA	4,98,430/-	10,000/-	Two months	350/-
20	R/R damages on Alsindi Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:- Providing retaining wall at RD 2/175 to 2/186) under PDNA 2023	4,19,943/-	8,400/-	Two months	350/-

21	R/R damages on Alsindi Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:- Providing retaining wall at RD 1/990 to 2/003) under PDNA 2023	4,93,346/-	10,000/-	Two months	350/-
22	R/R damages on Alsindi Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:- ROFD at various RDs between in Km. 0/00 to 5/00) under PDNA 2023	4,93,346/-	10,000/-	Two months	350/-
23	R/R damages on Alsindi Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:- Providing retaining wall at RD 2/160 to 2/169) under PDNA 2023	4,05,427/-	8,200/-	Two months	350/-
24	R/R damages on Thakurthana to Delag road Km. 0/00 to 7/100 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)	98,900/-	2,000/-	One month	350/-
25	R/O Residence of Hon'ble Judge at Tehsil Karsog Distt. Mandi H.P. (SH:- Putty, shutter in cupboard and dismantling of toilet floor works in residence at Karsog) Job No. 2	98,497/-	2,000/-	One month	350/-

TERMS & CONDITIONS:-

1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act.
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
9. As per Govt. Notification **PW/CTR/32-20Genl Inst-CPWD/2020-37996-3809+5 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.**

Executive Engineer
B&R Division
HPPWD Karsog

No. PW-E-Tender-NIT/2025-26- 12547-52 Dated:- 30-1-2026

1. All the Assistant Engineers, working under this Division.
2. Copy to Drawing & Account Branch.
3. Notice board of this office.

Executive Engineer,
B&R Division,
HP PWD Karsog

Percentage Schedule of Quantity

Estimated Cost	98900
Earnest Money	2000
Time	One Month

Name of Work:- R/R Damages on Kelodhar sainj road Km. 0/00 to 19/00(SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Quoted Rate in Figures			Select		98900.00	
Quoted Rate in Words		Zero and Paise Zero Only				

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	98900
Earnest Money	2000
Time	One Month

Name of Work:-R/R Damages on Seri Mahawan road Km. 0/00 to 8/00 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips between Km. 4/00 to 8/00)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Quoted Rate in Figures			Select		98900.00	
Quoted Rate in Words		Zero and Paise Zero Only				

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 98900
Earnest money 2000
Time One Month

Name of Work:- R/R Damages on various roads under Chindi Section under HPPWD Pangna Sub Division(SH:- Hiring of JCB/Excavator cum loader for removal of slips at various RD's)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs.	Total Amount with all taxes including GST In Words
1	Hiring of JCB/excavator for removal of slips and boulderlin all kinds of soil including rock portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts as per direction of Engineer-In-Charge. Any loss to the public/private property or any accident etc. should be absolute responsibility of the JCB/excavator owner which shall have to be fully compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner,the repair and spare watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by Engineer-In-Charge.	86.00	Per Hour	1150.00	98900.00	Rupees Ninety Eight thousand Nine Hundred and Paise Zero only
Total in Figures					**98900.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	98900
Earnest Money	2000
Time	One Month

Name of Work:-R/R Damages on Katanda to Pokhi Road km 0/00 to 10/00 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Quoted Rate in Figures			Select		98900.00	
Quoted Rate in Words			Zero and Paise Zero Only			

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98900
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Shakelar Mahog via Navidhar road Km. 0/00 to 9/00 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Quoted Rate in Figures			Select		98900.00	
Quoted Rate in Words		Zero and Paise Zero Only				

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	98900
Earnest Money	2000
Time	One Month

Name of Work:- R/R Damages on Rangan Ghaini Shaindhal road Kmn, 0/00 to 5/500 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips between Km. 0/00 to 3/500)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Quoted Rate in Figures			Select		98900.00	
Quoted Rate in Words		Zero and Paise Zero Only				

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98900
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Mahunag to Sartyola road Km. 0/00 to 7/105 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips between Km. 0/00 to 3/500)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Quoted Rate in Figures			Select		98900.00	
Quoted Rate in Words		Zero and Paise Zero Only				

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 98900
Earnest money 2000
Time One Month

Name of Work:- R/R Damage on Shimla Mandi via Tattapani road Km 90/00 to 115/00 (SH:-Hiring of JCB /Excavator cum loader for Snow Clearence/removal slips between RD 90/00 to 103/00).

Sr.No	Sub-Head and Items of works	No.or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs.	Total Amount with all taxes including GST in Words
1	Hiring of JCB/Excavator for Snow clearence/removal of slips from the road surface by mechanical means and disposing it on the valley side as per month and IRC specification 48-1998.The machine/JCB should work 7hours daily.Any loss of public property and accident etc the contractor is fully responsible during the executiton of work.The POL and operation staff for the machine & repair charges of machinery will be provided by the owner.The repair charges of machinery during the execution of work will be borne by the Contractor or asper direction of Engineer-in-charge including carriage of material within all leads lifts and other incidentals.(taking thrice in winter	86.00	Per Hour	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero only
Total in Figure					98900.00	
Quoted Rate in Figure						
Quoted Rate in Words						

Executive Engineer
Karsog Division
HPPWD,Karsog

Percentage Schedule Of Quantity

Estimated Cost	98900
Earnest money	2000
Time	One Month

Name of Work:- R/R Damage on Shimla Mandi via Tattapani road Km 90/00 to 115/00 (SH:-Hiring of JCB /Excavator cum loader for Snow Clearence/removal slips between RD 103/00 to 115/00).

Sr.No	Sub-Head and items of works	No.or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs.	Total Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator for Snow clearence/removal of slips from the road surface by mechanical means and disposing it on the valley side as per month and IRC specification 48-1998.The machine/JCB should work 7hours dally.Any loss of public property and accident etc the contractor is fully responsible during the executiton of work.The POL and operation staff for the machine & repair charges of machinery will be provided by the owner.The repair charges of machinery during the execution of work will be borne by the Contractor or asper direction of Engineer-in-charge including carriage of material within all leads lifts and other incidentals.(taking thrice in winter	86.00	Per Hour	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero only
Total in Figure					98900.00	
Quoted Rate in Figure						
Quoted Rate in Words						

Executive Engineer
Karsog Division
HPPWD,Karsog

Percentage Schedule Of Quantity

Estimated Cost 98671
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Kelodhar Chhatri Road Km. 0/00 to 19/00 (SH:- Removal of land Slide Slips & Maintenance of Earthen Shoulders at various RD's in Km 16/500 to 19/00).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Toatal Amount	Toatal Amount with all taxes including GST In
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	533.29	Per Cubic Metre	120.00	63995.00	Rupees Sixty Three Thousand Nine Hundred Ninety Five and Paise Zero Only
3	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	1587.00	Per Square Metre	21.85	34676.00	Rupees Thirty Four Thousand Six Hundred Seventy Six and Paise Zero Only
Total in Figures					**98671.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99917
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on link road from Gannu to Dateha via Jhunjhuru Km 0/00 to 5/00(SH:- Removal of land slide slips & Maintenance of Earthen Shoulders at various RD's in Km 0/00 to 2/00).

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Removal of land slide slip clearance Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lift upto 1.5 m (one point five metre) and lead upto 1000m (one thousand metre) as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	633.81	Per Cubic Meter	120.00	76057.00	Rupees Seventy Six Thousand Fifty Seven and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto 1000m (one thousand metre) as per technical specification clause 1903 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals	1092.00	Per Square Meter	21.85	23860.00	Rupees Twenty Three Thousand Eight Hundred Sixty and Paise Zero Only
					99917.00	
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	98900
Earnest Money	2000
Time	One Month

Name of Work:- R/R Damages on Kumru to Khadain road Km. 0/00 to 5/00 and Bagshar Seri road Km. 0/00 to 8/00 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Quoted Rate in Figures			Select		98900.00	
Quoted Rate in Words			Zero and Paise Zero Only			

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	98900
Earnest Money	2000
Time	One Month

Name of Work:-R/R Damages on Kelodhar Chhatri road Km. 0/00 to 19/00 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips between Km. 0/00 to 10/00)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Quoted Rate in Figures			Select		98900.00	
Quoted Rate in Words		Zero and Paise Zero Only				

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	98900
Earnest Money	2000
Time	One Month

Name of Work:-R/R Damages on Kelodhar Chhatri road Km. 0/00 to 19/00 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips between Km. 10/00 to 19/00)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Quoted Rate in Figures			Select		98900.00	
Quoted Rate in Words		Zero and Paise Zero Only				

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 98900
Earnest money 2000
Time One Month

Name of Work:- R/R Damage on Bakhrot Sanarli Kelodhar Luhri road Km 0/00 to 41/800 (SH:-Hiring of JCB /Excavator cum loader for Snow Clearence/removal slips between RD 13/00 to 27/00).

Sr.No	Sub-Head and items of works	No.or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs.	Total Amount with all taxes including GST in Words
1	Hiring of JCB/Excavator for Snow clearence/removal of slips from the road surface by mechanical means and disposing it on the valley side as per month and IRC specification 48-1998.The machine/JCB should work 7hours daily.Any loss of public property and accident etc the contractor is fully responsible during the executiton of work.The POL and operation staff for the machine & repair charges of machinery will be provided by the owner.The repair charges of machinery during the execution of work will be borne by the Contractor or asper direction of Engineer-in-charge including carriage of material within all leads lifts and other incidentals.(taking thrice in winter	86.00	Per Hour	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero only
Total in Figure					98900.00	
Quoted Rate in Figure						
Quoted Rate in Words						

Executive Engineer
Karsog Division
HPPWD,Karsog

Percentage Schedule of Quantity

Estimated Cost	98900
Earnest Money	2000
Time	One Month

Name of Work:- R/R Damages on Pargagali Restadhar road Km. 0/00 to 5/500 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips between Km. 0/00 to 3/00)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight. Thousand Nine Hundred and Paise Zero Only
Quoted Rate in Figures			Select		98900.00	
Quoted Rate in Words			Zero and Paise Zero Only			

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	98900
Earnest Money	2000
Time	One Month

Name of Work:- R/R Damages on Kheel Kufri Mahunag road Km. 0/010 to 11/415 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Quoted Rate in Figures			Select		98900.00	
Quoted Rate in Words		Zero and Paise Zero Only				

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 499198
Earnest Money 10000
Time Two Months

Name of Work:- R/R Damages on Chauridhar Kotlu road Km. 0/00 to 8/00 (SH:- ROFD at various Stretches in Km 5/750 to 6/00)Under PDNA 2023.

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST In Rs.	Total Amount with all taxes Including GST In
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of **63.29** cubic metre @ Rs. 300/- per cubic metre amounting to Rs. **18987/-** only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	1476.83	Per Cubic Meter	338.02	499198.00	Rupees Four Lakhs Ninety Nine Thousand One Hundred Ninety Eight and Paise Zero Only
Total in Figures					**499198.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost	498430.00
Earnest Money	10000
Time	Two Months

Name of Work:- R/R Damages on Chauridhar Kotlu road KM 0/00 to 8/00 (SH:- C/O B/Wall at RD 5/750 to 5/765) Under PDNA.

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stemps and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	16.65	Per Cubic Meter	390.20	6497.00	Rupees Six Thousand Four Hundred Ninety Seven and Paise Zero Only
2	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	87.00	Per Cubic Meter	5500.00	478500.00	Rupees Four Lakhs Seventy Eight Thousand Five Hundred and Paise
3	Providing weep holes in brick masonary/stone masonary/plain reinforced concrete abutment,wing wall,return wall with 100 mm (one hundred milimetre) dia PVC pipe extending through the full width of structures with slope of 1(v):20 (H) towads drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	36.00	Each	373.15	13433.00	Rupees Thirteen Thousand Four Hundred Thirty Three and Paise Zero Only
Total in Figures					**498430.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 419943.00
Earnest Money 2000
Time Two Months

Name of Work:- R/R Damages on Alsindi Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:- Providing Retaining wall at RD 2/175 to 2/186)Under PDNA 2023.

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stemps and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	42.08	Per Cubic Meter	390.20	16420.00	Rupees Sixteen Thousand Four Hundred Twenty and Paise Zero Only
2	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	70.00	Per Cubic Meter	5500.00	385000.00	Rupees Three Lakhs Eighty Five Thousand and Paise Zero Only
3	Providing weep holes in brick masonary/stone masonary/plain reinforced concrete abutment,wing wall,return wall with 100 mm (one hundred milimetre) dia PVC pipe extending through the full width of structures with slope of 1(v):20 (H) towads drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	27.00	Each	373.15	10075.00	Rupees Ten Thousand Seventy Five and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	7.04	Per Cubic Meter	1200.00	8448.00	Rupees Ten Thousand Seventy Five and Paise Zero Only
Total in Figures					**419943.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 493346.00
Earnest Money 2000
Time Two Months

Name of Work:- R/R Damages on Alsindi Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:- Providing Retaining wall at RD 1/990 to 2/003)Under PDNA 2023.

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stemps and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	49.73	Per Cubic Meter	390.20	19405.00	Rupees Nineteen Thousand Four Hundred Five and Paise Zero Only
2	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	82.46	Per Cubic Meter	5500.00	453530.00	Rupees Four Lakhs Fifty Three Thousand Five Hundred Thirty and Paise Zero Only
3	Providing weep holes in brick masonary/stone masonary/plain reinforced concrete abutment,wing wall,return wall with 100 mm (one hundred milimetre) dia PVC pipe extending through the full width of structures with slope of 1(v):20 (H) towads drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	30.00	Each	373.15	11195.00	Rupees Eleven Thousand One Hundred Ninety Five and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	7.68	Per Cubic Meter	1200.00	9216.00	Rupees Eleven Thousand One Hundred Ninety Five
Total in Figures					**493346.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 482317
Earnest Money 10000
Time Two ~~One~~ month

Name of Work:- R/R Damages on Alsindi to Tattapani via Dhundan Road km 0/00 to 5/00 (SH:- ROFD at various RD's between in Km 0/00 to 5/00) Under PDNA- 2023.

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes	Toatal Amount with all taxes including GST In Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of **231.24** cubic metre @ Rs. 300/- per cubic metre amounting to Rs.**69372/-** only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1334.10	Per Cubic Metre	361.53	482317.00	Rupees Four Lakhs Eighty Two Thousand Three Hundred Seventeen and Paise Zero Only
Total in Figures					**482317.00**	
Quoted Rate in Figures					**0.00**	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost	405427.00
Earnest Money	8200
Time	Two Months

Name of Work:- R/R Damages on Alsindi Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:- Providing Retaining wall at RD 2/160 to 2/169)Under PDNA 2023.

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stemps and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	24.66	Per Cubic Meter	390.20	9622.00	Rupees Nine Thousand Six Hundred Twenty Two and Paise Zero Only
2	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	66.20	Per Cubic Meter	5500.00	364100.00	Rupees Three Lakhs Sixty Four Thousand One Hundred and Paise Zero Only
3	Providing weep holes in brick masonary/stone masonary/plain reinforced concrete abutment,wing wall,return wall with 100 mm (one hundred milimetre) dia PVC pipe extending through the full width of structures with slope of 1(v):20 (H) towads drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	32.00	Each	373.15	11941.00	Rupees Eleven Thousand Nine Hundred Forty One and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	16.47	Per Cubic Meter	1200.00	19764.00	Rupees Eleven Thousand Nine Hundred Forty One
Total in Figures					405427.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98900
Earnest Money 2000
Time One Month

Name of Work:-R/R damages on Thakurthana to Delag road km 0/00 to 7/100 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Quoted Rate in Figures			Select		98900.00	
Quoted Rate in Words			**Zero and Paise Zero Only**			

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 98497
Earnest Money 2000
Time One Month

Name of Work:- R/O Residence of Hon'ble Judge at Karsog Tehsil Karsog Distt. Mandi (H.P) (Sh:- Putty , shutter in cupboard and dismantling of toilet floor works in Residence at Karsog)Job No.2

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Providing and applying white cement based putty of average thickness 1 mm,(one mili metre) of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete and as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	76.50	Per Square Metre	121.55	9299.00	Rupees Nine Thousand Two Hundred Ninety Nine and Paise Zero Only
2	Providing and laying full body vitrified floor tiles (premium quality) in different sizes(thickness to be specified by manufacturer), with waterabsorption less than 0.08 % (zero point zero eight percent)and conforming to I.S.15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm(tweleve milimetre) thick bed of cementmortar 1:3 (1 cement: 3 coarse sand), jointing with greycement slurry @ 3.3 kg/ sqm(three point three kilogram/square metre) including grouting the joint with white cement & matching pigments etc. complete Size of Tile 600x600 mm (six hundred x six hundre milimetre)of Asian tiles/ Johnson/ Kajaria/ Orient Bell/ Simpolo/ Nitco or its equivalent and as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	10.74	Per Square Metre	2263.30	24308.00	Rupees Twenty Four Thousand Three Hundred Eight and Paise Zero Only
3	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm (twenty five milimetre to fourty milimetre) thick Partical board 12 mm(twelve milimetre) thick and as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	4.17	Per Square Metre	2020.80	8427.00	Rupees Eight Thousand Four Hundred Twenty Seven and Paise Zero Only
4	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres(fifty metre) lead as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	10.19	Per Cubic Metre	2397.15	24427.00	Rupees Twenty Four Thousand Four Hundred Twenty Seven and Paise
5	P/F 19 mm(ninteen milimetre) thick water proof termite resistant commerical/MDF board i/c shalvers and shutter, back side cupboard /cabinet shall be 8 mm(eight milimetre) thick ply and all cut portion of shalves shall ne finished with 6 mm(six milimetre) thick hard wood edging . The cut portion of shutter from all side shall be finished with 12 mm(twelve mili metre) thick hard wood edging. The shutter shall be finished with 1 mm(one milimetre) thick lamination of approved shade i/c piano hinges and magnetic catcher with all accessories etc. complete and as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	2.73	Per Square Metre	7576.60	20684.00	Rupees Twenty Thousand Six Hundred Eighty Four and Paise Zero Only
6	Providing and Fixing Soap dish stainless steel CAN -1131N of Jaquar or equivalent complete in all respect as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1.00	Each	802.90	803.00	Rupees Eight Hundred Three and Paise Zero
7	Providing and fixing PTMT extension nipple for water tank pipe, fittings of approved quality and colour15 mm (fifteen milimetre) nominal dia as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	3.00		120.60	362.00	Rupees Three Hundred Sixty Two and Paise Zero Only
8	Providing and fixing C.P. brass long nose bib cock Cat no.OPP -15037PM Jaquar or equivalent single control of approved quality conforming to IS standards. 15 mm (fifteen mili metre) nominal bore as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1.00	Each	828.70	829.00	Rupees Eight Hundred Twenty Nine and Paise Zero Only
9	P/F Glass shelf 600 mm(six hundred mili metre) long with C.P. Brass bracket and guard rail no. AKP-CHR-35771P of Jaquar or equivalent fixed with C.P. Brass screws etc complete as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1.00	Each	2253.30	2253.00	Rupees Two Thousand Two Hundred Fifty Three and Paise Zero Only
10	Providing and fixing Towel Rack with lower hanger No. AHS-1581H of hotelier series of JAQUAR, or equivalent of superior quality as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1.00	Each	1209.70	1210.00	Rupees One Thousand Two Hundred Ten and Paise Zero Only
11	Providing and FixingAC- 407 ACRYLIC SELF (46X13CM) & AC- 506 TOILET PAPER HOLDER WITH LID RECESSED OF ESS-ESS BATH FITTINGS BY ASIAN PAINTS/HINDWARE/ SOMANY/KOHLER complete in all respect as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1.00	Each	1539.85	1540.00	Rupees One Thousand Five Hundred Forty and Paise Zero Only

12	Providing and fixing 600x450 mm (six hundred x four hundred fifty milimetre) beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete and as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1.00	Each	1528.05	1528.00	Rupees One Thousand Five Hundred Twenty Eight and Paise Zero Only
13	Providing and fixing uplasticised PVC connection pipe with brass unions as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1.00	Each	106.75	107.00	Rupees One Hundred Seven and Paise Zero
14	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1.00	Each	107.50	108.00	Rupees One Hundred Eight and Paise Zero Only
15	Providing and fixing 8mm(eitht milimetre) dia C.P./S.S. Jet with flexible tube upto 1 metre (one metre) and as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. long with S.S. triangular plate to Eureopean type W.C. of quality and make as approved by Engineer - in - charge and as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1.00	Each	529.80	530.00	Rupees Five Hundred Thirty and Paise Zero Only
16	Providing and fixing CP brass grating of approved quality and colour as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1.00	Each	108.30	108.00	Rupees One Hundred Eight and Paise Zero Only
17	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1.00	Each	1510.05	1510.00	Rupees One Thousand Five Hundred Ten and Paise Zero Only
18	Providing and fixing brass stop cock of approved quality as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1.00	Each	463.95	464.00	Rupees Four Hundred Sixty Four and Paise Zero
Total in Figures					**98497.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.