OFFICE OF
EXECUTIVE ENGINEER (KILLAR DIVISION)
H.P. PUBLIC WORKS DEPARTMENT, KILLAR, PANGI-176323
FAX: 01897-242223, email.hp-chm1@nic.in

Himachal Pradesh
Public Works Department
No. PW-KD-(Killar)E-Tender/NIT-2025-26/-12645-51 Dated: 01/01/2026

To

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject: Publishing of Tender Notice on the Departmental Website

Dear Sir,

Enclosed herewith is the Tender Notice for the work specified in the Notice Inviting Tender (NIT). You are kindly requested to upload the same on the official website of the department in accordance with Notification No. PBW(B)A(3)1/2024 dated 03.01.2024 and Notification No. PBW(B)A0(3)1/2024-241828 dated 17.07.2025 issued by the Secretary (PW) to the Government of Himachal Pradesh.

The works mentioned in the tender notice are of urgent nature and in the public interest. Kindly ensure the prompt publication of the same on the website.

Encl.: Notice Inviting Tender
32 Nos Schedule of Quantity

Yours faithfully,

Executive Engineer
Killar Division,
HPPWD Killar (Pangi)

Copy for information and necessary action to:

1. The Superintending Engineer, 7th Circle, HPPWD, Dalhousie.
2. All Assistant Engineers working under this Division.
3. The Drawing Branch of this office.
4. Notice Board.

Executive Engineer
Killar Division,
HPPWD Killar (Pangi)

OFFICE OF
EXECUTIVE ENGINEER (KILLAR DIVISION)
H.P. PUBLIC WORKS DEPARTMENT, KILLAR, PANGI-176323
FAX: 01897-242223, email.hp-chm1@nic.in

CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS, AS CALLED WIDE THIS OFFICE LETTER NO-PW-KD-CB-GA/TENDER 2025-26 12645-51 DATED 01.01.2026 ARE URGENT NATURE AND PUBLIC INTEREST.

Executive Engineer,
Killar Division,
HP.PWD. Killar (Pangi)

HIMACHAL PRADESH

PUBLIC WORK DEPARTMENT

"NOTICE INVITING TENDER"

Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, Killar Division H.P.PWD, Killar on behalf of the Governor of HP for the following works from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **13.01.2026** up to **10.30 A.M** and will be opened on the same day at **11.00** Noon in the presence of intending contractors or their authorized representatives. The tender forms can be had from this office against cash payment (Non refundable) on **12.01.2026** between **2.00 PM up to 5:00** P.M and the application for issue of tender forms shall be received on **12.01.2026** between 10:00AM to 12:00 PM.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Killar must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 90 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Job No.	Name of Work	Estimated cost	Earnest Money	Cost of form (Rs.)	Time period for completion	Form No.	Eligibility of contractors
1	Restoration of Rain and snow damages on Various road Under HPPWD Sub_Division NO-II Sach (SH:- Hiring of JCB for removal of Solidified snow slips and Boulders at different Rds.)	499280	10000	350	Three month	6&8	D & C
2	Restoration of Rain and snow damages on Various road Under HPPWD Sub_Division NO-II Sach (SH:- Hiring of JCB for removal of Solidified snow slips and Boulders at different Rds.)	499280	10000	350	Three month	6&8	D & C
3	Restoration of Rain and snow damages on Saichu to Chasak Bhaiori road Km. 0/0 to 7/0 (SH: C/o R/wall at RD 5/360 to 5/382.50)	481291	10000	350	Three month	6&8	D & C
4	Restoration of Rain and snow damages on Killar to Punto road Km. 0/0 to 5/00 (SH:- C/o Pushta in PCC 1:2:4 at RD 0/790 to 0/791.75 and C/o R/wall in CM 1:6 at RD 0/790 to 0/791.75 and C/o R/wall in CM 1:6 at RD 0/790 to 0/781.75 and C/o Wire Crete wall in RD 3/210 to 3/225 2nd and 3rd Layer)	496185	10000	350	Three month	6&8	D & C
5	Restoration of Rain and snow damages on Killar to Punto road Km. 0/0 to 5/00 (SH - C/o wire crate R/wall at RD 2/195 to 3/210 2nd and 3rd layer and 3/210 to 3/225 1st and 2nd layer)	497150	10000	350	Three month	6&8	D & C
6	Restoration of Rain and snow damages on Purthi to Thandal road Km. 0/0 to 6/500 (SH:- C/o R/wall at RD 0/800 to 0/815)Against PDNA 2023	496178	10000	350	Three month	6&8	D & C
7	Restoration of Rain and snow damages on Purthi to Thandal road Km. 0/0 to 6/500 (SH:- C/o R/wall at RD 1/200 to 1/215)Against PDNA 2023	499876	10000	350	Three month	6&8	D & C
8	Restoration of Rain and snow damages on A.K road Km. 0/0 to 27/500 (SH:- C/o R/wall in PCC 1:3:6 at RD 10/680 to 10/687.45) Against PDNA 2023	499199	10000	350	Three month	6&8	D & C
9	Restoration of Rain and snow damages on A.K road Km. 0/0 to 27/500 (SH:- C/o R/wall in PCC 1:3:6 at RD 11/874.60 to 11/879.40) Against PDNA 2023	487210	10000	350	Three month	6&8	D & C
10	Restoration of Rain and snow damages on A.K road Km. 0/0 to 27/500 (SH:- C/o R/wall in PCC 1:3:6 at RD 7/620 to 7/626) Against PDNA 2023	496655	10000	350	Three month	6&8	D & C
11	Restoration of Rain and snow damages on Killar to Punto road Km. 0/0 to 5/00 (SH:- C/o Pushta in PCC 1:2:4 at RD 0/794.65 to 0/979.55 and C/o R/wall in CM 1:6 at RD 0/794.65 to 0/797.55)	496432	10000	350	Three month	6&8	D & C
12	Restoration of Rain and snow damages on Killar to Punto road Km. 0/0 to 5/00 (SH:- C/o Pushta in PCC 1:2:4 at RD 0/800.45 to 0/803.35 and C/o R/wall in CM 1:6 at RD 0/800.45 to 0/830.45)	496432	10000	350	Three month	6&8	D & C
13	C/o Mobile Link road to Village Changali Punto Km. 0/0 to 2/135 (SH:- C/o R/wall wire crate back side of Changali Nalah at Rd 1/935 to 1/950)	492669	10000	350	Three month	6&8	D & C
14	Restoration of Rain and snow damages on Killar to Punto road Km. 0/0 to 5/00 (SH:- C/o R/wall in CM 1:6 at RD 3/462 to 3/481)	499456	10000	350	Three month	6&8	D & C
15	Restoration of Rain and snow damages on Thamloo to Ghusal road Km. 0/0 to 4/500 (SH:- C/o R/wall at RD 0/025 to 0/044)	484008	10000	350	Three month	6&8	D & C
16	Restoration of Rain and snow damages on Killar to Punto road Km. 0/0 to 5/00 (SH:- C/o Pushta in PCC 1:2:4 at RD 0/797.50 to 0/800.45 and C/o R/wall in CM 1:6 at RD 0/797.55 to 0/800.45)	496432	10000	350	Three month	6&8	D & C
17	Restoration of Rain and snow damages on Killar to Punto road Km. 0/0 to 5/00 (SH:- C/o Pushta in PCC 1:2:4 at RD 0/791.75 to 0/794.65 and C/o R/wall in CM 1:6 at RD 0/791.75 to 0/794.65)	496432	10000	350	Three month	6&8	D & C
18	Restoration of Rain and snow damages on Gref Juction to Chowki Bazar Killar Km. 0/0 to 2/500 (SH:- C/o R/wall at RD 0/135 to 0/146)	499941	10000	350	Three month	6&8	D & C
19	Restoration of Rain and snow damage on link road to upper Kuffa road Km. 0/0 to 1/0 (SH:- C/o R/wall at RD 0/205 to 0/224.50)	499540	10000	350	Three month	6&8	D & C
20	Restoration of Rain and snow damages on Gref Juction to Chowki Bazar Killar Km. 0/0 to 2/500 (SH:- C/o R/wall with U-Shape Drain at RD 0/960 to 1/005)	499473	10000	350	Three month	6&8	D & C
21	Restoration of Rain and snow damages on Chalöli road Km 0/0 to 2/600 (SH:- C/o R/wall at RD 2/370 to 2/382)	490444	10000	350	Three month	6&8	D & C
22	Restoration of Rain and snow damages on Khangsar to Sural Helipad road Km. 0/0 to 2/0 (SH:- C/o R/wall at RD 0/800 to 0/805)	498305	10000	350	Three month	6&8	D & C
23	Restoration of Rain and snow damages on Khangsar to Sural Helipad road Km. 0/0 to 2/0 (SH:- C/o R/wall at RD 0/795 to 0/800)	498305	10000	350	Three month	6&8	D & C
24	Restoration of Rain and snow damages on Sach to Kumar Bhaiori road Km. 0/0 to 11/280 (SH:- C/o R/Wall at RD KM. 4/090 to 4/102)	479343	10000	350	Three month	6&8	D & C
25	Restoration of Rain and snow damages on Seri Bhatwas to Village Parmas KM. 0/0 to 2/100 (SH:- C/o R/Wall at RD 1/040 to 1/061)	496960	10000	350	Three month	6&8	D & C
26	Restoration of Rain and snow damages on Village Changali Pimto Km. 0/0 to 2/135 (SH:- C/o R/Wall at RD 1/709 to 1/725)	496965	10000	350	Three month	6&8	D & C
27	Restoration of Rain and snow damages on Village Changali Pimto Km. 0/0 to 2/135 (SH:- C/o R/Wall at RD 1/435 to 1/454)	497560	10000	350	Three month	6&8	D & C

28	A/R & M/O Non Residential Building HPPWD Division at Killar (Sub Head:- Providing and Installation of Computer, printer, Accessories, LED TV, Dish Networking Equipment and Heater etc.)	489500	10000	350	Three month	6&8	D & C
29	Restoration of Rain and snow damages on Link road from Mall road Killar to Food Godown Killar Km 0/0 to 0/200 (SH:- C/o R/Wall at RD 0/160 to 0/181)	496060	10000	350	Three month	6&8	D & C
30	A/R & M/O Karyas to Tattan Mata Mandir road Km 0/0 to 8/600 (Sub Head:- P/F crash barrierit Rd 4/427 to 4/479)	398774	10000	350	Three month	6&8	D & C
31	Restoration of Rain and snow damages on Link road from Purthi to Ajog Km 0/0 to 2/600 (SH:- C/o R/Wall at Edging at RD 2/255 to 2/275)	415484	10000	350	Three month	6&8	D & C
32	Restoration of Rain and snow damages on Link road Godhan to Korei Km 0/0 to 0/825 (SH:- C/o B/Wall at RD 0/660 to 0/677.50)	499276	10000	350	Three month	6&8	D & C

TERMS & CONDITION:-

1. The contractor will have to produce the copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not
2. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue
3. Only two tenders form will be issued to the contractor/firm which may be noted.
4. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway
5. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the
6. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
7. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved permit

Executive Engineer
Killar Division HP PWD
Killar (Pangi)

For and on behalf of the governor of HP.

No. PW- KD- CB-GA-Tender/2025-26-12652-12751 **DATED:- 01-01-2026**

Copy forwarded for information and necessary action to :-

1. The Engineer-in-Chief HPPWD Shimla
2. The Chief Engineer (SZ) HPPWD Dharmshala.
3. The Resident Commissioner Pangi at Killar.
4. All the Superintending Engineer's/Executive Engineers in HPPWD.
5. The Tehsildar, Pangi at Killar.
6. The Block Development Officer, Pangi at Killar
7. All the Assistant Engineer's working under this Division.
8. All the Head of Branches of this office.
9. All the contractors
10. Notice Board

Executive Engineer.
Killar Division HP PWD
Killar (Pangi)

Job.No-1

Percenatge Schedule of Quantity					Estimated Cost	499280.00
Name of Work:-Restoration of rain and snow damages on Various roads under HPPWD Sub-Division No-II Sach(Sub-Head:-Hiring of JCB for removal of Solidified snow, slips and Boulders at different Rds.)					Earnest Money	10000.00
					Time	Three Month
Sr. NO	**Description of work**	**Quantity**	**Unit**	**Estimated Rate (in Rs.)**	**Total Amount with all taxes Including GST in Rs.**	**Total Amount with all taxes Including GST in Word**
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debries clear from road surface upto any height, depth and lead including treaming and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfactions of Engineer-in-Charge. The J.C.B./Excavator cum Loader should work minimum 8.00 hours from 9.00 AM to 5: 00PM daily and excavate at least 30 cum quantity per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Exacavator owner which shall have to be fully compensated by the contrator in all cases. The fule and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	316.00	Per Hour.	1580.00	499280.00	Rupees Four Lakh Ninety Nine Thousand Two Hundred & Eighty Only
	Total:-				**499280.00**	
	Quated Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

Job No · 2

Percenatge Schedule of Quantity					Estimated Cost	499280.00
Name of Work:-Restoration of rain and snow damages on Various roads under HPPWD Sub-Division No II Sach(Sub-Head:-Hiring of J C B for removal of Solidified snow, slips and Boulders at different Rds.)					Earnest Money	10000.00
					Time	Three Month
Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Word
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debries clear from road surface upto any height, depth and lead including treaming and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfactions of Engineer-in-Charge. The J.C. B./Excavator cum Loader should work minimum 8.00 hours from 9.00 AM to 5: 00PM daily and excavate at least 30 cum quantity per hour. Any loss to the public/private property or any accident etc. happened durmg the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Exacavator owner which shall have to be fully compensated by the contrator in all cases. The fule and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	316.00	Per Hour	1580.00	499280.00	Rupees Four Lakh Ninety Nine Thousand Two Hundred & Eighty Only
	Total:-				**499280.00**	
	Quated Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure(+/-)(-----------%)
Quoted Rate in Words(+/-) (-----------%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

Job No.3

Percenatge Schedule of Quantity					Estimated Cost	481291.00
Name of Work:-Restoration of rain and snow damages on Saichu to Chasak Bhatori road km 0/0 to 7/0 (Sub-Head:- C/o B/wall at Rd 5/360 to 5/382.50)					Earnest Money	10000.00
					Time	Three Month
Sr. NO	**Description of work**	**Quantity**	**Unit**	**Estimated Rate (in Rs.)**	**Total Amount with all taxes Including GST in Rs.**	**Total Amount with all taxes Including GST in Word.**
1	Excavation in hilly area in all heights and depths and in all kind of soil by mannual/mechanical means including saturated soil comprising of ordinary soil,soft rock,hard rock chiselling,wedging out of rock(where blasting is prohibited) and their intermediate classification of soild setting out true to the required lines grades width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-Charge at site according to the MORD technical specification clause 302,1603 and 1603.2 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transporation of unuseful material for filling in road wyas camber,embankments for grade improvements and disposal of all material to required width of the road or on approved dumping site through all modes of transporation including head load or animal transport or mechanical means alongwith its levelling fine dressing and carriage of machineries ,materials, rolls,equipments and safety measures and incidentials necessary to complete the work by mechanical means.and labour if required all Any loss to the public private property during the course of execution shall be the absolute respensibility of the contractor which shall have to be compensated by him in all cases.The rate including octroi royality Malkhana toll tax sale tax or other taxes imposed by the Govenment	51.53	Per cubic metre	182.20	9389.00	Rupees Nine Thousand Three Hundred & Eighty Nine Only
2	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering. and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. . Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases .	10.80	Per cubic metre	539.90	5831.00	Rupees Five Thousand Eight Hundred & Thirty One Only
3	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concretenominal mix 1:4:8(one cement is to four sand is to eight graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls,Abutments,toe walls and the like in foundation of R/walls, B/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	4.73	Per cubic metre	6871.89	32504.00	Rupees Thirty Two Thousand Five Hundred & Four Only

4	Random rubble masonry with hard stones of approved quality in sub structure in cement mortar 1:6 (one cement is to six sand) for structure like retaining walls, breast walls, wing walls, toe walls, abutment and similar works excetera, in all heights/depths in or under water including pumping or bailing out water (surface and sub soil water) / dewatering, removal of slushies, which may arise at the time of masonry work under water complete including curing complete as per drawing and technical specification clause 702, 704,1202 and 1204 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	30.47	Per cubic metre	5338.80	216064.00	Rupees Two Lakh Sixteen Thousand &Sixty One Only
5	Random course rubble dry stone masonry with hard stone of approved quality in sub structure for structure like retaining walls, breast walls excetra in all heights/depths as per MORD technical specification clause 702,704,1606.5 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	51.36	Per cubic metre	4037.80	207381.00	Rupees Two Lakh Seven Thousand Three Hundred & Eighty One Only
6	Providing and laying P.C.C. M-20 copping on the top of the wing wall,return wall & Breast wall etc.complete as per drawing and technical specification clause 012.710.1204,3.1(1:2:4)and as per directions of Engineer - in Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	22.50	Per Running metre	450.00	10125.00	Rupees Ten Thousand One Hundred & Twenty Five Only
	Total:-				481291.00	
	Quated Rate in Figures		Select			
	Quoted Rate in Words					

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words(+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

Job No.4

Percenatge Schedule of Quantity					Estimated Cost	496383.00
Name of Work:-Restoration of rain and snow damages on Killar to Punto road km 0/0 to 5/00 (Sub-Head:- C/o Pushta in C.C (1:2:4) at Rd 0/790 to to 0/791.75 and C/o R/wall in cm 1:6 at Rd 0/790 to 0/781.75 and C/o Wire crate B/wall at Rd 3/210 to 3/225 2nd and 3rd Layer)					Earnest Money	10000.00
					Time	Three Month
Sr. NO	**Description of work**	**Quantity**	**Unit**	**Estimated Rate (in Rs.)**	**Total Amount with all taxes Including GST in Rs**	**Total Amount with all taxes Including GST in Word**
1	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. . Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	15.75	Per cubic metre	396.00	6237.00	Rupees Six Thousand Two Hundred & Thirty Seven Only
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS :280 and IS: 4826 in 100mm X100mm mesh including 10 percecent extra for laps and joints laid with stone boulders weight not less then 25kg each as per drawing and technical specification clause 1301 as per direction of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals.The rate including octroi,royalty, Malkana toll tax, sale tax or other taxes imposed by the Government.	54.68	Per cubic metre	3600.00	196848.00	Rupees One Lakh Ninety Six Thousand Eight Hundred & Fourty Eight Only
3	Providing and laying mechanically mixed and vibrated and vibrated plain cement concrete in sub structure for all type of sub structure using plain cement concreteof grade M-20 nominal mix cement concrete 1:2:4 (one cement : two sand: four graded stone aggregate of 20 mm graded crushed / broken stone aggregate nominal size and down gauge and curing complete including the cost of form work with cement contents not less than 330 kg per cubic meter complete as per drawing and technical specification clause 800,900 &1200 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi royality, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	8.75	Per Cubic Metre	15500.00	135625.00	Rupees One Lakh Thirty Five Thousand Six Hundred & Twenty Five Only
4	Random rubble masonry with hard stones of approved quality in sub structure in cement mortar 1:6 (one cement to six sand) for structure like retaining walls, breast walls, wing walls, toe walls, abutment and similar works etcetera in all heights/depths in or under water including pumping or bailing out water (surface and sub soil water) / dewatering, removal of slushies, which may arise at the time of masonry work under water complete including curing complete as per drawing and technical specification clause 702, 704,1202 and 1204 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	20.01	Per cubic metre	6500.00	130065.00	Rupees One Lakh Thirty Thousand &Sixty Five Only

	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1204.3.8 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	19.67	Per cubic metre	1345.70	26470.00	Rupees Twenty Six Thousand Four Hundred & Seventy Only
6	Providing and laying P.C.C. M-20 copping on the top of the wing wall,return wall & Breast wall etc complete as per drawing and technical specification clause 612.710.1204.3.f(1:2:4)and as per directions of Engineer - in Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	1.75	Per Running metre	650.00	1138.00	Rupees One Thousand One Hundred & Thirty Eight Only
	Total:-				**496383.00**	
	Quoted Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words(+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

Job No.5

Percenatge Schedule of Quantity					Estimated Cost	492156.00
Name of Work:-Restoration of rain and snow damages on Killar to Punto road km 0/0 to 5/00 (Sub-Head:- C/O Wire crate B/wall at Rd 2/195 to 3/210 2nd and 3rd Layer and 3/210 to 3/225 1st and 2nd Layer)					Earnest Money	10000.00
					Time	Three Month
Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs	Total Amount with all taxes Including GST in Word
1	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS :280 and IS: 4826 in 100mm X100mm mesh including10 percent extra for laps and joints laid with stone boulders'weight not less then 25kg each as per drawing and technical specification clause 1301 as per direction of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidentials.The rate including octroi,royalty, Malkand toll tax ,sale tax or other taxes imposed by the Goverment.	136.71	Per cubic metre	3600.00	492156.00	Rupees Four Lakh Ninety Two Thousand One Hundred & Fifty Six Only
	Total:-				492156.00	
	Quoted Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

Job No.6

Percenatge Schedule of Quantity					Estimated Cost	496178.00
Name of Work:-Restoration of rain and snow damages on Purthi to Thandal road km 0/0 to 6/500 (Sub-Head:- C/o R/wall at Rd 0/800 to 0/815) AGAINEST PDNA 2023					Earnest Money	10000.00
					Time	Three Month
Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Word.
1	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls,aprons, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material in the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering, and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases .	22.05	Per cubic metre	539.00	11905.00	Rupees Eleven Thousand Nine Hundred & Five Only
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concreteNominal mix 1:4:8(1 one cement is to six sand is to twelve graded crushed stone aggregate 20millimeter (Twenty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls,Abutments,toe walls and the like in foundation of R/walls, D/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi, royality, Malkana, toltax, Sale Tax or other taxes imposed by the government	6.45	Per Cubic Metre	9354.75	60338.00	Rupees Sixty Thousand Three Hundred & Thirty Eight Only
3	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concreteNominal mix 1:4:8(one cement is to four sand is to eight graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls,Abutments,toe walls and the like in foundation of R/walls, R/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	2.70	Per cubic metre	9918.70	26780.00	Rupees Twenty Six Thousand Seven Hundred & Eighty Only

4	Random rubble masonry with hand stone of approved quality in sub structure in cement mortar 1:6 (one cement is to six sand) for structure like retaining walls, breast walls, wing walls, ice wards, abutments and similar works/ erections, in all heights/depths in or under water including pumping or bailing out water (surface and sub soil water) / dewatering, removal of shuttres, which may arise at the time of masonry work under water complete including curing complete as per drawing and technical specification clause 702, 704,1702 and 1204 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	78.70	Per cubic metre	7438.00	213471.00	Rupees Two Lakh Thirteen Thousand Four Hundred & Seventy One Only
5	Random course rubble dry stone masonry with hand stone of approved quality in sub structure for structure like retaining walls, breast walls etcetra in all heights/depths as per MORD technical specification clause 702,704,1600.5 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect	39.62	Per cubic metre	4037.80	159978.00	Rupees One Lakh Fifty Nine Thousand Nine Hundred & Seventy Eight Only
6	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and MORTH technical specification clause 1204.3.8 and as per directions of Engineer - In- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect	12.60	Per cubic metre	1345.70	16956.00	Rupees Sixteen Thousand Nine Hundred & Fifty Six Only
7	Providing and laying P.C.C. M-20 topping on the top of the wing wall,return wall & Breast wall etc.complete as per drawing and technical specification clause 612,710,1201.3.1(1:2:4)and as per directions of Engineer - in Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect	15.00	Per Running metre	450.00	6750.00	Rupees Six Thousand Seven Hundred & Fifty Only
	Total:-				**496178.00**	
	Quated Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

Job No. 7

Percentage Schedule of Quantity

Name of Work:-Restoration of rain and snow damages on Purbi to Thandal road km 0/0 to 6/500 (Sub-Head:- S.O R/wall at Rd 1/200 to 1/235) AGAINST PDNA 2023

					Estimated Cost	499870.00
					Earnest Money	10000.00
					Time	Three Month
Sr. No	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Words.
1	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling, wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etc. as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- in- Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling of trenches with excavated suitable approved material to the required surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering, and as per directions of Engineer - in- Charge including hauling, carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. Any loss to the public - private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	28.90	Per cubic metre	539.00	15603.00	Rupees Fifteen Thousand Six Hundred & Three Only
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete(nominal mix 1:2:4) the cement is to six sand is to twelve graded crushed stone aggregate 20millimeter (Twenty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls,Abutments,toe walls and the like in foundation of R/walls, B/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling ,carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi, royalty, Malkana, toltax, Sale Tax or other taxes imposed by the government.	6.45	Per Cubic Metre	9354.75	60338.00	Rupees Sixty Thousand Three Hundred & Thirty Eight Only
3	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete(nominal mix 1:2:4) the cement is to four sand is to eight graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls,Abutments,toe walls and the like in foundation of R/walls, B/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling ,carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	2.70	Per cubic metre	9919.70	26780.00	Rupees Twenty Six Thousand Seven Hundred & Eighty Only

4	Random rubble masonry with hard stones of approved quality in sub structure in cement mortar 1:6 (one cement (6 to 8% sand) for structure like retaining walls, breast walls, wing walls, toe walls, abutment and similar works etcetera, in all heights/depths in or under water including pumping or bailing out water (surface and sub soil water) / dewatering, removal of shuttles, which may arise in the time of masonry work under water complete including curing complete as per drawing and technical specification clause 202, 704.1.3(i) and 1204 and as per directions of Engineer – in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	28.70	Per cubic metre	7438.00	213471.00	Rupees Two Lakh Thirteen Thousand Four Hundred & Seventy One Only
5	Random course rubble dry stone masonry with hard stone of approved quality in sub structure for structure like retaining walls, breast walls, cretin in all heights/depths as per MORD technical specification clause 702,704,1606.5 and as per directions of Engineer – in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	39.62	Per cubic metre	4037.80	159978.00	Rupees One Lakh Fifty Nine Thousand Nine Hundred & Seventy Eight Only
6	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1204.5.8 and as per directions of Engineer – in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	12.60	Per cubic metre	1345.70	16956.00	Rupees Sixteen Thousand Nine Hundred & Fifty Six Only
7	Providing and laying P.C.C. M-20 copping on the top of the wing wall,return wall &,Breast wall etc.complete as per drawing and technical specification clause 612.7(i) 1204.3.1(1:2:4)and as per directions of Engineer - in Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	15.00	Per Running metre	450.00	6750.00	Rupees Six Thousand Seven Hundred & Fifty Only
	Total:-				**499876.00**	
	Quated Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure (-) (-----------%)
Quoted Rate in Words (-) (-----------%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

Job No-8

Percenatge Schedule of Quantity

Name of Work:- R/O rain and snow damages on A.K road km 0/0 to 27/500 (Sub Head:- C/o R/wall in PCC 1:3:6 at Rd 10/680 to 10/687.45) Against PDNA 2023					Estimated Cost	499194.00
					Earnest Money	10000.00
					Time	Three Month
Sr. NO	**Description of work**	**Quantity**	**Unit**	**Estimated Rate (in Rs.)**	**Total Amount with all taxes Including GST in**	**Total Amount with all taxes Including GST in Word.**
1	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specifications clause 305) and as per direction of the Engineer In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transporation all leads, lifts and other incidental complete in all respect . Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases .	51.82	Per cubic metre	539.00	18799.00	Rupees Eighteen Thousand Seven Hundred & Ninety Nine Only
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations for all types of structure complete using plain cement concrete grade M-10 (M 1cm) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 40 mm (Forty Millimeters) nominal and below size in or under water including curing complete ,pumping or bailing out water ,dewatering removal of slush as required at site which may arrisen at the time of laying under water complete for all heights/depths including the cost of form work as per drawings and M.O.R.D. technical specifications section 800, 900 & 1200 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental The rate including of GST, or other taxes imposed by the government.	38.28	Per ~~Square~~ Cubic metre	11833.20	454154.00	Rupees Four Lakh Fifty Four Thousand One Hundred & Fifty Four Only
3	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1204.3.8 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transporation all leads, lifts and other incidental complete in all respect.	19.37	Per cubic metre	1354.70	26241.00	Rupees Twenty Six Thousand Two Hundred & Fourty One Only
	Total:-				**499194.00**	
	Quated Rate in Figures					
	Quoted Rate in Words		Seven			

Quoted Rate in Figures =-(.....%)

Quoted Rate in Words (-/+) (=-----%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

Job No-9

Percenatge Schedule of Quantity					Estimated Cost	487210.00
Name of Work:- R/O rain and snow damages on A.K road km 0/0 to 27/500 (Sub Head:- C/o R/wall in PCC 1:3:6 at Rd 11/874.60 to 11/879.40) Against PDNA 2023					Earnest Money	9800.00
					Time	Three Month
Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in	Total Amount with all taxes Including GST in Word,
1	Earth work in excavation by shoring and in all type of classification of soil comprising of ordinary soil ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcexcavation as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer In Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness, including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering and as per directions of Engineer In Charge including loading carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases	7.30	Per cubic metre	539.90	3941.00	Rupees Three Thousand Nine Hundred & Fourty One Only
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations for all type of structure complete using plain cement concrete grade M-10 (M 1ey) nominal mix 1:3:6 (one cement Three sand Six graded crushed broken stone aggregate 40 mm (Forty Milimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arrisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and M.O.R.D. technical specifications section 800, 900 & 1000 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate including of GST, or other taxes imposed by the government.	40.56	Per cubic metre	11835.00	479950.00	Rupees Four Lakh Seventy Nine Thousand Nine Hundred & Fifty Only
3	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1204.3.8 and as per directions of Engineer In Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	2.45	Per cubic metre	1354.70	3319.00	Rupees Three Thousand Three Hundred & Nineteen Only
	Total:				487210.00	
	Quated Rate in Figures					
	Quoted Rate in Words		(also)			

Quoted Rate in Figures:- -) (.....%)
Quoted Rate in Words :- -) (.....%)

Condition :-

Rate should be quoted for all heights including all loads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

Job no/b

Percenatge Schedule of Quantity					Estimated Cost	496655.00
Name of Work:- R/O rain and snow damages on A.K road km 0/0 to 27/500 (Sub Head:- C/o R/wall in PCC 1:3:6 at Rd 7/620 to 7/626) Against PDNA 2023					Earnest Money	2000.00
					Time	Three Month
Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Word
1	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D technical specification clause 305) and as per direction of the Engineer- in – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering, and as per directions of Engineer – in- Charge including loading carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	25.54	Per cubic metre	539.90	13789.00	Rupees Thirteen Thousand Seven Hundred & Eighty Nine Only
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations for all type of structure complete using plain cement concrete grade M-10 (M 1on) nominal mix 1:3:6 (one cement :three sand :Six graded crushed broken stone aggregate 40 mm (Forty Millimeters) nominal and below size in or under water including curing complete pumping or bailing out water ,dewatering removal of slush as required at site which may arrisen at the time of laying under water complete for all heights/depth , including the cost of form work, as per drawings and M.O.R.D. technical specifications section 800, 900 & 1500 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate including of GST, or other taxes imposed by the government.	40.25	Per Cubic metre	11833.00	476282.00	Rupees Four Lakh Seventy Six Thousand Two Hundred & Eighty Two Only
3	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1204.3.8 and as per directions of Engineer – in-Charge including loading /carriage of materials to various location through all modes of transportation ,all leads, lifts and other incidental complete in all respect.	4.86	Per cubic metre	1354.70	6584.00	Rupees Six Thousand Five Hundred & Eighty Four Only
	Total:-				496655.00	
	Quoted Rate in Figures					
	Quoted Rate in Words		Subject			

Quoted Rate in Figures +/-) (.....%)
Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

Job No-1

Percenatge Bill of Quantity

Name of Work:-Restoration of rain and snow damages on Killar to Punto road km 0/0 to 5/00 (Sub-Head:- Co Pushta in C.C (1:2:4) at Rd 0/794.65 to 0/979.55 and C/o R/wall in cm 1:6 at Rd 0/794.65 to 0/797.55)					**Estimated Cost**	**496432.00**
					Earnest Money	**10000.00**
					Time	**Three Month**
Sr. NO	**Description of work**	**Quantity**	**Unit**	**Estimated Rate (in Rs.)**	**Total Amount with all taxes Including GST in Rs.**	**Total Amount with all taxes Including GST in Word.**
1	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In- Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases .	26.10	Per cubic metre	396.00	10336.00	Rupees Ten Thousand Three Hundred & Thirty Six Only
2	Providing and laying mechanically mixed and vibrated and vibrated plain cement concrete in sub structure for all type of sub structure using plain cement concrete of grade M-20 nominal mix cement concrete 1:2:4 (one cement two sand: four graded stone aggregate of 20 mm graded crushed / broken stone aggregate nominal size and down gauge and curing complete including the cost of form work with cement contents not less than 330 kg per cubic meter complete as per drawing and technical specification clasus 800.900 & 1200 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi royality, Malkana, tollTax, Safe Tax or other taxes imposed by the government.	14.50	Per Cubic Metre	15500.00	224750.00	Rupees Two Lakh Twenty Four Thousand Seven Hundred & Fifty Only
3	Random rubble masonry with hard stones of approved quality in sub structure in cement mortar 1:6 (one cement is to six sand) for structure like retaining walls, breast walls, wing walls, toe walls, abutment and similar works etcetera, in all heights/depths in or under water including pumping or bailing out water (surface and sub soil water) / dewatering, removal of slushes, which may arise at the time of masonry work under water complete including curing complete as per drawing and technical specification clause 703, 704,1202 and 1704 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	33.17	Per cubic metre	6500.00	215605.00	Rupees Two Lakh Fifteen Thousand Six Hundred & Five Only
4	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1204.7.8 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	32.59	Per cubic metre	1345.70	43856.00	Rupees Fourty Three Thousand Eight Hundred & Fifty Six Only

5	Providing and laying P.C .C. M-20 copping on the top of the winw wall,return wall & Breast wall etc.complete as per drawing and technical specification clause 612.710.1204.3 111.2.4)and as per directions of Engineer - in Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	2.90	Per Running metre	650.00	1885.00	Rupees One Thousand Eight Hundred & Eighty Five Only
	Total:-				**496432.00**	
	Quated Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost..

Executive Engineer
Killar Division
HPPWD Killar

Job No.12

Percenatge Schedule of Quantity					Estimated Cost	496432.00
Name of Work:-Restoration of rain and snow damages on Killar to Punto road km 0/0 to 5/00 (Sub-Head:- Co Pushta in C.C (1:2:4) at Rd 0/800.45 to 0/803.35 and C/o R/wall in cm 1:6 at Rd 0/800.45 to 0/830.45)					Earnest Money	10000.00
					Time	Three Month
Sr. NO	**Description of work**	**Quantity**	**Unit**	**Estimated Rate (in Rs.)**	**Total Amount with all taxes Including GST in Rs**	**Total Amount with all taxes Including GST in Word**
1	Earth work in excavation for structure and in all type of classification of soil composing of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305-1 and as per direction of the Engineer-In-Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads lifts and other incidental complete in all respect. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	26.10	Per cubic metre	396.00	10336.00	Rupees Ten Thousand Three Hundred & Thirty Six Only
2	Providing and laying mechanically mixed and vibrated and vibrated plain cement concrete in sub structure for all type of sub structure using plain cement concreteof grade M-20 nominal mix cement concrete 1:2:4 (one cement two sand: four graded stone aggregate of 20 mm graded crushed / broken stone aggregate nominal size and down gauge and curing complete including the cost of form work with cement contents not less than 330 kg per cubic meter complete as per drawing and technical specification clause 800,900 & 1200 and as per directions of Engineer - in- Charge including hauling carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	14.50	Per Cubic Metre	15500.00	224750.00	Rupees Two Lakh Twenty Four Thousand Seven Hundred & Fifty Only
3	Random rubble masonry with hard stones of approved quality in sub structure in cement mortar 1:6 (one cement to six sand) for structure like retaining walls, breast walls, wing walls, toe walls, abutment and similar works etcetera, in all heights/depths in or under water including pumping or bailing out water (surface and sub soil water) dewatering, removal of slushies, which may arise at the time of masonry work under water complete including curing complete as per drawing and technical specification clause 702, 704,1202 and 1204 and as per directions of Engineer - in- Charge including hauling carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	33.17	Per cubic metre	6500.00	215605.00	Rupees Two Lakh Fifteen Thousand six Hundred & Five Only
4	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1204.3.8 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	32.59	Per cubic metre	1345.70	43856.00	Rupees Forty Three Thousand Eight Hundred & Fifty Six Only

5	Providing and laying P.C.C. M-20 copping on the top of the wing wall,return wall & Breast wall etc.complete as per drawing and technical specification clause 612.710.1204.3 (1:2:4)and as per directions of Engineer - in Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect	2.90	Per Running metre	650.00	1885.00	Rupees One Thousand Eight Hundred & Eighty Five Only
	Total:-				**496432.00**	
	Quated Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

Job No. 13

Percenatge Schedule of Quantity					Estimated Cost	492669.00
Name of Work:-C/O M/able Link road to Village Changali Punto Km 0/0 to 2/135 (Sub Head:-C/O B/wall Wire crate back side of changali Nalah at Rd 1/935 to 1/950)					Earnest Money	10000.00
					Time	Three Month
Sr No	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs	Total Amount with all taxes Including GST in Word
1	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, slacking, wedging out rock (Where blasting is prohibited for retaining walls, wing walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 1500mm (one hundred fifty millimeters) compacted thickness including pumping and making out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise on during dewatering, and as per directions of Engineer - in- Charge including hauling, carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect . Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	70.35	Per cubic metre	539.00	37982.00	Rupees Thirty Seven Thousand Nine Hundred & Eighty Two Only
2	Providing and laying in boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS :280 and IS: 4826 in 100mm X100mm mesh including 10 percent extra for laps and joints laid over stone boulders weight not less then 25kg each as per drawing and technical specification clause 1501, as per direction of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidentials.The rate including necessary all Malkauns toll tax, sale tax or other taxes imposed by the Government	93.75	Per cubic metre	3600.00	337500.00	Rupees Three Lakh Thirty Seven Thousand Five Hundred Only
3	Back filling with previous material behind abutments, wing walls, return walls complete as per drawings and M.O.R.D. technical specification clause 1204.3.8 and as per directions of Engineer- in- Charge including hauling carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	93.75	Per cubic metre	1250.00	117188.00	Rupees One Lakh Seventeen Thousand One Hundred & Eighty Eight Only
	Total:-				492669.00	
	Quoted Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figures (+/-) (-----------%)
Quoted Rate in Words (+/-) (-----------%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Kilhar Division
HPPWD Kilhar

Job No. 14

Percenatge Schedule of Quantity					Estimated Cost	499456.00
Name of Work:- -R/o rain and snow damages on Killar to Punto road km 0/0 to 5/0 (Sub Head:- C/o B/wall at in CM 1:6 at Rd 3/462 to 3/481))					Earnest Money	10000.00
					Time	Three Month
Sr. NO	**Description of work**	**Quantity**	**Unit**	**Estimated Rate (in Rs.)**	**Total Amount with all taxes Including GST in Rs.**	**Total Amount with all taxes Including GST in Word**
1	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering. and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. . Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases .	123.12	Per cubic metre	250.00	30780.00	Rupees Thirty Thousand Seven Hundred & Eighty Only
2	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering. and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. . Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases .	15.58	Per cubic metre	396.00	6170.00	Rupees Six Thousand One Hundred & Seventy Only

3	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concretenominal mix 1:4:8(one cement is to four sand is to eight graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls,Abutments,toe walls and the like in foundation of R/walls, B/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	3.99	Per cubic metre	7800.00	31122.00	Rupees Thirty One Thousand One Hundred & Twenty Two Only
4	Random rubble masonry with hard stones of approved quality in sub structure in cement mortar 1:6 (one cement is to Six sand) for structure like retaining walls, breast walls, wing walls, toe walls, abutment and similar works etcetera, in all heights/depths in or under water including pumping or bailing out water (surface and sub soil water) / dewatering, removal of slushies, which may arise at the time of masonry work under water complete including curing complete as per drawing and technical specification clause 702, 704.1202 and 1204 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	48.39	Per Cubic Metre	5600.00	270984.00	Rupees Two Lakh Seventy Thousand Nine Hundred & Eighty Four Only
5	Random course rubble dry stone masonry with hard stone of approved quality in sub structure for structure like retaining walls, breast walls etcetra in all heights/depths as per MORD technical specification clause 702,704,1606.5 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	42.30	Per cubic metre	3500.00	148050.00	Rupees One Lakh Fourty Eight Thousand &Fifty Only
6	Providing and laying P.C.C. M-20 copping on the top of the winw wall,return wall & Breast wall etc complete as per drawing and techanical specification clause 612,710.1204,3.1(1:2:4)and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	19.00	Per Running metre	650.00	12350.00	Rupees Twelve Thousand Three Hundred & Fifty Only
	Total:-				**499456.00**	
	Quated Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words (+/-) (-----%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

Job 100/5

Percenatge Schedule of Quantity					Estimated Cost	484008.00
Name of Work:-Restoration of rain and snow damages on Thamloo to Ghisal road km 0/0 to 4/500 (Sub-Head:- C/o B/wall at Rd 0/025 to 0/044)					Earnest Money	10000.00
					Time	Three Month
Sr. NO	**Description of work**	**Quantity**	**Unit**	**Estimated Rate (in Rs.)**	**Total Amount with all taxes Including GST in Rs.**	**Total Amount with all taxes Including GST in Word.**
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil,soft rock,hard rock chiselling,wedging out of rock(where blasting is prohibited) and their intermediate classification of soil(d setting out true to the required lines grades width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-Charge at site according to the MORD technical specification clause 302.1603 and 1603.2 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transporation of unuseful material for filling in road wyas cambet,embankments for grade improvements and disposal of all material to required width of the road or on approved dumping site through all modes of transporation including head load or animal transport or mechanical means alongwith its levelling fine dressing and carriage of machineries ,materials, tolls,equipments and satety measures and incidentials necessary to complete the work by mechanical means and labour if required all Any loss to the public private property during the course of execution shall be the absolute respensibility of the contractor which shall have to be compensated by him in all cases.The rate including octroi royality Malkhana toll tax sale tax or other taxes imposed by the Government	37.05	Per cubic metre	182.20	6751.00	Rupees Six Thousand Seven Hundred & Fifty One Only
2	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering. and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incedental complete in all respect. . Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases .	17.48	Per cubic metre	539.90	9437.00	Rupees Nine Thousand Four Hundred & Thirty Seven Only
3	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete(nominal mix 1:4:8(one cement is to four sand is to eight graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls,Abutments,toe walls and the like in foundation of R/walls, B/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802.803.1202 and 1203 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	4.18	Per cubic metre	6871.89	28725.00	Rupees Twenty Eight Thousand Seven Hundred & Twenty Five Only

4	Random rubble masonry with hard stones of approved quality in sub structure in cement mortar 1:6 (one cement is to six sand) for structure like retaining walls, breast walls, wing walls, toe walls, abutment and similar works etcetera, in all heights/depths in or under water including pumping or bailing out water (surface and sub soil water) / dewatering, removal of slushies, which may arise at the time of masonry work under water complete including curing complete as per drawing and technical specification clause 702, 704,1202 and 1204 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	48.35	Per cubic metre	5338.80	258131.00	Rupees Two Lakh Fifty Eight Thousand One Hundred & Thirty One Only
5	Random course rubble dry stone masonry with hard stone of approved quality in sub structure for structure like retaining walls, breast walls etcetra in all heights/depths as per MORD technical specification clause 702,704,1606.5 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	42.70	Per cubic metre	4037.80	172414.00	Rupees One Lakh Seventy Two Thousand Four Hundred & Fourteen Only
6	Providing and laying P.C.C. M-20 copping on the top of the winw wall,return wall & Breast wall etc complete as per drawing and technical specification clause 612,710.1204.3.1(1:2:4)and as per directions of Engineer - in Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	19.00	Per Running metre	450.00	8550.00	Rupees Eight Thousand Five Hundred & Fifty Only
	Total:-				**484008.00**	
	Quated Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Kilar Division
HPPWD Kilar

Job No-6

Percenatge Bill of Quantity					Estimated Cost	496432.00
Name of Work:-Restoration of rain and snow damages on Killar to Punto road km 0/0 to 5/00 (Sub-Head:- Co Pushta in C.C (1:2:4) at Rd 0/797.55 to 0/800.45 and C/o R/wall in cm 1:6 at Rd 0/797.55 to 0/800.45)					Earnest Money	10000.00
					Time	Three Month
Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in R.	Total Amount with all taxes Including GST in Word.
1	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads lifts and other incidental complete in all respect. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	26.10	Per cubic metre	396.00	10336.00	Rupees Ten Thousand Three Hundred & Thirty Six Only
2	Providing and laying mechanically mixed and vibrated and vibrated plain cement concrete in sub structure for all type of sub structure using plain cement concrete of grade M-20 nominal mix cement concrete 1:2:4 (one cement two sand four graded stone aggregate of 20 mm graded crushed/ broken stone aggregate nominal size and down gauge and curing complete including the cost of form work with cement contents not less than 330 kg per cubic meter complete as per drawing and technical specification clause 800,900 & 1200 and as per directions of Engineer - In- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi, royalty, Malkana, toltax, Sale Tax or other taxes imposed by the government.	14.50	Per Cubic Metre	15500.00	224750.00	Rupees Two Lakh Twenty Four Thousand Seven Hundred & Fifty Only
3	Random rubble masonry with hard stones of approved quality in sub structure in cement mortar 1:6 (one cement is to six sand) for structure like retaining walls, breast walls, wing walls, toe walls, abutment and similar works etcetera, in all heights/depths in or under water including pumping or bailing out water (surface and sub soil water) / dewatering, removal of slushies, which may arise at the time of masonry work under water complete including curing complete as per drawing and technical specification clause 702, 704,1202 and 1204 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	33.17	Per cubic metre	6500.00	215605.00	Rupees Two Lakh Fifteen Thousand Six Hundred & Five Only
4	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1204.2.8 and as per directions of Engineer – in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	32.50	Per cubic metre	1345.70	43856.60	Rupees Fourty Three Thousand Eight Hundred & Fifty Six Only.

5	Providing and laying P.C.C. M-20 copping on the top of the wing wall,return wall & Breast wall etc.complete as per drawing and technical specification clause 612.710.1204.3.1(1.2.3 and as per directions of Engineer - in Charge including hauling /carriage of materials to various location through all modes of transportation all leads lifts and other incidental complete in all respect.	2.90	Per Running metre	650.00	1885.00	Rupees One Thousand Eight Hundred & Eighty Five Only
	Total:-				**496432.00**	
	Quated Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost..

Executive Engineer
Killar Division
HPPWD Killar

Job No.17

Percenatge Schedule of Quantity					Estimated Cost	496432.00
Name of Work:-Restoration of rain and snow damages on Killar to Punto road km 0/0 to 5/00 (Sub-Head:- C/O Pushta in CC (1:2:4) at Rd 0/791.75 to 0/794.65 and C/o R/wall in CM 1:6 at Rd 0/791.75 to 0/794.95)					Earnest Money	10000.00
					Time	Three Month
Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Word.
1	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In -Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering and as per directions of Engineer - In- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases	26.10	Per cubic metre	396.00	10336.00	Rupees Ten Thousand Three Hundred & Thirty Six Only
2	Providing and laying mechanically mixed and vibrated and vibrated plain cement concrete in sub structure for all type of sub structure using plain cement concreteof grade M-30 nominal mix cement concrete 1:2:4 (one cement : two sand: four graded stone aggregate of 20 mm graded crushed / broken stone aggregate nominal size and down gauge and curing complete including the cost of form work with cement contents not less than 330 kg per cubic meter complete as per drawing and technical specification clasus 800,900 &1200 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octori, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	14.50	Per Cubic Metre	15500.00	224750.00	Rupees Two Lakh Twenty Four Thousand Seven Hundred & Fifty Only
3	Random rubble masonry with hard stones of approved quality in sub structure in cement mortar 1:6 (one cement to six sand) for structure like retaining walls, breast walls, wing walls, pie walls, abutment and similar works etcetera, in all heights/depths in or under water including pumping or bailing out water (surface and sub soil water) / dewatering, removal of slushies, which may arise at the time of masonry work under water complete including curing complete as per drawing and technical specification clause 702, 704,1202 and 1204 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	33.17	Per cubic metre	6500.00	215605.00	Rupees Two Lakh Fifteen Thousand Six Hundred & Five Only
4	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1204.3.8 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	32.59	Per cubic metre	1345.70	43856.480	Rupees Fourty Three Thousand Eight Hundred & Fifty Six Only

5	Providing and laying P.C.C. M-20 copping on the top of the wing wall/return wall & Breast wall etc.complete as per drawing and technical specification clause 612.710.1204.3 (1.2.4)and as per directions of Engineer - in Charge including hauling /carriage of materials to various location through all modes of transportation all leads lifts and other incidental complete in all respect.	2.90	Per Running metre	650.00	1885.00	Rupees One Thousand Eight Hundred & Eighty Five Only
	Total				**496432.00**	
	Quated Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Sr. No. 684 For the year 2025-26
DNIT/Bill of Quantity Approved for Rs. 496432.00 Only

Executive Engineer
Killar Division
HPPWD Killar

Job No. 18

Percenatge Schedule of Quantity					Estimated Cost	499941.00
Name of Work:-Restoration of rain and snow damages on Gref Junction to chowki Bazar Killar km 0/0 to 2/500 (Sub-Head:- Construction of R/wall at Rd 0/135 to 0/146)					Earnest Money	10000.00
					Time	Three Months
Sr. NO	**Description of work**	**Quantity**	**Unit**	**Estimated Rate (in Rs.)**	**Total Amount with all taxes Including GST in**	**Total Amount with all taxes Including GST in Word.**
1	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering, and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect . Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases	30.80	Per cubic metre	539.90	16629.00	Rupees Sixteen Thousand Six Hundred & Twenty Nine Only
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concretenominal mix 1:4:8(one cement is to four sand is to eight graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls,Abutments,toe walls and the like in foundation of R/walls, B/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	55.56	Per cubic metre	8280.50	460065.00	Rupees Four Lakh Sixty Thousand &Sixty Five Only
3	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1204.3.8 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	17.16	Per Cubic metre	1354.70	23247.00	Rupees Twenty Three Thousand Two Hundred & Fourty Seven Only
	Total:-				**499941.00**	
	Quated Rate in Figures					
	Quoted Rate in Words		*Select			

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

Job No. 19

Percenatge Schedule of Quantity

Name of Work:- Restoration of rain and snow damages on Link road to Village upper Kuffa road Km 0/0 to 1/0 (Sub Head:-C/o B/wall at Rd 0/205 to 0/224.50)

					Estimated Cost	499540.00
					Earnest Money	10000.00
					Time	Three Month
Sr. NO	**Description of work**	**Quantity**	**Unit**	**Estimated Rate (in Rs.)**	**Total Amount with all taxes Including GST in R.**	**Total Amount with all taxes Including GST in Word**
1	Excavation in hilly area in all heights and depths and in all kind of soil by mannual/mechanical means including saturated soil comprisng of ordinary soil,soft rock,hard rock chiselling,wedging out of rock(where blasting is prohibited) and their intermediate classification of soild setting out true to the required lines grades width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-Charge at site according to the MORD technical specification clause 302,1603 and 1603.2 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transporation of unuseful material for filling in road wyas camber,embankments for grade improvements and disposal of all material to required width of the road or on approved dumping site through all modes of transporation including head load or animal transpoet or mechanical means alongwith its levelling fine dressing and carriage of machineries ,materials, tolls,equipments and safety measures and incidentials necessary to complete the work by mechanical means,and labour if required all Any loss to the public private property during the course of execution shall be the absolute respensibility of the contractor which shall have to be compensated by him in all cases.The rate including octroi royality Malkhana toll tax sale tax or other taxes imposed	92.82	Per cubic metre	252.00	23391.00	Rupees Twenty Three Thousand Three Hundred & Ninety One Only
2	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering. and as per directions of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation all leads, litts and other incidental complete in all respect. - Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to	15.80	Per cubic metre	539.90	8530.00	Rupees Eight Thousand Five Hundred & Thirty Only
3	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concretenominal mix 1:4:8(one cement is to four sand is to eight graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls,Abutments,toe walls and the like in foundation of R/walls, B/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	4.29	Per cubic metre	7345.40	31512.00	Rupees Thirty One Thousand Five Hundred & Twelve Only

4	Random rubble masonry with hard stones of approved quality in sub structure in cement mortar 1:6 (one cement is to six sand) for structure like retaining walls, breast walls, wing walls, toe walls, abutment and similar works etcetera, in all heights/depths in or under water including pumping or bailing out water (surface and sub soil water) / dewatering, removal of slushies, which may arise at the time of masonry work under water complete including curing complete as per drawing and technical specification clause 702, 704,1202 and 1204 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	49.17	Per cubic metre	5338.80	262509.00	Rupees Two Lakh Sixty Two Thousand Five Hundred & Nine Only
5	Random course rubble dry stone masonry with hard stone of approved quality in sub structure for structure like retaining walls, breast walls etcetra in all heights/depths as per MORD technical specification clause 702,704,1606.5 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	40.82	Per cubic metre	4037.80	164823.00	Rupees One Lakh Sixty Four Thousand Eight Hundred & Twenty Three Only
6	Providing and laying P.C.C. M-20 copping on the top of the winw wall,return wall & Breast wall etc,complete as per drawing and techanical specification clause 612.710.1204.3.1(1:2:4)and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	19.50	Per Running metre	450.00	8775.00	Rupees Eight Thousand Seven Hundred & Seventy Five Only
	Total:-				**499540.00**	
	Quated Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

Job No-20

Percenatge Schedule of Quantity

Name of Work:-R/o of rain and snow damages on Link road from Gref Junction to Chowki Bazzar km 0/0 to 2/500 (Sub Head:-C/o E/wall With U-Shape Drain at RD km 0/960 to 1/005)

Estimated Cost	499473.00
Earnest Money	10000.00
Time	Three Month

Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Word
1	Excavation in hilly area in all heights and depths and in all kind of soil by manmual/mechanical means including saturated soil comprising of ordinary soil,soft rock,hard rock chiselling,wedging out of rock(where blasting is prohibited) and their intermediate classification of soild setting out true to the required lines grades width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-Charge at site according to the MORD technical specification clause 302,1603 and 1603.2 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transporation of unuseful material for filling in road wyas camber,embankments for grade improvements and disposal of all material to required width of the road or on approved dumping site through all modes of transporation including head load or animal transport or mechanical means alongwith its levelling fine dressing and carriage of machineries ,materials, tolls,equipments and safety measures and incidentials necessary to complete the work by mechanical means.and labour if required all Any loss to the public private property during the course of execution shall be the absolute respensibility of the contractor which shall have to be compensated by him in all cases.The rate including octroi royality Malkhana toll tax sale tax or other taxes imposed by the Govenment	48.30	Per cubic metre	215.3	10399.00	Rupees Ten Thousand Three Hundred & Ninety Nine Only
2	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering. and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect . Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases .	30.10	Per cubic metre	539.90	16251.00	Rupees Sixteen Thousand Two Hundred & Fifty One Only
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations for all types of structure complete using plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (Twenty Milimeters) nominal and below size in or under water including curing complete. pumping or bailing out water ,dewatering removal of slush as required at site which may arrisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and M.O.R.D. technical specifications section 800, 900 & 1200 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate including of GST, or other taxes imposed by the government.	12.25	Per Cubic Metre	9527.30	116709.00	Rupees One Lakh Sixteen Thousand Seven Hundred & Nine Only

4	Random rubble masonry with hard stones of approved quality in sub structure in cement mortar 1:6 (one cement is to six sand) for structure like retaining walls, breast walls, wing walls, toe walls, abutment and similar works etcetera, in all heights/depths in or under water including pumping or bailing out water (surface and sub soil water) / dewatering, removal of slushies, which may arise at the time of masonry work under water complete including curing complete as per drawing and technical specification clause 702, 704,1202 and 1204 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	51.00	Per cubic metre	5338.80	272279.00	Rupees Two Lakh Seventy Two Thousand Two Hundred & Seventy Nine Only
5	Steel work welded in built up sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint in trusses and trussed purlins in building, as per specification, approved drawing, design, to the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, GST or any other taxes imposed by the Government.	4.22	Per Quintal	18000.00	75960.00	Rupees Seventy Five Thousand Nine Hundred & Sixty Only
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 complete as per M.O.R.D. technical specifications section No. 503 including hauling/ carriage of materials to various location through all modes of transportation all leads, lifts and other incidental and as per direction of Engineer-In-Charge. The rate is inclusive of GST or other taxes imposed by the government.	15.00	Each	525.00	7875.00	Rupees Seven Thousand Eight Hundred & Seventy Five Only
	Total:-				**499473.00**	
	Quoted Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words (+/-) (----------%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

Job No-21

Percenatge Schedule of Quantity

Name of Work:-R/o rain and snow damages on Chaloli road km 0/0 to 2/600 (Sub Head:-C/o R/wall at Rd 2/370 to 2/382)					**Estimated Cost**	**490444.00**
					Earnest Money	**10000.00**
					Time	**Three Month**
Sr. NO	**Description of work**	**Quantity**	**Unit**	**Estimated Rate (in Rs.)**	**Total Amount with all taxes Including GST in Rs.**	**Total Amount with all taxes Including GST in Word**
1	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering. and as per directions of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. . Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to	46.08.	Per cubic metre	539.90	24879.00	Rupees Twenty Four Thousand Eight Hundred & Seventy Nine Only
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concretenominal mix 1:6:12(one cement is to six sand is to twelve graded crushed stone aggregate 20millimeter (Twenty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls,Abutments,toe walls and the like in foundation of R/walls, B/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer – in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi, royality, Malkana, tolltax,	8.64	Per Cubic Metre	6871.89	59373.00	Rupees Fifty Nine Thousand Three Hundred & Seventy Three Only
3	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concretenominal mix 1:4:8(one cement is to four sand is to eight graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls,Abutments,toe walls and the like in foundation of R/walls, B/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental	5.16	Per cubic metre	7341.40	37882.00	Rupees Thirty Seven Thousand Eight Hundred & Eighty Two Only

4	Random rubble masonry with hard stones of approved quality in sub structure in cement mortar 1:6 (one cement to six fine sand) for structure like retaining walls, breast walls, wing walls, side walls, abutment and similar works excetra, in all heights/depths in or under water including pumping or bailing out water surface and sub soil water, dewatering, removal of shuttering, which may arise at the time of masonry work under water complete including curing complete as per drawing and technical specification clause 702, 704,1202 and 1204 and as per directions of Engineer - in- Charge including loading, carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	37.92	Per cubic meter	2238.80	84883.00	Rupees Two Lakh Two Thousand Four Hundred & Fourty Seven Only
5	Random coursed rubble dry stone masonry with hard stone of approved quality in sub structure for structure like retaining walls, breast walls excetra in all heights/depths as per S&BD technical specification clause 702, 704,1606.5 and as per directions of Engineer - in-Charge including loading carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	35.28	Per cubic meter	1037.80	18279.00	Rupees One Lakh Fourty Two Thousand Four Hundred & Fifty Four Only
6	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and S&WRD technical specification clause 1204.3.8 and as per directions of Engineer - in-Charge including loading carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	17.28	Per cubic meter	1354.70	23409.00	Rupees Twenty Three Thousand Four Hundred & Nine Only
	Total:-				**490444.00**	
	Quoted Rate in Figures					
	Quoted Rate in Words					

Quoted Rate in Figures (+/-)[_____]%

Quoted Rate in Words (+/-) [_____]%

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MOR (I) at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

J06 D0.22

Percenatge Schedule of Quantity

Name of Work:-Restoration of rain and snow damages on Link road from Rakhani Nallah to Nichala Kuthal km 0/0 to 1/800(Sub-Head:- C/o R/wall at Rd 0/750 to 0/762.60)

Estimated Cost	498305.00
Earnest Money	10000.00
Time	Three Month

Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Word.
1	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering. and as per directions of Engineer - in- Charge including hauling carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases	42.50	Per cubic metre	539.90	22946.00	Rupees Twenty Two Thousand Nine Hundred & Fourty Six Only
2	Providing and laying Mechanically mixed and vibrated concrete for plain reinforced concretenominal mix 1:4:8(one cement is to four sand is to eight graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls,Abutments,toe walls and the like in foundation of R/walls, R/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect	33.49	Per cubic metre	7345.40	245997.00	Rupees Two Lakh Fourty Five Thousand Nine Hundred & Ninety Seven Only
3	Random rubble masonry with hard stones of approved quality in sub structure in cement mortar 1:6(one cement is to six sand) for structure like retaining walls, breast walls, wing walls, toe walls, abutment and similar works etcetera, in all heights/depths in or under water including pumping or bailing out water (surface and sub soil water) dewatering, removal of slushies, which may arise at the time of masonry work under water complete including curing complete as per drawing and technical specification clause 702, 704.1202 and 1204 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	19.33	Per cubic metre	5338.80	103199.00	Rupees One Lakh Three Thousand One Hundred & Ninety Nine Only
4	Random course rubble dry stone masonry with hard stone of approved quality in sub structure for structure like retaining walls, breast walls etcetera in all heights/depths as per MORD technical specification clause 702,704,1606.5 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	27.32	Per cubic metre	4037.80	110313.00	Rupees One Lakh Ten Thousand Three Hundred & Thirteen Only

5	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1204.3.8 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect	11.70	Per cubic metre	1354.70	15850.00	Rupees Fifteen Thousand Eight Hundred & Fifty Only
	Total:-				**498305.00**	
	Quated Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) (----------%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

Job no. 23

Percenatge Schedule of Quantity					Estimated Cost	498305.00
Name of Work:-Restoration of rain and snow damages on Khangsar to Sural Helipad road km 0/0 to 2/0 (Sub-Head: C/o R/wall at Rd 0/795 to 0/800)					Earnest Money	10000.00
					Time	Three Month
Sr. NO	**Description of work**	**Quantity**	**Unit**	**Estimated Rate (in Rs.)**	**Total Amount with all taxes Including GST in Rs.**	**Total Amount with all taxes Including GST in Word.**
1	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D technical specification clause 305.1 and as per direction of the Engineer- In - Charge including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering, and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other meidental complete in all respect. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases	42.50	Per cubic metre	539.90	22946.00	Rupees Twenty Two Thousand Nine Hundred & Fourty Six Only
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concretenominal mix 1:4:8(one cement is to four sand is to eight graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls,Abutments,toe walls and the like in foundation of R/walls, B/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	53.49	Per cubic metre	7345.40	245997.00	Rupees Two Lakh Fourty Five Thousand Nine Hundred & Ninety Seven Only
3	Random rubble masonry with hard stones of approved quality in sub structure in cement mortar 1:6 (one cement is to six sand) for structure like retaining walls, breast walls, wing walls, toe walls, abutment and similar works etcetera, in all heights/depths in or under water including pumping or bailing out water (surface and sub soil water) / dewatering, removal of slushies, which may arise at the time of masonry work under water complete including curing complete as per drawing and technical specification clause 702, 704.1202 and 1204 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	19.33	Per cubic metre	5338.80	103199.00	Rupees One Lakh Three Thousand One Hundred & Ninety Nine Only
4	Random course rubble dry stone masonry with hard stone of approved quality in sub structure for structure like retaining walls, breast walls etcetra in all heights/depths as per MORD technical specification clause 702,704,1606.5 and as per directions of Engineer - In- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	27.32	Per cubic metre	4037.80	110313.00	Rupees One Lakh Ten Thousand Three Hundred & Thirteen Only

5	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1204.3.8 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect	11.70	Per cubic metre	1354.70	15850.00	Rupees Fifteen Thousand Eight Hundred & Fifty Only
		Total:-			**498305.00**	
	Quated Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

Job.No.24

Percenatge Schedule of Quantity					Estimated Cost	479343.00
Name of Work:-R/o of rain and snow damages on Sach to Kumar Parmar Bhatori road km 0/0 to 11/280 (Sub Head:-C/o R/wall at RD km 4/090 to 4/102)					Earnest Money	10000.00
					Time	Three Month
Sr. NO	**Description of work**	**Quantity**	**Unit**	**Estimated Rate (in Rs.)**	**Total Amount with all taxes Including GST in Rs.**	**Total Amount with all taxes Including GST in Word**
1	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. . Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases .	41.28	Per cubic metre	539.90	22287.00	Rupees Twenty Two Thousand Two Hundred & Eighty Seven Only
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concretenominal mix 1:6:12(one cement is to six sand is to twelve graded crushed stone aggregate 20millimeter (Twenty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls,Abutments,toe walls and the like in foundation of R/walls, B/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi, royality, Malkana, tolltax, Sale Tax or other taxes imposed by the government	8.64	Per Cubic Metre	6871.89	59373.00	Rupees Fifty Nine Thousand Three Hundred & Seventy Three Only
3	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concretenominal mix 1:4:8(one cement is to four sand is to eight graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls,Abutments,toe walls and the like in foundation of R/walls, B/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental	5.28	Per cubic metre	7345.40	38784.00	Rupees Thirty Eight Thousand Seven Hundred & Eighty Four Only

4	Random rubble masonry with hard stones of approved quality in sub structure in cement mortar 1:6 (one cement is to six sand) for structure like retaining walls, breast walls, wing walls, toe walls, abutment and similar works etcetera, in all heights/depths in or under water including pumping or bailing out water (surface and sub soil water) / dewatering, removal of slushies, which may arise at the time of masonry work under water complete including curing complete as per drawing and technical specification clause 702, 704,1202 and 1204 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	37.02	Per cubic metre	5338.80	197642.00	Rupees One Lakh Ninety Seven Thousand Six Hundred & Fourty Two Only
5	Random course rubble dry stone masonry with hard stone of approved quality in sub structure for structure like retaining walls, breast walls etcerra in all heights/depths as per MORD technical specification clause 702,704,1606.5 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	35.36	Per cubic metre	4037.80	142777.00	Rupees One Lakh Fourty Two Thousand Seven Hundred & Seventy Seven Only
6	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1204.3.8 and as per directions of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	9.72	Per cubic metre	1345.70	13080.00	Rupees Thirteen Thousand &Eighty Only
7	Providing and laying P.C.C. M-20 copping on the top of the winw wall,return wall & Breast wall etc.complete as per drawing and techanical specification clause 612,710.1204.3.1(1:2:4)and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	12.00	Per Running metre	450.00	5400.00	Rupees Five Thousand Four Hundred Only
	Total:-				**479343.00**	
	Quated Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words (+/-) (----------%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

Job No. 29

Percenatge Schedule of Quantity					Estimated Cost	496960.00
Name of Work: Name of Work: R/O Rain and Snow damages on Seri Bhatwas to Village Parmas km 0/0 to 2/100(Sub Head:- C/O R/wall at Rd1/040 to 1/061)					Earnest Money	10000.00
					Time	Three Month
Sr. NO	**Description of work**	**Quantity**	**Unit**	**Estimated Rate (in Rs.)**	**Total Amount with all taxes Including GST in Rs.**	**Total Amount with all taxes Including GST in Word**
1	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering. and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. . Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases .	62.40	Per cubic metre	539.00	33634.00	Rupees Thirty Three Thousand Six Hundred & Thirty Four Only
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concretenominal mix 1:6:12(one cement is to six sand is to twelve graded crushed stone aggregate 20millimeter (Twenty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breasi walls,Abutments,toe walls and the like in foundation of R/walls, B/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi, royality, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	9.03	Per Cubic Metre	6871.89	62053.00	Rupees Sixty Two Thousand &Fifty Three Only
3	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concretenominal mix 1:4:8(one cement is to four sand is to eight graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls,Abutments,toe walls and the like in foundation of R/walls, B/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	3.78	Per cubic metre	7341.40	27750.00	Rupees Twenty Seven Thousand Seven Hundred & Fifty Only

4	Random rubble masonry with hard stones of approved quality in sub structure in cement mortar 1:6 (one cement is to six sand) for structure like retaining walls, breast walls, wing walls, toe walls, abutment and similar works etcetera, in all heights/depths in or under water including pumping or bailing out water (surface and sub soil water) / dewatering, removal of slushies, which may arise at the time of masonry work under water complete including curing complete as per drawing and technical specification clause 702, 704,1202 and 1204 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	30.65	Per cubic metre	5338.80	163634.00	Rupees One Lakh Sixty Three Thousand Six Hundred & Thirty Four Only
5	Random course rubble dry stone masonry with hard stone of approved quality in sub structure for structure like retaining walls, breast walls etcetra in all heights/depths as per MORD technical specification clause 702,704,1606.5 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	45.64	Per cubic metre	4037.80	184285.00	Rupees One Lakh Eighty Four Thousand Two Hundred & Eighty Five Only
6	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1204.3.8 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	18.90	Per cubic metre	1354.70	25604.00	Rupees Twenty Five Thousand Six Hundred & Four Only
	Total:-				**496960.00**	
	Quated Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

Job No.-25

Percenatge Schedule of Quantity					Estimated Cost	496965.00
Name of Work:-R/O rain and snow damages on Link road to Village Changali Punto km 0/0 to 2/135 (Sub Head:- C/o R/wall at Rd 1/709 to 1/725)					Earnest Money	10000.00
					Time	Three Month
Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Word
1	Earth work in excavation for all types of road structures such as retaining wall, breast wall, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary Rock,Hard rock, chiseling/wedging out of rock (where blasting is prohibited) as per drawing and M.O.R.D. technical specifications Clause 305 and 1603.4 as per direction of the Engineer -in - charge including setting out, shoring and bracing, removal of stumps and other deleterious material and disposal of material upto any leads and upto any lifts , including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundered fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer - in Charge . Including carriage of materials within all leads and lifts and other incidental . The rate including of GST, or other taxes imposed by the government.	59.92	Per cubic Metre	539.90	32351.00	Rupees Thirty Two Thousand Three Hundred & Fifty One Only
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concretenominal mix 1:6:12(one cement is to six sand is to twelve graded crushed stone aggregate 20millimeter (Twenty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls.Abutments,toe walls and the like in foundation of R/walls, B/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi, royality, Malkana, tolltax,	7.84	Per Cubic Metre	7200.00	56448.00	Rupees Fifty Six Thousand Four Hundred & Fourty Eight Only
3	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concretenominal mix 1:4:8(one cement is to four sand is to eight graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls.Abutments,toe walls and the like in foundation of R/walls, B/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	3.20	Per cubic metre	7800.00	24960.00	Rupees Twenty Four Thousand Nine Hundred & Sixty Only

4	Random rubble masonry with hard stones of approved quality in sub structure in cement mortar 1:6 (one cement is to Six sand) for structure like retaining walls, breast walls, wing walls, toe walls, abutment and similar works etcetera, in all heights/depths in or under water including pumping or bailing out water (surface and sub soil water) / dewatering, removal of slushies, which may arise at the time of masonry work under water complete including curing complete as per drawing and technical specification clause 702, 704,1202 and 1204 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	33.36	Per Cubic Metre	5500.00	183480.00	Rupees One Lakh Eighty Three Thousand Four Hundred & Eighty Only
5	Random course rubble dry stone masonry with hard stone of approved quality in sub structure for structure like retaining walls, breast walls etcetra in all heights/depths as per MORD technical specification clause 702,704,1606.5 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	44.46	Per cubic metre	4037.80	179521.00	Rupees One Lakh Seventy Nine Thousand Five Hundred & Twenty One Only
6	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1204.3.8 and as per directions of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	9.60	Per cubic metre	1354.70	13005.00	Rupees Thirteen Thousand &Five Only
7	Providing and laying P.C.C. M-20 copping on the top of the winw wall,return wall & Breast wall etc.complete as per drawing and technical specification clause 612,710.1204.3.1(1:2:4)and as per directions of Engineer - in Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	16.00	Per Running metre	450.00	7200.00	Rupees Seven Thousand Two Hundred Only
	Total:-				**496965.00**	
	Quated Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words (+/-) (.....%)

Condition :-
Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications

Executive Engineer
Killar Division
HPPWD Killar

Job No-27

Percenatge Schedule of Quantity					Estimated Cost	497560.00
Name of Work:-R/O Rain and snow damages on Link road to Village Changli km 0/0 to 2/235 (Sub Head:-C/O B/wall at Rd 1/435 to 1/454)					Earnest Money	10000.00
					Time	Three Month
Sr. NO	**Description of work**	**Quantity**	**Unit**	**Estimated Rate (in Rs.)**	**Total Amount with all taxes Including GST in Rs.**	**Total Amount with all taxes Including GST in Word**
1	Excavation in hilly area in all heights and depths and in all kind of soil by mannual/mechanical means including saturated soil comprising of ordinary soil,soft rock,hard rock chiselling,wedging out of rock(where blasting is prohibited) and their intermediate classification of solid setting out true to the required lines grades width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-Charge at site according to the MORD technical specification clause 302.1603 and 1603.2 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transporation of unuseful material for filling in road wyas camber,embankments for grade improvements and disposal of all material to required width of the road or on approved dumping site through all modes of transporation including head load or animal transport or mechanical means alongwith its levelling fine dressing and carriage of machineries ,materials, tolls,equipments and safety measures and incidentials necessary to complete the work by mechanical means,and labour if required all Any loss to the public private property during the course of execution shall be the absolute respensibility of the contractor which shall have to be compensated by him in all cases.The rate including octroi royality Malkhana toll tax sale tax or other taxes imposed	140.22	Per cubic metre	182.20	25548.00	Rupees Twenty Five Thousand Five Hundred & Fourty Eight Only
2	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering. and as per directions of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. . Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to	15.58	Per cubic metre	539.90	8412.00	Rupees Eight Thousand Four Hundred & Twelve Only

3	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concretenominal mix 1:4:8(one cement is to four sand is to eight graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls,Abutments,toe walls and the like in foundation of R/walls, B/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental	3.99	Per cubic metre	6871.89	27419.00	Rupees Twenty Seven Thousand Four Hundred & Nineteen Only
4	Random rubble masonry with hard stones of approved quality in sub structure in cement mortar 1:6 (one cement is to Six sand) for structure like retaining walls, breast walls, wing walls, toe walls, abutment and similar works etcetera, in all heights/depths in or under water including pumping or bailing out water (surface and sub soil water) / dewatering, removal of slushies, which may arise at the time of masonry work under water complete including curing complete as per drawing and technical specification clause 702, 704,1202 and 1204 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	46.70	Per Cubic Metre	5338.80	249322.00	Rupees Two Lakh Fourty Nine Thousand Three Hundred & Twenty Two Only
5	Random course rubble dry stone masonry with hard stone of approved quality in sub structure for structure like retaining walls, breast walls etcetra in all heights/depths as per MORD technical specification clause 702,704,1606.5 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	44.16	Per cubic metre	4037.80	178309.00	Rupees One Lakh Seventy Eight Thousand Three Hundred & Nine Only
6	Providing and laying P.C.C. M-20 copping on the top of the winw wall,return wall & Breast wall etc.complete as per drawing and techanical specification clause 612,710.1204,3.1(1:2:4)and as per directions of Engineer - in Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	19.00	Per Running metre	450.00	8550.00	Rupees Eight Thousand Five Hundred & Fifty Only
	Total:-				**497560.00**	
	Quated Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words (+/-) (.....-%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

Percenatge Schedule of Quantity					Estimated Cost	489500.00
Name of Work:-A/R & M/O Non Residntial Building HPPWD Division at Killar (Sub-Head:- Providing and Installation of computer,printer, Accessories ,LED TV,Dish, Networking Equipment and Heater etc.)					Earnest Money	10000.00
					Time	Three Month
Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Word.
1	Providing and Installation of computer equipment with make and modal of DELL Desktop i5 (I Five) processor, 8GB ram and I TBHHD window 10 original with warranty to be provided by the company itself during warranty period from authorized HP world stoe as entire satisfaction and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	3.00	Nos	73500.00	220500.00	Rupees Two Lakh Twenty Thousand Five Hundred Only
2	Providing and Installation of Printer be provided by the company itself during warranty period from authorized HP world stoe as entire satisfaction and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	3.00	Nos	29000.00	87000.00	Rupees Eighty Seven Thousand Only
3	Providing and Installation of electric and Gas heater be provided by the company itself during warranty period from authorized HP world stoe as entire satisfaction and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	7.00	Nos	12500.00	87500.00	Rupees Eighty Seven Thousand Five Hundred Only
4	Providing and Installation of LED TV Samsung 32 inch be provided by the company itself during warranty period from authorized HP world stoe as entire satisfaction and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	1.00	Nos	29000.00	29000.00	Rupees Twenty Nine Thousand Only
5	Providing and Installation of Receiver Samsung be provided by the company itself during warranty period from authorized HP world stoe as entire satisfaction and as per directions of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	2.00	Nos	7500.00	15000.00	Rupees Fifteen Thousand Only
6	Providing and Installation of Dish Airtel be provided by the company itself during warranty period from authorized HP world stoe as entire satisfaction and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	1.00	Nos	3500.00	3500.00	Rupees Three Thousand Five Hundred Only
7	Providing and Installation of Internet Router be provided by the company itself during warranty period from authorized HP world stoe as entire satisfaction and as per directions of Engineer – in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	1.00	Nos	7500.00	7500.00	Rupees Seven Thousand Five Hundred Only
8	Providing and Laying of wire for internet router be provided by the company itself during warranty period from authorized HP world stoe as entire satisfaction and as per directions of Engineer – in-Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	250.00	Per running meter	98.00	24500.00	Rupees Twenty Four Thousand Five Hundred Only

9	Providing and Installation of mannual chang over three phase be provided by the company itself during warranty period from authorized HP world stoe as entire satisfaction and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	1.00	Nos	15000.00	15000.00	Rupees Fifteen Thousand Only
	Total:-				**489500.00**	
	Quated Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words (+/-) (----------%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

Job No. 29

Percenatge Schedule of Quantity					Estimated Cost	496960.00
Name of Work:-Restoration of rain and snow damages on Link road from Mall road Killar to Food Godown Killar km 0/0 to 0/500 (Sub-Head:- C/o R/wall at Rd 0/160 to 0/181).					Earnest Money	10000.00
					Time	Three Month
Sr. NO	**Description of work**	**Quantity**	**Unit**	**Estimated Rate (in Rs.)**	**Total Amount with all taxes Including GST in Rs.**	**Total Amount with all taxes Including GST in Word.**
1	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets,etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering. and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect . Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases	62.40	Per cubic metre	539.00	33634.00	Rupees Thirty Three Thousand Six Hundred & Thirty Four Only
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concretenominal mix 1:6:12(one cement is to six sand is to twelve graded crushed stone aggregate 20millimeter (Twenty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls. Breast walls,Abutments,toe walls and the like in foundation of R/walls, B/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D technical specificatioo Clauses 802.803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi, royality, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	9.03	Per Cubic Metre	6871.89	62053.00	Rupees Sixty Two Thousand &Fifty Three Only
3	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concretenominal mix 1:4:8(one cement is to four sand is to eight graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls. Breast walls,Abutments,toe walls and the like in foundation of R/walls, B/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specificatioo Clauses 802.803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	3.78	Per cubic metre	7341.40	27750.00	Rupees Twenty Seven Thousand Seven Hundred & Fifty Only

4	Random rubble masonry with hard stones of approved quality in sub structure in cement mortar 1:6 (one cement is to six sand) for structure like retaining walls, breast walls, wing walls, toe walls, abutment and similar works etcetera, in all heights/depths in or under water including pumping or bailing out water (surface and sub soil water) / dewatering, removal of slushies, which may arise at the time of masonry work under water complete including curing complete as per drawing and technical specification clause 702, 704,1202 and 1204 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect	30.65	Per cubic metre	5338.80	163634.00	Rupees One Lakh Sixty Three Thousand Six Hundred & Thirty Four Only
5	Random course rubble dry stone masonry with hard stone of approved quality in sub structure for structure like retaining walls, breast walls etcetra in all heights/depths as per MORD technical specification clause 702.704,1606.5 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	45.64	Per cubic metre	4037.80	184285.00	Rupees One Lakh Eighty Four Thousand Two Hundred & Eighty Five Only
6	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1204.3.8 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect	18.90	Per cubic metre	1354.70	25604.00	Rupees Twenty Five Thousand Six Hundred & Four Only
	Total:-				**496960.00**	
	Quated Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words (+/-) (----------%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

Job No. 30

Percenatge Schedule of Quantity

Name of Work:-A/R & M/O Karyas to Tattan Mata Mandir road km 0/0 to 8/600 (Sub Head:-P/F crash barrier at Rd. 4/427 to 4/479)					Estimated Cost	398774.00
					Earnest Money	7975.00
					Time	Three Month
Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Word
1	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering, and as per directions of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. . Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases .	4.04	Per cubic metre	539.90	2181.00	Rupees Two Thousand One Hundred & Eighty One Only
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations for all types of structure complete using plain cement concrete grade M-15 (M fifteen) nominal mix 1:2.5:5 (one cement : Two piont five sand :Six graded crushed /broken stone aggregate 40 mm (Forty Milimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arrisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and M.O.R.D. technical specifications section 800, 900 & 1200 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental.The rate including of GST, or other taxes imposed by the government.	4.04	Per Cubic Metre	13794.00	55728.00	Rupees Fifty Five Thousand Seven Hundred & Twenty Eight Only

3	Providing and fixing "W" metal beam crash barrier compeising of 3mm (three millimetre) thick corrugated steel metal beam rail, 70cm (seventy centimetre) above road ground level, fixed on ISMC series channel vertical post 150x75x5mm (onehundred fifty into seventy five into five millimetre) spaced @ 2.0 mtr.(two metre) centre to centre 1.80 mtre.(one point eight zero metre) height 1.10 mtr.(one point one zero metre) below ground/road level all steel parts and fitment conform to IS:1367 and IS 1364, metal beam rail to be fixed on the vertical post with a spacer of channe section 150xx75x5mm (one hundred fifty into seventy five into five millimetre) 330 mtr.(three hundred thirty metre) long complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling carriage of materials to	52.00	Per Running metre	6555.10	340865.00	Rupees Three Lakh Fourty Thousand Eight Hundred & Sixty Five Only
	Total:-				**398774.00**	
	Quated Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

Job No.3/

Percenatge Bill of Quantity					Estimated Cost	415444.00
Name of Work:-R/O Rain and Snow damages on Link road from Purthi to Ajog km 0/0 to 2/600(Sub Head:-C/o R/wall at Edging at Rd 2/255 to 2/275)					Earnest Money	8300.00
					Time	Three Month
Sr. NO	**Description of work**	**Quantity**	**Unit**	**Estimated Rate (in Rs.)**	**Total Amount with all taxes Including GST in Rs.**	**Total Amount with all taxes Including GST in Word.**
1	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiscling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering, and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. . Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases .	36.00	Per cubic metre	396.00	14256.00	Rupees Fourteen Thousand Two Hundred & Fifty Six Only
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concretenominal mix 1:6:12(one cement is to six sand is to twelve graded crushed stone aggregate 20millimeter (Twenty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls,Abutments,toe walls and the like in foundation of R/walls, B/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi, royality, Malkana, toiltax, Sale Tax or other taxes imposed by the government.	7.00	Per Cubic Metre	6871.89	48103.00	Rupees Fourty Eight Thousand One Hundred & Three Only
3	Random rubble masonry with hard stones of approved quality in sub structure in cement mortar 1:6 (one cement is to six sand) for structure like retaining walls, breast walls, wing walls, toe walls, abutment and similar works etcetera, in all heights/depths in or under water including pumping or bailing out water (surface and sub soil water) / dewatering, removal of slushies, which may arise at the time of masonry work under water complete including curing complete as per drawing and technical specification clause 702, 704,1202 and 1204 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	62.50	Per Cubic Metre	5338.80	333675.00	Rupees Three Lakh Thirty Three Thousand Six Hundred & Seventy Five Only
4	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1204.3.8 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	10.20	Per cubic metre	1050.00	10710.00	Rupees Ten Thousand Seven Hundred & Ten Only

4	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1204.3.8 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	10.20	Per cubic metre	1050.00	10710.00	Rupees Ten Thousand Seven Hundred & Ten Only
5	Providing and laying P.C.C. M-20 copping on the top of the winw wall,return wall & Breast wall etc.complete as per drawing and technical specification clause 612,710.1204,3.1(1:2:4)and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	20.00	Per Running metre	435.00	8700.00	Rupees Eight Thousand Seven Hundred Only
	Total:-				**415444.00**	
	Quated Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) (----------%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

Job No. 32

Percenatge Schedule of Quantity					Estimated Cost	499276.00
Name of Work:-Restoration of rain and snow damages on Link road Godhan to Korei Km 0/0 to 0/825 (Sub-Head:- C/o B/wall at Rd 0/060 to ~~0/863~~ 0/077.50)					Earnest Money	10000.00
					Time	Three Month
Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in R.	Total Amount with all taxes Including GST in Word
1	Excavation in hilly area in all heights and depths and in all kind of soil by mannual/mechanical means including saturated soil comprising of ordinary soil,soft rock,hard rock chiselling,wedging out of rock(where blasting is prohibited) and their intermediate classification of soild setting out true to the required lines grades width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-Charge at site according to the MORD technical specification clause 302,1603 and 1603.2 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transporation of unuseful material for filling in road wyas camber,embankments for grade improvements and disposal of all material to required width of the road or on approved dumping site through all modes of transporation including head load or animal transport or mechanical means alongwith its levelling fine dressing and carriage of machineries ,materials, tolls,equipments and safety measures and incidentials necessary to complete the work by mechanical means.and labour if required all Any loss to the public private property during the course of execution shall be the absolute respensibility of the contractor which shall have to be compensated by him in all cases.The rate including octroi royality Malkhana toll tax sale tax or other taxes imposed by the Government	49.15	Per cubic metre	182.20	8955.00	Rupees Eight Thousand Nine Hundred & Fifty Five Only
2	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering. and as per directions of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. . Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases	25.55	Per cubic metre	539.90	13794.00	Rupees Thirteen Thousand Seven Hundred & Ninety Four Only

3	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concretenominal mix 1:4:8(one cement is to four sand is to eight graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls,Abutments,toe walls and the like in foundation of R/walls, B/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental	4.20	Per cubic metre	7345.40	30851.00	Rupees Thirty Thousand Eight Hundred & Fifty One Only
4	Random rubble masonry with hard stones of approved quality in sub structure in cement mortar 1:6 (one cement is to six sand) for structure like retaining walls, breast walls, wing walls, toe walls, abutment and similar works etcetera, in all heights/depths in or under water including pumping or bailing out water (surface and sub soil water) / dewatering, removal of slushies, which may arise at the time of masonry work under water complete including curing complete as per drawing and technical specification clause 702, 704,1202 and 1204 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	38.10	Per cubic metre	5338.80	203408.00	Rupees Two Lakh Three Thousand Four Hundred & Eight Only
5	Random course rubble dry stone masonry with hard stone of approved quality in sub structure for structure like retaining walls, breast walls etcetra in all heights/depths as per MORD technical specification clause 702,704,1606.5 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	60.00	Per cubic metre	4037.80	242268.00	Rupees Two Lakh Fourty Two Thousand Two Hundred & Sixty Eight Only
	Total:-				**499276.00**	
	Quated Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar