

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No.PW-MDI(P)E-Tender-NIT/2025-26- 14199-205 Dated:- 9/1/26

To

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per Notification Secretary (PW) to the Govt. of H.P. letter No. PBW (B) A (3) 8/2025-300858 dated 13th Nov. 2025 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

Copy alongwith copy of Tender Notice is forwarded to the following for information and necessary action:-

1. The Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar.
2. All the Assistant Engineers, Working under this Division.
3. The Drawing Branch of this office.
4. Notice Board.

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed percentage rate tender on form No. 6&8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 19.01.2026 up to 12:00 Noon and the same shall be opened on the same day at 12:30 P.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 17.01.2026 upto 12.00 Noon.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.


Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Restoration of rain damages on Drang Seridhar Soyla road Km 0/0 to 3/500 (PDNA-2023) (SH:- Construction of Breast wall at RD 1/990 to 2/010).	2,60,503.36	5200/-	350/-	One month
2	Restoration of rain damages on Drang Seridhar Soyla road Km 0/0 to 3/500 (PDNA-2023) (SH:- Construction of Breast wall at RD 0/315 to 0/325).	1,87,558.78	3800/-	350/-	One month
3	Restoration of rain damages on Drang Seridhar Soyla road Km 0/0 to 3/500 (PDNA-2023) (SH:- Construction of Breast wall at RD 0/075 to 0/085).	1,26,759.14	2500/-	350/-	One month
4	Restoration of rain damages on Thaltukhod to Graman road Km 0/00 to 5/00 (PDNA-2023) (SH:- Construction of Retaining wall at RD 1/250 to 1/253.60)	94,341.85	1900/-	350/-	One month
5	Restoration of rain damages on Thaltukhod to Graman road Km 0/00 to 5/00 (PDNA-2023) (SH:- Construction of Retaining wall at RD 1/253.60 to 1/257.20)	94,312.40	1900/-	350/-	One month
6	Restoration of rain damages on Ghatasani Jhatingri Tikkan Barot road Km 0/00 to 25/00. (PDNA-2023) (SH:- Construction of Breast Wall at RD 3/020 to 3/035)	2,77,568.58	5600/-	350/-	One month
7	Restoration of rain damages on Silhbudhani Sudhar road Km 0/0 to 5/00. (PDNA-2023) (SH:- Construction of Retaining wall at RD 0/765 to 0/777)	3,24,096.76	6500/-	350/-	One month
8	Restoration of rain damages on Silhbudhani Sudhar road Km 0/0 to 5/00. (PDNA-2023) (SH:- Construction of Breast wall at RD 0/765 to 0/777)	1,55,912.54	3100/-	350/-	One month
9	Restoration of rain damages on Silhbudhani Sudhar road Km 0/0 to 5/00. (PDNA-2023) (SH:- Construction of Retaining wall at RD 1/635 to 1/646)	2,97,349.34	5900/-	350/-	One month

10	Restoration of rain damages on Ropa Kathog road Km 0/0 to 5/500. (PDNA-2023) (SH:- Construction of Retaining wall at RD 1/120 to 1/130)	2,62,023.91	5200/-	350/-	One month
11	Restoration of rain damages on Ropa Kathog road Km 0/0 to 5/500. (PDNA-2023) (SH:- Construction of Retaining wall at RD 1/690 to 1/705)	3,93,012.05	7900/-	350/-	One month
12	Restoration of rain damages on Silhbudhani Kungri Kortang road Km 0/0 to 5/00. (PDNA-2023) (SH:- Construction of Retaining wall at RD 1/825 to 1/837)	4,28,678.62	8600/-	350/-	One month
13	Restoration of rain damages on Silhbudhani Kungri Kortang road Km 0/0 to 5/00. (PDNA-2023) (SH:- Construction of Retaining wall at RD 3/980 to 3/993)	3,48,046.72	7000/-	350/-	One month
14	Restoration of rain damages on Silhbudhani Kungri Kortang road Km 0/0 to 5/00. (PDNA-2023) (SH:- Construction of Retaining wall at RD 4/850 to 4/855)	1,33,937.87	2700/-	350/-	One month
15	Restoration of rain damages on Barot Mayot road Km 0/0 to 7/960. (PDNA-2023) (SH:- Construction of Retaining wall at RD 3/010 to 3/030)	4,10,484.14	8200/-	350/-	One month
16	Restoration of rain damages on Barot Mayot road Km 0/0 to 7/960. (PDNA-2023) (SH:- Construction of Retaining wall at RD 5/600 to 5/615)	3,96,380.40	7900/-	350/-	One month

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit/undertaking that he is not having more two works.
5. Only two tenders form will be issued to the contractor/firms which may be noted.
6. The intending Contractors are requested to see the site of the work before submitting the tender.
7. The offer of the tender shall remain valid upto 75 days after the opening of tender.
8. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


 Executive Engineer,
 Mandi Division No. I,
 HPPWD, at Padhar Distt. Mandi (H.P.)
 on behalf of Governor of Himachal Pradesh

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 260503.36
 Earnest Money Rs:- 5200.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.
 Name of work :- Restoration of rain damages on Drang Seridhar Soyla road km. 0/00 to 3/500. (PDNA-2023). (Sub Head:- Construction of Breast wall at RD 1/990 to 2/010).

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Excavation in soil in hilly area in ordinary rock not required blasting by mechanical means for all kinds of soil including cutting and trimming of side slopes and disposing of cut materials with a lift upto 1.5 meter (one point five) and lead upto 20 (twenty meter) as per technical specification clause 1603.2. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	28.16	Per cubic metre	162.70	4581.63	Rupees Four Thousand Five Hundred Eighty One and Paise Sixty Three Only
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	25.30	Per cubic metre	522.50	13219.25	Rupees Thirteen Thousand Two Hundred Nineteen and Paise Twenty Five Only
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	46.36	Per cubic metre	4994.10	231526.48	Rupees Two Lakh Thirty One Thousand Five Hundred Twenty Six and Paise Forty Eight Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	40.00	Each	279.40	11176.00	Rupees Eleven Thousand One Hundred Seventy Six Only
Total in figure :					260503.36	Rupees Two Lakh Sixty Thousand Five Hundred Three and Paise Thirty Six Only
Total in Words :					Rupees Two Lakh Sixty Thousand Five Hundred Three and Paise Thirty Six Only	

Executive Engineer,
 Mandi Division No.1,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 187558.78
 Earnest Money Rs:- 3800.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of rain damages on Drang Seridhar Soyla road km. 0/00 to 3/500. (PDNA-2023). (Sub Head:- Construction of Retaining wall at RD 0/315 to 0/325).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	11.10	Per cubic metre	522.50	5799.75	Rupees Five Thousand Seven Hundred Ninety Nine and Paise Seventy Five Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	33.55	Per cubic metre	4994.10	167552.06	Rupees One Lakh Sixty Seven Thousand Five Hundred Fifty Two and Paise Six Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	20.00	Each	279.40	5588.00	Rupees Five Thousand Five Hundred Eighty Eight Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	5.70	Per cubic metre	1512.10	8618.97	Rupees Eight Thousand Six Hundred Eighteen and Paise Ninety Seven Only
Total in figure :					187558.78	Rupees One Lakh Eighty Seven Thousand Five Hundred Fifty Eight and Paise Seventy Eight Only
Total in Words :		Rupees One Lakh Eighty Seven Thousand Five Hundred Fifty Eight and Paise Seventy Eight Only				

Executive Engineer,
 Mandi Division No.I,
 HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 126759.14
Earnest Money Rs:- 2500.00
Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of rain damages on Drang Seridhar Soyla road km. 0/00 to 3/500. (PDNA-2023). (Sub Head:- Construction of Breast wall at RD 0/075 to 0/085).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Excavation in soil in hilly area in ordinary rock not required blasting by mechanical means for all kinds of soil including cutting and trimming of side slopes and disposing of cut materials with a lift upto 1.5 meter (one point five) and lead upto 20 (twenty meter) as per technical specification clause 1603.2. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	10.63	Per cubic metre	162.70	1729.50	Rupees One Thousand Seven Hundred Twenty Nine and Paise Fifty Only
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	7.04	Per cubic metre	522.50	3678.40	Rupees Three Thousand Six Hundred Seventy Eight and Paise Forty Only
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	23.18	Per cubic metre	4994.10	115763.24	Rupees One Lakh Fifteen Thousand Seven Hundred Sixty Three and Paise Twenty Four Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	20.00	Each	279.40	5588.00	Rupees Five Thousand Five Hundred Eighty Eight Only
Total in figure :					126759.14	Rupees One Lakh Twenty Six Thousand Seven Hundred Fifty Nine and Paise Fourteen Only
Total in Words :		Rupees One Lakh Twenty Six Thousand Seven Hundred Fifty Nine and Paise Fourteen Only				

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 94341.85

Earnest Money Rs:- 1900.00

Time:- one month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.

Name of work :- Restoration of Rain Damages on Thaltukhod to Graman road km.0/00 to 5/00. (PDNA-2023). (Sub Head :- Construction of Retaining wall at R.D. 1/250 to 1/253.60).

Contract No:-

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	7.06	Per cubic metre	491.80	Rupees Three Thousand Four Hundred Seventy Two and Paise Eleven Only	3472.11
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	17.52	Per cubic metre	4879.60	Rupees Eighty Five Thousand Four Hundred Ninety and Paise Fifty Nine Only	85490.59
3	Providing weep hole in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia. (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical into twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	6.00	Each	282.90	Rupees One Thousand Six Hundred Ninety Seven and Paise Forty Only	1697.40
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	2.50	Per cubic metre	1472.70	Rupees Three Thousand Six Hundred Eighty One and Paise Seventy Five Only	3681.75
Total in figure :					Rupees Ninety Four Thousand Three Hundred Forty One and Paise Eighty	94341.85
Total in Words :					Rupees Ninety Four Thousand Three Hundred Forty One and Paise Eighty Five Only	

Executive Engineer,
Mandi Division No.1,
HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 94312.40

Earnest Money Rs:- 1900.00

Time:- one month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of Rain Damages on Thaltukhod to Graman road km.0/00 to 5/00. (PDNA-2023). (Sub Head :- Construction of Retaining wall at R.D. 1/253.60 to 1/257.20).						
Contract No:-						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	7.06	Per cubic metre	491.80	3472.11	Rupees Three Thousand Four Hundred Seventy Two and Paise Eleven Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	17.52	Per cubic metre	4879.60	85490.59	Rupees Eighty Five Thousand Four Hundred Ninety and Paise Fifty Nine Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	6.00	Each	282.90	1697.40	Rupees One Thousand Six Hundred Ninety Seven and Paise Forty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	2.48	Per cubic metre	1472.70	3652.30	Rupees Three Thousand Six Hundred Fifty Two and Paise Thirty Only
Total in figure :					94312.40	Rupees Ninety Four Thousand Three Hundred Twelve and Paise Forty Only
Total in Words :		Rupees Ninety Four Thousand Three Hundred Twelve and Paise Forty Only				

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 277568.58
Earnest Money Rs:- 5600.00
Time:- Two month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 H.P.W.D. at Padhar.					
Name of work :- Restoration of rain damages on Ghatasni Jhatingri Tikkan Barot road km. 0/00 to 25/00. (PDNA -2023). (Sub Head: - Construction of Breast at R.D. 3/020 to 3/035).					
Contract No. :					
Bidder Name :					
SCHEDULE OF WORKS					
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	20.10	Per cubic metre	491.80	Rupees Nine Thousand Eight Hundred Eighty Five and Paise Eighteen Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	54.00	Per cubic metre	4863.40	Rupees Two Lakh Sixty Two Thousand Six Hundred Twenty Three and Paise Sixty Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	18.00	Each	281.10	Rupees Five Thousand Fifty Nine and Paise Eighty Only
Total in figure :					277568.58 Rupees Two Lakh Seventy Seven Thousand Five Hundred Sixty Eight and Paise Fifty Eight Only
Total in Words :					Rupees Two Lakh Seventy Seven Thousand Five Hundred Sixty Eight and Paise Fifty Eight Only

Executive Engineer
Mandi Division No 1
H.P.W.D. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 324096.76
 Earnest Money Rs:- 6500.00
 Time:- Two month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

Name of work :- Restoration of rain damages on Sihbudhani Sudhar road km. 0/00 to 5/00. (PDNA -2023). (Sub Head:- Construction of retaining wall at R.D. 0/765 to 0/777).

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	29.04	Per cubic metre	491.80	14281.87	Rupees Fourteen Thousand Two Hundred Eighty One and Paise Eighty Seven Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	60.06	Per cubic metre	4933.70	296318.02	Rupees Two Lakh Ninety Six Thousand Three Hundred Eighteen and Paise Two Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	285.30	3423.60	Rupees Three Thousand Four Hundred Twenty Three and Paise Sixty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	6.84	Per cubic metre	1472.70	10073.27	Rupees Ten Thousand Seventy Three and Paise Twenty Seven Only
Total in figure :					324096.76	Rupees Three Lakh Twenty Four Thousand Ninety Six and Paise Seventy Six Only
Total in Words :		Rupees Three Lakh Twenty Four Thousand Ninety Six and Paise Seventy Six Only				

Executive Engineer,
 Mandi Division No.I,
 HP.PWD at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 155912.54
Earnest Money Rs:- 3100.00
Time:- Two month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

Name of work :- Restoration of rain damages on Silbudhani Sudhar road km. 0/00 to 5/00. (PDNA -2023). (Sub Head: - Construction of Breast wall at R.D. 0/765 to 0/777).

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	20.04	Per cubic metre	491.80	9855.67	Rupees Nine Thousand Eight Hundred Fifty Five and Paise Sixty Seven Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	28.91	Per cubic metre	4933.70	142633.27	Rupees One Lakh Forty Two Thousand Six Hundred Thirty Three and Paise Twenty Seven Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	285.30	3423.60	Rupees Three Thousand Four Hundred Twenty Three and Paise Sixty Only
Total in figure :					155912.54	Rupees One Lakh Fifty Five Thousand Nine Hundred Twelve and Paise Four Only
Total in Words :		Rupees One Lakh Fifty Five Thousand Nine Hundred Twelve and Paise Fifty Four Only				

Executive Engineer,
Mandi Division No.I,
HP.PWD at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 297349.34
 Earnest Money Rs:- 5900.00
 Time:- Two month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

Name of work :- Restoration of rain damages on Silhbudhani Sudhar road km. 0/00 to 5/00. (PDNA -2023). (Sub Head: - Construction of Retaining wall at R.D. 1/635 to 1/646).

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	26.62	Per cubic metre	491.80	13091.72	Rupees Thirteen Thousand Ninety One and Paise Seventy Two Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	55.05	Per cubic metre	4933.70	271600.19	Rupees Two Lakh Seventy One Thousand Six Hundred and Paise Nineteen Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	285.30	3423.60	Rupees Three Thousand Four Hundred Twenty Three and Paise Sixty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	6.27	Per cubic metre	1472.70	9233.83	Rupees Nine Thousand Two Hundred Thirty Three and Paise Eighty Three Only
Total in figure :					297349.34	Rupees Two Lakh Ninety Seven Thousand Three Hundred Forty Nine and Paise Four Only
Total in Words :					Rupees Two Lakh Ninety Seven Thousand Three Hundred Forty Nine and Paise Thirty Four Only	

**Executive Engineer,
 Mandi Division No.I,
 HP.PWD at Padhar**

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 262023.91
Earnest Money Rs:- 5200.00
Time:- Two month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of rain damages on Ropa Kathog road km. 0/00 to 5/500. (PDNA -2023). (Sub Head: - Construction of Retaining wall at R.D. 1/120 to 1/130).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	24.20	Per cubic metre	491.80	11901.56	Rupees Eleven Thousand Nine Hundred One and Paise Fifty Six Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	50.05	Per cubic metre	4763.10	238393.16	Rupees Two Lakh Thirty Eight Thousand Three Hundred Ninety Three and Paise Sixteen Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	277.90	3334.80	Rupees Three Thousand Three Hundred Thirty Four and Paise Eighty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	5.70	Per cubic metre	1472.70	8394.39	Rupees Eight Thousand Three Hundred Ninety Four and Paise Thirty Nine Only
Total in figure :					262023.91	Rupees Two Lakh Sixty Two Thousand Twenty Three and Paise Ninety One Only
Total in Words :					Rupees Two Lakh Sixty Two Thousand Twenty Three and Paise Ninety One Only	

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 393012.05
Earnest Money Rs:- 7900.00
Time:- Two month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 H.P.W.D. at Padhar.						
Name of work :- Restoration of rain damages on Ropa Kathog road km. 0/00 to 5/500. (PDNA -2023). (Sub Head: - Construction of Retaining wall at R.D. 1/690 to 1/705).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	36.30	Per cubic metre	491.80	17852.34	Rupees Seventeen Thousand Eight Hundred Fifty Two and Paise Thirty Four Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	75.07	Per cubic metre	4763.10	357565.92	Rupees Three Lakh Fifty Seven Thousand Five Hundred Sixty Five and Paise Ninety Two Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	18.00	Each	277.90	5002.20	Rupees Five Thousand Two and Paise Twenty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	8.55	Per cubic metre	1472.70	12591.59	Rupees Twelve Thousand Five Hundred Ninety One and Paise Fifty Nine Only
Total in figure :					393012.05	Rupees Three Lakh Ninety Three Thousand Twelve and Paise Five Only
Total in Words :		Rupees Three Lakh Ninety Three Thousand Twelve and Paise Five Only				

Executive Engineer
Mandi Division No 1
H.P.W.D. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 428678.62

Earnest Money Rs:- 8600.00

Time Two month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of Rain Damages on Sihbudhani Kungri Kortang road km.0/00 to 5/00. (PDNA-2023). (Sub Head :- Construction of Retaining wall at R.D. 1/825 to 1/837).						
Contract No:-						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Excavation in soil in hilly area by mechanical means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	41.64	Per cubic metre	491.80	20478.55	Rupees Twenty Thousand Four Hundred Seventy Eight and Paise Fifty Five Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	78.03	Per cubic metre	4942.80	385686.68	Rupees Three Lakh Eighty Five Thousand Six Hundred Eighty Six and Paise Sixty Eight Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	285.60	3427.20	Rupees Three Thousand Four Hundred Twenty Seven and Paise Twenty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.96	Per cubic metre	1472.70	19086.19	Rupees Nineteen Thousand Eighty Six and Paise Nineteen Only
Total in figure :					428678.62	Rupees Four Lakh Twenty Eight Thousand Six Hundred Seventy Eight and Paise Sixty Two Only
Total in Words :		Rupees Four Lakh Twenty Eight Thousand Six Hundred Seventy Eight and Paise Sixty Two Only				

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 348046.72

Earnest Money Rs:- 7000.00

Time Two month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

Name of work :- Restoration of Rain Damages on Sihbudhani Kungri Kortang road km.0/00 to 5/00. (PDNA-2023). (Sub Head :- Construction of Retaining wall at R.D. 3/980 to 3/993).

Contract No:-

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Excavation in soil in hilly area by mechanical means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	30.29	Per cubic metre	491.80	14896.62	Rupees Fourteen Thousand Eight Hundred Ninety Six and Paise Sixty Two Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	63.28	Per cubic metre	4960.80	313919.42	Rupees Three Lakh Thirteen Thousand Nine Hundred Nineteen and Paise Forty Two Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	15.00	Each	286.50	4297.50	Rupees Four Thousand Two Hundred Ninety Seven and Paise Fifty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	10.14	Per cubic metre	1472.70	14933.18	Rupees Fourteen Thousand Nine Hundred Thirty Three and Paise Eighteen Only
Total in figure :					348046.72	Rupees Three Lakh Forty Eight Thousand Forty Six and Paise Seventy Two Only
Total in Words :		Rupees Three Lakh Forty Eight Thousand Forty Six and Paise Seventy Two Only				

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 133937.87
Earnest Money Rs:- 2700.00
Time Two month

Order Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

Work of work :- Restoration of Rain Damages on Silhbudhani Kungri Kortang road km.0/00 to 5/00. (PDNA-2023). (Sub Head :- Construction of Retaining wall at R.D. 4/850 to 4/855).

Contract No:-

Order Name :-

SCHEDULE OF WORKS

Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
Excavation in soil in hilly area by mechanical means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	11.65	Per cubic metre	491.80	5729.47	Rupees Five Thousand Seven Hundred Twenty Nine and Paise Forty Seven Only
Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	24.34	Per cubic metre	4960.80	120745.87	Rupees One Lakh Twenty Thousand Seven Hundred Forty Five and Paise Eighty Seven Only
Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	6.00	Each	286.50	1719.00	Rupees One Thousand Seven Hundred Nineteen Only
Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	3.90	Per cubic metre	1472.70	5743.53	Rupees Five Thousand Seven Hundred Forty Three and Paise Fifty Three Only
in figure :				133937.87	Rupees One Lakh Thirty Three Hundred Thirty Seven and Paise
in Words :	Rupees One Lakh Thirty Three Thousand Nine Hundred Eighty Seven Only				

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar.

ITEM RATE BILL OF QUANTITY

Estimated Cost Rs:- 410484.14
Earnest Money Rs:- 8200.00
Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP PWD. at Padhar.

Name of Work:- Restoration of rain damages on Barot Mayot road Km 0/00 to 7/960. (PDNA- 2023). (Sub Head:-Construction of Retaining Wall at RD's 3/010 to 3/030).

Contract No. :
Name of the Bidder/Bidding Firm/Company :

PRICE SCHEDULE					
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	42.80	Per cubic metre	522.50	Rupees Twenty Two Thousand Three Hundred Sixty Three Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803,1202 & 1203. P.C.C. nominal mix 1:5:10 (40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	72	Per cubic metre	5024.80	Rupees Three Lakh Sixty One Thousand Seven Hundred Eighty Five and Paise Sixty Only
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	32.00	Each	284.30	Rupees Nine Thousand Ninety Seven and Paise Sixty Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	11.40	Per cubic metre	1512.10	Rupees Seventeen Thousand Two Hundred Thirty Seven and Paise Ninety Four Only
Total in figure :					410484.14
Total in Words :					Rupees Four Lakh Ten Thousand Four Hundred Eighty Four and Paise Fourteen Only

Executive Engineer,
Mandi Division No.1,
HP PWD at Padhar.

ITEM RATE BILL OF QUANTITY

Estimated Cost Rs:- 396380.40
 Earnest Money Rs:- 7900.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

Name of Work:- Restoration of rain damages on Barot Mayot road Km 0/00 to 7/960. (PDNA- 2023). (Sub Head:-Construction of Retaining Wall at RD's 5/600 to 5/615).

Contract No. :

Name of the Bidder/Bidding Firm/Company :

PRICE SCHEDULE

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in Rs. P.	Total Amount with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	42.00	Per cubic metre	522.50	21945.00	Rupees Twenty One Thousand Nine Hundred Forty Five Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. P.C.C. nominal mix 1:5:10 (40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	70.13	Per cubic metre	5042.80	353651.56	Rupees Three Lakh Fifty Three Thousand Six Hundred Fifty One and Paise Fifty Six Only
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm. dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7.including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	18.00	Each	285.20	5133.60	Rupees Five Thousand One Hundred Thirty Three and Paise Sixty Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	10.35	Per cubic metre	1512.10	15650.24	Rupees Fifteen Thousand Six Hundred Fifty and Paise Twenty Three Only
Total in figure :					396380.40	Rupees Three Lakh Ninety Six Thousand Three Hundred Eighty and Paise Forty Only
Total in Words :					Rupees Three Lakh Ninety Six Thousand Three Hundred Eighty and Paise Forty Only	

Executive Engineer,
 Mandi Division No.I,
 HP.PWD. at Padhar.