

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
"NOTICE INVITING TENDER"**

Sealed **Percentage rates** tender in emergent condition on form 6 & 7 are invited on behalf of Governor of Himachal Pradesh for the following work covered under emergent/inescapable nature from the approved and eligible contractors enlisted in H.P.PWD so as to reach in this office on or **14.01.2026 Up to 11.30 A.M.** and will be opened on the same day at 3.30 P.M. in the presence of interested contractors or their authorized representatives who may like to be present. If it happens to be holiday on the schedule date of opening of tender, the same will be opened on next working day. The application for obtaining the tender form will be received upto **01.00 PM** & without EMD tender form will not be accepted, moreover the tender form can be had from this office against cash payment (Nonrefundable) up to 5.00 P.M. on **13.01.2026**.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account in any of the Post Office and Banks of Himachal Pradesh duly pledged in favour of the Xen Mandi Division No. II must accompany with each tender. Conditional tender and the tender received without earnest money will summarily be rejected. The earnest money should be attached with application. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr. No	Name of work	Estt. cost	E/Money	Cost of tender form	Time limit
1.	RRD on Ganpati Kun Ka Tar road km. 0/00 to 21/500 (SH:- P/L Cement concrete for edging in front of House Damages at Rd 3/00 to 3/010 under PDNA 2023)	Rs 4,87,186.00	Rs 9,800.00	350	"D"
2.	RRD on Link road from Dhandal to Kolka km. 0/00 to 2/100. (SH:- C/O R/wall at Rd 0/025 to 0/045, and 0/645 to 0/656) Under PDNA 2023	Rs 4,31,938.00	Rs 8,700.00	350	"D"
3.	RRD on link road from Dhandal to Kolka km. 0/00 to 2/100.(SH:- C/O R/wall at Rd 0/040 to 0/055, and 0/170 to 0/177)Under PDNA 2023	Rs 4,67,503.00	Rs 9,400.00	350	"D"
4.	Restoration of rain damages on Ganpati kun Ka Tar road km 0/00 to 21/500. (SH:- Construction of 450mm diameter half cut pipe drain and G-III stone soling in shoulders with cement concrete at RD 3/00 to 3/200) Under PDNA 2023	Rs 4,72,443.00	Rs 9,500.00	350	"D"
5.	Annual repair and maintenance of Victoria Bridge over river Beas at District Mandi H.P (SH:- Providing painting work on old bridge.	Rs 79,428.00	Rs 1,600.00	350	"D"
6.	Annual repair and maintenance of 124.00mtr span bridge over river Beas near Victoria Bridge at District Mandi (H.P) (SH:- Providing painting works (New Bridge).	Rs 98,490.00	Rs 2,000.00	350	"D"
7.	Annual repair and maintenance of old Suketi bridge at District Mandi H.P. (SH:- Providing painting works).	Rs 47,779.00	Rs 1,000.00	350	"D"
8.	Restoration of rain damages on various roads under Kolti sub Division HPPWD Kolti (Gokhara Section) (SH:- Hiring of JCB for removal of slips, muck clearing of debris, drains and dressing of berms etcetera) Job No.1	Rs 99,000.00	Rs 2,000.00	350	"D"
9.	Restoration of rain damages on various roads under Kolti sub Division HPPWD Kolti (Gokhara Section) (SH:- Hiring of JCB for removal of slips, muck clearing of debris, drains and dressing of berms etcetera) Job No.2	Rs 99,000.00	Rs 2,000.00	350	"D"
10.	Construction of Manthala Rachwana Gaterbag road km. 0/00 to 3/350. (SH:- Construction of Retaining wall at RD 3/335 to 3/350). Under MMGSY	Rs 4,58,573.00	Rs 9,200.00	350	"D"
11.	Construction of Manthala Rachwana Gaterbag road km. 0/00 to 3/350. (SH:- Construction of Retaining wall at RD 2/125 to 2/145) Under MMGSY	Rs 4,32,656.00	Rs 8,700.00	350	"D"
12.	Special repair of ramp door in Zonal Hospital Mandi District Mandi H.P. (SH:- Providing and fixing panelled door, steel works etcetera in District store Mandi) Deposit work	Rs 56,180.00	Rs 1,200.00	350	"D"
13.	Renovation of Conference Hall in the office of CMO Mandi District Mandi H.P. (SH:- Providing and fixing GRG ceiling, brick work etcetera (Deposit work)	Rs 37,954.00	Rs 800.00	350	"D"
14.	Blockage of sewerage system inside near Nursing Hostel Zonal Hospital Mandi. (SH:- Providing and laying concrete work, PVC pipe and chamber work etcetera) Deposit work	Rs 60,497.00	Rs 1,200.00	350	"D"
15.	RRD on Bindrawani Majhwar Kotmorse Moviseri road km. 0/00 to 19/800. (SH:- C/O 900mm dia RCC Hume pipe culvert along with both side wing wall at Rd 14/230) under PDNA 2023	Rs 4,37,270.00	Rs 9,000.00	350	"D"



16.	RRD on Bindrawani Majhwar Kotmorse Moviseri road km. 0/00 to 19/800. (SH:- C/O 900MM Dia RCC hume pipe culvert along with both side wing wall at Rd 15/310) Under PDNA 2023	Rs 4,66,671.00	Rs 9,500.00	350	"D"
-----	---	----------------	-------------	-----	-----

### CERTIFICATE

It is certified that the above works are required to be carried out immediately, being of emergent nature and in the larger public interest.

### Tender Notice – Terms & Conditions

The tender documents shall be issued only to those Contractors/Firms who submit the following documents along with their application:

1. Valid enlistment/registration of contractor in the appropriate class.
2. Permanent Account Number (PAN).
3. GST Registration Number.
4. Earnest money in the shape of National Saving Certificate/Time Deposit Account in any Post Office in Himachal Pradesh, or F.D.R. from any Nationalized Bank duly pledged in favour of the Executive Engineer, Mandi Division No. 2, HPPWD, Mandi H.P.
5. Earnest money and cost of tender form for the above works must be submitted along with the application for purchase of tender form. Applications received without earnest money and cost of tender form shall be summarily rejected.
6. The offer of the tender shall remain valid for 75 (seventy-five) days after the opening of the tender.
7. Ambiguous, telephonic, conditional tenders or tenders submitted by fax/e-mail shall not be considered and will be summarily rejected.
8. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reason.
9. If the date specified above happens to be a holiday, the tenders shall be processed on the next working day.
10. The Contractor/Firm must quote their rates both in words as well as in figures, failing which the Executive Engineer reserves the right to accept or reject any or all tenders.
11. Tender forms shall not be issued to those Contractors/Firms whose past performance is not found satisfactory or who have failed to complete previously awarded works within the stipulated period.
12. No contractor shall have more than two major works in hand at a time.
13. The work shall be completed by the Contractor within the stipulated period.

No.PW-MDII-CB NIT (off line) /2025-

17962-74

Dated: ..

*Shalpa Arora*  
Executive Engineer  
Mandi Division No.II  
HP.PWD Mandi  
3 01/2026

Copy forwarded to the following for information and necessary action: -

1. The Engineer-in-chief, HPPWD: Shimla.
2. The Deputy Commissioner Mandi Distt. Mandi HP
3. The Sub Divisional officer (Civil) Sadar Mandi Distt. Mandi HP
4. The Chief Engineer, (MZ)HPPWD: Mandi.
5. The Superintending Engineer, 1<sup>st</sup> Circle, HPPWD: Mandi.
6. The Distt. Panchyat officer Mandi Distt. Mandi HP
7. The Commissioner Nagar Nigam Mandi Distt. Mandi HP
8. All A. E, S under this division.
9. The President of Contractor's Association.
10. Notice Board/Accounts Branch/Drawing Branch/Supdt. With spare copies.

*Shalpa Arora*  
Executive Engineer  
Mandi Division No.II  
HP.PWD Mandi



Estimated Cost :- 4,87,186/-  
Earnest Money:- 9,800/-  
Time:- One Month

Tender Inviting Authority : Executive Engineer, Mandi Division No.II HPPWD Mandi  
Percentage of BOQ

Name of work :- RRD on Ganpati Kun Ka Tar Road Km 0/00 to 21/500 (SH:- P/L Cement concrete for edging in front of House damaged at Rd 3/00 to 3/010 under PDNA)

Contract No. :

Name of the Bidder/ Bidding Firm/ Company :	
---	--

PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #
Sl. No.	Item Description	Quantity	Unit	Estimate Rate with all taxes including GST in Rs. P	TOTAL AMOUNT With all Taxes including GST in Rs. P	TOTAL AMOUNT with all Taxes including GST in Words
1	2 Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	3 15.00	4 Per Cubic Metre	5 609.10	6 9,137.00	7 Rupees Nine Thousand One Hundred Thirty Seven Only
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	90.00	Per Cubic Metre	5311.65	4,78,049.00	Rupees Four Lakh Seventy Eight Thousand Nine Forty Only
Total				4,87,186.00		Rupees Four Lakh Eighty Seven Thousand One Hundred Eighty Six

BOQ approved for Rs. 4,87,186/- only.

Executive Engineer,  
Mandi Division No.II,  
HP.PWD. Mandi.







7	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including cartage of materials with in all trade, lifts and other incidentals as per direction and entire satisfaction of Engineer in charge.	19.54	Per Cubic Metre	1665.00	32,534.00	Rupees Thirty Two Thousand Five Hundred Thirty Four Only
1					4,31,938.00	Rupees Four Lakh Thirty Nine Thousand Three Hundred Thirty Eight Only

Noted Rate in Figures :  
Noted Rate in words :

*Bill of quantity checked and approved for R.B. 4,31,938 only.*

*[Signature]*  
Executive Engineer,  
Mandi Division No II.,  
J.P. P.W.D. Mandi.



47

Estimated Cost :- 4,67,503-  
Earnest Money:-9,400/-  
Time:- One Month

Percentage of BOQ

Tender Inviting Authority : Executive Engineer, Mandi Division No.II HPPWD Mandi

Name of work : RRD on link road from Dhandal to Kolka Km. 0/00 to 2/100 (SH: C/O R/wall at Rd 0/040 to 0/055,0 AND 0/170 to 0/177) under PDNA

Name of the Bidder/ Bidding Firm/ Company : **PRICE SCHEDULE**  
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	NUMBER #	TEXT #	NUMBER #	TEXT #
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	3	4	5	6
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	35.01	Per Cubic Metre	609.10	21,325.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	76.30	Per Cubic Metre	5311.65	4,05,279.00
3	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1204.3.7 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	14.48	Per Cubic Metre	1665.00	24,109.00
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.				4,67,503.00
Total					Rupees Four Lakh Sixty Seven Thousand Five Hundred Three Only

Quoted Rate in Figures : **Rate of quantity checked and approved for Rs 4,67,503 only**

Executive Engineer,  
Mandi Division No.II,  
H.P.W.D. Mandi.

3



63

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 472443.00  
 Earnest Money Rs: 9500.00  
 Time :- One Month

Tender Inviting Authority :- Executive Engineer, Mandi Division No.II, HPPWD

Name of work :- Restoration of rain damages on Ganpati Kun Ka Tar road 0/00 to 2/1500. (SH:- Construction of 450mm diameter half cut pipe drain and G-II stone soling in shoulders with Cement concrete at RD 3/00 to 3/200) under PDNA 2023


Contract No.:-  
 Bidder Name:-

Sr. No.	Item Description	SCHEDULE OF WORKS					TOTAL AMOUNT with all Taxes including GST in words.
		Quantity	Units	Estimated Rate P. Rs.	TOTAL AMOUNT with all Taxes including GST in Rs. P.		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50m, dressing of sides and bottoms and back filling in trenches with excavated suitable materials, complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	70.53	Per cubic metre	609.10	42960.00	Rupees Forty Two Thousand Nine Hundred Sixty Only	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications clauses 802.803.1202 and 1203 C.C. 1:3:6 (one cement three coarse sand six graded, crushed stone aggregate 40mm (forty millimetre) nominal size), as per entire satisfaction and direction of Engineer-in-Charge.	25.20	Per cubic metre	6713.35	169176.00	Rupees One Lakh Sixty Nine Thousand One Hundred Seventy Six Only	
3	Providing and laying 450mm diameter (Four hundred fifty millimetre) reinforced cement concrete pipe NP2 class (right duty) for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two fine sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1106 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-Charge.	180.00	Per running metre	930.00	167400.00	Rupees One Lakh Sixty Seven Thousand Four Hundred Only	



St. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes including GST in Rs. P.	TOTAL AMOUNT with all Taxes including GST in words.
1						
4	Providing, laying, spreading and compacting stone aggregates Grading-III of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel/ vibratory roller 8-10 tonnes (Eight to ten tonnes) in stages to proper grade and camber, applying and brooming, requisite type of screening/ binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density, complete as per Technical Specification Clause 405 By Manual/Mechanical means including carriage of materials with in all leads, lifts and other incidentals	7.08	Per cubic metre	3200.00	22656.00	Rupees Twenty Two Thousand Six Hundred Fifty Six Only
5	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications clauses 802, 803, 1202 and 1203 P.C.C. 1:2:4 (one cement two coarse sand : four graded, crushed stone aggregate 40mm (forty millimetre) nominal size), as per entire satisfaction and direction of Engineer-in-Charge.	9.45	Per cubic metre	7434.00	70251.00	Rupees Seventy Thousand Two Hundred Fifty One Only
Total in Figure					472443.00	Rupees Four Lakh Seventy Thousand Four Hundred Forty
Quoted Rate in Words		Rupees Four Lakh Seventy Two Thousand Four Hundred Forty Three Only				

*Bill of quantity checked and approved  
for Rs. 4,72,443/- only*

  
Executive Engineer,  
Candi Division No II,  
I.P.PWD Mandi



### Percentage Rate Schedule of Quantity

**Estimated Cost:- Rs. 79428.00**

<b>Earnest Money:- Rs.</b>	<b>1600.00</b>
----------------------------	----------------

Time:- One Month

Sr.	Name of work:- Annual repair and maintenance of Victoria Bridge over river Beas at Distt. Mandi (H.P.).
	Sub Head:- Providing painting work on old bridge.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1			4	5	6	7
1	Painting one or more coats on old work with synthetic enamel paint ICI (Dulux Gloss), Nerolac, Berger (Luxol High Gloss), Asian Paints (Premium Apocolite Gloss), Shalimar of approved brand and manufacture of required colour to give an even shade complete within all leads, lifts of carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.	931.16 Sqm.	85.30	Rupees Eighty Five and Paise Thirty Only	Per square metre	79428.00
				Total:-		79428.00

Note:- It must be ensured that only preferred makes of material be used.

**Note:-** It must be ensured that only preferred makes of material be used as per agreement. No other material will be allowed at site.

~~Electrician Engineer~~  
Mandi Division No. II,  
P.W.D. Mandi. *dy*



# Percentage Rate Schedule of Quantity

Name of work:- Annual repair and maintenance of 124.00mtr. span bridge over river Beas near Victoria Bridge at Distt. Mandi (H.P.).  
Sub Head:-Providing painting works. (New Bridge)

Estimated Cost:- Rs. 98490.00  
Earnest Money:- Rs. 2000.00  
Time:- One Month

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	1	3	4	5	6	7
1	Wall painting one or more coats on old work with plastic emulsion paint ICI (Dulux Gloss), Nerolac, Berger (Luxol High Gloss), Asian Paints (Premium Apcolite Gloss), Shalimar of approved brand and manufacture to give an even shade complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.	670.12 Sqm.	98.35	Rupees Ninety Eight and Paise Thirty Five Only	Per square metre	65906.00
2	Painting one or more coats on old work with synthetic enamel paint ICI (Dulux Gloss), Nerolac, Berger (Luxol High Gloss), Asian Paints (Premium Apcolite Gloss), Shalimar of approved brand and manufacture of required colour to give an even shade complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.	106.44 Sqm.	85.30	Rupees Eighty Five and Paise Thirty Only	Per square metre	9079.00
3	Removing dry or oil bound distemper, water proofing cement paint and the like by scraping, sand papering and preparing the surface smooth including necessary repairs to scratches etcetera complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.	167.53 Sqm.	17.10	Rupees Seventeen and Paise Ten Only	Per square metre	2865.00
4	Providing and applying white cement based putty of average thickness 1 mm (one millimetre), of approved brand and manufacture, over the plastered wall surface to prepare the surface even and smooth complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire direction and satisfaction of Engineer-in-Charge.	167.53 Sqm.	123.20	Rupees One Hundred Twenty Three and Paise Twenty Only	Per square metre	20640.00
Total:-						98490.00

Note:- It must be ensured that only preferred makes of material be used as per agreement. No other material will be allowed at site.

  
Executive Engineer,  
Mandi Division No.II,  
H.P. PWD, Mandi.



# Percentage Rate Schedule of Quantity

Name of work:- Annual repair and maintenance of old Sukeiti bridge at Distt. Mandi (H.P.)  
Sub Head:- Providing painting works

Estimated Cost:- Rs. 47779.00  
Earnest Money:- Rs. 1000.00  
Time:- One Month

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	1	2	3	4	5	6
1	Painting one or more coats on old work with synthetic enamel paint ICI (Dulux Gloss), Nerolac, Berger (Luxol High Gloss), Asian Paints (Premium Appolite Gloss), Shalimar of approved brand and manufacture of required colour to give an even shade complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.	509.10 Sqm.	85.30	Rupees Eighty Five and Paise Thirty Only	Per square metre	43426.00
2	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etcetera complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.	254.55 Sqm.	17.10	Rupees Seventeen and Paise Ten Only	Per square metre	4353.00
Total:-						47779.00

Note:- It must be ensured that only preferred makes of material be used as per agreement. No other material will be allowed at site.

  
Executive Engineer,  
Mandi Division No.II,  
AP PWD, Mandi.



**Percentage Rate Schedule of Quantity**

**Estimated Cost:-** 99000.00  
**Earnest Money:-Rs.** 2000.00  
**Time:-** One month

**Name of work:-** Restoration of rain damages on various roads under Kotli Sub-Division HP.PWD. Kotli. (Gokhtra Section)  
**Sub Head:-** Hiring of J.C.B. for removal of slips, muck, cleaning of debris, drains and dressing of berms etcetra.) Job No.1

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of J.C.B. one Cum bucket capacity for removal of slips, clearing of debris, cleaning of drains, dressing of berms etcetra from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etcetra happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	90.00 Hours	1100.00	Rupees thousand hundred and paise nil only	one Per hour	99000.00
<b>Total:-</b>						<b>99000.00</b>

**Conditions:-**

i) The intending bidders must have ownership of JCB in their name and copy of RC must be uploaded online as a proof.

*Shafiq Ahmad*  
 Executive Engineer,  
 Mandi Division No. II,  
 HP.PWD. Mandi.



# Percentage Rate Schedule of Quantity

Estimated Cost:- 99000.00  
 Earnest Money:-Rs. 2000.00  
 Time:- One month

Name of work:- Restoration of rain damages on various roads under Kotli Sub-Division HP PWD, Kotli. (Gokhra Section)

Sub Head:- Hiring of J.C.B. for removal of slips, muck, clearing of debris, drains and dressing of berms etcetra.) Job No.11

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of J.C.B. one Cum bucket capacity for removal of slips, clearing of debris, cleaning of drains, dressing of berms etcetra from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etcetra happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	90.00 Hours	1100.00	Rupees one thousand hundred and paise nil only	Per hour	99000.00
Total:-						99000.00

## Conditions:-

- The intending bidders must have ownership of JCB in their name and copy of RC must be uploaded online as a proof.

*Shafiq Akmal*  
 Executive Engineer,  
 Mandi Division No.11,  
 HP PWD, Mandi.



**PERCENTAGE RATE BILL OF QUANTITY**

Estimated Cost Rs:- 458573.00  
Earnest Money Rs: 9200.00  
Time :- One Month

Tender Inviting Authority :- Executive Engineer, Mandi Division No II, HP PWD Mandi.  
Name of work :- Construction of Manthla Rachwana Gaterbag road KM.0/00 to 3/350. (SH:- Construction of Retaining wall at RD 3/335 to 3/350) under MMGSY

Contract No.:


Bidder Name:

**SCHEDULE OF WORKS**

Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes including GST in Rs. P	TOTAL AMOUNT with all Taxes including GST in words.
1	Excavation in soil in Hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5m and a lead upto 20m as per drawing and Technical Specification Clause 1603.1 including carriage of materials within all leads, lifts and other incidentals as per direction of Engineer-in-Charge.	18.00	Per cubic metre	198.90	3580.00	Rupees Three Thousand Five Hundred Eighty Only
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50m, dressing of sides and bottoms and back filling in trenches with excavated suitable materials, complete within all leads, lifts, carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	27.75	Per cubic metre	609.10	16903.00	Rupees Sixteen Thousand Nine Hundred Three Only
3	Providing and laying 1.5:10 (One cement five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including formwork as per drawing and technical specifications clauses 802 803 1202 and 1203 including carriage of materials within all leads, lifts and other incidentals as per direction of Engineer-in-Charge.	76.20	Per cubic metre	5311.65	404748.00	Rupees Four Lakh Four Thousand Seven Hundred Forty Eight Only

Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes including GST in Rs. P.	TOTAL AMOUNT with all Taxes including GST in words.
1					Rs. P.	7
4	Providing weepholes in brick masonry/ stone masonry / plain/ reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) AC pipe extending through the full width of the structures with slope of 1V:20H (one vertical is to twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 and other incidental as per direction, entire satisfaction of Engineer-in-charge.	29.00	Each	365.10	10588.00	Rupees Ten Thousand Five Hundred Eighty Eight Only
5	Back filling behind abutment wing wall and return wall/retaining wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads: lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	13.95	Per cubic metre	1631.10	22754.00	Rupees Twenty Two Thousand Seven Hundred Fifty Four Only
Total in Figure					458573.00	Rupees Four Lakh Fifty Eight Thousand Five Hundred Seventy Three Only
Quoted Rate in Words						Rupees Four Lakh Fifty Eight Thousand Five Hundred Seventy Three Only

Bill of Quantity checked and approved for Rs. 4,58,573/-  
(Rupees Four Lakh Fifty eight thousand five hundred  
seventy three only-).

  
Engineer,  
Muz. District No. 11,  
R.B. D. S. (Muz. No. 11)



66

**PERCENTAGE RATE BILL OF QUANTITY**

Tender Inviting Authority:- Executive Engineer, Mandi Division No.11, HPPWD, Mandi.  
Name of work:- Construction of Manthla Rachwana Gatebag road KM 0/00 to 3/350. (SH)- Construction of Breast wall at RD 2/125 to 2/145) under MMGSY

Estimated Cost Rs:- 432656.00  
Earnest Money Rs: 8700.00  
Time :- One Month

Contract No.:  
Bidder Name:

**SCHEDULE OF WORKS**

Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes including GST in Rs. P.	TOTAL AMOUNT with all Taxes including GST in words.
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5m and a lead upto 20m as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	99.20	Per cubic metre	198.90	19731.00	Nineteen Thousand Seven Hundred Thirty One Only
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause, 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50m, dressing of sides and bottoms and back filling in trenches with excavated suitable materials; complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-charge.	24.60	Per cubic metre	609.10	14984.00	Fourteen Thousand Eight Hundred Eighty Four Only
3	Providing and laying 1:5 10 (One cement five sand ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1247 and 1248 including carriage of material with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	73.20	Per cubic metre	5311.65	388613.00	Rupees Three Lakh Eighty Eight Thousand Eight Hundred Eighty Only
4	Providing and laying 1:5 brick masonry / stone masonry / plain concrete / reinforced concrete abutment wing wall retaining wall with 100mm dia (one hundred millimetre diameter) AC pipe extending through the structure with slope of 1V20H (one vertical to twenty horizontal) towards the structure complete as per drawing and technical specifications clauses 614, 709, 1247 and 1248 including carriage of material and other incidentals as per direction of Engineer-in-charge.	25.00	Each	528.00	9128.00	Nine Thousand Two Hundred Eighty Only

11

Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes including GST in Rs. P.	TOTAL AMOUNT with all Taxes including GST in words.
1						
Total in Figure		3	4	5	432656.00	Rupees Four Lakh Thirty Two Thousand Six Hundred Fifty Six
Quoted Rate in Words		Rupees Four Lakh Thirty Two Thousand Six Hundred Fifty Six Only				

*Bill of Quantity checked and approved for Rs. 4,32,656/-  
(Rupees Four Lakh thirty two thousand six hundred  
fifty six only).*

  
Executive Engineer,  
Mandi Division No II  
B.P.W.D. Mandi.



### Percentage Rate Schedule of Quantity

Estimated Cost:- Rs.	56180.00
Earnest Money:- Rs.	1200.00
Time:-	One Month

Description of item	Deposited work
...	...

Sr. No.	Description of item	Qty.	In Figure	Rate In Words	Unit	Amount
1	Providing and fixing 35mm (thirty five millimetre) thick second class deodar wood panelled glazed or panelled and glazed shutters for doors, windows and clearstory windows including black enamelled iron but hinges with necessary screws including carriage of material within all leads and lifts and other incidentals complete and as per the entire direction and satisfaction of Engineer-in-Charge.	3	4921.10	Rupees Thousand Hundred Twenty One and Paise Ten Only	Per square metre	14763.00
2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge.	255.02	136.95	Rupees One Hundred Thirty Six and Paise Ninety Five Only	Per kilo gram	34925.00
3	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in (ten squaremetre) on plan), including dressing of sides and ramming of bottoms, upto any lift, any lead including carriage of material within all leads, lifts and other incidental charges upto complete in all respect as per direction and satisfaction of Engineer-in-Charge.	0.10	233.10	Rupees Two Hundred Thirty Three and Paise Ten Only	Per cubic metre	23.00
4	Providing and laying in position cement concrete 1:2:4 (one cement two coarse sand : four graded, crushed stone aggregate 20mm (twenty millimetre) nominal size excluding the cost of centering and shuttering in all works up to all floor level including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	0.10	6696.00	Rupees Six Thousand Six Hundred Ninety Six Only	Per cubic metre	670.00
5	Providing and fixing 4mm (four millimetre) thick float glass panes with putty and glazing clips in steel door, window and clerestory window complete in all respect including carriage of material within all leads and lifts as per direction and satisfaction of Engineer-in-Charge.	4.05	1431.80	Rupees Thousand Four Hundred Thirty One and Paise Eighty Only	Per square metre	5799.00
	Total:-					56180.00

Page 1

Shafiqul Haque  
Executive Engineer,  
Mandi Division No.-II  
~~PPWD~~, Mandi *Sh*



### Percentage Rate Schedule of Quantity


**Name of work:-** Renovation of Conference hall in the office of CMO Mandi Dist. Mandi (H.P.)  
**Sub Head:-** Providing and fixing GRG ceiling, brick work etcetera. (Deposit work)

**Estimated Cost:-** Rs. 37954.00  
**Earnest Money:-** Rs. 800.00  
**Time:-** One Month

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (one hundred twenty grams per squaremetre) (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm (twenty five millimetre) wide x 16 mm (one point six millimetre) thick with flanges of size seven millimetre) and 37mm (thirty seven millimetre), at 1200 mm (one thousand two hundred millimetre) centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia (twelve point five millimetre) x 50mm (fifty millimetre) long with 6mm (six millimetre) diameter bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm (twenty five into ten into zero point five zero millimetre) of required length with nuts and bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm (forty five into fifteen into zero point nine millimetre) running at the spacing of 1200mm (one thousand two hundred millimetre) centre to centre, to which the ceiling section 0.5 mm (zero point five millimetre) thick bottom wedge of 80 mm (eighty millimetre) with tapered flanges of 26 mm (twenty six millimetre) each having lips of 10.5 mm (ten point five millimetre), at 450 mm (four hundred fifty millimetre) centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm (two point six four millimetre) diameter x 230 mm (two hundred thirty millimetre) long G.I. wire at every junction, including fixing perimeter channels 0.5 mm (zero point five millimetre) thick 27 mm (twenty seven millimetre) high having flanges of 20 mm (twenty millimetre) and 30 mm (thirty millimetre) long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm (four hundred fifty millimetre) centre, with 25mm (twenty five millimetre) long dry wall screws @ 230 mm at the rate of two hundred thirty millimetre interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm (three point five into twenty five millimetre) at 230 mm c/c (two hundred thirty millimetre centre to centre), including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound, jointing tapes finishing with jointing compound in 3(three) layers covering upto 150 mm (one hundred fifty millimetre) on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of 12.5mm (twelve point five millimetre) thick tapered edge gypsum moisture resistant board complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire direction and satisfaction of Engineer-in-Charge.	15.48	2407.45	Rupees Two Thousand Four Hundred Seven and Paise Forty Five Only	Per square metre	37267.00



Description of Item	Qty.	Rate		Unit	Amount
		In Figure	In Words		
2	3	4	5	6	7
Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in cement mortar 1:3 (one cement : three sand) complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	0.63	1090.10	Rupees One Thousand Ninety and Paise Ten Only	Per square metre	687.00
Total:-					37954.00

  
 Executive Engineer,  
 Mandi Division No.II,  
 P.W.D. Mandi.

# Percentage Rate Schedule of Quantity

Estimated Cost:- Rs. 60497.00

Earnest Money:- Rs. 1200.00

Time:- One Month


Work:- Blockage of sewerage system inside near Nursing Hostel Zonal Hospital Mandi.

Work:- Providing and laying concrete work, PVC pipe and chamber work etcetera) Deposit work

Description of item	Qty.	Rate		Unit	Amount
		In Figure	In Words		
1	3	4	5	6	7
2	4.05	233.10	Rupees Two Hundred Thirty Three and Paise Ten Only	Per cubic metre	944.00
Earth work in excavation for all kinds of soil by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten squaremetre) on plan), including dressing of sides and ramming of bottoms, upto any lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge.					
2	4.05	5495.00	Rupees Five Thousand Hundred Ninety Five Only	Per cubic metre	22255.00
Providing and laying in position cement concrete 1:4:8 (one cement four coarse sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size ) excluding the cost of centering, shuttering, in all works up to all floor level complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.					
3	30.00	305.50	Rupees Three Hundred Five and Paise Fifty Only	Per Running metre	9165.00
Providing and fixing 110mm (one hundred ten millimetre) diameter single socketed unplasticised Rigid PVC rain water pipes on wall face conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (ten millimetre) gap for thermal expansion complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.					
4					
Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (ten millimetre) gap for thermal expansion complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.					
	2.00	138.05	Rupees One Hundred Thirty Eight and Paise Five Only	Each	276.00
Bend 87.5° (eighty seven point five degree) 110mm (one hundred ten millimetre) bend					
5					
Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (ten millimetre) gap for thermal expansion complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.					



Description of item	Qty.	Rate		Unit	Amount
		In Figure	In Words		
2	3	4	5	6	7
mm (one hundred ten millimetre) coupler	2.00	125.25	Rupees One Hundred and Twenty Five Paise Only	Each	251.00
Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (ten millimetre) gap for thermal expansion complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.					
110mm (one hundred ten millimetre) tee	2.00	216.15	Rupees Two Hundred Sixteen and Paise Fifteen Only	Each	432.00
7	1.00	11138.40	Rupees Eleven Thousand Hundred Thirty Eight and Paise Forty Only	Each	11138.00
Constructing masonry Chamber 60x60x75 cm (sixty into sixty into seventy five centimetre) inside, in brick work in cement mortar 1:4 (one cement : four coarse sand) for sluice valve, with C.I. surface box 100mm (one hundred millimetre) top diameter, 160 mm (one hundred sixty millimetre) bottom diameter and 180 mm (one hundred eighty millimetre) deep ( inside) with chained lid and RCC top slab 1:2:4 mix (one cement : two coarse sand : four graded stone aggregate 20mm (twenty millimetre) nominal size ) , including necessary excavation, foundation concrete 1:5:10 (one cement : five fine sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) and inside plastering with cement mortar 1:3 (one cement : three coarse sand) 12 mm (twelve millimetre) thick, finished with a floating coat of neat cement complete as per standard design, including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.					
8	1.00	16035.80	Rupees Sixteen Thousand Three Hundred Fifty and Paise Eighty Only	Each	16036.00
Providing and fixing floor mounted, white vitreous china single piece, double traps syphonic water closet of approved brand/make, shape, size and pattern including integrated white vitreous china cistern of capacity 10(ten) litres with dual flushing system, including all fittings and fixtures with seat cover, cistern fittings, nuts, bolts and gasket etcetera including making connection with the existing P/S trap, including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.					
Total:-					60497.00

  
 Executive Engineer,  
 Mandi Division No II,  
 PWD, Mandi



67

Estimated Cost :- 4,37,270/-  
Earnest Money:-9,000/-  
Time:- One Month

Percentage of BoQ

Tender Inviting Authority : Executive Engineer, Mandi Division No. II HPPWD Mandi

Name of work :- RRD on Bindrabani Majhwar Kotmorse Moviseri road Km. 0/00 to 19/800. (SH- C/ O 900 mm dia RCC hume pipe culvert alongwith both side wing wall at Rd 14/230) under PDVA

Contract No. :

Name of the Bidder/ Bidding Firm/ Company :		Name of work :- A7057:B763						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	NUMBER #	TEXT #	
Sl. No.	Item Description	Quantity	Unit	Estimate Rate with all taxes including GST in Rs. P	TOTAL AMOUNT With all Taxes including GST in Rs. P	TOTAL AMOUNT with all Taxes including GST In Words		
1	2	3	4	5	6	7		
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	12.00	Per cubic metre	198.60	2,383.00	Rupees Two Thousand Three Hundred Eighty Three		
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	67.17	Per Cubic Metre	609.10	40,913.00	Rupees Forty Thousand Nine Hundred Thirteen Only		
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	53.22	Per Cubic Metre	5311.65	2,82,686.00	Rupees Two Lakh Eighty Two Thousand Six Hundred Eighty Six Only		
4	Providing concrete for plain concrete 1:3:6 (One cement : Three sand : Six graded stone aggregate) Mechanically Mixed in open foundation and curing complete including form work as per drawings and technical specification Clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	10.05	Per cubic metre	6067.15	60,975.00	Rupees Sixty Thousand Nine Hundred Seventy Five Only		
5	Providing and laying 900mm dia (Nine hundred millimetre) reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	7.50	Per running metre	4410.65	33,080.00	Rupees Thirty Three Thousand Eighty Only		

15



7	providing weep holes in block masonry / stone masonry / plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1204.3.7 including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.	13.00	Each	365.00	4,745.00	Rupees Four Thousand Seven Hundred Forty Five Only
	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.	7.50	Per Cubic Metre	1665.00	12,488.00	Rupees Twelve Thousand Four Hundred Eighty Eight
<b>Total</b>					<b>4,37,270.00</b>	Rupees Four Lakh Seven Thousand Two Hundred
<b>Quoted Rate in Figures :</b>						
<b>Quoted Rate in words:</b>						

*Bill of Quantity checked and approved for Rs. 4,37,270/- only*

*Shaila Bhal*  
Executive Engineer,  
Mandi Division No. II. .  
Rajpawd. Mandi.

Estimated Cost :-4,66,671/-  
Earnest Money:-9500/-  
Time:- One Month

**Mandi**  
(SH: C/O 900 mm dia RCC hume pipe culvert alongwith both side wing wall at Rd 15/310) under PDNA

Name of the Bidder/ Bidding Firm/ Company :	

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
SL. No.	Item Description	Quantity	Unit	Estimate Rate with all taxes including GST in Rs. P	TOTAL AMOUNT With all Taxes including GST in Rs. P	TOTAL AMOUNT with all Taxes including GST In Words
1	2	3	4	5	6	7
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	13.28	Per cubic metre	198.60	2,637.00	Rupees Two Thousand Six Hundred Thirty Seven
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	68.92	Per Cubic Metre	609.10	41,979.00	Rupees Forty One Thousand Nine Hundred Seventy Nine Only
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	58.30	Per Cubic Metre	5311.65	3,09,669.00	Rupees Three Lakh Nine Thousand Six Hundred Sixty Nine Only
4	Providing concrete for plain concrete 1:3:6 (One cement : Three sand : Six graded stone aggregate) Mechanically Mixed in open foundation and curing complete including form work as per drawings and technical specification Clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	10.05	Per cubic metre	6067.15	60,975.00	Rupees Sixty Thousand Nine Hundred Seventy Five
5	Providing and laying 900mm dia (Nine hundred millimetre) reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	7.50	Per running metre	4410.65	33,080.00	Rupees Thirty Three Thousand Eighty Only



	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1204.3.7 including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.	13.00	Each	365.00	4,745.00	Rupees Four Thousand Seven Hundred Forty Five Only
7	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.	8.16	Per Cubic Metre	1665.00	13,586.00	Rupees Thirteen Thousand Five Hundred Eighty Six Only
<b>Total</b>					<b>4,66,671.00</b>	Rupees Four Lakh Sixty Six Thousand Six Hundred Seventy One
<b>Quoted Rate in Figures :</b>						
<b>Quoted Rate in words:</b>						

*Bill of Quantity checked and approved for Rs. 4,66,671/- only*

*Shailendra*  
Executive Engineer,  
Mandi Division No. II.,  
P.W.D. Mandi.