

Himachal Pradesh
Public Works Department

NO/PW/TLD/Tender/2025: - 12/68-77
To

Dated: - 02.01.2026

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2


Subject: -

Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as given in the Notice Inviting Tender for uploading on Department website as per Notification No. Principal Secretary (PW), to the Govt. of HP letter No. PBW (B) 1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA: - NIT.


Executive Engineer,
HPPWD Division (B&R),
Thalout at Pandoh


HPPWD Mandi for information please.

Copy is forwarded to Superintending Engineer, 1st Circle,

Division.


Copy to All the Assistant Engineers working under this

Copy to AB/DB in this office.
Copy to Notice board.


Executive Engineer,
HPPWD Division (B&R),
Thalout at Pandoh

Certificate

Certified that the tender called vide this office letter No. PW/TLD/Tender/2025-12158-67 dated 02-01-2026 is emergent nature and in Public interest.


Executive Engineer,
HPPWD Division (B&R),
Thalout at Pandoh

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDER"**

Scaled Percentage tender on form No. 6&8 for the following works detailed in the table below hereby invited by the Executive Engineer, HPPWD Division (B&R), Thalout at Pandoh on behalf of Governor of Himachal Pradesh from the eligible contractors of appropriate Class registered in HPPWD as per revised enlistment rule so as to reach in his office on 13.01.2026 at 11.00 A.M. The tenders shall be opened on the same date at 11.30 A.M. in the presence of intending contractors or their authorized representative who wish to be present. The request for issuing tenders form along with earnest money must reach in his office up to 3.00 P.M. on 09.01.2026 and that tender documents can be had from his office on cash payment noted against each (Non-Refundable) on 12.01.2026 up to 5.00 P.M on any working day. Notice Inviting Tender and other specification and conditions of the tender can be seen by the contractor in the office of the Executive Engineer, HPPWD Divisio (B&R), Thalout at Pandoh during office hour on any working day.

Sr. No.	Name of work	Estima ted cost	Earne st mone y	Cost of for m	Time Period	For m No.	Eligib ility of Contr actor s
1	RRD on Bhatwari to Rensh road Km. 0/00 to 8/640 (SH: - C/o created R/Wall at RD 4/595 to 4/600).	88294	2000	Rs. 350/-	One month	6&8	D
2	RRD on Rahla to Shayari road km. 0/00 to 2/500 (SH: - C/O crated R/wall at RD 2/486) to 2/490).	99932	2000	Rs. 350/-	One month	6&8	-do-
3	RRD on Sansoi to Kashana road KM. 0/0 to 6/250 (SH: - C/o crated B/wall at RD 3/630 to 3/639).	92819	2000	Rs. 350/-	One month	6&8	-do-
4	RRD on various roads under Panarsa Sub Division (SH: - Hiring of Excavator cum loader for Removal of slips/boulders, muck debris etc. at various RDs in Nagwain Section) Job No. 1	99600	2000	Rs. 350/-	One month	6&8	-do-
5	RRD on Aut Takoli Parashar road Km 0/00 to 27/00(SH:-Hiring of Excavator cum loader for Removal of slips/boulders, muck debries etc. at Km 0/00 to 5/00)	99600	2000	Rs. 350/-	One month	6&8	-do-
6	RRD on various roads under Panarsa Sub Division (SH:- Hiring of Tipper for carriage of muck/debris etc. at various RDs) Job No-1 Nagwain Section	98000	2000	Rs. 350/-	One month	6&8	-do-
7	RRD on Panarsa to Kotdhar road km/0/0 to 5/825 (SH:- Hiring of Excavator cum loader for Removal of slips/boulders, muck debris etc. at various RDs) DC Deposit	99600	2000	Rs. 350/-	One month	6&8	-do-
8	RRD on Aut Takoli Parashar road Km 0/00 to 27/00 (SH:- Hiring of Excavator cum loader for Removal of slips/boulders, muck debris etc. at Km 10/00 to 15/00	99600	2000	Rs. 350/-	One month	6&8	-do-

9	RRD on Dehri Nallah to Chhurgari Mohal (SH:- Hiring of Excavator cum loader for removal of slips/boulders, muck debris etc. at various RDs) DC Deposit	74400	1500	Rs. 350/-	One month	6&8	-do-
10	RRD on various roads of Panarsa Sub Division (SH:- Hiring of Excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Nagwain Section) Job No-2	99600	2000	Rs. 350/-	One month	6&8	-do-
11	RRD on Sansoi to Kashna road km 0/0 to 6/250 (SH:- Hiring of Excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs.)	99600	2000	Rs. 350/-	One month	6&8	-do-
12	RRD on Jala Nallah to Paror Mohal (SH:-Hiring of Excavator cum loader for Removal of slips/boulders, muck debris etc. at various RDs) DC Deposit	74400	1500	Rs. 350/-	One month	6&8	-do-
13	RRD on various roads under Panarsa Sub Division (SH:- Hiring of Excavator cum loader for removal of slips/boulders, muck debris etc. at various RDs in Nagwain Section) Job No-3	99600	2000	Rs. 350/-	One month	6&8	-do-
14	RRD on various roads of Panarsa Sub Division (SH:- Hiring of Excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Panarsa Section) Job No-1	99600	2000	Rs. 350/-	One month	6&8	-do-
15	RRD on Takoli Bhamsoi Bhalthar road km 0/0 to 4/00 (SH:- Hiring of Excavator cum loader for removal of slips/boulders, muck debris etc. at various RDs) DC Deposit	99600	2000	Rs. 350/-	One month	6&8	-do-
16	RRD on various roads of Panarsa Sub Division (SH:- Hiring of Excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Panarsa Section) Job No.2	99600	2000	Rs. 350/-	One month	6&8	-do-
17	RRD on Chamarjani to Sansoi road km 0/0 to 2/00 (SH:-Hiring of Excavator cum loader for removal of slips/boulders, muck debris etc. at various RDs) DC Deposit	99600	2000	Rs. 350/-	One month	6&8	-do-
18	RRD on Sansoi to Kashana road Km 0/0 to 6/250 (SH:-C/O crated B/wall at RD 3/648 to 3/657)	92819	2000	Rs. 350/-	One month	6&8	-do-
19	RRD on Rahla to Shayari road km 0/00 to 2/500 (SH:- C/O crated R/Wall at RD 2/480 to 2/483)	99916	2000	Rs. 350/-	One month	6&8	-do-

20	RRD on Bhatwari to Rensh road Km 0/00 to 8/640 (SH:-C/o created R/wall at RD 4/580 to 4/585).	88314	2000	Rs. 350/-	One month	6&8	-do-
21	RRD on Aut Takoli Parashar road Km 0/0 to 27/00 (SH:- Hiring of Excavator cum loader for removal of slips/boulders, muck debris etc. at Km 5/00 to 10/00)	99600	2000	Rs. 350/-	One month	6&8	-do-
22	RRD on road from Dhamu to Massar Km 0/0 to 4/680 (SH:- C/O R/wall in R/R Masonry at RD 0/405 to 0/414) PDNA 2023	298987	6000	Rs. 350/-	One month	6&8	-do-
23	RRD on road from Dhamu to Deori km 0/0 to 2/645 (SH:- C/O R/wall in R/R Masonry at RD 1/700 to 1/710) PDNA 2023	446506	9000	Rs. 350/-	One month	6&8	-do-

TERMS & CONDITIONS: -

1. The Tender form will not be issued to those contractors whose performance is not found satisfactory.
2. The Contractor whose rates are abnormally low may be asked to furnish the full justification of his rate failing which he will be debarred to complete in tendering for four months.
3. The Contractor must be ensured that he is not having more than two works in hand and their detail must be prescribed in the proforma & attached with the application and only upto completion of work Satisfactory including adherence to quality parameters further work will be awarded to him & two jobs shall be considered in one application subject to above.
4. The rates beyond the limit over +5% will be rejected besides this the Additional Performance security will have to borne @ 20 % & 30 % for unbalanced bid in case the rates is lower than 10 % but upto 20 % & lower than 20 % upto 30 % respectively. The tender will be accepted beyond the limit of -30 % also.

Executive Engineer,
HPPWD Division (B&R),
Thalout at Pandoh

NO/PW/TLD/Tender/2025: - 12/58-67
Copy forwarded to the following for information and necessary action: -

1. The Engineer-in-Chief HPPWD Shimla.
2. The Deputy Commissioner Mandi Distt. Mandi HP.
3. The Sub Divisional Officer Balichowki, Distt. Mandi HP.
4. The Chief Engineer, (MZ) HPPWD Mandi.
5. The Superintending Engineer, 1st Circle, HPPWD Mandi HP.
6. The Distt. Panchayat Officer Mandi HP.
7. All AEs under this Division.
8. The President of Contractor's Association.
9. Notice Board/Accounts Branch/Drawing Branch/Supdt. With spare copies.

Executive Engineer,
HPPWD Division (B&R),
Thalout at Pandoh

BILL OF QUANTITY

Name of work:- RRD on Bhatwari to Rensh road Km 0/00 to 8/640 (SH: - C/o created R/wall at RD 4/595 to 4/600).

Estimated Cost: 88294.00
Earnest Money :- 2000.00

Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	19.20	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	7645.00
2	Providing and laying of Boulder upron laid in wire crates with 4 mm (four millimetre) dia G.I.wire conforming to IS : 280 and IS:4826 in 100 mm x 100 mm (hundred into hundred millimetre) mesh (woven) diagonally) including 10 (Ten persant) percent extra for laps and joints laid with stones boulders weighting not less then 25 kg (Twenty five kilograme) each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	23.44	3254.70	Rs. Three thousand two hundred fifty four and paise seventy only	Per Cubic Metre	76290.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	3.45	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	4359.00
	Total					88294.00

Bill of quantity approved for Rs. 88,294/- only

Executive Engineer,
Thalout Division
HP, PWD, Thalout

BILL OF QUANTITY

Name of work :- RRD on Rahla to Shayeri road Km 0/00 to 2/500 (S.H.) C/O graded R/Wall at RD 2/485 to 2/450

Estimated Cost: 99932.00
Earnest Money :- 2000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	26.46	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	10536.00
2	Providing and laying of Boulder upon laid in wire crates with 4 mm dia G.I.wire conforming to IS - 280 and IS-4826 in 150 mm x 150 mm mesh (woven) diagonally) including 10 percent extra for laps and joints laid with stones boulders weighting not less than 25 kg each as per drawing and technical specifications clause 1301 within all leads, lifts, carriage of materials and other incidental complete.	27.80	3098.00	Rs. Three thousand ninety eight and paise zero only	Per Cubic Metre	86124.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge	2.59	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	3272.00
Total						99932.00

Bill of Quantity approved for Rs. 99,932/-

Executive Engineer
Thalout Division,
HP, PWD, Thalout


BILL OF QUANTITY

Name of work:- RRD on Sansoi to Kashana road Km 0/0 to 6/250 (SH: - C/O crated B/wall at RD 3/630 to 3/639).

Estimated Cost: 92819.00
Earnest Money :- 2000.00
Time :- One Month

S. No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Excavation in soil in hilly area by mechanical means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift up to 1.5 metre (One point five meter) and a lead upto 20 metre (Twenty meter) as per technical specification clause 1603.1 + 1603.2 and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	9.50	140.20	Rs. one hundred forty and paise twenty only	Per Cubic Metre	1332.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated ssuitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	4.13	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	1645.00
3	Providing and laying of Boulder upron laid in wire crates with 4 mm dia G.I.wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm mesh (woven) diagonally) including 10 percent extra for laps and joints laid with stones boulders weighting not less then 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	29.00	3098.00	Rs. Three thousand ninty eight and paise zero only	Per Cubic Metre	89842.00
					Total	92819.00

Bill of quantity approved for Rs. 92819/- only


 Executive Engineer,
 Thalout Division,
 HP, PWD, Thalout


BILL OF QUANTITY

Name of work:- RRD on various roads under Panarsa Sub Division (SH:- Hiring of Excavator cum loader for Removal of slips/boulders, muck debris etc. at various RDs in Nagwain Section)
Job No-1

Estimated Cost:- 99600.00
Earnest Money:- 2000.00
Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in	Unit	Amount
				Words		
1	Hiring of Excavator-cum-loader for removal of slips/debris/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	99600.00

Bill of quantity approved for Rs. 99600/- only


 Executive Engineer,
 Thalout Division,
 HP PWD Thalout


BILL OF QUANTITY

Name of work:- RRD on Aut Takoli Parashar road Km 0/00 to 27/00(SH: - Hiring of Excavator cum loader for Removal of slips/boulders, muck debris etc. at Km 0/00 to 5/00)

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of slips/debris/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per drection of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	99600.00

Bill of Quantity approved for Rs. 99600/- only


Executive Engineer,
Thalout Division,
HP PWD Thalout.

NAME OF WORK: DRP

BILL OF QUANTITY

BILL OF QUANTITY	
Name of work:- RRD on various roads under Panarsa Sub Division (SH:- Hiring of Tipper for carriage of muck/debris etc. at various RDs) Job No-1	Nagpurin Section

Estimated Cost:- 98000.00

Earnest Money:- 2000.00

Time:- One Month

Time:- One Month						
S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
	Hiring of Tipper for carriage of debris/ muck / unservicable material from the various reaches of the road including all leads, lifts and unloading of material at suitable places as per entire satisfaction of Engineer-in-Charge (9.00 am to 5.00 pm) Terms and conditions:- 1. The daily logbook will be maintained at site which should be daily verified by the Engineer-in-Charge. 2. During working hours any type of accident the owner is responsible. 3. Driver will be provided by the owner.	28	3500.00	Rupees Three thousand five hundred only	Per day	98000.00
					Total	98000.00

8

BILL OF QUANTITY


Name of work:- NDF/2025/39 - RRD on Panarsa to Kotdhar road km 0/0 to 5/825 (SH:- Hiring of Excavator cum loader for Removal of slips/boulders, muck debris etc. at various RDs) DC Deposit

Estimated Cost:- 99600.00
Earnest Money:- 2000.00

Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of slips/debries/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	99600.00

Bill of quantity approved for Rs. 99600.


Executive Engineer,
 Thalout Division,
 HP PWD Thalout.

BILL OF QUANTITY

Name of work:- RRD on Aut Takoli Parashar road Km 0/00 to 27/00(SH:- Hiring of Excavator cum loader for Removal of slips/boulders, muck debries etc. at Km 10/00 to 15/00)

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of slips/debries/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per drection of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationa staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	99600.00

Bill of Quantity approved for Rs. 99600/- only

[Signature]
Executive Engineer,
Thalout Division,
HP PWD Thalout

BILL OF QUANTITY


Name of work:- RRD on Aut Takoli Parashar road Km 0/00 to 27/00(SH: - Hiring of Excavator cum loader for Removal of slips/boulders, muck debries etc. at Km 10/00 to 15/00)

Estimated Cost:-99600.00
Earnest Money:-2000.00

Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of slips/debries/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per drection of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	99600.00

Bill of Quantity approved for Rs. 99600/- only


Executive Engineer,
 Thalout Division,
 HP PWD Thalout.

	UNIT	PRICE	AMOUNT
BILL OF QUANTITY			

BILL OF QUANTITIES	
Name of work:- VKV/2025/1047 - RRD on Dehri Nallah to Chhurgari Mohal (SH: - Hiring of Excavator cum loader for Removal of slips/boulders, muck debries etc. at various RDs) DC Deposit	

Estimated Cost:-74400.00

Earnest Money:-1500.00

Time:- One Month

[illegible]

BILL OF QUANTITY	
Name of work:- RRD on various roads of Panarsa Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Nagwain Section) Job No-2	Estimated Cost:-99600.00
	Earnest Money:-2000.00

BILL OF QUANTITY	
Name of work:-	RRD on various roads of Panarsa Sub Division (SH:- Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Nagwain Section) Job No-2

Estimated Cost:-99600.00
Earnest Money:-2000.00

Time:- One Month

S. No.	Description of Item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00 (Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	99600.00

Bill of quantity approved for Rs. 99600.00

Executive Engineer,
Thalout Division,
HP PWD Thalout.

Bill of quantity approved for Rs. 99600/- only.

Executive Engineer,
Thalout Division,
HP PWD Thalout.

BILL OF QUANTITY


Name of work:- RRD on Sansoi to Kashna road km 0/0 to 6/250 (SH:- Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs).

Estimated Cost:-99600.00
Earnest Money:-2000.00

Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in	Unit	Amount
				Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debris/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	99600.00

Bill of quantity approved for Rs. 99600 only.


Executive Engineer,
Thalout Division,
HP PWD Thalout.

BILL OF QUANTITY	
Name of work:- VKV/2025/1048 - RRD on Jala Nallah to Paror Mohal (SH: - Hiring of Excavator cum loader for Removal of slips/boulders, muck debries etc. at various RDs) DC Deposit	


Estimated Cost: 74400.00

Earnest Money:-1500.00

Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of slips/debris/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	62.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	74400.00
					Total	74400.00

Bill of quantity approved for Rs. 74400/-


 Executive Engineer,
 Thalout Division,
 HP PWD Thalout.

15

Name of work:- KRD on various roads under Panarsa Sub Division (SH:- Hiring of Excavator cum loader for Removal of slips/boulders, muck debris etc. at various RDs in Nagwain Section)

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

[illegible]

Name of work:- RRD on various roads of Panarsa Sub Division (SH:- Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Panarsa Section) Job No.1	Estimated Cost:-99600.00
	Earnest Money:-2000.00
	Time:- One Month

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

Bill of quantity approved for Rs. 99,600/- only					
---	--	--	--	--	--

Executive Engineer,
Thalout Division
HP PWD Thalout.

Name of work:- NDF/2025/37 - RRD on Takoli Bhamsoi Bhalthar road km 0/0 to 4/00 (SH:- Hiring of Excavator cum loader for Removal of slips/boulders, muck debris etc. at various RDs) DC Deposit

Estimated Cost:-99600.00
Earnest Money:-2000.00

Executive Engineer,
Thalout Division,
HP PWD Thalout.

BILL OF QUANTITY

Name of work:- RRD on various roads of Panarsa Sub Division (SH:- Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Panarsa Section) Job No.2

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in	Unit	Amount
				Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debris/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	99600.00

Bill of quantity approved for Rs. 99600 only

Executive Engineer,
Thalout Division
HP PWD Thalout


BILL OF QUANTITY

Name of work:- NDF/2025/40 - RRD on Chamarjani to Sansoi road km 0/0 to 2/00 (SH: - Hiring of Excavator cum loader for Removal of slips/boulders, muck debris etc. at various RDs) DC Deposit

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in	Unit	Amount
				Words		
1	Hiring of Excavator-cum-loader for removal of slips/debris/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable material from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00 (Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operation staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	99600.00

Bill of quantity approved for Rs. 99600.00 only


 Executive Engineer,
 Thalout Division,
 HP PWD Thalout.

BILL OF QUANTITY

Name of work:- RRD on Sansoi to Kashana road Km 0/0 to 6/250 (SH: - C/O crated B/wall at RD 3/648 to 3/657).

Estimated Cost: 92819.00
Earnest Money :- 2000.00
Time :- One Month

S. No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Excavation in soil in hilly area by mechanical means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift up to 1.5 metre (One point five meter) and a lead upto 20 metre (Twenty meter) as per technical specification clause 1603.1 + 1603.2 and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	9.50	140.20	Rs. one hundred forty and paise twenty only	Per Cubic Metre	1332.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	4.13	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	1645.00
3	Providing and laying of Boulder upon laid in wire crates with 4 mm dia G.I.wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm mesh (woven diagonally) including 10 percent extra for laps and joints laid with stones boulders weighting not less than 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	29.00	3098.00	Rs. Three thousand ninty eight and paise zero only	Per Cubic Metre	89842.00
					Total	92819.00

Bill of quantity approved for Rs. 92819/- only

Executive Engineer,
Thalout Division,
HP, PWD, Thalout

BILL OF QUANTITY

Name of work:- RRD on Rahla to Shayari road km 0/00 to 2/500 (SH)- C/O crated R/Wall at RD 2/480 to 2/483

Estimated Cost: 99916.00
Earnest Money :- 2000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	26.45	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	10532.00
2	Providing and laying of Boulder upon laid in wire crates with 4 mm dia G.I wire conforming to IS : 280 and IS-4826 in 150 mm x 150 mm mesh (woven) diagonally) including 10 percent extra for laps and joints laid with stones boulders weighting not less than 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	27.80	3098.00	Rs. Three thousand ninty eight and paise zero only	Per Cubic Metre	86124.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	2.58	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	3260.00
Total						99916.00

Bill of Materials approved for Rs 99,916/- only

Bill of quantity approved for Rs 99,916/- only

Executive Engineer,
Theatout Division,
HP, PWD, Thala

BILL OF QUANTITY

Name of work:- RRD on Bhatwari to Rensh road Km 0/00 to 8/640 (SH: - C/o created R/wall at RD 4/580 to 4/585).

Estimated Cost: 88314.00

Earnest Money :- 2000.00

Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other delatarious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	19.25	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	7665.00
2	Providing and laying of Boulder upron laid in wire crates with 4 mm (four milimetre) dia G.I.wire conforming to IS : 280 and IS:4826 in 100 mm x 100 mm (hundred into hundred milimetre) mesh (woven) diagonally) including 10 (Ten persant) percent extra for laps and joints laid with stones boulders weighing not less then 25 kg (Twenty five kilograme) each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	23.44	3254.70	Rs. Three thousand two hundred fifty four and paise seventy only	Per Cubic Metre	76290.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	3.45	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	4359.00
	Total					88314.00

Bill of quantity approved for Rs 88,314 only

Executive Engineer,
Thalout Division,
HP,PWD,Thalout


BILL OF QUANTITY

Name of work:- RRD on Aut Takoli Parashar road Km 0/00 to 27/00(SH: - Hiring of Excavator cum loader for Removal of slips/boulders, muck debris etc. at Km 5/00 to 10/00)

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in	Unit	Amount
				Words		
1	Hiring of Excavator-cum-loader for removal of slips/debris/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	99600.00

Bill of Quantity approved for Rs. 99600/- only


Executive Engineer,
 Thalout Division,
 HP PWD Thalout.

BILL OF QUANTITY

Name of work:- RRD on road from Dhamu to Massar km 0/0 to 4/680 (SH:- C/O R/wall in R/R Masonry at RD 0/405 to 0/414.) PD NA 2023

Estimated Cost:- 298987.00
Earnest Money :- 6000.00
Time :- One Month

S. No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with all kind of soil upto any depth including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	15.98	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	6363
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 as per entire satisfaction and direction of Engineer-in-Charge. In c.c:1:4:8	21.60	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	105659
3	Stone masonry work in Random Rubble masonry in cement mortar 1:6 (one cement: 6 sand) in foundation complete as per drawing and technical specifications Clause 702,704,1202 and 1203 including all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	25.05	5197.20	Rs. Five thousand one hundred ninety seven and paise twenty only	Per Cubic Metre	130190
4	Construction of dry rubble masonry for retaining walls, breast walls revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification Clause 704.6 and 1302.5 as per entire satisfaction and direction of Engineer-in-Charge.	10.74	3751.20	Rs. Three thousand Seven hundred fifty one and paise twenty only	Per Cubic Metre	40288.00
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	13.05	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	16487
					Total	298987.00

Bill of quantity prepared for Rs. 298987/- only

Executive Engineer,
Thalout Division,
HP, PWD, Thalout.

BILL OF QUANTITY

Name of work:-RRD on road from Dhamu to Deori km 0/0 to 2/645 (SH:- C/O R/wall in R/R Masonry at RD 1/700 to 1/710) PDNA 2923

Estimated Cost:-446506.00
Earnest Money :- 9000.00
Time :- One Month

S. No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with all kind of soil upto any depth including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	17.8	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	7088
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 as per entire satisfaction and direction of Engineer-in-Charge. In c.c.1:4:8	24.00	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	117398
3	Stone masonry work in Random Rubble masonry in cement mortar 1:6 (one cement: 6 sand)in foundation complete as per drawing and technical specifications Clause 702,704,1202 and 1203 including all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	28.00	5197.20	Rs. Five thousand one hundred ninety seven and paise twenty only	Per Cubic Metre	145522
4	Construction of dry rubble masonry for retaining walls, breast walls revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification Clause 704.6 and 1302.5 as per entire satisfaction and direction of Engineer-in-Charge.	42.10	3751.20	Rs. Three thousand Seven hundred fifty one and paise twenty only	Per Cubic Metre	157926.00
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	14.70	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	18572
					Total	446506.00

Bill of Quantity approved for Rs 446,506.00

[Signature]
Executive Engineer,
Thalout Division,
HP, PWD, Thalout.