

Himachal Pradesh
Public Works Department

NO.PW.THD/CB-tender/2025-26

9928-45

Dated:-

5/1/2026

To

✓ The Executive Engineer, (IT Cell)
O/O Engineer-in- Chief,
H.P.P.W.D., NirmnBhawan, Shimla-2

Subject:- Publication of Tender notice.

Sir,

I am enclosing herewith Notice Inviting Tender for the various works typed in English for uploading the same on department website in view of Principal Secretary (PW) to the Government of Himachal Pradesh Notification No. PBW (B) A (3)8/2025 300858 dated 13th Nov. 2025.

As the work mentioned in the tender notice are urgent in nature and in public interest.


Executive Engineer,
TheogDivision, B&R,
H.P.P.W.D., Theog

Copy forwarded to the following a/w copy of tender notice for information:-

- The Deputy Commissioner, Shimla Distt. Shimla H.P
- The Superintending Engineer, 4th circle H.P.P.W.,D , Shimla-3.
- The Sub-divisional officer© Theog.
- The municipal Council Theog.
- Block development officer, Theog block.
- All the Assistant Engineer working under this division
- Superintendent Gr-II (Estt.) in this division.
- Drawing branch in this office.
- Notice Board


Executive Engineer,
TheogDivision, B&R,
H.P.P.W.D., Theog

Himachal Pradesh
Public Works Department
NOTICE INVITING TENDER


Sealed percentage rate tenders on PWD form 6 & 8 are hereby invited by the Executive Engineer, /-Theog Division, H.P.P.W.D., Theog on behalf of the Governor of HP. for the following works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the H.P. General Sales Tax Act, 1968 so as to reach in this office on or **before 16.01.2026 up to 11.00 A.M.** and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representative who may like to be present. The tender documents can be had from this office against cash payment (Non-refundable) on **15.01.2026 up to 4.00 P.M.** and the application for issue of tender form shall be received on **14.01.2026 up to 4.00 P.M.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/ Bank duly pledged in favour of XEN HPPWD. Theog must be accompanied with the application for tender documents. Please note no exemption orders of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 120 days. The Executive Engineer reserves the right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on the next working day at the same time and venue.

Sr.No	Name of work	Name of Divn.	Estimated cost(Rs.)	EMD (Rs.)	Cost of form (Rs)	Time Allowed
1	2	3	4	5	6	7
1	R/R of Snow Damages on Various Roads under Sainj Sub-Division (SH:- Hiring of JCB for removal of Snow in Sainj Section)	Theog	99,875=	2,000=	350/-	One Month
2	R/R of Snow Damages on Various Roads under Sainj Sub-Division (SH:- Hiring of JCB for removal of Snow in Sainj Section)	Theog	99,875=	2,000=	350/-	One Month
3	Restoration of Snow falls in Various Road Under Sainj Sub-Division (SH:- Supplying and stacking at site crusher sand)	Theog	99,000=	2,000=	350/-	One Month
4	R/R of Snow Damages on Various Roads under Sainj Sub-Division (SH:- Hiring of JCB for removal of Snow in Kuthar Section)	Theog	99,875=	2,000=	350/-	One Month
5	Repair & renovation of Veterinary Hospital Dr. Residence Building at Matiana Tehsil theog Distt Shimla (SH:- P/F ceramic glazed wall tiles, Providing and fixing wash basin, etc)	Theog	61,360=	1,250=	350/-	One Month
6	Restoration of rain Damages on Various Road Under Sainj Sub-Division (SH:- Hiring of JCB for removal of slips) Deha section	Theog,	99,750=	2,000=	350/-	One Month
7	Restoration of rain Damages on Various Road Under Theog Sub-Division (SH:- Hiring of JCB Excavator -cum-loader for removal of slips etc. in various roads) Fagu section	Theog,	99,750=	2,000=	350/-	One Month


8	Restoration of rain Damages on Various Road Under Sainj Sub-Division (SH:- Hiring of JCB for removal of slips/debris on various roads) Sainj section	Theog	99,750=	2,000=	350/-	One Month
9	R/R Damages on Various Road Under Sainj Sub-Division Deha Section (SH:- Hiring of JCB for removal of Land slide /debries etc. on various Rds in various road)	Theog,	99,750=	2,000=	350/-	One Month
10	R/R Damages on Various Road Under Theog Sub-Division Fagu Section (SH:- Hiring of JCB Excavator-cum-loader for removal of Land slide /debries etc. on various Rds in various road)	Theog	99,750=	2,000=	350/-	One Month
11	C/O Govt. Seinio Secndary School building at Chanair, Tehsil Theog District Shimla LHP (SH:- C/o Steel work for Gate & fencing etc.	Theog	1,86,450=	3,730=	350/-	One Month
12	R/R of rain damages on Chalari to Lower Kiara Km/Rd 0/0 to 3/240 (SH:- C/O B/wall at Km/Rd 2/780 to 2/790)	Theog,	1,42,597=	2,852=	350/-	One Month
13	R/R rain damages on Sarog Barog Doba road km 0/0 to 13/060 (SH:- C/O RCC R/wall at Km/Rd 8/720 to 8/732)	Theog	1,42,399=	2,850=	350/-	One Month
14	R/R of rain damages on Runkali Chikhar road km 0/0 to 6/500 (SH:- C/O B/wall at Km/Rd 0/600 to 0/620)	Theog	3,15,088=	6,350=	350/-	One Month
15	C/O Kiar Kalaher Samber road km 0/0 to 6/500 (SH:- C/o RCC B/wall at Km/Rd 3/857 to 3/868)	Theog	3,85,585=	7,800=	350/-	One Month
16	R/R of rai damages on Lafughati Patinal road km/Rd 0/0 to 10/00 (SH:- C/O R/wall at Km/Rd 3/580 to 3/585)	Theog	1,38,907=	2,800=	350/-	One Month

- The contractors are required to produce a copy of their PAN No. GST and should also produce a copy of enlistment /renewal letter.
- Special care should be taken to write the rates both in figures and in words failing which tender is likely to be rejected
- The contractor will have to submit the proof of registration Under Employees Provident Fund & Miscellaneous Provision Act, 1952 at the time of tender. Failure to observe this condition shall render the tender of contractor liable to summary rejection.


 Executive Engineer.
 Theog Division B&R,
 H.P.P.W.D Theog.

"Exigency Certificate"

It is certified that the tenders for various works as called for vide this office letter No. PW/THD/CB/Tender/2025-26 998-45 dt 3/1/2026 are of emergent nature in exigency of public interest.


Executive Engineer,
Theog Division, B&R,
H.P.P.W.D., Theog

Schedule of Quantity


Estimated Cost: 99875/-
Earnest Money: 2000/-
Time: 1 Month

Name of Work:- R/R of snow damages on various roads under Sainj Sub-Division
(SH:- Hiring of JCB for removal of snow in Sainj Section).

Sr. No.	Description of Item	Qty.	Rate	Unit	Amount
1	Snow clearance from road surface by bulldozer /JCB and disposing it on the velly sides as per MORTH and IRC specification 48-1998 i/c all leads and lifts and as per direction of the Engineer-in- Charge.	21250.00	4.70	P/cum	99875.00
				Total:	99875.00
				(% above/below & at par DNIT amount)	

1. All the POL charges shall be born by the Contractor.

2. All the repair of Machinery shall be born by the contractor.


Executive Engineer,
Theog Division,
HP.PWD. Theog

Schedule of Quantity

Estimated Cost: 99875/-
Earnest Money: 2000/-
Time: 1 Month

Name of Work:- R/R of snow damages on various roads under Sainj Sub-Division
(SH:- Hiring of JCB for removal of snow in ~~Dehra~~ ^{Sainj} Section).

Sr. No.	Description of Item	Qty.	Rate	Unit	Amount
1	Snow clearance from road surface by bulldozer /JCB and disposing it on the velly sides as per MORTH and IRC specification 48-1998 i/c all leads and lifts and as per direction of the Engineer-in- Charge.	21250.00	4.70	P/cum	99875.00
				Total:	99875.00
				(% above/below & at par DNIT amount)	

1. All the POL charges shall be born by the Contractor.

2. All the repair of Machinery shall be born by the contractor.


Executive Engineer,
Theog Division,
HP.PWD. Theog

3 14

Schedule of Quantity

Estimated Cost Rs: 99000/-
Earnest Money Rs 2000/-
Time: One Month

Name of Work:- Restoration of Snow falls in Various Road under Sainj Sub Division (SH:- Supplying and Stacking at site crusher sand)

Sr.N o.	Description of Item	Qty.	Rate	Unit	Amount
1	Supply and stacking at site of work crusher sand clean and free from adherent coating and organic matter and shall not contain any appreciable amount of nayclay bails pills etc. in all leads and lifts and as per the Engineer-in-Charge.	90.00	1100.00	P/cum	99000.00
				Total:	99000.00
			(% above/below & at par DNIT amount)		
	Quoted Rate (In Fig)				
	Quoted Rate (In words)				


Executive Engineer,
Theog Division,
HP.PWD. Theog

4

Schedule of Quantity

Estimated Cost: 99875/-
Earnest Money: 2000/-
Time: 1 Month

Name of Work:- R/R of snow damages on various roads under Sainj Sub-Division
(SH:- Hiring of JCB for removal of snow in Kuthar Section).

Sr. No.	Description of Item	Qty.	Rate	Unit	Amount
1	Snow clearance from road surface by bulldozer /JCB and disposing it on the velly sides as per MORTH and IRC specification 48-1998 i/c all leads and lifts and as per direction of the Engineer-in- Charge.	21250.00	4.70	P/cum	99875.00
				Total:	99875.00
				(% above/below & at par DNIT amount)	

1. All the POL charges shall be born by the Contractor.
2. All the repair of Machinery shall be born by the contarctor.


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs. 61360/

Earnest Money: 1250/

Time: One Months

Name of Work :- Repair & renovation of Veterinary Hospital Dr. Residence Building at Matiana Tehsil Theog Distt Shimla (SH:- P/F ceramic glazed wall

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete including in all leads and lifts as per direction of Engineer-in-Charge.	43.80	1020.10	Rupees One Thousand Twenty and Paise Ten Only	Per square meter	44680
2	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require including in all leads and lifts as per direction of Engineer-in-Charge.	1.00	2750.00	Rupees Two Thousand Seven Hundred Fifty Only	each	2750
3	Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms including in all leads and lifts as per direction of Engineer-in-Charge. 15 mm nominal bore	3.00	820.10	Rupees Eight Hundred Twenty and Paise Ten Only	each	2460

5(ii)

4	Renewing glass panes, with wooden fillets wherever necessary Float glass panes of nominal thickness 4 mm (weight not less than 10kg/sqm) including in all leads and lifts as per direction of Engineer-in-Charge.	4.71	1020.70	Rupees One Thousand Twenty and Paise Seventy Only	Per square meter	4807
5	Providing and fixing insulating board ceiling of approved quality with necessary nails etc. complete (frame work to be paid separately including in all leads and lifts as per direction of Engineer-in-Charge. 12 mm thick	7.20	925.25	Rupees Nine Hundred Twenty Five and Paise Twenty Five Only	Per square meter	6662
						61360
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			

Executive Engineer,
Theog Division,
HPPWD Theog

Schedule OF Quantity

Estimated Cost: 99750-
Earnest Money: 2000/-
Time: one month

Name of Work:- Restoration of rain damages on Various road Under Sainj sub division (SH:-Hiring of JCB for removal of land slide/debris on various Road (Deha Section)

Sr.No	Description of Item	Qty.	Rate	Unit	Amount
1	Hiring of JCB earth cutting / excavating machinaries to be deployed for earth cutting/excavation for filling including cost of fuel oil lubricants and wages of operational staff any repair brackage during operation will be carried out by the owner at his risk and cost including shifting of machinaries from one place to other at required locations, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum excavation in all kinds of soil including loading in tipper /truks and disposing excavated earth in all leads and lifts will have to be ensured in one hour working (a. excavator -cum-loader)	95.00	1050.00	Hrs	99750.00
				Total:-	99750.00
	Rate Quoted by the Contarctor	(Rs in Fig)	% above/Below /as per Dnit amount.		
		(Rs In words)			

Executive Engineer,
Theog Division,
HP.PWD. Theog

Schedule of Quantity

Estimated Cost: 99750/-
Earnest Money: 10000/-
Time: Three month

Name of Work:- Restoration of rain damages on various road under Theog Sub Division(Fagu Section) (SH:-Hiring of JCB Excavator-Cum-Loader for removal of slips etc in various Road)

Sr.N o.	Description of Item	Qty.	Rate	Unit	Amount
1	Hiring of JCB earth cutting / excavating machinaries to be deployed for earth cutting/excavation for filling including cost of fuel oil lubricants and wages of operational staff any repair brackage during operation will be carried out by the owner at his risk and cost including shifting of machinaries from one place to other at required locations, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum excavation in all kinds of soil including loading in tipper /truks and disposing excavated earth in all leads and lifts will have to be ensured in one hour working (a. excavator -cum-loader)	95.00	1050.00	Hrs	99750.00
				Total	99750.00
					(% above/below & at par DNIT amount)


Executive Engineer,
Theog Division,
HP PWD, Theog

Schedule OF Quantity

Estimated Cost: 99750-
Earnest Money: 2000/-
Time: one month

Name of Work:- Restoration of rain damages on Various road Under Sainj sub division (SH:-Hiring of JCB for removal of land slide/debries on various Road (Sainj Section)

Sr.No	Description of Item	Qty.	Rate	Unit	Amount
1	Hiring of JCB earth cutting / excavating machinaries to be deployed for earth cutting/excavation for filling including cost of fuel oil lubricants and wages of operational staff any repair brackage during operation will be carried out by the owner at his risk and cost including shifting of machinaries from one place to other at required locations, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum excavation in all kinds of soil including loading in tipper /truks and disposing excavated earth in all leads and lifts will have to be ensured in one hour working (a. excavator -cum-loader)	95.00	1050.00	Hrs	99750.00
				Total:-	99750.00
	Rate Quoted by the Contarctor	(Rs in Fig)	% above/Below /as per Dnit amount.		
		(Rs In words)			

Executive Engineer,
Theog Division,
HP.PWD. Theog

Schedule OF Quantity

Estimated Cost: 99750-
Earnest Money: 2000/-
Time: one month

Name of Work:- Restoration of rain damages on Various road Under Sainj sub division (SH):-Hiring of JCB for removal of land slide/debries on various Road (Deha Section)

Sr.No	Description of Item	Qty.	Rate	Unit	Amount
1	Hiring of JCB earth cutting / excavating machinaries to be deployed for earth cutting/excavation for filling including cost of fuel oil lubricants and wages of operational staff any repair brackage during operation will be carried out by the owner at his risk and cost including shifting of machinaries from one place to other at required locations, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum excavation in all kinds of soil including loading in tipper /truks and disposing excavated earth in all leads and lifts will have to be ensured in one hour working (a. excavator -cum-loader)	95.00	1050.00	Hrs	99750.00
				Total:-	99750.00
	Rate Quoted by the Contarctor	(Rs in Fig)	% above/Below /as per Dnit amount.		
		(Rs In words)			


Executive Engineer,
Theog Division,
HP.PWD. Theog

Schedule of Quantity

Estimated Cost: 99750/-
Earnest Money: 10000/-
Time: Three month

Name of Work:- Restoration of rain damages on various road under Theog Sub Division (Fagu Section) (SH:-Hiring of JCB Excavator-Cum-Loader for removal of slips etc in various Road)

Sr.N o.	Description of Item	Qty.	Rate	Unit	Amount
1	Hiring of JCB earth cutting / excavating machinaries to be deployed for earth cutting/excavation for filling including cost of fuel oil lubricants and wages of operational staff any repair brackage during operation will be carried out by the owner at his risk and cost including shifting of machinaries from one place to other at required locations, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum excavation in all kinds of soil including loading in tipper /truks and disposing excavated earth in all leads and lifts will have to be ensured in one hour working (a. excavator -cum-loader)	95.00	1050.00	Hrs	99750.00
				Total	99750.00
				(% above/below & at par DNIT amount)	


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs. 186450/-

Earnest Money: 3730.00

Time: one Months

Name of work:- C/O Govt.Snr.Sec.school Building at Chanair Tehsil Theog Distt Shimla (H.P) (SH:- C/O Steel work for Gate & fencing etc)						
Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil) including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	1.20	235.05	Rupees Two Hundred Thirty Five and Paise: Five Only	Per Cum	282.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802, 803, 1202 and 1203. including all leads and lifts or as per the direction of Engineer - in Charge (1:4:8) (40 mm nominal size)	1.20	4655.20	Rupees Four Thousand Six Hundred Fifty Five and Paise Twenty Only	Per Cum	5586.00
3	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat red lead paint upto all floor level including all leads and lifts of materials or as per the direction of Engineer-in-Charges.	1374.81	107.45	Rupees One Hundred Seven and Paise Forty Five Only	Per/Kg	147723.00
4	Providing and fixing welded mesh 25mm x 25mmX 3mm thick as per approved design by welding with electrical plant complete including priming coat of red lead paint as per HP,PWD specification 1990 volume-I including carriage of materials upto all leads and lifts..	50.12	655.60	Rupees Six Hundred Fifty Five and Paise Sixty Only	Per/Kg	32859.00
Total						186450.00
			Quoted rate in figer+/-			
			Quoted rate in words			

Opened by me today on

Dated.....

E.E.

Cutting..... Overwriting.....

Conditions.....

E.E.

Executive Engineer,
Theog Division,
HP.PWD, Theog

Schedule Of Quantity

Estimated Cost 142597/-

Earnest Money: ~~10100~~ /- 2852/-

Time: One month

Name of Work:- R/R Rain Damages on Chellari to Lower Kiara km 0/0 to 3/240(SH:-C/O B/Wall at RD2/780 to 2/790)

Sr. No.	Description of Items	QTY.	Rate	in feg	in words	Unit	Amount
1	Excavation in Hilly areas in soil by mechanical means excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts as per direction of Engineer in-Charge.	28.00	150.00		Rupees One Hundred Fifty Only	P/cum	4200.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	11.20	220.00		Rupees Two Hundred Twenty Only	P/cum	2464.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. including all leads and lifts as per direction of the Engineer-in-Charge. (1:4:8) 40 mm nominal size	30.60	4378.40		Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	P/cum	133979.04
4	Providing and fixing weapholes in brick masonry/stone masonry, plain RCC abutment, B/wall, R/wall with 100 mm dia PVC pipe i/c all leads and lifts. as per direction of the Engineer-in-Charge	8.00	244.30		Rupees Two Hundred Forty Four and Paise Thirty Only	Each	1954.40
					Total:-		142597.44
						Quoted Rates (In Fig) (% above/below / at Par)	
						Quoted Rates (In Words)	

Executive Engineer
Theog Division
HP.PWD. Theog

Schedule Of Quantity

Estimated Cost 142399/-

Earnest Money: 2850/-

Time: One month

Name of Work:- R/R Rain Damages on Bhakality Sarog Doba Road km 0/0 to 13/060(SH:- C/O RCC R/Wall at RDs 8/720 to 8/732)

Sr. No.	Description of Items	QTY.	Rate	Unit	Amount
			in fig	in words	
1	Excavation in Hilly areas in soil by mechanical means excavation in soil in hilly area by mechanical means including cutting and trimming of side slopess and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts as per direction of Engineer-in-Charge.	15.60	180.00	P/cum Rupees One Hundred Eighty Only	2808.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	11.76	220	P/cum Rupees Two Hundred Twenty Only	2587.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802.803, 1202 and 1203. including all leads and lifts as per direction of the Engineer-in-Charge. (1:4:8) 25 mm nominal size)	29.28	4550.00	P/cum Rupees Four Thousand Five Hundred Fifty Only	133224.00
4	Providing and fixing weapholes in brick masonry/stone masnory, plain RCC abutment, B/wall, R/wall with 100 mm dia PVC pipe i/c all leads and lifts. as per direction of the Engineer-in-Charge	14.00	270.00	Each Rupees Two Hundred Seventy Only	3780.00
				Total:-	142399.00
				Quoted Rates (In Fig)	
				Quoted Rates (In Words)	
				(% above/below / at Par)	

Executive Engineer

Theog Division

HP.PWD. Theog

14

Schedule Of Quantity

Estimated Cost 315088/-
Earnest Money: 6350 /-
Time: One month

Name of Work:- R/R Rain Damages on Runkali Chikhar Road km 0/0 to 6/500 (SH:-C/O B/Wall at RD0/600 to 0/620))

Sr. No.	Description of Items	QTY.	Rate	Unit	Amount
			in fig	in words	
1	Excavation in Hilly areas in soil by mechanical means excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts as per direction of Engineer in-Charge.	50.00	180.00	Rupees One Hundred Eighty Only	9000.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	60.00	220.00	Rupees Two Hundred Twenty Only	13200.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802, 803, 1202 and 1203. including all leads and lifts as per direction of the Engineer-in-Charge. (1:6:12) 40 mm nominal size	6.00	4000.00	Rupees Four Thousand Only	24000.00
4	Stone masonry in cement mortar for substructure complete as per drawing and technical specification clause 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:6 including all leads and lifts as per direction of the Engineer-in-Charge. (1:6)	70.76	3800.00	Rupees Three Thousand Eight Hundred Only	268888.00
				Total:-	315088.00
				Quoted Rates (In Fig)	
				Quoted Rates (In Words)	
				(% above/below / at Par)	

Executive Engineer
Theog Division
HP.PWD. Theog

15

Schedule Of Quantity

Estimated Cost: 385585/-
 Earnest Money: 7800 /-
 Time: One month

Name of Work:- C/O Kiar Kalahar Samber Road km 0/0 to 6/500(SH:- C/O RCC B/Wall at RDs3/857 to 3/868)

Sr. No.	Description of Items	QTY.	Rate in feg	in words	Unit	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	42.52	220	Rupees Two Hundred Twenty Only	P/cum	9354.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. including all leads and lifts as per direction of the Engineer-in-Charge. (1:4:8) 25 mm nominal size)	75.13	4680.00	Rupees Four Thousand Six Hundred Eighty Only	P/cum	351608.00
3	Providing and fixing weapholes in brick masonry/stone masonry, plain RCC abutment, B/wall, R/wall with 100 mm dia PVC pipe i/c all leads and lifts. as per direction of the Engineer-in-Charge	33.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	7990.95
4	Back stone Filling behind abutment wing wall/and R/wall complete as per drawing & technical specification clause 1204.3.8	15.84	1050.00	Rupees One Thousand Fifty Only	P/cum	16632.00
				Total:-		385585.00
				Quoted Rates (In Fig)		
				Quoted Rates (In Words)		
				(% above/below / at Par)		

Executive Engineer
 Theog Division
 HP.P.W.D. Theog

Estimated Cost 138907/-
Earnest Money:2800 /-

Estimated Cost 138907/-
Earnest Money:2800 /-

Time: One month

III. C/O BWall at RD 3/580 to 3/585)

Quoted Rates (In Fig)	Quoted Rates (In Words)
1.0000	one and 00/100
1.0005	one and 5/100
1.0010	one and 10/100
1.0015	one and 15/100
1.0020	one and 20/100
1.0025	one and 25/100
1.0030	one and 30/100
1.0035	one and 35/100
1.0040	one and 40/100
1.0045	one and 45/100
1.0050	one and 50/100
1.0055	one and 55/100
1.0060	one and 60/100
1.0065	one and 65/100
1.0070	one and 70/100
1.0075	one and 75/100
1.0080	one and 80/100
1.0085	one and 85/100
1.0090	one and 90/100
1.0095	one and 95/100
1.0100	one and 00/100
1.0105	one and 5/100
1.0110	one and 10/100
1.0115	one and 15/100
1.0120	one and 20/100
1.0125	one and 25/100
1.0130	one and 30/100
1.0135	one and 35/100
1.0140	one and 40/100
1.0145	one and 45/100
1.0150	one and 50/100
1.0155	one and 55/100
1.0160	one and 60/100
1.0165	one and 65/100
1.0170	one and 70/100
1.0175	one and 75/100
1.0180	one and 80/100
1.0185	one and 85/100
1.0190	one and 90/100
1.0195	one and 95/100
1.0200	two and 00/100
1.0205	two and 5/100
1.0210	two and 10/100
1.0215	two and 15/100
1.0220	two and 20/100
1.0225	two and 25/100
1.0230	two and 30/100
1.0235	two and 35/100
1.0240	two and 40/100
1.0245	two and 45/100
1.0250	two and 50/100
1.0255	two and 55/100
1.0260	two and 60/100
1.0265	two and 65/100
1.0270	two and 70/100
1.0275	two and 75/100
1.0280	two and 80/100
1.0285	two and 85/100
1.0290	two and 90/100
1.0295	two and 95/100
1.0300	three and 00/100
1.0305	three and 5/100
1.0310	three and 10/100
1.0315	three and 15/100
1.0320	three and 20/100
1.0325	three and 25/100
1.0330	three and 30/100
1.0335	three and 35/100
1.0340	three and 40/100
1.0345	three and 45/100
1.0350	three and 50/100
1.0355	three and 55/100
1.0360	three and 60/100
1.0365	three and 65/100
1.0370	three and 70/100
1.0375	three and 75/100
1.0380	three and 80/100
1.0385	three and 85/100
1.0390	three and 90/100
1.0395	three and 95/100
1.0400	four and 00/100
1.0405	four and 5/100
1.0410	four and 10/100
1.0415	four and 15/100
1.0420	four and 20/100
1.0425	four and 25/100
1.0430	four and 30/100
1.0435	four and 35/100
1.0440	four and 40/100
1.0445	four and 45/100
1.0450	four and 50/100
1.0455	four and 55/100
1.0460	four and 60/100
1.0465	four and 65/100
1.0470	four and 70/100
1.0475	four and 75/100
1.0480	four and 80/100
1.0485	four and 85/100
1.0490	four and 90/100
1.0495	four and 95/100
1.0500	five and 00/100
1.0505	five and 5/100
1.0510	five and 10/100
1.0515	five and 15/100
1.0520	five and 20/100
1.0525	five and 25/100
1.0530	five and 30/100
1.0535	five and 35/100
1.0540	five and 40/100
1.0545	five and 45/100
1.0550	five and 50/100
1.0555	five and 55/100
1.0560	five and 60/100
1.0565	five and 65/100
1.0570	five and 70/100
1.0575	five and 75/100
1.0580	five and 80/100
1.0585	five and 85/100
1.0590	five and 90/100
1.0595	five and 95/100
1.0600	six and 00/100
1.0605	six and 5/100
1.0610	six and 10/100
1.0615	six and 15/100
1.0620	six and 20/100
1.0625	six and 25/100
1.0630	six and 30/100
1.0635	six and 35/100
1.0640	six and 40/100
1.0645	six and 45/100
1.0650	six and 50/100
1.0655	six and 55/100
1.0660	six and 60/100
1.0665	six and 65/100
1.0670	six and 70/100
1.0675	six and 75/100
1.0680	six and 80/100
1.0685	six and 85/100
1.0690	six and 90/100
1.0695	six and 95/100
1.0700	seven and 00/100
1.0705	seven and 5/100
1.0710	seven and 10/100
1.0715	seven and 15/100
1.0720	seven and 20/100
1.0725	seven and 25/100
1.0730	seven and 30/100
1.0735	seven and 35/100
1.0740	seven and 40/100
1.0745	seven and 45/100
1.0750	seven and 50/100
1.0755	seven and 55/100
1.0760	seven and 60/100
1.0765	seven and 65/100
1.0770	seven and 70/100
1.0775	seven and 75/100
1.0780	seven and 80/100
1.0785	seven and 85/100
1.0790	seven and 90/100
1.0795	seven and 95/100
1.0800	eight and 00/100
1.0805	eight and 5/100
1.0810	eight and 10/100
1.0815	eight and 15/100
1.0820	eight and 20/100
1.0825	eight and 25/100
1.0830	eight and 30/100
1.0835	eight and 35/100
1.0840	eight and 40/100
1.0845	eight and 45/100
1.0850	eight and 50/100
1.0855	eight and 55/100
1.0860	eight and 60/100
1.0865	eight and 65/100
1.0870	eight and 70/100
1.0875	eight and 75/100
1.0880	eight and 80/100
1.0885	eight and 85/100
1.0890	eight and 90/100
1.0895	eight and 95/100
1.0900	nine and 00/100
1.0905	nine and 5/100
1.0910	nine and 10/100
1.0915	nine and 15/100
1.0920	nine and 20/100
1.0925	nine and 25/100
1.0930	nine and 30/100
1.0935	nine and 35/100
1.0940	nine and 40/100
1.0945	nine and 45/100
1.0950	nine and 50/100
1.0955	nine and 55/100
1.0960	nine and 60/100
1.0965	nine and 65/100
1.0970	nine and 70/100
1.0975	nine and 75/100
1.0980	nine and 80/100
1.0985	nine and 85/100
1.0990	nine and 90/100
1.0995	nine and 95/100
1.1000	ten and 00/100

Executive Engineer
Theog Division
HP.PWD. Theog