

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW-AD-EA-I-Tender-2025-26

13041-49

Dated:- 17/02/2026


To

The Executive Engineer (IT Cell)
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- Notice Inviting Tender for uploading the same on departmental website.

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office as per notification Secy.(PW) to the Govt. of Himachal Pradesh letter no. PBW(B)A0(3)8/2025-300858 dated shimla-2 the 09.10.2025 and letter No. PWD-B0(3)1/2024-241828 dated Shimla 2.02.2026 as the works mentioned in the tender notice are uploading the same on departmental website at the earliest please.

Encl:-Copy of NIT


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.
Ph. 01796-220714

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla.
3. The Superintending Engineer, 3rd Circle, HPPWD., Solan.
4. The Deputy Commissioner Solan, Distt. Solan.
5. The Sub Divisional Magistrate Arki.
6. All the Executive Engineers in HPPWD, (SZ).
7. All the Assistant Engineer, working under this division.
8. All the heads of the branches in this office.
9. Notice Board.


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.
Ph. 01796-220714

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Arki Division H.P.P.W.D. Arki on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Service Tax Act, 2017 so as to reach in this office on before **26.02.2026 up to 11:30 AM** and the same shall be opened on the same day at **12:00 A.N.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **25.02.2026 up to 4:30 PM** and the application for issue of tender form shall be received on **25.02.2026 up to 5:00 PM.**


The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Arki Division HPPWD Arki must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

| Sr. No | Name of Work | Estimated Cost | Earnest Money | Time | Cost of Form |
|--------|--|----------------|---------------|---------|--------------|
| 1 | Restoration of rain damages on various roads under Kunihar Sub-Division under Jainagar section(SH:-Hiring of JCB for removal of slips, etc.)Job No.15 | 99,000/- | 2000/- | 1 Month | 350/- |
| 2. | Restoration of rain damages on various roads under Kunihar Sub-Division under Jainagar section(SH:-Hiring of JCB for removal of slips, etc.)Job No.16 | 99,000/- | 2000/- | 1 Month | 350/- |
| 3 | Restoration of rain damages on various roads under Kunihar Sub-Division under Jainagar section(SH:-Hiring of JCB for removal of slips, etc.)Job No.17 | 99,000/- | 2000/- | 1 Month | 350/- |
| 4 | Restoration of rain damages on various roads under Kunihar Sub-Division under Jainagar section(SH:-Hiring of JCB for removal of slips, etc.)Job No.18 | 99,000/- | 2000/- | 1 Month | 350/- |
| 5 | Extension of Stage & Pre-Painted Sheet Roofing Over Stage at GHS Mangrud Tehsil Arki Distt. Solan H.P(SH:-Providing and fixing Roofing on Stage in GHS Mangrud)DMFT Deposit | 1,43,715/- | 3000/- | 1 Month | 350/- |
| 6 | (1)C/o link road from Piplughat to village Pather Km. 0/0 to 1/300(2)C/o link road village Sokhar km. 0/0 to 0/600(3)C/o link road to village Kyari km. 0/0 to 0/300(SH:-Jeepable to | 1,49,776/- | 3000/- | 1 Month | 350/- |

| | | | | | |
|----|---|------------|----------|--------|-------|
| | Motorable road(1)Km. 0/090 to 0/150(2)Kmm. 0/0 to 0/090 and(3) Km. 0/165 to 0/270)VKVNY Deposit | | | | |
| 7 | C/o link road from Jabloo Kanswala to village Khata G.P. Rouri km. 0/0 to 1/500(SH:-F/C in km. 0/0 to 0/315)DMFT Deposit. | 4,90,412/- | 10,000/- | 1Month | 350/- |
| 8 | C/o Govt. Degree College Darlaghat(SH:-P/L Boulder Apron Wire crate in front of Building(Balance work) | 99,540/- | 2000/- | 1Month | 350/- |
| 9 | Restoration of rain damages on Bathalang Bara Tamred road km. 0/0 to 3/0(SH:-C/o B/wall at RD 0/210 to 0/221.30) | 99,337/- | 2000/- | 1Month | 350/- |
| 10 | Restoration of rain damages on Bathalang Bara Tamred road km. 0/0 to 3/0(SH:-C/o R/wall at RD 0/327 to 0/341) | 98,978/- | 2000/- | 1Month | 350/- |
| 11 | Restoration of Rain damages on Kunihar Baijkihatti Shelly Brampukhar road portion km. 39/0 to 56/200 and Jamli to Jainagar road under PDNA 2023(SH:-C/o R/wall at RD 50/475 to 50/486.50) | 4,99,081/- | 10,000/- | 1Month | 350/- |
| 12 | C/o link road from Samana Paza to Kaldwar km. 0/0 to 2/450(SH:-F/C in km. 0/0 to 0/945)DMFT Deposit | 4,91,068/- | 10,000/- | 1Month | 350/- |
| 13 | R/R damages on Kunihar Bainj Ki Hatti Shelly Brapukhar road km. 11/0 to 39/0(SH:-C/o R/wall at Rd 34/160 to 34/177)Balance work under PDNA | 4,99,553/- | 10,000/- | 1Month | 350/- |
| 14 | C/o link road from Karoda to Nouni road km. 0/0 to 1/500(SH:-C/o R/wall at RD 0/910 to 0/932)DMFT Deposit | 4,74,697/- | 9500/- | 1Month | 350/- |
| 15 | C/o link road Anial Husbandary Darla t Kotla Numhal Kotla Pujaria Datti Shiv nagar road km. 0/0 to 4/500(SH:-C/o B/wall house of Het Ram at Rd 0/080 to 0/090,1/0 to 1/035 and F/C in k . 0/280 to 1/035)DMFT Deposit | 3,87,830/- | 8000/- | 1Month | 350/- |
| 16 | C/o link road from Chandi Rudal Harsangdhar road km. 0/0 to 8/330(SH:-C/o R/wall at RD 8/316 to 8/321.50)DMFT | 1,97,630/- | 4000/- | 1Month | 350/- |
| 17 | C/o link road from Siharli to Sakor km. 0/0 to 4/200(SH:-Surface dressing, Kharnja soling,P.C.C. 1:4:8, P.C.C. 1:2:4 and side drain at RD 2/920 to 3/045)DMFT Deposit) | 4,32,680/- | 9,000/- | 1Month | 350/- |

Followings documents should be attached with the application for tenders:-

- The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.


Executive Engineer
Arki Division,
H.P.P.W.D. Arki.


No: PW-AD-EA-I-Tender-2025-26-

13041-49

Dated:- 17/02/2026


Copy forwarded for the following for information and necessary action to:-

- 1.The Superintending Engineer 3rd Circle HPPWD Solan.
- 2.The all Assistant Engineer working under this division for information and necessary action.
- 3.All the heads of the branches in this office.
- 4.Notice Board.


Executive Engineer
Arki Division
H.P.P.W.D.Arki.

Certificate


Certified that the tenders called vide this notice inviting tender for
17(seventeen) jobs are due to exigencies/emergency of works in the larger public interest.


Executive Engineer
Arki Division
H.P.P.W.D. Arki.


| SCHEDULE OF QUANTITY | | | | | | | |
|---|---|-------|-------|-----------|--|-----------|----------|
| Name of Work:-Restoration of rain Damages on various roads under kunihar sub division under Jainagar section.(Sh-Hiring of JCB for removal of slips etc.) Job No - 15 | | | | | Estimated Cost :- Rs 99,000.00 | | |
| | | | | | Earnest money :- Rs 2,000.00 | | |
| | | | | | Time: One month | | |
| Sr.No. | Sub Head and Items of Work | Qty. | | Rate | | Unit | Amount |
| 1 | 2 | 3 | | In figure | In words | 6 | 7 |
| 1.00 | Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 meters and lead upto 1000 meters as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer in charge. | 99.00 | Hours | 1000.00 | Rupees One thousand and paise Nil Only | Per Hours | 99000.00 |
| | | | | | | Total | 99000.00 |


 Executive Engineer
 Arki Division (B&R)
 HR, PWD, Arki.

| SCHEDULE OF QUANTITY | | | | | | | |
|--|---|-------|-------|-----------|--|-----------|----------|
| Name of Work:-Restoration of rain Damages on various roads under kunihar sub division under Jainagar section.(Sh-Hiring of JCB for removal of slips etc.) Job no. 16 | | | | | Estimated Cost :- Rs 99,000.00 | | |
| | | | | | Earnest money :- Rs 2,000.00 | | |
| | | | | | Time: One month | | |
| Sr.No. | Sub Head and Items of Work | Qty. | | Rate | | Unit | Amount |
| 1 | 2 | 3 | | In figure | In words | 6 | 7 |
| 1.00 | Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 meters and lead upto 1000 meters as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer in charge. | 99.00 | Hours | 1000.00 | Rupees One thousand and paise nil Only | Per Hours | 99000.00 |
| | | | | | | Total | 99000.00 |


 Executive Engineer
 Arki Division (B&R)
 HP. PWD. Arki.

| SCHEDULE OF QUANTITY | | | | | | |
|--|---|-------|-------|--------------------------------|---------------------------------------|----------------|
| Name of Work:-Restoration of rain Damages on various roads under kunihar sub division under Jainagar section.(Sh-Hiring of JCB for removal of slips etc.) Job No. 17 | | | | Estimated Cost :- Rs 99,000.00 | | |
| | | | | Earnest money :- Rs 2,000.00 | | |
| | | | | Time: One month | | |
| Sr.No. | Sub Head and Items of Work | Qty. | | Rate | | Amount |
| 1 | 2 | 3 | | In figure | In words | 6 |
| 1.00 | Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 meters and lead upto 1000 meters as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer in charge. | 99.00 | Hours | 1000.00 | Rupees One thousand and paisenil Only | Per Hours |
| | | | | | | 99000.00 |
| | | | | | | Total 99000.00 |


 Executive Engineer
 Arki Division (B&R)
 HP. PWD. Arki.

| SCHEDULE OF QUANTITY | | | | | | | |
|--|---|-------|-------|-----------|---------------------------------------|-----------|----------|
| Name of Work:-Restoration of rain Damages on various roads under kunihar sub division under Jainagar section.(Sh-Hiring of JCB for removal of slips etc.) Job no. 18 | | | | | Estimated Cost :- Rs 99,000.00 | | |
| | | | | | Earnest money :- Rs 2,000.00 | | |
| | | | | | Time: One month | | |
| Sr.No. | Sub Head and Items of Work | Qty. | | Rate | | Unit | Amount |
| 1 | 2 | 3 | | In figure | In words | 6 | 7 |
| 1.00 | Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 meters and lead upto 1000 meters as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer in charge. | 99.00 | Hours | 1000.00 | Rupees One thousand and paisenil Only | Per Hours | 99000.00 |
| | | | | | | Total | 99000.00 |


 Executive Engineer
 Arki Division (B&R)
 HP. PWD. Arki.

| SCHEDULE OF QUANTITY | | | | | | Estimated Cost: -Rs1,43,715/- only | |
|--|---|--------|---------|---|--------|------------------------------------|--|
| Name of Work:-Extension of Stage & Pre-Painted Sheet Roofing Over Stage at GHS Mangrud Tehsil Arki, Distt. Solan, H.P.(SH:- Providing & Fixing Roofing on Stage in GHS Mangrud) DMFT Deposit | | | | | | Earnest Money :-Rs3,000/-Only | |
| Sub head and items of work | | | | | | Time :-One Month | |
| S. No. | 2 | Qty. | Rate In | Unit | Amount | | |
| | | | Figure | Words | | | |
| | | 3 | 4 | 5 | 6 | | |
| 1 | Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge | 0.85 | 171.40 | Rupees One hundred seventy one and paise forty only | P.Cum. | 146 | |
| 2 | Providing and laying cement concrete work 1:2:4 (one cement : two sand : four graded stone aggregate 20mm nominal size) mechanically mixed and compecting with vibrator and curing complete excluding cost of form work and reinforced concrete work including carriage of materials within all leads and lifts and as per the direction of Engineer-In-Charge | 0.85 | 5954.35 | Rupees five thousand nine hundred fifty four and paise thirty five only | P.Cum. | 5061 | |
| 3 | Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge . | 811.20 | 86.65 | Rupees eighty six and paise sixty five only | P.Kg | 70290 | |
| 4 | Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces) including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge . | 30.00 | 837.30 | Rupees eight hundred thirty seven and paise thirty only | P.Sqm. | 25119 | |
| 5 | Providing ridges or hips of width 60 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete 0.63 mm thick with zinc coating not less than 275 gm/m ² carriage of materials in all leads and lifts and as per the direction of Engineer-in-Charge. | 4.10 | 550.90 | Rupees five hundred fifty and paise ninty only | P.Rmt | 2259 | |
| 6 | Providing and fixing M.S. B.P. sheet 1.66 to 2 mm thick in eaves board / facia / soffits / ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete (Base members of steel work shall be measured & paid separately) as per HP. PWD. Specifications of 1990 vplume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge. | 24.60 | 1660.15 | Rupees One thousand six hundred sixty and paisa fifteen only | P.Sqm | 40840 | |
| | | | | | Total | 143715 | |

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


Executive Engineer
Arki Division HPPWD
Arki .

Job No 6

SCHEDULE OF QUANTITY

Name of Work:- (1) C/o Link Road from Piplught to Village Pather Km 0/00 to 1/300, (2) C/o Link Road Village Sokhar Km 0/00 to 0/600, (3) C/o Link Road to Village Kyari Km 0/00 to 0/300. (SH:-Jeepable to Moterale Road (1) Km 0/090 to 0/150, (2) Km 0/00 to 0/090, and (3) Km 0/165 to 0/270) (VKVNY Deposit)

Estimated Cost: -Rs 1,49,776/- only

Earnest Money :-Rs3,000/-Only

Time :- One Month

| S.No. | Sub head and items of work | Qty. | Unit | Rate | | Amount |
|-------|--|--------|--------------|--------|--|--------|
| | | | | Figure | Words | |
| 1 | Excavation in earthwork in hilly area by mechanical means all hights and depth, in all kind of soil including saturated soil comprising of mixed soil , ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution , etc. and to protect stabality of hill side . Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in - Charges, in conformity with the requirement of technical specification for Rural Road, August 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation wothd including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut matereial inspecified manner, tremming, filling of unevenness, blindage and finishing of the road to specified dimensions or as dirrcted by the Engineer-in -Charge for smooth riding. The recovery of useful stone that is 16.82 cubic meter in all cases falling which recovery @ Rupees 300/- only (Rupees three hundereed only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. | 841.20 | Per. Cum. | 178.05 | Rupees one hundred seventy eight and paise five only . | 149776 |
| | | | | | Total | 149776 |

Quoted Rate in figure :

Quoted Rate in words:

- sd -
Executive Engineer
Arki Division,
HPPWD, Arki

| SCHEDULE OF QUANTITY | | | | | | |
|---|---|---------|--------------|-------------------------------------|---|--------|
| Name of Work:- C/o Link Road from Jabloo Kanswala to Village Khata G.P. Rouri Km 0/00 to 1/500 (SH:- F/C in Km 0/00 to 0/315) DMFT Deposit | | | | Estimated Cost: -Rs 4,90,412/- only | | |
| | | | | Earnest Money :-Rs10,000/-Only | | |
| | | | | Time :- One Month | | |
| S.No. | Sub head and items of work | Qty. | Unit | Rate | | Amount |
| | | | | Figure | Words | |
| 1 | Excavation in earthwork in hilly area by mechanical means all hights and depth, in all kind of soil including saturated soil comprising of mixed soil , ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution , etc. and to protect stability of hill side . Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in - Charges, in conformity with the requirement of technical specification for Rural Road, August 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut material in specified manner, dressing, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in -Charge for smooth riding. The recovery of useful stone that is 172.98 cubic meter in all cases falling which recovery @ Rupees 300/- only (Rupees three hundred only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. | 2692.50 | Per. Cum. | 182.14 | Rupees one hundred eighty two and paise fourteen only | 490412 |
| | | | | | Total | 490412 |

Quoted Rate Percentage in Figure
Quoted Rate Percentage in Words


Executive Engineer
B&R Division HPPWD
Arki

| SCHEDULE OF QUANTITY | | | | | Estimated Cost: -Rs 99,540/- only | |
|--|--|-------|---------|---|-----------------------------------|--------|
| Name of Work:- C/o Govt. Degree College Darlaght.(SH:- P/L Boulder Apron Wire Crate in front of Building (Balance work)) | | | | | Earnest Money :- Rs2,000/-Only | |
| | | | | | Time :-One Month | |
| S. No. | Sub head and items of work | Qty. | Rate In | | Unit | Amount |
| | | | Figure | Words | | |
| 1 | 2 | 3 | 4 | 5 | 6 | |
| 5 | P/L of boulder apron laid in wire crates with 4mm dia GI wire confirming to IS:280 and IS:4826 in 100mmx100mm mesh(woven diagonally including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25Kg each as per drawing and clause 1301. technical specifications with in all leads & lifts, and as per direction of Engineer-in-charge. | 33.60 | 2962.50 | Rupees two thousand nine hundred sixty two and paise fifty only | P.Cum. | 99540 |
| | | | | | Total | 99540 |

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

Name of work:-R/R damage on Bathalang - Bara - Tamred road km. 0/00 to 3/00 (SH:-C/O B/wall at RD 0/210 to 0/221.30)

SCHEDULE OF QUANTITY

Estimated Cost:-Rs.-99337/-only


Earnest Money:-Rs.-2000/-only

Time - one Month

| S. No. | Sub head and items of work | Qty. | Rate | Unit | Amount |
|--------|--|-----------|--------------------|---|---------------------------|
| 1 | 2 | 3 | In figure In words | 6 | 7 |
| 1 | Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge | 17.02 Cum | 171.40 | Rupees one hundred seventy one and paise fourty only | Per cubic metre 2917.00 |
| 2 | Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803, 1202 & 1203 including carriage of materials upto all leads and lifts.(i) 1:5:10 (40mm). | 21.28 Cum | 4390.60 | Rupees four thousand three hundred ninty and paise sixty only | Per cubic metre 93431.00 |
| 3 | Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts. | 10.90 Rmt | 274.25 | Rupees two hundred seventy four and paise twenty five only | Per running metre 2989.00 |
| | | | | Total:- | 99337.00 |


Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


Executive Engineer,
B&R Division HPPWD
Arki.

| SCHEDULE OF QUANTITY | | | | | Estimated Cost: -Rs98978/- only | |
|---|--|-------|---------|--|---------------------------------|--------|
| Name of Work:- Restoration of Rain Damages on Bathalang Bara Tamred road km 0/00 to 3/00 {SH:- C/O R/Wall at RD 0/327 to 0/341} | | | | | Earnest Money :-Rs2000/-Only | |
| | | | | | Time :-One Month | |
| S. No. | Sub head and items of work | Qty. | Rate In | | Unit | Amount |
| | | | Figure | Words | | |
| 1 | 2 | 3 | 4 | 5 | 6 | |
| 1 | Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge | 8.40 | 171.40 | Rupees one hundred seventy one and paise forty only | P.Cum. | 1440 |
| 2 | Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge | 19.60 | 4390.60 | Rupees four thousand three hundred ninety and paise sixty only | P.Cum. | 86056 |
| 3 | Backfilling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge | 7.56 | 1203.30 | Rupees one thousand two hundred three and paise thirty only | P.Cum. | 9097 |
| 4 | Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge | 8.70 | 274.25 | Rupees two hundred seventy four and paise twenty five only | Rmt | 2386 |
| | | | | | Total | 98978 |

Quoted Rate Percentage in Figure
Quoted Rate Percentage in Words



Executive Engineer
Arki Division HPPWD
Arki

| SCHEDULE OF QUANTITY | | | | | | | |
|---|---|--------|-----|-----------|--|-------------------|-----------|
| Name of work :-R/R damages on Kunihar Bainjkihatti Selli Brampukhar Road portion Km 39/00 to 56/200 and Jamli to Jainagar road UNDER PDNA-2023.(SH:-C/O of Retaining wall at RD 50/475 to 50/486.50 etc.) | | | | | Estimated Cost :- Rs 4,99,081.00 | | |
| | | | | | Earnest money :- Rs 10,000.00 | | |
| | | | | | Time: One month | | |
| Sr.No. | Sub Head and Items of Work | Qty. | | Rate | | Unit | Amount |
| 1 | 2 | 3 | | In figure | In words | 6 | 7 |
| 1.00 | Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In- Charge | 39.44 | Cum | 171.40 | Rupees One Hundred Seventy One and Forty paise Only | Per cubic metre | 6760.00 |
| 2.00 | Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 milimetre(forty milimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge. | 105.80 | Cum | 4390.60 | Rupees Four Thousand Three Hundred Ninety and Sixty paise Only | Per cubic metre | 464525.00 |
| 3.00 | Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge. | 10.92 | Cum | 1203.30 | Rupees One Thousand Two Hundred Three and Thirty paise Only | Per cubic metre | 13140.00 |
| 4.00 | Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)milimetre dia PVC pipe extending through the full width of the structures with slop of 1(v):20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge. | 53.44 | Rmt | 274.25 | Rupees Two Hundred Seventy Four and Twenty Five paise Only | Per running metre | 14656.00 |
| | | | | | | Total | 499081.00 |

Material will be procured by the contractor himself and bills will be submitted to the nearest HP Civil Supply Depot.

Conditions:- (i) All the material will be procured by the contractor himself and bills will be submitted.(ii) The cement will be procured by the contractor from the nearest HP Civil Supply Depot.

Quoted Rate Percentage in Figures
Quoted Rate Percentage in Words


Executive Engineer
Arki Division (B&R)
HP. PWD. Arki.

SCHEDULE OF QUANTITY

Name of Work:- C/o Link Road from Samana Paza to Kaldwar Km 0/00 to 2/450 (SH:- F/C in Km 0/00 to 0/945) DMFT Deposit

Estimated Cost: -Rs 4,91,068/- only


Earnest Money :-Rs10,000/-Only

Time :- One Month

| S.No. | Sub head and items of work | Qty. | Unit | Rate | | Amount |
|-------|---|---------|--------------|--------|---|--------|
| | | | | Figure | Words | |
| 1 | Excavation in earthwork in hilly area by mechanical means all hights and depth, in all kind of soil including saturated soil comprising of mixed soil , ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution , etc. and to protect stabality of hill side . Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in - Charges, in conformity with the requirement of technical specification for Rural Road, August 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut material in specified manner, dressing, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in -Charge for smooth riding. The recovery of useful stone that is 131.98 cubic meter in all cases falling which recovery @ Rupees 300/- only (Rupees three hundred only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. | 2505.45 | Per. Cum. | 196.00 | Rupees one hundred ninety six and paise zero only . | 491068 |
| | | | | | Total | 491068 |

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 B&R Division HPPWD
 Arki

| SCHEDULE OF QUANTITY | | | | | | Estimated Cost :-Rs4,99,553/- only | |
|--|--|--------|---------|--|--------|------------------------------------|--|
| Name of Work:-R/R Damages on Kunihar Bainj-Ki-Hatti-Seli Brampukhar Road Km 11/00 to 39/00.(SH:- C/o R/wall at Rd 34/160 to 34/177) (Balance work under PDNA) | | | | | | Earnest Money :-Rs10,000/-Only | |
| | | | | | | Time :-One Month | |
| S. No | Sub head and items of work | Qty. | Rate In | | Unit | Amount | |
| 1 | 2 | | Figure | Words | 5 | 6 | |
| 1 | Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge | 61.32 | 171.40 | Rupees One hundred seventy one and paise forty only | P.Cum. | 10510 | |
| 2 | Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge | 107.73 | 4390.60 | Rupees four thousand three hundred ninety and paise sixty only | P.Cum. | 472999 | |
| 3 | Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge | 58.50 | 274.25 | Rupees two hundred seventy four and paise twenty five only | P.Rmt | 16044 | |
| | | | | | Total | 499553 | |

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

| SCHEDULE OF QUANTITY | | | | | | Estimated Cost: -Rs474697/- only | |
|---|--|-------|---------|--|--------|----------------------------------|--|
| Name of Work:- C/O of Link road from Karoda to Nouni road km 0/00 to 1/500 [SH:- C/O R/ Wall at RD 0/910 to 0/932] DMFT Deposit | | | | | | Earnest Money :-Rs9500/-Only | |
| S. No. Sub head and items of work | | | | | | Time :-One Month | |
| 1 | 2 | Qty. | Rate In | | Unit | Amount | |
| | | | Figure | Words | | | |
| 3 | 4 | 5 | 6 | | | | |
| 1 | Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge | 48.62 | 171.40 | Rupees one hundred seventy one and paise fourty only | P.Cum. | 8333 | |
| 2 | Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge | 96.36 | 4390.60 | Rupees four thousand three hundred ninety and paise sixty only | P.Cum. | 423078 | |
| 3 | Backfilling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge | 26.40 | 1203.30 | Rupees one thousand two hundred three and paise thirty only | P.Cum. | 31767 | |
| 4 | Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge | 42.00 | 274.25 | Rupees two hundred seventy four and paise twenty five only | Rmt | 11519 | |
| | | | | | Total | 474697 | |

Quoted Rate Percentage in Figure
Quoted Rate Percentage in Words


Executive Engineer
Arki Division HPPWD
Arki

| SCHEDULE OF QUANTITY | | | Estimated Cost: -Rs3,87,830/- only | | | |
|---|--|-------|------------------------------------|--|--------|--------|
| Name of Work:-C/o Link Road Animal Husbandry Darla to Kotla Numhal Kotla Pujaria Datti Shiv Nagar Road Km 0/00 to 4/500(SH:- C/o B/wall H/o Sh.Het Ram at Rd 0/080 to 0/090,1/00 to 1/035 and F/C in Km 0/280 to 1/035.) DMFT Deposit | | | Earnest Money -Rs8,000/-Only | | | |
| | | | Time :-One Month | | | |
| S. No | Sub head and items of work | Qty | Rate In | | Unit | Amount |
| 1 | 2 | | Figure | Words | 5 | 6 |
| 1 | Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge | 62.10 | 171.40 | Rupees One hundred seventy one and paise forty only | P.Cum. | 10644 |
| 2 | Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts, and as per the direction of Engineer-In- Charge | 81.00 | 4390.60 | Rupees four thousand three hundred ninety and paise sixty only | P.Cum. | 355639 |
| 3 | Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge | 32.80 | 274.25 | Rupees two hundred seventy four and paise twenty five only | P.Rmt | 8995 |
| 4 | Excavation in earthwork in hilly area by mechanical means all hights and depth, in all kind of soil including saturated soil comprising of mixed soil , ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution , etc. and to protect stabality of hill side . The recovery of useful stone that is 5.64 cubic meter in all cases falling which recovery @ Rupees 300/- only (Rupees three hundereed only) per cubic metre shall be effected on prorata basis.Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. | 70.50 | 178.05 | Rupees one hundred seventy eight and paise five only | P.Cum. | 12553 |
| | | | | | Total | 387830 |

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


Executive Engineer
Arki Division HPPWD
Arki

| SCHEDULE OF QUANTITY | | | | | Estimated Cost: -Rs197630/- only | |
|--|--|-------|---------|--|----------------------------------|--------|
| Name of Work:- C/O Link road from Chandi Rudal Harsangdhar road km 0/00 to 8/330 | | | | | Earnest Money :-Rs4000/-Only | |
| [SH:- C/O R/Wall at RD 8/316 to 8/321.50] | | | | | Time :-One Month | |
| S. No. | Sub head and items of work | Qty. | Rate In | | Unit | Amount |
| 1 | 2 | 3 | Figure | Words | 5 | 6 |
| 1 | Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge | 16.34 | 171.40 | Rupees one hundred seventy one and paise fourty only | P.Cum. | 2801 |
| 2 | Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge | 40.10 | 4390.60 | Rupees four thousand three hundred ninety and paise sixty only | P.Cum. | 176063 |
| 3 | Backfilling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge | 11.22 | 1203.30 | Rupees one thousand two hundred three and paise thirty only | P.Cum. | 13501 |
| 4 | Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge | 19.20 | 274.25 | Rupees two hundred seventy four and paise twenty five only | Rmt | 5266 |
| | | | | | Total | 197630 |

Quoted Rate Percentage in Figure
Quoted Rate Percentage in Words


Executive Engineer
Arki Division HPPWD
Arki

| SCHEDULE OF QUANTITY | | | | | | Estimated Cost: -Rs 4,32,680/- only | |
|--|--|--------|---------|---|--------|-------------------------------------|--|
| Name of Work:- C/o Link Road from Siharli to Sakor Km 0/00 to 4/200.(SH:- Surface dressing, Kharnja soling, P.C.C. 1:4:8, P.C.C. 1:2:4 and side drain at RD 2/920 to 3/045.) DMFT Deposit | | | | | | Earnest Money :- Rs9,000/-Only | |
| | | | | | | Time :-One Months | |
| S. No. | Sub head and items of work | Qty. | Rate In | | Unit | Amount | |
| | | | Figure | Words | | | |
| 1 | 2 | 3 | 4 | 5 | 6 | | |
| 1 | Surface dressing of Ground including removing of Vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. all kinds of soil and as directed by Engineer-In- Charge | 387.50 | 14.00 | Rupees fourteen and paise zero only | P.Sqm. | 5425 | |
| 2 | Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) and as directed by Engineer-In- Charge | 38.75 | 1425.25 | Rupees one thousand four hundred twenty five and paise twenty five only | P.Cum. | 55228 | |
| 3 | Providing and Laying concrete for plain/reinforced concrete 1:4:8 (one cement : four sand: eight graded stone aggregate 40mm (fourty millimeter) nominal size in open foundations and curing complete including cost of form work plain/ reinforced concrete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials within all leads and lifts . The rate including octroi, royalty, malkhana, toll tax sale tax or other taxes imposed by the Government. | 29.06 | 4955.20 | Rupees four thousand nine hundred fifty five and paise twenty only | P.Cum. | 143998 | |
| 4 | Providing and laying cement concrete work 1:2:4 (one cement : two sand : four graded stone aggregate 20mm nominal size) mechanically mixed and compecting with vibrator and curing complete excluding cost of form work and reinforced concrete work including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge . | 29.06 | 5954.35 | Rupees five thousand nine hundred fifty four and paise thirty five only | P.Cum. | 173033 | |
| 5 | Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge | 31.25 | 171.40 | Rupees One hundred seventy one and paise fourty only | P.Cum | 5356 | |
| 6 | Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202 &1203 including carriage of materials in all leads and lifts. a)P.C.C 1:3:6.(1 Cement :3 sand : 6 Agg. 20mm nominal Size) i/c carriage of material within all leads & lifts As per the direcion of Engineer In-Charge. | 9.38 | 5291.95 | Rupees. five thousand two hundred ninety one and paise ninety five only | P.Cum. | 49638 | |
| | | | | | Total | 432680 | |

Quoted Rate Percentage in Figure
Quoted Rate Percentage in Words


Executive Engineer
Arki Division HPPWD
Arki