Office of the
Executive Engineer
UnaDivision, HP PWD Una
Tel: +911975226036,
E-mail: ee-una-hp@nic.in

No.PWU/CB//TA/Tender/2025-26/- 8846-55 **Dated** 13/02/2026

To

The Executive Engineer (IT) Cell,
Nirman Bhawan, Nigam Vihar,
Shimla-171002.

Subject: - Regarding publication of Tenders Notice.

Sir,

"JAI HIND"

Enclosed please find herewith Tenders Notice along with Schedule of Quantities for uploading the same on Departmental website as per Notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B) A(3)1/2024 dated Shimla-2 the 03.01.2025 as the work mentioned in the Tender Notice are urgent in nature and in Public interest. This is for your kind information and necessary action at your end please.

DA:-As above.

Executive Engineer,
Bharwain , Division,
HPPWD, Bharwain

Copy along with its enclosures is forwarded to the following for favour of information please:-

1. The Superintending Engineer, 15th Circle, HPPWD, Una.
2. All the Assistant Engineer, working under this Division.
3. All the Head of Branches in this office.
4. Notice Board.

Executive Engineer,
Bharwain , Division,
HPPWD, Bharwain

Scanned with OKEN Scanner

Certificate

Certified that the tenders called vide this office letter No.PWU/CB/TA/Tender Notice 2025-26 :- 8846-55 dated 13/02/2026 emergent nature and in Public interest.

Executive Engineer,
Bharwain , Division,
HPPWD, Bharwain

Scanned with OKEN Scanner

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDERS"

Sealed Percentage rate tender on PWD Form No. 6 & 8 are hereby invited by the Executive Engineer, Bharwain Division HPPWD Bharwain H.P. on behalf of Governor of H.P for the following works from the approved and eligible contractors/ firms enlisted in PWD Department so as to reach in this office and opened as per time schudle given below.The offer of the tender will be kept open for 75 days from the date of opening of the tenders.

Date and time of receipt of applications for the tender form;- 21-02-2026(upto 02.00 P.M.)

Date of time issue/sale of tender forms against cash payment:- 21-02-2026(3.00 to 5.00 PM)

Date and time of receipt of tenders:- 23-02-2026 (upto 11.00 AM)

Date and time of opening of tenders:- 23-02-2026 at 11.30 AM

The earnest money in the shape of F.D.Rs if any of the Nationalized Bank in H.P. duly pledged in the favour of the Executive Engineer, Bharwain Division HPPWD Bharwain , will be received alongwith the applications for obtaining tender forms. The applications received without earnest money shall summarily be rejected. The Executive Engineer reserves the right to reject any tender without assigning any reason. The conditional / telegraphic tenders shall also be rejected. The scope of the work can be increased/ decreased without any Notice.

Sr. No	Name of work	Estimate Amount	Earnest Money	Time	Cost of tender	Eligible class of contractor
1	Repair / Restoration on link road Haria ka Talab to Harizan Basti Dharmshala Mahantan via Patial Basti km 0/0 to 2/450 (SH:- C/O Retaining wall at RD 0/810 to 0/822 & V-Shape drain in km 0/835 to 0/940) Under PDNA-2023.	**4,15,242/-**	**8400/-**	Three months	350/-	Class-C & D
2	Restoration of rain damages on link road to Upper Beher Jaswan km 0/0 to 3/500 (SH:- C/O Retaining wall at RD 2/180 to 2/192.50 RHS) Under PDNA-2023.	**2,55,253/-**	**5200/-**	Three Months	350/-	Class-C & D
3	Restoration of rain damages on link road Karluhi to Mandholi Km 0/0 to 5/500 (SH:- removal of slips filling rain cuts and C/o of unlined drain 0/0 to 2/500)	**99773/-**	**2000/-**	One Month	350/-	Class-C & D
4	Restoration of rain damages on Jawar Maslana Rajpura road km 0/0 to 6/500 (SH:- C/O Retaining wall at RD 3/0 to 3/030 RHS) under PDNA-2023.	**1,91,458/-**	**3900/-**	Three Months	350/-	Class-C & D
5	Restoration of rain damages on link road Amb to Saloi km 0/0 to 6/100 (SH:-C/O Retaining wall at RD 0/520 to 0/550 LHS) Under PDNA-2023	**1,91,453/-**	**3900/-**	Three Months	350/-	Class-C & D
6	Restoration of rain damages on link road from Karluhi to Amban da Padhar via Mathed km 0/0 to 9/0 (SH:- C/O CC Pavement road in km 4/455 to 4/500) Under PDNA-2023	**2,87,844/-**	**5800/-**	Three Months	350/-	Class-C & D
7	Restoration of rain damages on Chowar to Jowar road km 8/570 to 10/075 (SH:- C/O V-Shape drain with berm, Edge wall (LHS) & Repair of Pot hole in km 9/510 to 9/585) Under PDNA-2023.	**4,79,057/-**	**9600/-**	Three Months	350/-	Class-C & D
8	Restoration of rain damages on link road Baruhi to Dumkhar Km 0/0 to 16/00 (SH:- removal of slips filling rain cuts and C/o of unlined drain 0/0 to 2/500)	**98350/-**	**2000/-**	One Month	350/-	Class-C & D
9	Restoration of rain damages on link road Amban Da Paddar to Saloi km 0/0 to 4/315 & link road from Koharchhan to Basantpura km. 0/0 to 2/0 (SH:- C/O Retaining wall in km. 3/330 to 3/348 & C/O CC Pavement in km. 1/235 to 1/257 respectively) under PDNA-2023.	**3,05,723/-**	**6200/-**	Three Months	350/-	Class-C & D

Scanned with OKEN Scanner

10	Balance work for C/O Jeepable road from Jole to Khurwain road to Seri ward No. 4 village Bhagnal Deeraj Distt. Una to Abadi Atma Ram, Vinod Kumar, Hem Raj, Naresh Kumar in G.P. Ambehra (SH:- Providing and Laying 60mm thick C.C. interlocking paver block in km 0/355 to 0/382) Against BASP.	99,316/-	2000/-	Three Months	350/-	Class-C & D
11	A/R & M/O Bharwain Chintpurni Talwara road 0/0 to 15/310(SH:- Providing & installation of computer system with UPS, printer, intercom system.	98500/-	2000/-	One month	350/-	Class-C & D
12	Balance work for C/O Jeepable road from Jole to Khurwain road to Seri ward No. 4 village Bhagnal Deeraj Distt. Una to Abadi Atma Ram, Vinod Kumar, Hem Raj, Naresh Kumar in G.P. Ambehra (SH:- Providing and Laying 60mm thick C.C. interlocking paver block in km 0/382 to 0/400) Against BASP.	99379/-	2000/-	Three Months	350/-	Class-C & D

TERM & CONDITIONS: -

1. The contractor/ firms should be registered as or/ dealer under HP Sales Tax Act, 1968 and also produce Sale Tax clearance certificate from the Excise and Taxation Department, GST No. and Permanent account No. (PAN No.).
2. The intending contractors/ firms shall have to produce the copy of latest enlistment and renewal enlisted in HP: PWD.
3. The contractor/firms are required to quote their rates clearly both in words as well as in figures, failing which the Executive Engineer reserve the right to accept/ reject any or all tenders.
4. The conditional / ambiguous/ telegraphic tenders or tender by fax shall not entertain/ considered in any case
5. No payment will be made to the contractor/ firms for damage caused by flood, rain, local disturbance, war, epidemic or either natural calamities during execution of work and no such claim on this account will be entertained.
6. Security shall be released after 1 year from the date of completion of work provided no defect certificate is issued by the Engineer-in-charge.
7. The Executive Engineer has right to accept or reject any or all the tender without assigning any reason.
8. Any material left at site one month after completion of work shall become the property of the department and no payment shall be made to the contractor for the material.
9. A sign Board ``Men at work / work in progress `` shall be placed `` by Contr. At least 200-150 meters ahead or places / roads where road are under repair / construction.
10. The tender shall be issued to those contractors/ firms who have not more than two works in hand.
11. Work should be completed by the contractor within stipulated period.

DA Notice inviting tender / Schedule of Quantity and A Certificate.

Executive Engineer
Bharwain Division,
HP: PWD, Bharwain..

Copy is forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP: PWD, Shimla-1.
2. The Chief Engineer, Hamirpur Zone, HP: PWD, Hamirpur.
3. The Superintending Engineer, 15th Circle, HPPWD, Una.
4. All the Assistant Engineers under this Division.
5. All the Head of the Branches in this office.
6. The Notice Board.

Executive Engineer
Bharwain Division,
HP: PWD, Bharwain

Scanned with OKEN Scanner

Schedule of Quantity

Estimated Cost:- 415242/-
Earnest Money:- 8400/-
Time:- Three Months

Name of Work:- Repair / Restoration on link road Haria ka Talab to Harizan Basti Dharmshala Mahantan via Patial Basti km 0/0 to 2/450 (SH:- C/O Retaining wall at RD 0/810 to 0/822 & V-Shape drain in km 0/835 to 0/940) Under PDNA-2023.

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
1	Excavation in earth work in foundation and trenches eteetera in all kind and classification of soil such as pick work, jumper work, pick jumper work, blasting work and hard blasting work and saturated soil any other mixed verity of soil in dry or saturated condition upto any depth and lift upto any height including chiseling/wedging out rocks where blasting prohibited dewatering pumping or bailing out water where required and/ removal of slush seprately as directed which may arise during the execution including stacking the serviceable and unserviceable material and then returning stacked soil in any thickness of layers when required into plinth side of foundation eteetera consolidating each deposited layers by ramming and watering then disposing of all surplus unserviceable excavated earth as specified dumping place as per CPWD specifications 2019 complete and direction of Engineer in- charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	45.40	cum	180.00	Rs. One hundred eighty and paise zero only	Per Cubic metre	8172
2	Providing and laying in position cement concrete 1:4:8(one cement: four sand: eight graded/crushed stone aggregate 40mm (forty miillmeter) nominal size mechanically mixed and vibrated curing complete including cost of centering and shuttering in Retaining wall / Breast wall as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of material/ machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	59.38	Cum	3750.00	Rs. Three thousand seven hundred fifty and paise zero only	Per cubic metre	222675
3	Providing weepholes in brick masonry stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeters) dia PVC pipe OF MAKE D-PLAST/POLY.having pressure of 4.5 kg per square meter extending through the full width of the structures with slope of 1(V):20(H) (one vertical: twenty horizontal) towards drawing face complete as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes	20.00	Number	250.00	Rs. Two hundred fifty and paise zero only	Each	5000
4	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing and direction of Engineer in charge including carriage of materials machinery required to execute the work as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi, royality, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	14.30	Cum	650.00	Rs. Six hundred fifty and paise zero only	Per Cubic metre	9295

Scanned with OKEN Scanner

	Providing and laying in position cement concrete 1:3:6 (one cement : three sand: six graded/crushed stone aggregate 20 mm (twenty millimeter) nominal size mechanically mixed and curing complete including cost of centring and shuttering in Retaining wall / Breast wall as per CPWD specifications 2019 complete and direction of Engineer-in- charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials.The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	40.50	Cum	4200.00	Rs. Four thousand two hundred and paise zero only	Per Cubic metre	170100
	Total						**415242**
	Percentage rate (Above or Below)						

Executive Engineer,
Bharwain Division,
HPPWD, Bharwain.

Scanned with OKEN Scanner

Scanned with OKEN Scanner

Job No. 2

Schedule of Quantity

Estimated Cost:- 255253/-
Earnest Money:- 5200/-
Time:- Three Months

Name of Work:- Restoration of rain damages on link road to Upper Beher Jaswan km 0/0 to 3/500 (SH:- C/O Retaining wall at RD 2/180 to 2/192.50 RHS) Under PDNA-2023.

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
1	Excavation in earth work in foundation and trenches etcetera in all kind and classification of soil such as pick work, jumper work, pick jumper work, blasting work and hard blasting work and saturated soil any other mixed verity of soil in dry or saturated condition upto any depth and lift upto any height including chiseling/wedging out rocks where blasting prohibited dewatering pumping or bailing out water where required and/ removal of slush seprately as directed which may arise during the execution including stacking the serviceable and unserviceable material and then returning stacked soil in any thickness of layers when required into plinth side of foundation etcetera consolidating each deposited layers by ramming and watering then disposing of all surplus unserviceable excavated earth as specified dumping place as per CPWD specifications 2019 complete and direction of Engineer-in- charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials.The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	18.75	cum	180.00	Rs. One hundred eighty and paise zero only	Per Cubic metre	3375
2	Providing and laying in position cement concrete 1:4:8(one cement: four sand: eight graded/crushed stone aggregate 40mm (forty miillmeter) nominal size mechanically mixed and vibrated curing complete including cost of centering and shuttering in Retaining wall / Breast wall as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of material/ machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	64.69	Cum	3700.00	Rs. Three thousand seven hundred and paise zero only	Per cubic metre	239353
3	Providing weepholes in brick masonry/ stone masonry, plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeters) dia PVC pipe OF MAKE D-PLAST POLY.having pressure of 4.5 kg per square meter extending through the full width of the structures with slope of 1(V):20(H) (one vertical: twenty horizontal) towards drawing face complete as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials.The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	15.00	Number	250.00	Rs. Two hundred fifty and paise zero only	Each	3750

4	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing and direction of Engineer in charge including carriage of materials/machinery required to execute the work as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi, royality, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	13.50	Cum	650.00	Rs. Six hundred fifty and paise zero only	Per Cubic metre	8775
	Total						**255253**
	Percentage rate (Above or Below)						

Executive Engineer,
Bharwain Division,
HPPWD, Bharwain.

Scanned with OKEN Scanner

Job No-3

SCHEDULE OF QUANTITY

Estimated Cost:-99773/-
Earnest Money:- 2000/-
Time Limit:- One Month

Name of Work:- Restoration of rain Damages on Link road Karluhi to Mandholi km 0/0 to 5/500. (SH:-Removal of slips, filling rain Cuts & C/O Unlined drain km 0/0 to 2/500 at various RD's)

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material upto any lift and lead as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi. royality. Malkana. toll tax, goods service tax. labour cess or other taxes imposed by the Government	570.00	cum	100.00	Rs. One hundred and paise zero only	Per Cubic metre	57000
2	Restoration of rain cuts with soil. moorum gravel or a mixture of these, clearing the loose soil. benching for 300 mm width laying fresh material in layers not exceeding 250mm and campaction with plate compactor of power rammer to restore the original alignment. level and slopes as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi. royality. Malkana. toll tax, goods service tax. labour cess or other taxes imposed by the G ernment	145.50	Cum	195.00	Rs. One hundred ninty five and paise zero only	Per Cubic metre	28373
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades. levels and dimensions excavated material to be used in embankment at site with in any lead and lift as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi. royality. Malkana. toll tax, goods service tax. labour cess or other taxes imposed by the Government.	360.00	Rmt.	40.00	Rs. Forty and paise zero only	Per Running Meter	14400
	Total						99773
	Quoted percent rate in figure						
	Quoted percent rate in Words						

Executive Engineer,
Bharwain Division,
HPPWD Bharwain

Scanned with OKEN Scanner

Job No. 34

Schedule of Quantity

Estimated Cost:- 191458/-
Earnest Money:- 3900/-
Time:- Three Months

Name of Work:- Restoration of rain damages on Jawar Maslana Rajpura road km 0/0 to 6/500 (SH:- C/O Retaining wall at RD 3/0 to 3/030 RHS) under PDNA-2023.

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
1	Excavation in earth work in foundation and trenches etcetera in all kind and classification of soil such as pick work, jumper work, pick jumper work, blasting work and hard blasting work and saturated soil any other mixed verity of soil in dry or saturated condition upto any depth and lift upto any height including chiseling/wedging out rocks where blasting prohibited dewatering pumping or bailing out water where required and/ removal of slush seprately as directed which may arise during the execution including stacking the serviceable and unserviceable material and then returning stacked soil in any thickness of layers when required into plinth side of foundation etcetera consolidating each deposited layers by ramming and watering then disposing of all surplus unserviceable excavated earth as specified dumping place as per CPWD specifications 2019 complete and direction o Engineer-in- charge including carriage of materials/machinery required to xecute the work in all leads and lifts and other incidentials.The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	25.60	cum	180.00	Rs. One hundred eighty and paise zero only	Per Cubic metre	4608
2	Providing and laying in position cement concrete 1:4:8(one cement: four sand: eight graded/crushed stone aggregate 40mm (forty miillmeter) nominal size mechanically mixed and vibrated curing complete including cost of centering and shuttering in Retaining wall Breast wall as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of material/ machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	46.14	Cum	3750.00	Rs. Three thousand seven hundred fifty and paise zero only	Per cubic metre	173025
3	Providing weepholes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeters) dia PVC pipe OF MAKE D-PLAST POLY.having pressure of 4.5 kg per square meter extending through the full width of the structures with slope of 1(V):20(H) (one vertical: twenty horizontal) towards drawing face complete as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials machinery required to execute the work in all leads and lifts and other incidentials.The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	20.50	Number	250.00	Rs. Two hundred fifty and paise zero only	Each	5125

Scanned with OKEN Scanner

	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing and direction of Engineer in charge including carriage of materials/machinery required to execute the work as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi, royality, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	14.50	Cum	600.00	Rs. six thousand and paise zero only	Per Cubic metre	8700
	Total						**191458**
	Percentage rate (Above or Below)						

Executive Engineer,
Bharwain Division,
HPPWD, Bharwain.

Scanned with OKEN Scanner

Job No. 5

Schedule of Quantity

Estimated Cost:-191453/-
Earnest Money:-3900/-
Time Limit:- Three Months

Name of Work:- Restoration of rain damages on link road Amb to Saloi km 0/0 to 6/100 (SH:-C/O Retaining wall at RD 0/520 to 0/550 LHS) Under PDNA-2023.

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
1	Excavation in earth work in foundation and trenches etcetera in all kind and classification of soil such as pick work, jumper work, pick jumper work, blasting work and hard blasting work and saturated soil any other mixed verity of soil in dry or saturated condition upto any depth and lift upto any height including chiseling/wedging out rocks where blasting prohibited dewatering pumping or bailing out water where required and removal of slush seprately as directed which may arise during the execution including stacking the serviceable and unserviceable material and then returning stacked soil in any thickness of layers when required into plinth side of foundation etcetera consolidating each deposited layers by ramming and watering then disposing of all surplus unserviceable excavated earth as specified dumping place as per CPWD specifications 2019 complete and direction of Engineer-in- charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials.The rate includ octroi , royality , Malkhana , toll t.., goods service tax , labour cess or other taxes imposed by the Govt.	27.90	cum	180.00	Rs. One hundred eighty and paise zero only	Per Cubic metre	5022
2	Providing and laying in position cement concrete 1:4:8(one cement: four sand: eight graded/crushed stone aggregate 40mm (forty miillmeter) nominal size mechanically mixed and vibrated curing complete including cost of centering and shuttering in Retaining wall / Breast wall as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of material/ machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	47.74	Cum	3650.00	Rs. Three thousand six hundred fifty and paise zero only	Per cubic metre	174251
3	Providing weepholes in brick masonry stone masonry, plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeters) dia PVC pipe OF MAKE D-PLAST/POLY.having pressure of 4.5 kg per square meter extending through the full width of the structures with slope of 1(V):20(H) (one vertical: twenty horizontal) towards drawing face complete as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials.The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by	25.20	Number	250.00	Rs. Two hundred fifty and paise zero only	Each	6300

Scanned with OKEN Scanner

4	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing and direction of Engineer in charge including carriage of materials/machinery required to execute the work as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi, royality, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	9.80	Cum	600	Rs. Six hundred and paise zero only	Per Cubic metre	5880
	Total						**191453**
	Percentage rate (Above or Below)						

Executive Engineer,
Bharwain Division,
HPPWD, Bharwain.

Scanned with OKEN Scanner

Job No. 6

Schedule of Quantity

Estimated Cost:-287844/-
Earnest Money:-5800/-
Time Limit:- Three Months

Name of Work:- Restoration of rain damages on link road from Karluhi to Amban da Padhar via Mathed km 0/0 to 9/0 (SH:- C/O CC Pavement road in km 4/455 to 4/500) Under PDNA-2023.

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
1	Excavation in earth work in foundation and trenches etcetera in all kind and classification of soil such as pick work, jumper work, pick jumper work, blasting work and hard blasting work and saturated soil any other mixed verity of soil in dry or saturated condition upto any depth and lift upto any height including chiseling/wedging out rocks where blasting prohibited dewatering pumping or bailing out water where required and/ removal of slush seprately as directed which may arise during the execution including stacking the serviceable and unserviceable material and then returning stacked soil in any thickness of layers when required into plinth side of foundation etcetera consolidating each deposited layers by ramming and watering then disposing of all surplus unserviceable excavated earth as specified dumping place as per CPWD specifications 2019 complete and direction of Engineer-in- charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials.The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	28.69	cum	180.00	Rs. One hundred eighty and paise zero only	Per Cubic metre	5164
2	Providing and laying in position cement concrete 1:4:8(one cement: four sand: eight graded/crushed stone aggregate 40mm (forty miillmeter) nominal size mechanically mixed and vibrated curing complete including cost of centering and shuttering in Retaining wall / Breast wall as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of material/ machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	19.10	Cum	3750.00	Rs. Three thousand seven hundred fifty and paise zero only	Per cubic metre	71625
3	Providing and laying in position cement concrete 1:3:6 (one cement : three sand: six graded/crushed stone aggregate 20 mm (twenty millimeter) nominal size mechanically mixed and curing complete including cost of centring and shuttering in Retaining wall / Breast wall as per CPWD specifications 2019 complete and direction of Engineer-in- charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials.The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	5.85	Cum	4200.00	Rs. Four thousand two hundred and paise zero only	Per Cubic metre	24570

Scanned with OKEN Scanner

4	Providing and laying in position cement concrete 1:1.5:3 (one cement one point five sand: three graded/crushed stone aggregate 40mm (forty millimeter) nominal mix including cost of form work in foundation and plinth as per CPWD specifications 2019 complete and direction of Engineer-in- charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials.The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	28.69	Cum	6500.00	Rs. Six thousand five hundred and paise zero only	Per Cubic metre	186485
	Total						**287844**
	Percentage rate (Above or Below)						

Executive Engineer,
Bharwain Division,
HPPWD, Bharwain.

Scanned with OKEN Scanner

Job No. 7

Schedule of Quantity

Estimated Cost:-479057/-
Earnest Money:- 9600/-
Time Limit:- Three Months

Name of Work:- Restoration of rain damages on Chowar to Jowar road km 8/570 to 10/075 (SH:- C/O V-Shape drain with berm, Edge wall (LHS) & Repair of Pot hole in km 9/510 to 9/585) Under PDNA-2023.

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
1	Excavation in earth work in foundation and trenches etcetera in all kind and classification of soil such as pick work, jumper work, pick jumper work, blasting work and hard blasting work and saturated soil any other mixed verity of soil in dry or saturated condition upto any depth and lift upto any height including chiseling/wedging out rocks where blasting prohibited dewatering pumping or bailing out water where required and/ removal of slush seprately as directed which may arise during the execution including stacking the serviceable and unserviceable material and then returning stacked soil in any thickness of layers when required into plinth side of foundation etcetera consolidating each deposited layers by ramming and watering then disposing of all surplus unserviceable excavated earth as specified dumping place as per CPWD specifications 2019 complete and direction of Engineer-in- charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials.The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	87.75	cum	180.00	Rs. One hundred eighty and paise zero only	Per Cubic metre	15795
2	Providing and laying in position cement concrete 1:3:6 (one cement : three sand: six graded/crushed stone aggregate 20 mm (twenty millimeter) nominal size mechanically mixed and curing complete including cost of centring and shuttering in Retaining wall Breast wall as per CPWD specifications 2019 complete and direction of Engineer-in- charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials.The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt	81.00	Cum	4200.00	Rs. Four thousand two hundred and paise zero only	Per Cubic metre	340200
3	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM)specification including premixing the material with water at OMC in for all leads and lifts, laying in uniform layers in sub-base base course on well prepared surface and compacting with vibratory roller of 8 (eight) to 10 (ten) tonne capacity to achievethe desired density, complete as per specifications and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi, royality, Malkana, toil tax, goods service tax, labour cess or other taxes imposed by the Government.	27.57	Cum	1650.00	Rs. One thousand six hundred fifty and paise zero only	Per cubic metre	45491
4	Providing and applying tack coat using bitumen emulsion @ 0.40 kg sqm (at the rate of zero point forty kilogram per Sequare metre) conforming to IS 8887, using emulsion pressure distributer including preparing the surface & cleaning with mechanical broom and as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi, royality, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	183.79	Sqm	30.00	Rs. Thirty and paise zero only	Per Sqare metre	5514

Scanned with OKEN Scanner

5	Repair to pot holes and removal of loose mateial, trimming of sides, cleaning of surface by providing tack coat with bitumen VG-10 @ 3 kg per ten square metre , 20mm thick premix carpet with 0.27 cubic metre of stone aggregate mixed with bitumen VG-10 @ 14.6 kg (fourteen point six kilogram) per ten square metre and seal coat type B with 0.06 cubic metre fine aggregate mixed with bitumen VG-10 @ 6.8 kg (six point eight kilogram) per ten square metre of road surface as per specification Clause 1904.2 including carriage of materials within all leads and lifts and other incidentals . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	240.19	Sqm	300.00	Rs. Three hundred and paise zero only	Per Sqare metre	72057
	Total						**479057**
	Percentage rate (Above or Below)						

Executive Engineer,
Bharwain Division,
HPPWD, Bharwain.

Scanned with OKEN Scanner

Job No:- 8

SCHEDULE OF QUANTITY

Estimated Cost:-98350/-
Earnest Money:- 2000/-
Time Limit:- One Month

Name of Work:- Restoration of rain Damages on Baruhi to Dumkhar km 0/0 to 16/0 (SH:-Removal of slips, filling rain Cuts & C/O Unlined drain km 10/0 to 11/0 at various RD's)

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material upto any lift and lead as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi, royality, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government	660.00	cum	100.00	Rs. One hundred and paise zero only	Per Cubic metre	66000
2	Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300 mm width laying fresh material in layers not exceeding 250mm and campaction with plate compactor of power rammer to restore the original alignment, level and slopes as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi, royality, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government	90.00	Cum	195.00	Rs. One hundred ninty five and paise zero only	Per Cubic metre	17550
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions excavated material to be used in embankment at site with in any lead and lift as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi, royality, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	370.00	Rmt.	40.00	Rs. Forty and paise zero only	Per Running Meter	14800
	Total						**98350**
	Quoted percent rate in figure						
	Quoted percent rate in Words						

Executive Engineer,
Bharwain Division,
HPPWD Bharwain

Scanned with OKEN Scanner

Job No. 9

Schedule of Quantity

Estimated Cost:- 305723/-
Earnest Monry:-6200/-
Time:- Three Months

Name of Work:- Restoration of rain damages on link road Amban Da Paddar to Saloi km 0/0 to 4/315 & link road from Koharchhan to Basantpura km. 0/0 to 2/0 (SH:- C/O Retaining wall in km. 3/330 to 3/348 & C/O CC Pavement in km. 1/235 to 1/257 respectively) under PDNA-2023.

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
1	Excavation in earth work in foundation and trenches etcetera in all kind and classification of soil such as pick work, jumper work, pick jumper work, blasting work and hard blasting work and saturated soil any other mixed verity of soil in dry or saturated condition upto any depth and lift upto any height including chiseling/wedging out rocks where blasting prohibited dewatering pumping or bailing out water where required and/ removal of slush seprately as directed which may arise during the execution including stacking the serviceable and unserviceable material and then returning stacked soil in any thickness of layers when required into plinth side of foundation etcetera consolidating each deposited layers by ramming and watering then disposing of all surplus unserviceable excavated earth as specified dumping place as per CPWD specifications 2019 complete and direction of Engineer-in- charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials.The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	28.13	cum	180.00	Rs. One hundred eighty and paise zero only	Per Cubic metre	5063
2	Providing and laying in position cement concrete 1:4:8(one cement: four sand: eight graded/crushed stone aggregate 40mm (forty miillmeter) nominal size mechanically mixed and vibrated curing complete including cost of centering and shuttering in Retaining wall / Breast wall as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of material/ machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	43.88	Cum	3750.00	Rs. Three thousand seven hundred fifty and paise zero only	Per cubic metre	164550
3	Providing weepholes in brick masonry stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeters) dia PVC pipe OF MAKE D-PLAST/POLY.having pressure of 4.5 kg per square meter extending through the full width of the structures with slope of 1(V):20(H) (one vertical: twenty horizontal) towards drawing face complete as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials machinery required to execute the work in all leads and lifts and other incidentials.The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	30.00	Number	250.00	Rs. Two hundred fifty and paise zero only	Each	7500

Scanned with OKEN Scanner

4	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing and direction of Engineer in charge including carriage of materials machinery required to execute the work as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi, royality, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	9.00	Cum	650.00	Rs. Six hundred fifty and paise zero only	Per Cubic metre	5850
5	Providing and laying in position cement concrete 1:3:6 (one cement : three sand: six graded crushed stone aggregate 20 mm (twenty millimeter) nominal size mechanically mixed and curing complete including cost of centring and shuttering in Retaining wall / Breast wall as per CPWD specifications 2019 complete and direction of Engineer-in- charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials.The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	9.90	Cum	4150.00	Rs. Four thousand one hundred fifty and paise zero only	Per Cubic metre	41085
6	Providing and laying in position cement concrete 1:1.5:3 (one cement one point five sand: three graded/crushed stone aggregate 40mm (forty millimeter) nominal mix including cost of form work in foundation and plinth as per CPWD specifications 2019 complete and direction of Engineer-in- charge including carriage of materials machinery required to execute the work in all leads and lifts and other incidentials.The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	14.85	Cubic metre	5500.00	Rs. Five thousand five hundred and paise zero only	Per cubic metre	81675
	Total						**305723**
	Percentage rate (Above or Below)						

Executive Engineer,
Bharwain Division,
HPPWD, Bharwain.

Scanned with OKEN Scanner

Job No. 8 0

Schedule of Quantity

Estimated Cost:- 99316/-
Earnest Monry:-2000/-
Time:- Three Months

Name of Work:- Balance work for C/O Jeepable road from Jole to Khurwain road to Seri ward No. 4 village Bhagnal Deeraj Distt. Una to Abadi Atma Ram, Vinod Kumar, Hem Raj, Naresh Kumar in G.P. Ambehra (SH:- Providing and Laying 60mm thick C.C. interlocking paver block in km 0/355 to 0/382) Against BASP.

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
1	Excavation in earth work in foundation and trenches etcetera in all kind and classification of soil such as pick work, jumper work, pick jumper work, blasting work and hard blasting work and saturated soil any other mixed verity of soil in dry or saturated condition upto any depth and lift upto any height including chiseling/wedging out rocks where blasting prohibited dewatering pumping or bailing out water where required and/ removal of slush seprately as directed which may arise during the execution including stacking the serviceable and unserviceable material and then returning stacked soil in any thickness of layers when required into plinth side of foundation etcetera consolidating each deposited layers by ramming and watering then disposing of all surplus unserviceable excavated earth as specified dumping place as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials.The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	8.24	cum	180.00	Rs. One hundred eighty and paise zero only	Per Cubic metre	1483
2	Providing and laying in position cement concrete 1:4:8(one cement: four sand: eight graded/crushed stone aggregate 40mm (forty miillmeter) nominal size mechanically mixed and vibrated curing complete including cost of centering and shuttering in Retaining wall / Breast wall as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of material/ machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	8.24	Cum	3650.00	Rs. Three thousand six hundred fifty and paise zero only	Per cubic metre	30076

Scanned with OKEN Scanner

3	Providing and laying 60mm (sixty millimetre) chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all 60 mm thick C.C. paver block ISI marked of M-30 grade with approved color design and pattern.as per CPWD specifications 2019 complete and direction of Engineer-in- charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials.The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	82.35	Sq.m	750.00	Rs. Seven hundred fifty and paise zero only	Per Square metre	61763
4	Providing and laying in position cement concrete 1:2:4 (one cement two sand: four graded/crushed stone aggregate 20mm (twenty millimeter) nominal mix including cost of form work in foundation and plinth as per CPWD specifications 2019 complete and direction of Engineer-in- charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials.The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	1.08	Cum	5550.00	Rs. Five thousand five hundred fifty and paise zero only	Per cubic metre	5994
	Total						**99316**
	Percentage rate (Above or Below)						

Executive Engineer,
Bharwain Division,
HPPWD, Bharwain.

Scanned with OKEN Scanner

Job No-11

SCHEDULE OF QUANTITY

Estimate Cost :- Rs.98500/-
Earnest Money :-Rs.2000/-
Time Limit :- One Month.

Name of work:- A/R & M/O Bharwain Chintpurni Talwara road from km 0/0 to 15/310. (SH: Providing and installation of computer system with UPS, Printers, Intercom system)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and installation of Computer system of HP make with intel (R) Core ™ I-5- 4590 T CPU @ or higher @ 2.00 GHz. 2 MD L2 Cache, 800 MHzFSB/intel Q G31/033 or higher chipset/integrated GB LAN card/8 GB Dual channel DDR 3 Ram/1 TB HDD/DVD-RW driver (dual layer) 19.5" TTTT Analog colr Monitor/USB Key board/USB optical mouse/ PL-windows 7 ultimate/ PL-antivirus 60 days updating (6 years comprehensive on site warranty) complete. The rates are inclusive octroi, royality, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government	1.00 Number	67500.00	Rupees sixty seven thousand five hundred only	Each	67500.00
2	Providing of Elnova: 650 VA offline UPS system (12Vx7AHx2 No.) with 25-30 Min battary backup 3 years warranty on UPS & 18 month on batteries from date of delievery. The rates are inclusive octroi, royality, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	1.00 Number	3500.00	Rupees Three thousand five hundred only	Each	3500.00
3	HP Laserjet _____ a Monochrome printer with Print, scan and copy facility (A4 size): Prints upto 18ppm, 64MB RAM, 150 pages input 2 75 sheets output tray, high speed USB Port, Wi-Fi with one year warranty. The rates are inclusive octroi, royality, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	1.00 Number	27500.00	Rupees twenty seven thousand five hundred only	Each	27500.00
	TOTAL					**98500.00**
	Quoted percent rate in figure					
	Quoted percent rate in Words					

Executive Engineer,
Bharwain Division,
HPPWD Bharwain

Scanned with OKEN Scanner

Job No. 92

Schedule of Quantity

Name of Work:- Balance work for C/O Jeepable road from Jole to Khurwain road to Seri ward No. 4 village Bhagnal Deeraj Distt. Una to Abadi Atma Ram, Vinod Kumar, Hem Raj, Naresh Kumar in G.P. Ambehra (SH:- Providing and Laying 60mm thick C.C. interlocking paver block in km 0/382 to 0/400) Against BASP.

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
1	Excavation in earth work in foundation and trenches etcetera in all kind and classification of soil such as pick work, jumper work, pick jumper work, blasting work and hard blasting work and saturated soil any other mixed verity of soil in dry or saturated condition upto any depth and lift upto any height including chiseling/wedging out rocks where blasting prohibited dewatering pumping or bailing out water where required and/ removal of slush seprately as directed which may arise during the execution including stacking the serviceable and unserviceable material and then returning stacked soil in any thickness of layers when required into plinth side of foundation etcetera consolidating each deposited layers by ramming and watering then disposing of all surplus unserviceable excavated earth as specified dumping place as per CPWD specifications 2019 complete and direction of Engineer-in- charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials.The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	8.69	cum	180.00	Rs. One hundred eighty and paise zero only	Per Cubic metre	1564
2	Providing and laying in position cement concrete 1:4:8(one cement: four sand: eight graded/crushed stone aggregate 40mm (forty miillmeter) nominal size mechanically mixed and vibrated curing complete including cost of centering and shuttering in Retaining wall / Breast wall as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of material/ machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	8.69	Cum	3650.00	Rs. Three thousand six hundred fifty and paise zero only	Per cubic metre	31719
3	Providing and laying 60mm (sixty milimetre) chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all 60 mm thick C.C. paver block ISI marked of M-30 grade with approved color design and pattern.as per CPWD specifications 2019 complete and direction of Engineer-in- charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials.The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	82.80	Sqm	750.00	Rs. Seven hundred fifty and paise zero only	Per Square metre	62100

Scanned with OKEN Scanner

4	Providing and laying in position cement concrete 1:2:4 (one cement two sand: four graded/crushed stone aggregate 20mm (twenty millimeter) nominal mix including cost of form work in foundation and plinth as per CPWD specifications 2019 complete and direction of Engineer-in- charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials.The rate includes octroi , royality , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	0.72	Cum	5550.00	Rs. Five thousand five hundred fifty and paise zero only	Per cubic metre	3996
	Total						**99379**
	Percentage rate (Above or Below)						

Executive Engineer,
Bharwain Division,
HPPWD, Bharwain

Scanned with OKEN Scanner