HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed item rate / percentage rate tender are hereby invited on Form No. 6& 8 by the Executive Engineer, Bhoranj Division, HPPWD, Bhoranj on behalf of the Governor of Himachal Pradesh for the following works from the approved and eligible contractors/ firms of appropriate class enlisted in HPPWD (B&R) whose registration stood registered under the H.P. General Sales tax Act, 1968. As per latest instructions so as to reach and open in his office as per time schedule given below. The offer of the tender will be kept open for 20 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of Applications for tender form a/w requisite documents:- 26-02-2026 upto 10.00 AM to 11:00 AM.)
2. Date of issue/Sale of tender forms against Cash payment (Non- refundable) 26–02—2026 (3:00 PM to 5.00 PM)
3. Date of receipt of Tender:- 27-02-2026 at 10.30 AM.
4. Date of opening of Tender :- 27-02-2026 at 11.30 AM.

Sr. No.	Name of Road	Estimated Cost	Earnest Money	Time	Cost of Tender Form	Eligible class of Contractor
1	C/O Link Road to H.B. Dhamrola (SH:-C/O C.C. Pavement at RD 0/00 to 0/120)(VKVNY/2023/1207)	2,10,750/-	45,00/-	Two Months	Rs. 350/-	Class-D
2	C/O Link Road to H.B. Dhamrola (SH:- C/O R/wall at RD 0/00 to 0/015, 0/020 to 0/035 & 0/120 to 0/126.50) (VKVNY/2023/1207)	4,34,445/-	9,000/-	Two Months	Rs. 350/-	Class-D
3	Repair & Maintenance of Ludder Sulgwan road km. 0/00 to 5/00 (SH:- Maintenance of eathen at various RDs)	99,746/-	2,000/-	Two Months	Rs. 350/-	Class-D
4	Repair & Maintenance of Una Aghar Mandi road km. 79/00 to 91/00 (SH:- Dressing and cutting filling road side berms/shoulder km. 84/00 to 85/00 and 85/00 to 86/00) (section Jahu)	99,830/-	2,000/-	Two Months	Rs. 350/-	Class-D
5	Restoration of Bhareri Badehar via Jol Kota Road km 0/00 to 4/500 (SH:- Providing and Installation of crash barrier at various portion between km. 0/00 to 4/500) (PDNA)	4,97,800/-	10,000/-	Two Months	Rs. 350/-	Class-D
6	Restoration/Repair on Bassi Lajyani Dhamrol road 0/00 to 5/200. (SH:- Providing and installation of crash barrier at various portions between 0/00 to 2/500) (PDNA)	4,96,650/-	10,000/-	Two Months	Rs. 350/-	Class-D

Scanned with OKEN Scanner

7	R/R Damages on Various Road under Bhoranj Sub-Division (SH:- Maintenance of earthen shoulder, unlined surface drain and Removal of slip) (Bhoranj Section)	99,555/-	2,000/-	Two Months	Rs. 350/-	Class-D
8	Repair/Restoration link road Bassi Bhareri Tatahar Road km. 0/0 to 11/00 (SH:- C/O R/wall at RD 8/950 to 8/980) (PDNA)	4,99,200/-	10,000/-	Two Months	Rs. 350/-	Class-D
9	Repair/Restoration link road Bassi Bhareri Tatahar Road km 0/0 to 11/00 (SH:-C/O R/wall at RD 9/250 to 9/260, 9/200 to 9/230 & 9/150 to 9/165) (PDNA)	4,99,395/-	10,000/-	Two Months	Rs. 350/-	Class-D
10	Restoration of link road to H.B. Paplah km, 0/00 to 1/500 (SH:- P/L Paver block at RD 0/020 to 0/102) (PDNA)	4,99,796/-	10,000/-	Two Months	Rs. 350/-	Class-D
11	Restoration of link road to H.B. Paplah km. 0/00 to 1/500 (SH:- C/O Edge wall at RD 0/370 to 0/382 , V-shape Drain and Paver Block between km 0/280 to 0/354) (PDNA)	4,97,904/-	10,000/-	Two Months	Rs. 350/-	Class-D
12	C/O Ambulance Road to village Jol (G.P. Samirpur) km 0/00 to 0/500 (SH:- C/O B/wall at RD 0/110 to 0/133) VKVNY 2025/121.	2,60,599/-	5,500/-	Two Months	Rs. 350/-	Class-D
13	R/R Damages on Una Aghar Mandi Road km 79/00 to 91/00 (SH:-C/O R/wall at RD 82/055 to 82/061.50)	99,613/-	2,000/-	Two Months	Rs. 350/-	Class-D
14	R/R Damage on Una Aghar Mandi Road km 79/00 to 91/00 (SH:- C/O R/wall at RD 82/065 to 82/071.50)	99,613	2,000/-	Two Months	Rs. 350/-	Class-D

The earnest money in the shape of National Saving Certificate/ Time Deposit/ saving account of any post office or FDR of Nationalized Bank duly pledged in the name of undersigned must be accompanied with each tender. The Conditional tender and tender not accompanying the earnest money in the proper mode of deposit with summarily be rejected.

The Tender documents to be sent should have invariable be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No. Income Tax PAN No. & EPF No. must be attached with application.

TERMS AND CONDITIONS:-

The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which any be attached with their applications (The proof of ownership of machinery/ legal tie up arrangement). The tender forms will not be issued to those contractors whose performance is not found satisfactory.

Scanned with OKEN Scanner

The tender form will not be issued to those contractors who have already two works in hand. The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.
The conditional/ ambiguous/ telephonic tenders or tender by fax shall not entertain considered in any case.

(i) No Violation of social distancing.
(ii) Mandatorily wearing of face cover by everyone.
(iii) It is further added that any violation of the National directives & guidelines of containment of pandemic Covid-19 is liable for prosecution under section of IPC 1860.

Certified that the above work is of emergent nature in exigency of Public interest.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

For and on behalf of Governor of HP.

Dated:- 19-02-2026

No:-PW/BHD/TA/NIT/2025- 17911-950

Copy forwarded for information & necessary action to:-

1. The Engineer-in-Chief, Nirman Bhawan Nigam Vihar, HP:PWD., Shimla.
2. The Chief Engineer (HZ) HPPWD., Hamirpur.
3. The Superintending Engineer, 8th Circle HPPWD,Hamirpur.
4. All the Superintending Engineers/ Executive Engineers in HP.PWD.
5. The Deputy Commissioner, Hamirpur.
6. The Tehsildar, Bhoranj.
7. The B. D. O. Bhoranj.
8. The Municipal Committee, Bhoranj.
9. All the Assistant Engineers working under this Division.
10. Accounts Branch/ Drawing Branch/ Notice Board.
11. LokMitra, Bhoranj ,Various Contractors/ Firms.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK :- C/O Link Road to H.B Dhamrola (SH:- C/O C.C. Pavement at Rd 0/00 to 0/120)(VKVNY/2023/1207)					Estimated Cost	Rs. 2,10,752/-
					Earnest Money	Rs. 4500/-
					Time	2 month
Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	55.12	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete(M-20)(M-twenty) 1:2:4 (one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	26.99	Per Cubic Meter			
3	Providing concrete for plain/ reinforced concrete in P.C.C. grade $M\text{-}_{10}$(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm(forty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	7.87	Per cubic metre			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK :- C/O Link Road to H.B Dhamrola (SH:- C/O R/wall at Rd 0/00 to 0/015, 0/020 to 0/035 & 0/120 to 0/126.50) (VKVNY/2023/1207)				Estimated Cost	Rs. 4,24,445/-
				Earnest Money	Rs. 9000/-
				Time	2 month
Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	34.00	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	92.65	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	28.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	20.70	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK:- Repair & Maintenance of Ludder sulqwan road Km.0/00 to 5/00 (SH:- Maintenance of earthen at variour Rds)

Estimated Cost Rs 99,746-
Earnest Money Rs. 2000/-
Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregulartion on shoulders to the design level by adding fresh approoved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1196.00	Per square metre			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK:- Repair & Maintenance of Una Aghar Mandi road Km.79/00 to 91/00 (SH:- Dressing and cutting filling road side berms/ shoulder km .84/00 to 85/00 & 85/00 to 86/00) (Section Jahu).

Estimated Cost Rs 99,830/-
Earnest Money Rs. 2000/-
Time 2 Months

Sr.No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregulartion on shoulders to the design level by adding fresh approoved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1197.00	Per square metre			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK:-Restoration of Bhareri Badehar via Jol Kota Road Km 0/00 to 4/500 (SH:-Providing and installation of crash barrier at various portion between km. 0/00 to 4/500) PDNA

Estimated Cost Rs 4,97,800/-
Earnest Money Rs.10000/-
Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm(forty millimeters) nominal size i/c ereting W metal beam crash barrier comprising 3 mm thick corrugated sheet metal beam rail 70 cm (seventy centimeter) above the ground level fixed on ISMC series channel vertical post 150x75x5 mm spaced 2 mtr. Centre to centre 1.80 mtr. Height 1.010 meter below ground/road level and steel parts or fitment to be galvenised by hot dip process , all fitting to confirm to IS 1367 , metal beam rail to be fixed on the vertical posts with a spacer of channel section 150x75x5 mm 330 m long complete as per clause 810 as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	131.00	Per running metre			
-	**Total**					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration/ Repair on Bassi Lajyani Dhamrol road 0/00 to 5/200.
(S.H :- Providing and installation of crash barrier at Various portions between 0/00 to 2/500) (PDNA)

Estimated Cost Rs 495550/-
Earnest Money Rs.10000/-
Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm(forty millimeters) nominal size i/c ereting W metal beam crash barrier comprising 3 mm thick corrugated sheet metal beam rail 70 cm (seventy centimeter) above the ground level fixed on ISMC series channel vertical post 150x75x5 mm spaced 2 mtr. Centre to centre 1.80 mtr. Height 1.010 meter below ground/road level and steel parts or fitment to be galvenised by hot dip process , all fitting to confirm to IS 1367 , metal beam rail to be fixed on the vertical posts with a spacer of channel section 150x75x5 mm 330 m long complete as per clause 810 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	129.00	Per running metre			
	Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R Damages on Various Road under Bhoranj Sub - Division (SH:-Maintenance of earthen shoulder .unlined surface drain and Removal of slip.)) (Bhoranj Section).

Estimated Cost Rs 99,000/-
Earnest Money Rs. 2000/-
Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregulartion on shoulders to the design level by adding fresh approoved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	950.00	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Exacavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specifacation clause 307 as directed bythe engineer in charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	500.00	Per Running Mtr.			
3	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming og slope and disposal of cut material with in lift upto 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302.3.5 and 1611 and as per directon of Engineer-in-Charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	45.00	Per cubic metre			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK-: Repair/Restoration link road Bassi Bhareri Tatahar Road km. 0/0 to 11/00.(SH:- C/O R/wall at RD 8/950 to 8/980.) (PDNA)

Estimated Cost Rs 4,99,200/-
Earnest Money Rs. 10,000/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	42.00	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	104.70	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	45.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	27.40	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK-: Repair/Restoration link road Bassi Bhareri Tatahar Road km. 0/0 to 11/00.(SH:- C/O R/wall at RD.9/250 to 9/260,9/200 to 9/230 & 9/150 to 9/165.) (PDNA)

Estimated Cost Rs 4,99,395/-
Earnest Money Rs. 10,000/-
Time 2 month

Sr N	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	38.05	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	100.70	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	50.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	46.50	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of link road to H.B. Paplah km. 0/00 to 1/500.(SH:- P/L Paver block at RD. 0/020 to 0/102). (PDNA)

Estimated Cost Rs 4,99,794/-
Earnest Money Rs. 10000/-
Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includinmg dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	24.60	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	26.54	Per cubic meter			
3	Providing and laying mechanically mixed cement concrete(M-20)(M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	4.10	Per Cubic Meter			
4	Providing and laying in position specified grade of reinforced cement concrete, encluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size)as per directon of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	2.40	Per Cubic Meter			
5	Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-40(M-forty) grade including border or kurb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm(eighty millimeters) thick inter locking blocks (ISI approved), and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and lifts including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government	261.40	Per square meter			
	Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of link road to H.B. Paplah km. 0/00 to 1/500.(SH:- C/O Edge Wall at RD 0/370 to 0/382, V-Shape Drain an Paver block between km 0/280 to 0/354). (PDNA)

Estimated Cost Rs 4,97,904/-
Earnest Money Rs. 10000/-
Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	27.75	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	27.56	Per cubic meter			
3	Providing and laying mechanically mixed cement concrete(M-20)(M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	3.33	Per Cubic Meter			
4	Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-40(M-forty) grade including border or kurb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm(eighty millimeters) thick inter locking blocks (ISI approved), and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and lifts including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government	222.00	Per square meter			
5	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	11.40	Per Cubic Meter			
6	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material, including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	7.20	Per Cubic Meter			
7	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	12.00	Each			
	Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HPWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

					Estimated Cost	Rs. 2,60,599/-
					Earnest Money	Rs. 5500/-
					Time	2 month
NAME OF WORK :- C/O Ambulance Road to Village Jol (G.P Samirpur) Km 0/00 to 0/500 (C/O B/wall at Rd 0/110 to 0/133)VKVNY 2025 /121.						
Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	43.70	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	55.02	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	42.00	Each			
4	Total					
	Terms and Condition:-					
	1.Work shall be executed as per PWD specification.					

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK :- R/R Damage on Una Aghar Mandi Road Km 79/00 to 91/00.(SH:- C/O R/wall at RD 82/055 to 82/061.50)					Estimated Cost	Rs.99613/-
					Earnest Money	Rs. 2000/-
					Time	2 month
Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	11.44	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	20.50	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	12.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	5.45	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK :- R/R Damage on Una Aghar Mandi Road Km 79/00 to 91/00.(SH:- C/O R/wall at RD 82/065 to 82/071.50)					Estimated Cost	Rs.99,613/-
					Earnest Money	Rs. 2000/-
					Time	2 month
Sr No	**Description of Items**	**Quantity**	**Unit**	**Rate**	**Rates in Words**	**Amount**
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	11.44	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	20.50	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	12.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	5.45	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner